


CHEMICAL ENGINEERING

with CHEMICAL & METALLURGICAL ENGINEERING



Materials of Construction for the Atomic Age

For NOVEMBER, 1946 • TWELFTH BIENNIAL REPORT ON MATERIALS OF CONSTRUCTION • HOW SPECIAL MATERIALS SOLVED CORROSION PROBLEMS AT OAK RIDGE • DESIGN OF LIQUID AGITATORS • EQUIPMENT COSTS • SOLVENT SEPARATION OF FATTY ACIDS



Better starch paste at far less cost

Continuous, closed Votator equipment expedites another processing job

THIS time it's in the textile industry, at Rock Hill Printing and Finishing Company, Rock Hill, South Carolina.

Each 24-hour day, the company processes thousands of gallons of starch paste, vehicle for dyestuffs used in textile printing. This formidable cooking and cooling job required five men per shift with open kettle methods. But since converting to continuous, closed VOTATOR equipment, only two men are required, and half the floor space. The

paste is produced with 10% less starch. And because of positive control over temperatures and mixing, plus positive exclusion of grit, the paste is of uniform consistency.

The various VOTATOR advantages add up to savings in processing cost which will amortize Rock Hill's VOTATOR installation in little more than a year.


Starch paste, lard, photo emulsions, margarine, shortening, printing ink, polishes, paraffin wax, lubricating grease . . . VOTATOR equipment is a cost saver for many products which are processed in a viscous state and require heat

transfer. If you manufacture a product in this category write to The Girdler Corporation, Votator Division, Louisville 1, Kentucky.

District Offices:
150 Broadway, New York City 7
2612 Russ Building, San Francisco 4
617 Johnston Building, Charlotte 2 North Carolina



VOTATOR—T. M. Reg. U. S. Pat. Off.



VALVES




Fig. 6003—Class 600-pound Cast Steel Gate Valve. Has flanged ends, outside screw rising stem, bolted flanged yoke and taper wedge solid disc.

Fig. 3023—Class 300-pound 16" Cast Steel Gate Valve, designed especially for catalytic processing. Has automatic steam sealing mechanism and top-mounted, enclosed, explosion-proof, electric motor operator.





Fig. 1503—Class 150-pound Cast Steel Gate Valve. Has flanged ends, outside screw rising stem, bolted flanged yoke, taper wedge solid disc.




Fig. 1531—Class 150-pound Cast Steel Globe Valve. Has flanged ends, outside screw rising stem and bolted flanged yoke.

The Wm. Powell Co., Cincinnati 22, Ohio

DISTRIBUTORS AND STOCKS IN ALL PRINCIPAL CITIES

VALVES

WATCHING WASHINGTON

R. S. McBRIDE, Editorial Consultant • D. D. HOGATE, Chief of McGraw-Hill Washington Bureau • J. V. HIGHTOWER, Washington Correspondent

Board appointed to make inventory of government research activities . . . Proposal to ban patent rights to civilians engaged in federally-financed research . . . Controls on rubber held necessary to insure production of synthetic . . . Voluntary allocation of soda ash in effect . . . Seized corporations in which enemy aliens hold interest poses patent problem . . . War plants disposal may pass from War Assets Administration . . . Fertilizer men want uniform state fertilizer regulations . . . Army produces ammonia at Ordnance works . . . International trade agreements aim at elimination of tariffs

SURVEY OF FEDERAL SCIENCE

ESTABLISHMENT by executive order last month of the Presidential Research Board headed by OWMR Director Steelman was a recognition of the need for starting, without further delay, an inventory of federally financed research and development. Truman's move is understood to be the result of urging by members of OWMR and Congress who want federal research to be civilian-dominated. They think research is taking on a strong military cast, perhaps merely because there is yet no coordinating agency. With the help of the 12-man advisory board composed of government officials Mr. Steelman is required to find out in detail what is going on, why, and where, and to file a report containing his findings and recommendations.

This is a job that might have already begun if the House had got around to and passed S. 1850, the Science Foundation bill approved by the Senate in the last session. It is expected in Washington that another effort will be made next spring to enact this or a similar measure. However, in the months before a national act could begin functioning and giving direction to the onrush of federal science, the need for an interim organization has become apparent. Mr. Steelman has been given the nod. If it becomes clear by next spring that science legislation will be stalled indefinitely in Congress, it is believed that Steelman will recommend establishment of a permanent executive agency.

A FACT-FINDING JOB

STEELMAN has received plenary authority to ask for and receive facts from all departments and independent offices. He is therefore placed in a position to study the extent to which government funds are

being spent needlessly. Also, he should be able to determine whether there is building up an undesirable preponderance of research and development under purely military control. Steelman's job is basically a fact-finding, whither-are-we-drifting undertaking.

In issuing his order setting up the Research Board Mr. Truman said, "There must be no duplication, overlapping or inefficiency to hamper federal research." This was one of the premises on which the structure of S. 1850 was erected. The War and Navy Departments, both with burgeoning research and development programs, have set up a joint board to coordinate their work. There has been no equally tight coordinating group for all federal branches.

JUSTICE'S PATENT PLAN

SCHEDULED for White House attention last month was a Justice Department report recommending abolition of prevailing patent privileges accorded civilian organizations performing federally financed research and development. Justice would ban private patent rights in this field and substitute a policy of government patenting and selective licensing managed by a federal agency controlling all government-owned patents. Behind such a policy is the theory that it would be a helpful instrument in the Justice Department's anti-monopoly tool kit.

This is a far more slashing proposal than the basic patent provision in the Science Foundation bill passed by the Senate but stalled in the House at the last session. That bill provided that, with certain exceptions under which private patents might be taken out, patents arising out of federally financed private research would be

dedicated to the public. The Justice Department's plan would make such patents available only to those organizations acceptable to the federal patent agency. Washington offices which farm out research and which understand that the attractiveness of government contracts is greatly enhanced by the patent rights accorded organizations doing the work do not accord the Justice Department's idea a warm reception.


PRODUCTIVITY IS WHAT?

WHAT can be done toward arriving at accurate, informative means of measuring and accounting for labor productivity is a live subject in Washington these days. As it is a growing factor in collective bargaining and the work of plant engineers, something is being done about it. The Labor Department is aware of the need for developing more illuminating facts than were formerly gleaned from productivity data on an industry-wide basis. Government agencies are being asked by labor and management to get those facts.

RUBBER DECONTROL UNLIKELY

NOTWITHSTANDING the scheduled lifting of international allocations of natural rubber on January 1 at the request of foreign producers, and the contracts for 204c rubber negotiated last month in view of an improved outlook for supplies, rubber executives in Washington say the time has not yet come for abandoning the still existing domestic controls. They are particularly disturbed over the possibility of a sharp decline in the proportion of synthetic rubber in the total domestic new rubber consumption. Some officials estimate that this might eventually drop to 10 or 15 percent as compared with the present figure of 65 percent. Under specification rules likely to govern operations in the first quarter of 1947 it is understood that the ratio of natural to synthetic rubber will be held to about 50-50.

Despite the marked improvement in and current general acceptance of tires of the mixed rubbers the public, officials declare, is somewhat uncertain about these products. They suspect the uncertainty might be encouraged in a freely competitive market released from specification controls. They fear the results which such a development, if it persisted for any length



2 steps give complete protection!

It seems kind of silly to us, but many companies will spend good money to protect the inside of a tank from corrosive attack, and pay no attention to the outside. *Probably as many tanks fail from the outside in, as from the inside out.*

That's why it's standard practice with us to apply three coats of Tygon Paint to the exterior of tanks we line. The combination of a 3/32" thick Tygon sheet lining on the inside and three coats of Tygon Paint on the outside is hard to beat.

Tygon plastic Paint is made from the same basic sheet stocks used to line the tank's interior. Applied

in liquid form, Tygon Paint air dries quickly (by solvent evaporation) to form a tough, sturdy film of pure Tygon.

Tygon Paint possesses the same basic corrosion-resistant characteristics as Tygon sheet stocks. In fact, this tough, sturdy plastic coating is frequently used in place of a heavier, thicker lining where only mild corrosive problems are involved.

On your next tank installation, be sure to get this double protection: *Tygon-lined inside, Tygon-coated outside.*

U. S. Stoneware fabricates and installs a wide range of lining materials to meet highly specific conditions: Tygon plastic linings, Paraply rubber linings (natural rubber, GRS, or Neoprene), Republic sheet or homogeneous lead linings, Resilon synthetic linings, Acikote baked-on hard coatings. We'll be glad to submit suggestions, design detail, and specific recommendations as to the best material for your particular needs.



of time, would have on the general-purpose synthetic rubber industry. It is expected in Washington, that, regardless of the political complexion of Congress, strong support for legislation buttressing this industry will be manifested early next year. Belief is prevalent in the government rubber offices that a bill will stand a much better chance while the use of synthetic rubber is still obligatory.

RUBBER COMMITTEE CAUTIOUS

MEETING a few weeks ago with CPA, the Rubber Industry Advisory Committee was opposed to lifting domestic controls from rubber at present. This group recommended the temporary continuation of natural rubber purchases through the Rubber Development Corporation. Committee members also asked that specification and allocation controls such as exist in CPA Order R-1 should continue until at least March 31, and believed that similar controls will be required to protect the synthetic rubber industry after the Second War Powers Act expires on that date.

The advisory committee will study what type of legislation seems necessary to carry out the recent recommendations of the Inter-agency Policy Committee on Rubber. IPCR urges that at least a third of the annual rubber consumption, exclusive of specialty rubber, consist of general-purpose synthetic.

The 1947 program agreed upon last month by CPA and the advisory group is predicated on a consumption of 1,003,000 long tons of natural plus synthetic rubber. Of the total, 258,000 tons is first-quarter consumption, about half of which will be natural rubber. Estimates for the remaining quarters were not established.

ALIEN PATENTS FOR ALL

PATENTS resulting from the work of alien specialists engaged in civilian enterprise cannot be monopolized. This is one of the important conditions finally reached by the State-War-Navy Coordinating Committee with the approval of the Justice Department. The requirement is that such patents must be made generally available at "reasonable" royalties. Authorities in Washington say this condition is essential in order to avoid the charge that any agency of the government has been instrumental in importing foreign inventive genius for the sole benefit of a particular organization.

ALLOCATIONS FOR SODA ASH

WITH present production of soda ash about 15 percent below requirements of essential users, and no prospect of an early material increase in production, a voluntary allocation program was instituted last month by CPA and the Soda Ash Industry

Advisory Committee. CPA has been unwilling to assume this function, but was preparing in October to issue a direction to Priority Regulation 28 whereby priority assistance is limited in securing soda ash for emergency cases or to increase production of critical products. A short time ago CPA was discussing with other government agencies the practicability of putting soda ash under export license.

Under the voluntary program efforts will be made to step up the delivery of soda ash to the aluminum industry by 45,000 to 50,000 tons yearly above current deliveries, in order to support maximum aluminum output for the housing program. In addition, it is contemplated that the requirements of vital uses of soda ash will be met. CPA officials say it is up to the soda ash industry to work out the details to govern deliveries for these and other uses.

There is little expectation that production of soda ash, which suffered heavy drops last May and June because of strikes, can be increased during 1947 by way of new manufacturing capacity recently authorized. CPA reports new construction authorizations to the Solvay Process Corp. for plants at Baton Rouge, La., and Detroit, Mich., and to the Wyandotte Chemical Co. at Wyandotte, Mich. Little or no construction on these projects has begun.

ASH EXPORTS INCREASE

INCREASED exports of soda ash to regions formerly supplied by other countries, as well as heavy domestic consumption by the glass, chemicals and non-ferrous metals industries, are contributing to the scarcity of soda ash. Exports of the product in the first eight months of 1946 are reported as 108 million lb. compared with approximately 102 million lb. for the entire year of 1938. Department of Commerce authorities point out that a number of countries which formerly took little or no soda ash from the United States are clamoring for a supply which we cannot furnish them. The collapse of production in Germany and Japan and the drop in production in England have brought about this condition.

JUSTICE GETS AN APC ISSUE

HAVING taken over the functions of the Alien Property Custodian last month, the Department of Justice has the job of making effective a decision of the Inter-departmental Committee on Foreign Economic Policy that patents held by corporations in which enemy aliens own an interest which has been seized should be opened to the public. Alternative steps would be to place such patents in the public domain or to license them on a royalty-free, non-exclusive basis as has been done with wholly German-owned patents.

When APC seized the enemy holdings of such organizations as American Bosch, General Aniline and American Potash, no action was taken on patents which they held. The principal reason was that destruction of the value of these patents would be unfair to American and friendly foreign owners of minority interests in the companies. The problem facing the Justice Department is how to go about opening up the patents on an equitable basis with respect to the minority groups.

SEE OIT FOR GERMAN PLANTS


AMERICANS desirous of acquiring German chemical plants being declared available for reparations are asked by the Office of International Trade in the Department of Commerce for expressions of interest. Expressions of interest constitute no commitment to buy a plant if, as and when it is allocated to the American account by the Inter-Allied Reparations Agency. Plants or other facilities may be moved either to the United States or some other country. Such equipment, if acquired, cannot be left in Germany.

Acquisition of property, however, will not be an overnight matter. Thus far no policies or regulations governing the eventual transfer of reparations acquired by the United States to private concerns are established. Establishment of procedure is the task of the Office of Foreign Liquidation in the State Department. The work of designating the individual German plants available for reparations and the allocation of such plants among the claimant nations is still unfinished. Thus far about 40 chemical plants, including several I. G. installations, have been declared available for reparations.

WORK ON ALIEN ENTRY PLANS

HAVING worked most of the bugs out of a plan advanced last spring for making German and Austrian scientists and technologists available for American civilian enterprise, the State-War-Navy Coordinating Committee feels that it is now getting somewhere. As of last month decision had been reached to permit the presence, at any one time, of up to 1,000 of these aliens in the United States. With several hundred already here, it is believed the maximum contingent will be in this country by next spring. A majority of those in the list are slated initially for military assignments, although some are being imported as the result of requests filed with the Department of Commerce by industry and schools.

It is planned to release the foreign specialists to civilian tasks as rapidly as possible at the termination of their military assignments. However, there is a road block in the fact that the aliens, now entering this country under temporary status,



Building Blocks of Industry

These essential chemicals are aptly called "The Building Blocks of Industry," because without them products of modern Industry would not be the same as we know them today—and many could not be made at all.

COLUMBIA CHEMICALS

PITTSBURGH PLATE GLASS COMPANY
COLUMBIA CHEMICAL DIVISION

FIFTH AVENUE at BELLEFIELD • PITTSBURGH 13, PA.

CHICAGO • BOSTON • ST. LOUIS • PITTSBURGH • NEW YORK • CINCINNATI • CLEVELAND
PHILADELPHIA • MINNEAPOLIS • CHARLOTTE • SAN FRANCISCO

must be kept under military surveillance, which in effect limits them strictly to military work until their immigration status is clarified. Efforts were being made last month to reach a way out of the difficulty. Authorities close to this matter were confident of an early interdepartmental agreement whereby the specialists can be loaned to industry without surveillance during the period in which their eligibility for immigration is determined.

ORDERS FOR ALIENS

THE agencies concerned with the continuing movement of German and Austrian specialists of exceptional talents into this country are bringing in a number who are not specifically slated for military work. These constitute a pool from which withdrawals for civilian assignments probably can be effected before the services of most of those with preassigned military tasks can be obtained. For various reasons it is desired to complete the movement at an early date. This objective, however, poses a problem: The undesirable prospect of feeding and housing a large body of unassigned aliens or those whose military tasks will end soon and leave them idle at government expense for an indefinite period.

Officials facing this problem are anxious for requests to be filed in Washington now for the employment of aliens of outstanding qualifications already in this country or still in Europe. The Office of Technical Services in the Department of Commerce is the agency with which requests should be placed. There is already a sizeable file of requests from universities, research institutions, chemical manufacturers and oil companies.

WAA TO HAND OVER BALL

WORD from the vicinity of Congress is that War Assets Administration may soon be confronted with a demand that it hand over the battered ball of war plant disposal to some specially created agency, possibly called the Government Facilities Administration. The prospect is that such a proposal will taken form in the course of hearings scheduled to begin on December 10 before the Senate Small Business Committee. At that time the committee will begin to examine the record and try to determine what might be done about the glut of unmarketed plants.

As they stood last month the committee's plans call initially for a checkup on what has happened and is happening to the light metals plants, and then to shift to chemicals, petroleum refineries and other fields. In the course of this journey, it is understood the committee will launch some remarks about the need for a separate plant disposal agency, separately staffed from WAA, which, committee members feel,

has a topheavy contingent of men who think in terms of commodities rather than plants.

In addition, there is exploratory thinking in the committee that a new disposal agency should consider the broad question of adequacy of production facilities in the various industries in which the government owns productive capacity. In such deliberation the agency would, in the thinking of some committeemen, dwell on the practicability and desirability of setting up rival "small" businesses as rivals to the "big" companies.

FERTILIZER OFFICIALS JOIN

A NEW fertilizer organization, the Association of American Fertilizer Control Officials, was established last month in Washington at the annual meeting of the Association of Official Agricultural Chemists. Interests of this group of state control officials are concentrated on national and state laws affecting mixed fertilizers and fertilizer chemicals with respect to labeling, standards and other regulations. One immediate objective is to accelerate the promotion of uniform state fertilizer rules on the basis of a new draft drawn up last month. Officials are headed by D. S. Coltrane, assistant agriculture commissioner of North Carolina, the president, and A. B. Lemon, chief of the Bureau of Chemistry, California Department of Agriculture, the vice president.

ARMY PRODUCING FERTILIZER

THE War Department believes that its OWMR-directed program of producing 684,000 tons of fertilizer-grade ammonium nitrate in ordnance plants for shipment to Germany and Japan will be completed by next August. After four months of plant conversion work, the War Department finally got production of anhydrous ammonia under way in October at the Ohio River, Missouri and Cactus Ordnance Works, and planned to start production at the Morgantown Ordnance Works early this month.

Scheduled to begin this month the conversion of ammonia into ammonium nitrate solution were Indiana Arsenal, Joliet Arsenal, Radford Arsenal and the Sunflower and Wabash River Ordnance Works. Next month the Army expects the Holston Ordnance Works to be producing solution. The solutions are being or will be shipped this year to the following plants for graining, conditioning and bagging: Cornhusker, Nebraska, Illinois and Iowa Ordnance plants and the Milan and Ravenna Arsenals.

The War Department's program is intended to decrease and eventually eliminate the policy of shipping foodstuffs to the occupied areas, a policy considered by the State Department as essential for interna-

tional political reasons until such time as those areas can improve their agricultural production.

PEORIA COB PLANT IN USE

WASHINGTON officials of the Department of Agriculture look for economically significant results from the operation, started last month, of the department's semi-commercial plant at Peoria, Ill., for conversion of corn cobs and other cellulosic farm wastes into alcohols. Saccharification by dilute sulphuric acid, followed by fermentation, the principles of which have been long established, is the heart of the process. Primary interest, dictated by the congressional appropriation for synthetic liquid fuels in 1944, is the production of alcoholic motor fuel.

Specialists in Washington say the importance of the work at Peoria resides largely in costs of manufacture. High yields of byproduct furfural are looked for and are expected to figure to a large extent in the economic attractiveness of results obtained in the semi-commercial plant. No significant operating results are looked for before some time next year.

FTC HEARING ON DYES


FOLLOWING adoption in August of its new policy of industry-wide investigations the Federal Trade Commission last month scheduled for November 7 the first trade practice conference dealing with one of the chemical industries, household dye manufacturing and marketing. Decision to hold the conference resulted from several months of general investigation. The objective of this and all future conferences is to discuss the creation of a set of trade practice rules acceptable to the industry and subject to final approval by FTC. A Federal Trade spokesman said last month there were no other investigations under way in the chemical field.

HUNT FOR TANK CARS

IN AN effort to cope with the serious shortage of tank cars for chemicals the War Department, Office of Defense Transportation, and the War Assets Corporation set in motion last month a joint program to increase the supply of cars and improve efficiency of their use. The tank car shortage has been aggravated by reopening of ordnance plants for the production of nitrate fertilizers and by expansion of demand for cars to carry liquefied petroleum gases.

ODT is seeking to locate 525 petroleum tank cars capable of conversion into ammonium nitrate solution carriers. With a tough exchange job on its hands reminiscent of the war period, that agency is trying to replace cars taken from liquefied gas service either for commercial fertilizer

Dowtherm on the job!



Handling a big assignment in acid concentration

A battery of 30,000,000 Btu/hr. Dowtherm vaporizers supplies the heating requirements in this sulphuric acid concentration plant, built several years ago by a great Eastern firm. When the plant designers chose Dowtherm for this big installation, they simplified subsequent processing operations . . . and they also achieved a sizable reduction in the original construction costs of the plant!

Dowtherm was adopted because of its outstanding ability to combine high temperatures with low operating pressures. At a pressure of only 25 lb./sq. in. gauge, Dowtherm's temperature margin over the boiling point of the sulphuric acid was approximately four times as great as that of steam at 250 lb./sq. in. This advantage of Dowtherm cut down immensely on the heat transfer surface requirements . . . brought substantial savings in construction costs as a result. And the Dowtherm installation continues to pay dividends today in accurate, uniform heating with minimum maintenance requirements.


To users in many industries Dowtherm has brought a new experience in exact, low-pressure heating throughout the 300-725° F. range. It may point the way to new economies, greater product uniformity, and speedier production in your own processing operations! Dow's free booklet, "The Dowtherm Story," will give you the details.

THE DOW CHEMICAL COMPANY, MIDLAND, MICHIGAN

New York • Boston • Philadelphia • Washington • Cleveland • Detroit
Chicago • St. Louis • Houston • San Francisco • Los Angeles • Seattle

Dowtherm

*The high-temperature
low-pressure
heat transfer medium*



plants or the War Department as rapidly as production of new high pressure cars permits. The War Department's fertilizer program calls for the shifting of 280 cars in the anhydrous ammonia movement, and the withdrawal and conversion of 100 propane gas cars, in order to move ammonium nitrate solution. It is planned to replace most of these cars with the petroleum tank carriers which ODT is seeking. In addition to this shift-about program, ODT is trying to increase the efficiency of pressure cars by reducing cross-hauls and speeding turnaround time.

TRADE PLAN IDEAS OUTLINED

THE American government's tentative ideas of the system under which the proposed United Nations International Trade Organization might function if that agency becomes operative next year have been outlined by the State Department. Released last month, the U. S. Draft Charter is the initial move to attempt to crystallize into a "constitution" the free trade principles which this country attached last spring to the British loan.

Ideas presented in the charter for an international trade group are couched in terms too broad to indicate at this time what effects such an organization might have on the American chemical industry. However, the charter contemplates the establishment of a world organization of nations agreeing to adopt a trade policy aimed at the eventual elimination of tariffs, customs, bi-lateral trading, state trading, etc., and the substitution therefor of international trade as free as that between the American states.

With customary caution the State Department emphasizes that the charter is not necessarily fixed American policy. Early next year the State Department will open the charter to public hearings. At that time domestic groups concerned with foreign trade will be asked for their views on the principles set forth.

ONR CHEMICAL SEMINARS

THE Office of Naval Research, in an effort to bring about a closer relationship between ONR personnel and civilian scientists and technologists, has inaugurated a series of seminars in Washington for the discussion of research and development matters of interest to ONR. The series was launched last month with plastics as the subject. The plastics series, planned to extend over ten months, will include such subjects as synthetic lubricants, recent developments and applications of silicone rubbers, advances in laminated plastics and protective coverings. ONR has contracts with several universities and Goodyear Tire and Rubber Co. for plastics studies and expects to negotiate others. The Chemical Division of ONR has been working out a

seminar on chemicals but has not yet disclosed the specific subjects to be covered.

FROM CATTLE TO COPPER

WASHINGTON during the meat famine got a new demonstration of the interdependence of modern industries. Cattle did not come to slaughter. Immediately there was a scarcity of inedible tallow for soap, of hides for the tanner, of numerous other byproducts for industries of great importance.

Then came the sequence of secondary and later events. This is one chain reaction: no cattle, no tallow, no soap-stock, no glycerine, no dynamite, no copper. This sequence actually became a controversial administrative issue; and serious effort had to be made about Washington to get mining and industrial explosives lest very vital housing projects be held up.

FPC GETS FINAL BRIEFS

THE Federal Power Commission received a few weeks ago the last of a batch of briefs filed by the participants in the 11-month series of hearings before the commission on the subject of natural gas. The commission, according to opinion in and outside Washington, asked for these final rejoinders more as a matter of courtesy and form than as a means of helping the agency to make up its mind as to what changes in the Natural Gas Act it should seek from Congress. It is also thought that those who filed the briefs did so primarily out of the hope that when the gas fight opens next year, congressmen will be more likely to read and consider the final summaries of the petitioners than the voluminous testimony in the records of the hearings.

Gas industry men are convinced that FPC wants to get a declaration of Congressional policy on the competition between oil, gas and coal, and authority which would greatly extend FPC's present limited jurisdiction over natural gas. The natural gas industry has ready for Congress a program that would stop FPC from advancing a step beyond its present authority.

A SEARCH FOR CONTRACTS

INDICATIONS are that the military services, unless hampered by an era of economy in Congress, will for the next few years lay urgent demands upon private agencies for much research and development. In the aggregate the services would like to have a greater volume of contracts than they have thus far been able to place, largely with schools. The fighting agencies probably would do more work in their own shops if they were permitted to pay the kinds of salaries that are needed to secure qualified talent, but they lack this

advantage. Accordingly they are looking, contract in hand, for outside help.

Contracts for research and development, rather than production contracts, have become the principal current concern of procurement and planning authorities. Army and Navy funds for basic studies have become almost half as large as money for procurement of materials and are much larger than they were before the war. The industrial mobilization planners in Washington are determined to keep their plans supple and infused with the life of day-by-day scientific and engineering advances.

MINOR NEWS GLIMPSES

Silver bus bars, 16,300 tons of them, borrowed in 1942 for use in government war plants, are being returned to the Treasury from 13 plants which produced aluminum and magnesium and other scarce metals. RFC is returning the metal to the mints at Denver and Philadelphia and the Assay Office in New York City, where it will be recast into either coinage ingots or commercial bars. About 14,000 tons remains on loan to the War Department in the form of conductors at the Oak Ridge atomic bomb plant.

German chemical developments in detergents, emulsifiers, acetylene and pharmaceuticals continue to interest American chemical companies, which have sent their chemists and technologists to Germany this fall under arrangement with the Office of Technical Services, Department of Commerce.

Basic chemical industries, glass, and synthetic fibers as developed in the United States are interesting the Netherlands Indies government, which has sent Dr. D. R. Koolhaas, director of the Industrial Division of the Department of Economic Affairs, to this country. Koolhaas, stationed with the Netherlands Trade Commissioner in New York City, wants to learn about American methods and development which might be applied in the Netherlands Indies.

Unbalanced supplies of raw materials are causing much concern in many industries, and in Washington. Oftentimes the scarcity of one component or one reagent stops a whole factory. Some Washington observers think that this unbalance perhaps accounts for the very great recent increase in inventories of goods in process. There are no statistics to prove or disprove that interpretation.

Alcohol from wood will not be made at the new Oregon plant except on a small scale until the turn of the year. The government aid to that plant, which makes sugar from wood for fermentation, has not been enough to complete construction. A major delay has been caused by the lack of switches and starters.

CHEMICAL ENGINEERING

WITH CHEMICAL & METALLURGICAL ENGINEERING

ESTABLISHED 1902

NOVEMBER 1946

SIDNEY D. KIRKPATRICK, Editor

Always Building, Never Built

IT IS almost axiomatic that chemical plant construction is a never-ending process. An industry that stems primarily from research is always changing and with increasing tempo as new processes and products call for improved construction to resist temperatures, pressures and corrosives never previously encountered. We enter the Atomic Age with many new materials and methods available for the chemical engineer's study and application.

When our first corrosion issue was published almost a quarter of a century ago, chemical equipment construction was largely limited to lead, cast iron, wood and stoneware. The chrome-nickel and other corrosion-resistant alloys made their appearance in volume shortly after the first World War. The late twenties and early thirties ushered in the era of the stainless steels, which soon found a multitude of new applications. With the forties came the ascendancy of the non-metallics—plastics and synthetic rubber, glass and porcelain, carbon and graphite—that have now greatly broadened the field of materials for equipment design and construction. So important have they become that in this twelfth in our series of materials of construction reports, the non-metallics, for the first time, take their place in the combined tabulations of reference data on availability, properties and applications. This year's directory presents, in all, more than 600 construction materials and is followed by a table showing their resistance to commonly used chemicals.

It is appropriate that this report should be introduced by a splendid article on the corrosion-resistant materials used in the electromagnetic plant of the atomic bomb project in Oak Ridge, Tenn. A look behind the doors in one of the world's most interesting plants reveals a variety of new materials in unique and

daring applications. Less spectacular but sometimes as important as the materials themselves are the design and composition of gaskets that must withstand conditions of severest service in chemical equipment. This becomes the basis for a second useful contribution—an article that tabulates the general characteristics of both metallic and non-metallic gaskets and follows with recommendations for their selection and use in handling some 200 chemicals.

This country is now engaged in the biggest peacetime construction program in its history. In the six months ended September 26, Civilian Production Administration approved 52,000 applications for industrial buildings, estimated to cost just under two billion dollars. And the boom would have been half again as big had CPA not rejected 3,600 applications, worth \$1.4 billion. Some measure of what this program means to chemical engineers may be gaged by the fact that 50 of these projects in the process industries alone call for a total expenditure of \$180 million of which approximately \$130 million is for equipment and about \$50 million for buildings and structures. CPA, sated as it is with astronomical figures, is amazed at the size of the industrial program, particularly because it is coincidental with War Assets Administration's sale of some \$4 billion of surplus plants and facilities judged to have peacetime serviceability.


All of which adds up to the fact that the old is not good enough for the new plans and projects that are now coming from the research laboratories and drafting boards of the process industries. There is a big job to be done by chemical engineers in the days ahead and it is our earnest hope that this Twelfth Materials of Construction report will prove of practical help and inspiration in shouldering that heavy responsibility.

R. J. SCHRADER and A. De HAAN

Respectively Head of Chemical Engineering Department and Chemical Engineer, Tennessee Eastman Corp., Oak Ridge, Tenn.

Special Materials Solved CORROSION PROBLEMS

Production intricacies of materials for use in atomic bombs demand the most resistant materials of construction. Elimination of corrosion is a "must" not only for the prevention of equipment deterioration but for minimizing uranium losses. Many procedures developed especially for use at the electromagnetic separation plant of Clinton Engineer Works called for development of new alloys and non-metallic materials, and in addition special fabrication techniques. The valuable experience gained at Oak Ridge is applicable in almost every chemical plant. —Editors



PREVENTION of corrosion is a major problem in the successful operation of the electromagnetic separation plant at the Clinton Engineer Works. As was described in the Smyth Report, calutrons (electromagnetic separation units) must be cleaned periodically in order to recover unresolved uranium which is scattered over the units and to condition them for another run. To insure complete uranium recovery a variety of cleaning solutions are used, several of which contain nitric acid and small concentrations of hydrochloric acid. These solutions are then processed in chemical plants to recover pure uranium salts which are used again as feed for the calutrons. Elimination or reduction of corrosion of both piping and equipment is important not only for the prevention of equipment deterioration but to hold losses of uranium, which invariably accompany spills and leaks, to a minimum.

Many desirable chemical procedures which were worked out in the laboratory during the past three years have been used successfully on a production scale only after the development of new materials of construction and special fabrication techniques. The problem of choosing the

Manifold header showing combination of Pyrex glass and type 316 stainless steel piping, using ferrule joints. Glass gives visibility. Joints are covered with lead shields for safety against sudden leaks that may develop.

at Oak Ridge


proper materials of construction has been extremely difficult since it was necessary in many instances to proceed simultaneously with both the laboratory research work and the design and construction of equipment. The choice of materials was further complicated by procurement difficulties and the tight time schedule on which new construction and plant modifications had to be made.

The cycle of operations in the chemical plant requires equipment which will withstand a large variety of corrosive conditions, such as nitric acid solutions of various strengths which contain chloride ion, highly oxidized acidic and basic solutions, organic solvents containing nitric acid, and acid fumes at temperatures as high as 1,400 deg. F. Materials of construction which are used under these conditions include inorganic materials such as Pyrex glass, porcelain, stoneware, Alberene, Karbate, Transite, and glass lining; organic and plastic materials such as natural and synthetic rubber, Saran, Havg, Bisonite, Lucite, Teflon, Tygon, Silicones, and Koro-seal; and metals such as stainless steels, Hastelloys, tantalum, silver, gold, Monel, nickel, platinum, Inconel, lead and lead lining, copper, and aluminum.

PIPING

The complexity of the chemical operations carried on in the processing plants at Oak Ridge necessitated the use of almost every type of corrosion resistant piping known. In addition to standard materials such as stainless steel, many of the less common materials were tried and used on a greater scale than ever before. As a result, many new techniques of fabrication and installation were developed.

One of the standbys of the chemical process industries is stainless steel piping, and it was found again to be exceedingly versatile in its application. The main types of stainless steel used in process piping in the electromagnetic separation plant are types 302, 304, 316, 321, and 347. In the first installation, types 302 and 304



Solid bowl centrifuge installation with both Pyrex glass and stainless steel piping. Spot exhaust duct is of welded stainless steel construction


were used almost exclusively, and screwed fittings were widely used because of the ease of procurement and installation. Because of the difficulty of making many of the threaded joints tight, they were back-welded. This was a costly mistake because welding destroyed much of the corrosion resistance of the stainless steel and made any changes in the piping very difficult. Also, because of the high acidity and the chloride content of many of the process solutions, types 302 and 304 were attacked fairly rapidly. Consequently in all later installations type 316 stainless steel became standard for all stainless steel piping installations.

Type 316 is an 18-8 alloy containing about two percent of molybdenum which gives it considerable resistance to acid solutions containing small percentages of chlorides and to other corrosive agents. However, its austenitic structure tends to break down when it is heated in the range of 800 to 1,600 deg. F., and because of the resultant precipitation of chromium


carbides along the grain boundaries, it becomes subject to intergranular corrosion. Welding, of course, produces these conditions so that extreme care must be taken to use either a non-weld method of fabrication or to carefully heat treat all welded pieces. Because of the limited furnace size available at Oak Ridge, the latter technique is only practical for the field fabrication of small pieces such as special tees and reducers.

FERRULE FITTINGS

The best non-weld construction found involves the use of ferrule fittings. The ferrule is a stainless steel ring which fits snugly over the end of a piece of pipe or tubing. Machined in the inner surface of the ring are two grooves about 0.015 in. deep. By using a standard type of pipe expander the tube or pipe is rolled into these grooves, thus joining the two pieces very securely by cold working of the metal. A standard carbon steel slip-on flange is



Glass pipe arrangement in a process building. Ductwork is Type 316 stainless steel non-welded construction



Section of Saran pipe used for deionized water showing method of supporting valves and piping

installed behind the ferrule. Using a suitable gasket, the two pieces of pipe are bolted together. This method is especially adaptable to field fabrication since the ferrules can be rolled on while the pipe is in position. It is possible to use either special ferruled fittings or standard flanged fittings with ferruled pipe. Because standard cast stainless steel fittings are less expensive, they are used whenever possible; ferruled fittings are fabricated only when special fittings are required.

In installations where the use of screwed stainless steel fittings is desirable or necessary, tinning the threads of the pipe and fittings before assembly has been found to be effective in obtaining tight joints. If no nitric acid is present, the use of litharge-and-glycerine pipe dope likewise aids in the prevention of leaks.

In those cases where corrosion is less severe, type 321 and type 347 stainless steel piping is used. These steels are stabilized against carbide precipitation with titanium and columbium respectively, and standard welded construction can be used.

The second major piping material used is Pyrex glass pipe, which was discussed in detail in the July issue of *Chemical and Metallurgical Engineering* (pp. 112-115). Glass pipe is used where stainless steel is not adequate or where it is desirable for the interior of the piping to be visible. Prior to the installations at Oak Ridge, glass pipe had been used only to a very limited extent, and most of this was prefabricated by the Corning Glass Works. On large installations it is often impractical in the time available to freeze the design and to make the piping layouts accurately enough to use prefabricated glass piping. Field fabrication also simplifies maintenance and minor alteration problems since it is not necessary to carry in

stock very large numbers of special parts.

Primary considerations in the installation of glass pipe are the removal of all strains from it during fabrication and erection and the support and protection of the pipe after it is in place. The first requirement is accomplished by careful stress annealing of the pipe and fittings immediately after they are fabricated. Great pains are taken during the erection of the pipe to insure that no strains are introduced by misalignment or improper support. After installation, most of the glass piping is inspected for strains with a polariscope, and any strains that show up are removed with a portable electric annealing furnace. How well the stress relieving can be accomplished is indicated by the fact that all new glass pipe installations are tested hydrostatically at 100-lb. gage pressure. Most of the failures that occur during testing are at tees and other special fittings. Glass pipe should not be connected directly to equipment which vibrates considerably. Special flexible connections such as rubber or Tygon hose or flexible stainless steel tubing are used in these cases.

GLASS PIPE RESISTS SHOCK


The ability of glass pipe to resist shock when it is properly installed is remarkable. In the plant, very few cases of glass piping being broken during normal operations have occurred. However, care must be taken to protect the pipe wherever it runs in an exposed position near the floor. This can be done in most cases with a light angle-iron framework. Care must also be exercised to support all valves individually to prevent sudden stresses from being placed on the glass pipe while the valves are being operated.

Another type of special corrosion re-

sistant material which is used to a considerable extent for piping are the Hastelloy alloys. Both Hastelloy B and C are used, depending on the particular conditions. Hastelloy B is used for solutions containing high concentrations of hydrochloric or hypochlorous acid and other chlorides while "C" is used where oxidizing agents such as nitric acid or ferric chloride are present. It is believed that position welding of Hastelloy pipe in the field was utilized for the first time in these installations. This was done by using an electric arc with Hastelloy welding rod. Previously, most Hastelloy was fabricated using atomic hydrogen welding.

Many thousands of feet of Saran pipe have been installed to carry distilled and deionized water throughout some of the large chemical processing buildings. Because of its low mechanical strength, horizontal runs of Saran pipe have to be well supported and must be reasonably free of any strain or the pipe will fracture under pressure. The cutting and welding of Saran pipe can be done very simply in the field. Welding is accomplished by merely softening the two pipe ends on a hot plate and then pressing them together.

Porcelain pipe has been used extensively in places where solutions containing high concentrations of both nitric and hydrochloric acids are handled. Porcelain pipe, although it can also be field fabricated, is not as versatile as glass pipe in this respect. Its mechanical strength is somewhat greater and it does not have to be protected as well. For use at Oak Ridge, however, it has few advantages over Pyrex pipe and several major disadvantages such as its nontransparency, lower resistance to heat shock, and greater weight which makes supporting it more difficult. For the most part, horizontal runs of porcelain



316 stainless steel ductwork, stainless bolts and Tygon gaskets are used at joints. Drain leg removes condensed vapors

pipe are supported in plywood or metal angles rather than with standard pipe hangers.

GASKET MATERIALS

Obtaining suitable gasket materials was one of the major problems at the time the chemical plants were placed into operation. The use of ordinary material such as blue African asbestos, rubber, compounded asbestos, and metal gaskets was totally unsatisfactory for many applications where corrosion conditions were unusual. For use with glass-lined equipment and Pyrex glass pipe, the gasket material must not only resist attack from the fluid being handled but also be sufficiently elastic to make tight joints possible without setting up strains in the piping or equipment. The most satisfactory material found for this service has been Tygon of medium hardness. This material will satisfactorily withstand attack of most mineral acids and oxidizing agents up to a temperature of 160 deg. F. The material would be even more useful if it could be compounded with fine glass cloth which would provide added strength and tend to prevent creep under pressure.

For use with metal pipe and equipment, we have found Teflon (polytetrafluoroethylene) to be the most satisfactory gasket material. This material will withstand aqueous solutions of mineral acids and oxidizing agents in all concentrations as well as a wide variety of organic compounds. Its upper temperature limit for use as a gasket material is 300 deg. C. Because of their hardness, Teflon gaskets are used chiefly with metal joints. Even though its initial cost is relatively high, the over-all cost is not prohibitive since Teflon gaskets may be reused a number

of times. In special instances Teflon has been used satisfactorily in porcelain and Pyrex glass pipelines, although its use here is restricted because of the extreme care with which the piping must be aligned in order to obtain a tight but strain-free installation. Boiling the Teflon in water for 30 minutes just prior to its use in porcelain or glass pipelines has been found to aid materially in obtaining tight joints with lower flange pressures.

HIGH TEMPERATURE RESISTANCE

Many furnaces of the muffle type are used for incineration and calcining operations. These furnaces operate at temperatures ranging from 1,300 to 1,650 deg. F. in highly oxidizing atmospheres containing NO_2 , SO_2 , and small amounts of HCl . To facilitate the recovery of the incinerated material, metal furnace liners are used. Among the materials tried for this purpose have been types 309, 310, 316, and 347 stainless steels, Hastelloy C, and Inconel. Only those stainless steels containing a high percentage of nickel, such as types 309 and 310, have given reasonable service. Inconel liners have also stood up very well considering the extremely severe conditions.

HIGH-SPEED CENTRIFUGES


Large numbers of Model 16 Sharples super centrifuges are used in the chemical plants for making sharp separations of immiscible liquids and of fine solids from highly corrosive solutions. These centrifuges consist of a small diameter cylindrical bowl which turns at speeds up to 15,000 rpm. mounted in a cost supporting frame. Because of the early delivery dates required, it was not possible to ob-

tain centrifuges designed for use under severe corrosive conditions and standard centrifuges with cast iron frames were installed. It was found that a small amount of spray from the discharge of the centrifuge and leakage around the feed nozzle corroded the outer casting considerably. To combat this, a thin liner of sheet stainless steel was designed which could be slipped inside the casting and joined to the bearing assembly at the bottom to give a watertight enclosure. A trough around the top of the lining prevents solutions from leaking down between the casting and the liner. Other modifications to the centrifuges include replacements of the bronze drag bushing with one fabricated of carbon impregnated with paraffin and substitution of a stainless steel ferrule and Tygon ring for the brass bullet catcher assembly. These changes have made the standard centrifuges practical for use with many corrosive solutions.


TANKS AND VESSELS

The majority of the tanks and vessels are fabricated of some type of stainless steel or are of glass-lined construction. For mild corrosive conditions or where no chlorides are present, welded tanks using type 321 or 347 stainless steel have proved entirely satisfactory. For handling acidic solutions containing appreciable amounts of chlorides, tanks constructed of type 316 stainless steel are preferred. However, these tanks must be properly heat treated to preserve the corrosive resistance of the welded parts. It has been found, from bitter experience, that the quality of the welds on equipment which is to be heat treated must be very high as any pinholes or slag inclusions will generally be exposed by the annealing and pickling procedures. Experience with unannealed tanks made of type 302 or 304 stainless steel has shown that the region around the welds will be rapidly attacked by copper, nickel, and iron salts in their high valence or oxidized state even in alkaline solutions.

With equipment where annealing is not practical because of warpage or other reasons, adequate resistance to corrosion under many conditions is obtained by giving the equipment a high polish. It is probable that where there are pits or imperfections in the metal a concentration cell is set up with the metal surrounding the cell becoming cathodic. This cell becomes extremely intense in good electrolytes, since the area of the effective cathode becomes very large as compared to the anodic pit. As a result the penetration may be much greater than would be the case in an unannealed area where carbides are present. That this is the case is borne out by the fact that the use of a commercial 4B or equivalent finish on unannealed, type 316 stainless steel equipment has in some instances given better service than equipment



Stainless steel filter press covers and stainless floor. Press is mounted on stainless steel covered pads. Special thimbles are used where piping runs through floor



Hard rubber centrifugal pump, glass piping and porcelain valves. Valves are rigidly supported to protect pipe from excessive strains

which has been annealed but not polished. Both annealing and polishing is, of course, preferable but the cost of this procedure is usually prohibitive.

For large volumes, glass-lined equipment was found to be the most satisfactory material for holding hot solutions containing high concentrations of both nitric and hydrochloric acids. Of course, glass-lined tanks and reactors must be well protected against mechanical shock and abrasion, but aside from this, the chief points of weakness are the plugs in the enamel itself. Minute imperfections in the lining are repaired at the factory by the insertion of plugs of gold or ceramic material similar to the way a dentist fills a tooth. This same method is generally used for the repair of failures in glass-lined equipment in the field. Under severe corrosive conditions, however, this method of repair has proved highly unsatisfactory because of re-

current failures at the plugs. Maintenance of glass-lined equipment was greatly reduced through the development and use of fracture plugs. In this method of repair a hole is drilled entirely through the glass-lined vessel at the point of failure, and a fracture plug is inserted in the hole. The head of the fracture plug is designed in such a manner that a line contact is provided on a gasket which in turn bears against the glass lining of the tank. The stem of the fracture plug which extends through the side of the tank is threaded and a bolt is used to compress the gasket between the head of the fracture plug and the wall of the tank.

Some ceramic vessels and towers have been used where corrosion conditions are unusually severe. As in the case of glass piping, installation and maintenance of ceramic equipment should be done by specially trained crews. In these installations

care must be taken to avoid setting up strains in the equipment, and the installation must be well protected from mechanical shock and vibration. In some cases minor failures in ceramic equipment have been effectively repaired by coating the cracked sections with alternate layers of Permanite cement and thin glass cloth.

TANTALUM-LINED EQUIPMENT

One step in the chemical process involves the evaporation of a considerable volume of solution containing as high as 30 percent of nitric acid and up to 5 percent of hydrochloric acid. The only suitable material of construction found for evaporators under these conditions is tantalum, which is virtually unattacked by any mixture of these two acids. These evaporators are constructed with liners of tantalum, 0.013 in. thick, backed by heavy steel sheets. Although the tensile strength of tantalum sheet is high, its shear strength is much less so that considerable care must be exercised in the mechanical removal of scale from the evaporator parts. Chemical cleaning procedures are used for this operation whenever possible.

PAINTS AND PLASTIC COATINGS

Various paints and plastics such as Tygon, Amercoat, Vita-Var, Bisonite, and Silicones have been used as protective coatings. For application on metal surfaces the main consideration has been found to be the careful preparation of the

Comparison of Estimated Costs—Typical Piping Installations

Type of Material and Method of Installation	Material	Labor	Total Cost
Screwed 316 stainless steel pipe, fittings, valves, and flanges	45	55	100
Flanged 316 stainless steel fittings and valves, stainless steel pipe and screwed flanges	86	68	154
Ferrule type 316 stainless steel fittings, standard pipe flanged valves .	98	111	209
Ferrule type fittings on pipe only. Flanged valves and standard flanged fittings	84	86	170
Glass pipe and fittings with flanged glass lined, porcelain, or 316 stainless steel valves	39	122	161
Porcelain pipe and fittings, porcelain or 316 stainless steel flanged valves	40	103	143
Saran pipe, fittings and screwed 316 stainless steel valves	72	67	80
Wrought steel pipe with malleable iron screwed fittings, standard brass screwed valves	4	48	52

Note: All figures are based on the cost of 316 stainless steel screwed installations and labor costs were computed on the basis of \$2.70 per hr.


surface to be coated by removal of dirt and grease and roughening by sandblasting. Silicone resins are promising because of the tenacious bond they form, even with polished surfaces. The use of plastic films or of oil base paints has been generally unsatisfactory in combating severe corrosion. Painted or coated ductwork installed for use in handling corrosive vapors has been attacked because of breaks in the bond with the metal. Factory applied linings of rubber, Tygon, and Bisonite for tanks and large fans have given satisfactory service in most installations because of their greater thickness and continuity.

HOODS AND DUCTWORK


Hoods and ductwork which carry acid vapors and other corrosive fumes are in most instances constructed of stabilized stainless steel, using welded construction where these metals are not attacked. Otherwise, type 316 stainless steel fabricated without welds, Tygon and rubber lined steel, chemical stoneware, and Alberene are used. Non-welded stainless steel construction, which is relatively expensive, consists of using flanged joints with Tygon gaskets. All ductwork installations are provided with drains from low points in the system which serve to remove any liquids which condense out. Hoods fabricated from Transite and periodically painted with Tygon paint resist the attack of mild corrosive fumes in analytical laboratories. For the severe attack of combined nitric acid and hydrochloric acid fumes, hoods are constructed of Alberene or stainless steel. For extremely corrosive service with hot condensing acid fumes containing fluorides, hoods are made of Karbate.

PUMPS


The materials most used for the construction of pumps are stainless steels and high-silicon irons, although Pyrex glass and rubber pumps are also used. The major problem encountered in the maintenance of pumps handling corrosive liquids is maintaining a relatively tight seal at the packing gland. The use of Durasel type packing glands has proved satisfactory on pumps handling solutions which do not contain abrasive solids. A packing developed at the electromagnetic separation plant which has proved satisfactory for use in standard packing glands which are exposed to severe corrosive conditions is shredded Teflon mixed with a lubricant. It is not necessary for the lubricant to resist attack of the solutions being pumped since it acts primarily as a carrier for the Teflon chips. In pumps handling abrasive solids the use of Teflon spacers in the packing gland assembly is advantageous. These spacers are cut in the shape of washers and fit snugly around the pump shaft. In this way they form a partial



Typical ferrule joint used for type 316 stainless steel piping



Fracture plug used for repairing glass-lined equipment



Cutaway view of typical stainless steel floor showing method of supporting it and way it can be built around various equipment

seal around the shaft which helps prevent solids from entering the packing gland. Since Teflon is resistant to most inorganic acids and many organic materials, it approaches being an universal packing material for corrosive conditions.

CORROSION RESISTANT FLOORS

In areas where there is danger of floor contamination and where losses of uranium must be held at an absolute minimum special materials of construction for floors were used. Where there is no trucking or heavy traffic, such as in laboratories, Tygon flooring and heavy linoleum have proved satisfactory. Both are sufficiently resilient to reduce foot tiredness of operators who must stand on it for extended periods of time. The Tygon flooring in addition is not affected by many chemicals which attack asphalt tile or linoleum.

For production areas where the service is more severe continuous metal-clad floors

are most effective in preventing losses. The problem of installing welded stainless steel floors which do not buckle and feel firm to the tread is solved by welding the stainless plate to backing bars imbedded in the concrete flooring. Sixteen-gage stainless steel with a 2B commercial finish is used for most installations. The backing bars are 2-in. by $\frac{1}{2}$ -in. carbon steel rods installed in the concrete with a maximum spacing of 24 in. One-quarter inch half-holes punched along the edge of the sheet at 6 in. intervals are used to plug weld the sheet to the backing bars. An $\frac{1}{4}$ -in. butt weld can then be made between the sheets and the welds ground smooth without danger of buckling the stainless steel. The areas covered with stainless steel are provided with curbing and thresholds which retain any major liquid spills within the area. All curbing, equipment foundations, and pipe thimbles are provided with cove bases which aid in cleaning the floor.

Chemical and Heat Resistance of GASKET MATERIALS

Elsewhere in this special Materials of Construction issue there appears a lengthy compilation of data on the corrosion resistance of materials for general service. Gaskets, however, offer special problems in materials selection and must therefore be treated separately. Of the many factors which enter into the choosing of a gasket material, the two that are discussed here, heat and corrosion, are certainly among the most important.—Editors

SELECTING a gasket demands two decisions. What type of construction and what materials? The service factors which govern these decisions fall under two general headings, mechanical features of the joint and conditions of operation. These various factors are named in the accompanying outline. All have a direct bearing on the selection, and a change in any one can change the optimum construction or optimum materials of the gasket.

To give each of these factors the amount of attention it deserves would run to considerable length. Therefore, the scope of this article is limited; it is intended only (1) to skim briefly over the governing factors that are not going to be analyzed so there will be no misunderstanding about the nature and seriousness of the problems that remain; (2) to enumerate the gasket constructions in general use and to touch briefly on their applications; (3) to enu-

erate the ordinary gasket materials; and (4) to give detailed information on the two factors this article is really concerned with, namely, the heat and chemical resistance of the ordinary gasket materials. Thus, the only major contribution this article presumes to make to the literature on gaskets is the compilation of data on gasket materials versus heat and corrosion; the rest is offered more or less as orientation.

GOVERNING FACTORS

There are five features of the flanged assembly and four conditions of operation that influence gasket selection. This discussion will only name them and give examples of a few of the many ways they may limit the choice. The bolting available in an assembly sets the upper limit of gasket hardness since it determines the force that is available for seating the gasket or maintaining the seal at high fluid pressures. The material of which the flange is made has the same effect to the extent that some materials, chemical stoneware or glass-lined steel, for example, do not have the strength or abrasion resistance to withstand strong compression against a hard gasket. The surface finish of the flange facing also affects the permissible hardness of the gasket; both hard and soft gaskets are used with the smooth flat machine finish, but a soft non-metallic gasket is preferred for faces which are either roughened by service or deliberately serrated. The particular design of the flange face may best lend itself to, or even demand, a particular type of gasket. Thus,

non-metallic gaskets $\frac{1}{8}$ in. thick or more give best results on the straight faced cast iron flanges common on low pressure lines; whereas the ring type joint, with its special shaped groove, requires the use of an all-metal gasket of special cross section. The dimensions of the flange face restrict the dimensions of the gasket of course, and since all gasket designs cannot be fabricated in all widths, diameters and shapes, the dimensions and shape of the flange contact face are further limitations on gasket choice.

Of the four operating factors which affect gasket selection, temperature and corrosiveness of the confined fluid are of much greater importance than pressure and the operating cycle. High pressures generally have the effect of requiring the use of a gasket which will fit one or another of the special flange face designs. If the operating cycle involves frequent alternation of high and low temperatures or alternate filling and emptying of the lines, it may be necessary to adjust the choice of gasket to suit these conditions. The two remaining conditions of operation which affect gasket selection, temperature and corrosion, are extremely important and will be discussed later in considerable detail.

GASKET CONSTRUCTIONS

All of the ordinary constructions used in the fabrication of non-metallic, metal-clad and all-metal gaskets are shown in Fig. 1. Leather, paper, cork compounds, rubber, plastics, compressed asbestos sheet gaskets, Fig. 1 (a), and plain or treated thick woven asbestos gaskets, Fig. 1 (c), are generally satisfactory for ordinary service at low pressures and temperatures, the woven asbestos type being particularly suitable for rough, pitted or uneven surfaces and glass or glass-lined flanges. Round or special shaped gaskets, Fig. 1(b), molded from soft materials are useful in certain applications; round section metal gaskets have given excellent service in high vacuum installations. The plain corrugated metal

Outline of Service Factors Affecting Gasket Selection

- I. Mechanical Features of Flange
 - A. Bolting
 - B. Material
 - C. Surface finish of flange face (smooth, pitted, serrated, etc.)
 - D. Design of flange face (flat, raised, tongue-and-groove, etc.)
 - E. Dimensions
- II. Operating Conditions
 - A. Pressure
 - B. Cycle
 - C. Temperature
 - D. Corrosion

gaskets, Fig. 1(f), generally installed with a coating of gasket paste, and the asbestos-inlaid corrugated metal gaskets, Fig. 1(g) or (h), are used for relatively low pressures, the latter type being particularly suitable for rough or pitted flanges. The spirally wound metal-asbestos construction, Fig. 1(p), is suitable for all flange conditions, requires relatively light bolting, and is the most resilient of the metallic gasket designs. The metal jacketed asbestos gaskets, Fig. 1(d), are used for handhole openings and most small diameter closures of narrow widths. Fig. 1(e) is the standard double-jacketed metal-asbestos gasket for pipe flanges and heat exchangers, and Fig. 1(i) is a modification of this design, having improved resilience and requiring less bolting. The French type construction, Fig. 1(l) is used for valve bonnets, cylinder heads and vacuum service. A modification of this gasket using thick woven asbestos or rubber as a filler is finding extensive service in glass or glass-lined equipment. The all-metal gasket, Figs. 1(j) and (o), have to a great extent replaced plain, flat metal gaskets because of their lower bolting requirements. The ring joint gasket, Fig. 1(n), of oval or octagonal cross-section for use in ring type flange faces have found almost universal acceptance in the petroleum industry for all temperatures and pressures.

GASKET MATERIALS

All of the gasket materials ordinarily used in the chemical industry will be found either in the column headings of the long table which follows, or in the discussion below. This is the basic group of metallic

and nonmetallic substances that industry has adopted for almost all its gasketing in corrosive services. Those applications not handled by one or another of this group require the use of gaskets of special composition, unless a welded or ungasketed joint will be satisfactory.

HEAT AND CORROSION IN GENERAL

It might be assumed that a material suitably resistant in the form of a heavy reaction vessel would also be satisfactory as a gasket for the same conditions. Unfortunately, this is too often not the case. In the first place many materials do not lend themselves readily to fabrication in the form of gaskets, nor do they possess those basic physical characteristics requisite in every gasket design. The alloy cast irons, for example, are comparatively inexpensive and are ideal for some services, but they are too hard and brittle to be made into a satisfactory gasket. Then too, an all-metal or a metal-jacketed gasket is usually thin, highly stressed, and used in a location where turbulence is most likely to occur; a corrosive agent normally considered to have a low rate of attack may, when aided by the highly stressed condition of the metal and by the constant removal of any protective film by the turbulence at the joint, quickly eat through a gasket unless the material is almost perfectly resistant.



















Thus, the selection of a gasket material suitably resistant to corrosive media or to high temperature involves a number of considerations that are usually inconsequential in selecting materials for other equipment. In order to predict with any

degree of certainty the probable life of a gasket in corrosive or high temperature service the following factors must be carefully weighed. These are the opportunities for error. And at this time it should be stated emphatically that no compilation of data such as the table on pp. 106-109 could possibly take into account all of these variables; and to that extent the table is incomplete and dangerous. To select a gasket from the table without giving considerable thought to these other untabulated factors is only asking for trouble. As evidence of the danger observe in the table the many instances where inability to define all these service details has led different manufacturers to make different recommendations.

1. *Concentration of Corrosive Agents*—Concentration of the corrosive agents may have a decided effect upon the selection of a resistant gasket material. Dilute solutions are not necessarily less corrosive than those of full strength, and the reverse is often the case. Probably the most familiar example of this is the action of sulphuric acid on iron; concentrations over 90 per cent acid may be handled by iron without much difficulty, but below this concentration the rate of attack will increase rapidly with an increase in dilution.

2. *Purity of Corrosive Agent*—By purity, in this instance, is meant not concentration, but the absence of contaminating amounts of other corrosive compounds. For example, dissolved oxygen in otherwise chemically pure water can cause rapid deterioration of high-temperature steam generating equipment, and provisions are made to assure its removal from the feedwater. Another example would be the corrosive

Fig. 1—Gasket constructions commonly used in the chemical process industries

 <p>(a) Plain Washer or Ring</p> <p>Can be made from metal or any sheet gasket material</p>	 <p>(b) Plain Rings</p> <p>Usually made from metal machined all over but can be made of rubber or rubber-asbestos compounds</p>	 <p>(c) Asbestos-Metallic Cloth</p> <p>Folded and molded to any shape and thickness</p>	 <p>(d) Single Jacketed Metal-Asbestos</p> <p>Usually copper but can be made of other materials; asbestos paper core</p>	 <p>(e) Double Jacketed Metal-Asbestos</p> <p>Otherwise same as (d)</p>	 <p>(f) Corrugated Metal</p> <p>Can be made from any metal; with various groove gages</p>
 <p>(g) Corrugated Metal-Asbestos</p> <p>Same as (f) except corrugations filled with asbestos cord</p>	 <p>(h) Metal-Asbestos</p> <p>Same as (g) except contact surfaces graphited</p>	 <p>(i) Corrugated Jacketed Metal-Asbestos</p> <p>Similar to (e) except metal is corrugated</p>	 <p>(j) Profiled Metal</p> <p>Can be made from any metal; machined all over; concentric profiling</p>	 <p>(k) Profiled Metal-Asbestos</p> <p>Same as (j) except grooves filled with asbestos cord</p>	 <p>(l) Metal-Asbestos</p> <p>(French style) Same as (d) except opening at outer edge</p>
 <p>(m) Metal-Asbestos</p> <p>(French style) Same as (l) except opening at inner edge</p>	 <p>(n) Plain Rings</p> <p>Any solid metal</p>	 <p>(o) Flared Ring</p> <p>Same as (b) but usually made of metal with bearing surfaces ground to smooth finish</p>	 <p>(p) Metal-Asbestos</p> <p>Alternate layers of metal and asbestos wound in continuous strips to desired size</p>	 <p>(q) Valve-Disk Gasket</p> <p>Metal shell goes against valve seat</p>	 <p>(r) Serrated Metal</p> <p>Any metal; machined all over; concentric serrations</p>

attack by compounds that are derivatives of an acid; in the pure state these compounds may be relatively inert, but if contaminated by any "carry-over" of free acid they must be handled with this in mind.

3. Temperature—In addition to its effects upon the mechanical properties of the gasket, the temperature of the corrosive agent will have a marked influence upon the rate of attack, particularly if the increase in temperature results in a boiling action that might tend to hasten the removal of protective coatings.

Gasket constructions, as well as gasket materials, have their temperature limitations. The non-metallic gaskets and those incorporating low-melting metals are, with a few exceptions, limited to service temperatures below 250 deg. F. The semi-metallic constructions, comprising gaskets made up of asbestos partially or completely clad with metal, may be used at temperatures up to 850 deg. F. Above 850 deg. only all metal gaskets are satisfactory.

4. Location of the Gaskets—Gaskets at or above the solution level may be more subject to attack than those at a point below the surface. Likewise, gaskets in horizontal runs of pipe that are periodically emptied or only partially filled in service, generally suffer more severe corrosion than those in lines that are readily drained or are kept full at all times.

In selection of a gasket for a highly corrosive service, it is often advisable to dimension the gasket as close as possible to the bore of the pipe or vessel to eliminate pockets and reduce local turbulence.

5. Type of Gasket Construction—The effect of this particular factor may not readily be defined and reduced to a simple set rule. Generally speaking, the expected rate of corrosion will govern the selection of the type of gasket. A gasket construction composed of a soft filler jacketed with a thin sheet of metal not perfectly resistant to attack might fail in a service where a solid design of the same metal would have a reasonable life.

Materials abnormally subject to stress-corrosion should not be used in a gasket construction that relies upon highly localized stressing to form the seal.

6. Normal Frequency With Which Joint Will be Opened—Here again the expected rate of corrosion should govern the selection of the material. If a closure is opened for inspection at frequent intervals any severe corrosion of the gasket would be readily noted and a new gasket could be substituted. In service of this nature a less resistant and possibly less expensive material might be suitable. However, for trouble-free operation of flanged joints that are to be in service for prolonged periods it is generally advisable to use a gasket completely resistant to corrosion, if such is available.

7. Relative Cost of Materials—Gener-

ally speaking, the cost of gaskets is so small that it is poor economy to use a material that may incur frequent and high labor expenses for necessary but otherwise avoidable replacement. However, if the joint is normally opened periodically for inspection, as was discussed in the previous paragraph, the labor charge would be the same, regardless of the gasket installed, and a less resistant material might be practical, provided of course that corrosion products in the process fluid were not objectionable from the contamination standpoint.

8. Scrap Value of Gasket Materials—In many instances the selection of a gasket material for a certain service may be reduced to a choice between an only partially resistant, but standard material, and a totally resistant, but initially expensive rare metal. It should be remembered that a portion of the cost of a rare metal gasket may be recovered in the scrap value of the material, which, together with the saving resulting from the increased service, may bring the total expense to a figure comparable with or even lower than that of the initially less expensive gasket.

HEAT AND CORROSION VS. METALLIC GASKETS

Lead—Lead shows excellent resistance to the action of many corrosive agents and finds wide application as a gasket in the chemical and allied industries where temperatures do not exceed that of boiling water, and the solutions handled are close to the neutral point. For higher temperature service up to 400 deg. F., the closure must be designed to prevent excessive creep of the gaskets.

Tin—Tin is useful where extremely pure neutral solutions and foods are handled. It is strongly attacked by acids and alkalis. Under some conditions it may be used at temperatures up to 400 deg. F., but is generally not recommended for service over 200 deg. F.

Aluminum—Pure aluminum is widely used as a gasket material, and its resistance to corrosion is due to the presence of a protective film formed either by oxidation or by the action of the aluminum with the corrosive fluid.

The protective coatings are attacked by strong acids and alkalis, but their resistance is sufficient to allow the use of aluminum in a variety of services. Because of its protective oxide coating, aluminum may be used at temperatures up to 800 deg. F. Its resistance to the hot sulphur-bearing gases encountered in the petroleum industry accounts for its popularity in this field.

Copper—Copper has excellent corrosion resistance and for this reason is, next to iron, the most generally used gasket material. The oxidizing acids, wet ammonia, and some strongly corrosive substances,

such as chlorine, readily attack copper, as do sulphur and the sulphur compounds.

Copper is not recommended for gasket service at temperatures above 600 deg. F. This metal, unless it be deoxidized or oxygen-free, is also subject to embrittlement by exposure to hydrogen, carbon monoxide, and similar reducing gases at elevated temperatures.

Copper is not generally used as a gasket material in steel flanges if electrolysis can take place.

Brass—The common brasses act very much like copper in their resistance to corrosion. The high zinc alloys are subject to dezincification and in some instances to corrosion cracking, but proper selection of the alloy will guard against the former, and the latter may be eliminated by close fabricating controls.

Monel—Monel metal, because of its resistance to most acids, alkalis and other corrosive agents, both at normal and elevated temperatures, may be considered as one of the most versatile gasket materials.

Monel should not be used with the strongly oxidizing acids, such as nitric, nor with strong concentrations of hydrochloric acid. However, it is excellent for anhydrous hydrofluoric acid at elevated temperatures. Monel is subject to embrittlement when exposed to sulphur-bearing gases above 500 deg. F.

Monel may be used at temperatures up to 1,500 deg. F., under certain conditions. For steam service the upper limit appears to be approximately 800 deg. F., particularly for gaskets that might be subjected to stress-corrosion.

Nickel—Nickel does not have the all-around excellent resistance of Monel, but it does have definite advantages such as, for example, the ability to handle chlorine at temperatures up to 950 deg. F.

Nickel is subject to embrittlement by steam at temperatures above 800 deg. F., particularly if under stress. In oxidizing atmospheres this metal is useful up to 1,400 deg. F., and under controlled conditions may be used even higher.

Silver—Silver is resistant to alkalis, organic acids, and certain concentrations of hydrochloric and other mineral acids. Since its resistance to corrosion does not depend upon a protective oxide film, it may be used where such a film would be destroyed.

Wet corrosive gases, such as hydrogen sulphide, and the chlorine group, attack silver readily.

Silver may be used up to 1,200 deg. F., but must be reinforced at elevated temperatures to restrict creep of the material.

Platinum—Because of its initially high cost, platinum is used as a gasket metal only when no other material is available that will resist the corrosive action present. Platinum's low oxidation rate allows its use in ordinary atmospheres at temperatures up to 2,300 deg. F.

Ingot Iron and Low Carbon Steel (SAE 1010 to 1020)—Iron and low carbon steels are not suitable for handling crude acids or aqueous solutions of salts in the neutral or acid range. A high rate of failure may be expected for these materials used even in hot water service if the metal is highly stressed. Concentrated acids and most alkalis have little or no action on these materials, however, and iron and steel gaskets are regularly used for such services.

The upper temperature limit for iron gaskets is approximately 1,000 deg. F., particularly if the conditions are oxidizing. At this temperature steam will break down in contact with the iron and the rate of oxidation increases rapidly. Reducing gases carrying sulphur are strongly corrosive at temperatures above 600 deg. F.

Type 502 Chrome Steel with Molybdenum (4-6 Cr, 5 Mo)—This alloy, although not widely used outside of the oil industry, is particularly suitable for installations requiring resistance to oxidation at temperatures up to 1,200 deg. F. Its general corrosion resistance is somewhat better than iron. Its use at present is confined solely to ring-joint gaskets.

Type 410 Chrome Steel (11-14 Cr)—This alloy, because of its ability to resist oxidation at temperatures up to 1,300 deg. F., is used to some extent for certain specific gasket installations, but the 18-8 type stainless steels are generally more readily available, and in most instances would be preferable.

Type 304 Stainless Steel (Low Carbon 18-8)—This alloy is the standard stainless type chromium-nickel steel and it is used most extensively for gaskets under corrosive conditions.

Except for their inability to resist the attack of sulphuric acid and the halogens, particularly when wet, the 18-8 type stainless steels may be used in many services that cannot be handled by any other material.

The Type 304 alloy is made susceptible to intergranular corrosion only when it has been exposed to temperatures from 800 to 1,500 deg. F. for a length of time sufficient to allow the material to become unstable. In this unstable condition much of the corrosion resistance is lost and in addition the metal may become brittle. If the service in which the stainless steel is to be used involves a temperature above 800 deg. F., it is advisable to provide a gasket fabricated from a stabilized alloy, such as Type 347.

Type 347 Stainless Steel (Low Carbon 18-8 Cb Stabilized)—Stabilization of the straight 18-8 stainless steel by the addition of columbium raises the temperature at which the material can be used in continuous service. Since intergranular corrosion does not take place in the stabilized alloy, it may be used safely up to 1,700 deg. F.

The addition of the stabilizing agent does not result in any appreciable increase in the resistance of the alloy to corrosion as compared to the Type 304, and its use as a gasket material is generally limited to services above 800 deg. F. where the unstabilized alloy would not be suitable.

Type 316 Stainless Steel (Low Carbon 18-8 with Mo)—The addition of approximately 2 percent of molybdenum to the straight 18-8 alloy increases its strength at elevated temperatures and results in somewhat improved corrosion resistance. This material is subject to intergranular corrosion if exposed to temperatures within the critical range of 800 to 1,500 deg. F.

HEAT AND CORROSION VS. NON-METALLIC GASKETS

White Fiber Asbestos (Chrysotile)—The common white asbestos is a mineral consisting essentially of magnesium silicate combined with approximately 14 percent water of crystallization. In the pure form asbestos fiber has little strength, and for most gasket applications must be reinforced either with fine metal wire, if heat resistance is of prime importance, or with cotton for lower temperature service where softness is a factor.

Asbestos will retain most of its inherent strength up to about 900 deg. F., or just below a dull red heat. The loss of strength above 900 deg. F. is due to a gradual driving out of the water of crystallization. As the temperature goes above 900 deg. F., the rate of loss of strength increases rapidly, becoming almost instantaneous at 1,300 deg. F. Asbestos from which the water of crystallization has been driven by heating above 900 deg. F. may be reduced to a powder by merely rubbing the fibers between the fingers.

In the fabrication of gaskets, asbestos is used in two relatively pure forms, woven and as millboard or paper. In the woven form the asbestos is generally reinforced with both brass wire and cotton, and since the heat resistance is limited by the cotton content, plain woven asbestos gaskets are seldom used at temperatures above 300-400 deg. F., particularly if there is any considerable pressure to be held. Furthermore, since woven asbestos is very porous, gaskets of this type are usually impregnated with rubber or plastic compounds. Impregnation does not improve the heat resistance, as most of the compounds used are organic in nature and will themselves change in characteristics in the region of 200-400 deg. F. Asbestos millboard and paper are usually made up of relatively pure asbestos fibers bound with starch or sulphites. In gasket manufacture, millboard and paper are used as soft fillers for metal-jacketed designs, and allow use of these gaskets to temperatures up to 850 deg. F.

White asbestos has little resistance to the action of strong mineral acids. It may be used with weak acid and with most alkali solutions. This asbestos is seldom used as a gasket unless impregnated with rubber or sometimes a plastic, in which case the corrosion resistance of the gasket will depend upon the resistance of the impregnant as well as the asbestos.

Blue Fiber Asbestos (Crocidolite)—This material is widely used in the woven cloth form as an acid-resistant gasket for low pressures and relatively low temperatures. The temperature limit for blue asbestos is somewhat lower than for the white variety, and it is seldom used above 500 deg. F., unless reinforced or employed as an inlay in corrugated metal gaskets.

Rubber Sheetting from Nature Base Rubber—There are available numerous forms of rubber sheet material for gasket purposes. These forms vary in their rubber content and in the nature of their compounding. They have the general corrosion resistance of natural rubber compounds to the action of various chemicals, but are readily attacked by oils and petroleum solvents.

Rubber compounds will harden and become brittle by prolonged exposure to heat and are not to be recommended for gasket service at temperatures much above that of boiling water.

Synthetic Rubbers and Plastics—There are available gasket sheet materials compounded from innumerable synthetic rubber and plastic bases. Depending upon the base and the compounding used, a material suitable for almost every corrosive service may be had. These sheet materials are in most instances limited to low-temperature service and only a few may be used above 250 deg. F., which appears to be the useful limit. The recently developed silicone compounds are said to be useful as high as 575 deg. F., but because of their scarcity their current applications have been rather limited.

Asbestos Composition Sheet—This most widely used gasket sheet material is actually a rubber compound with a high percentage of asbestos fiber as filler. The resistance of these asbestos composition sheets to corrosive agents and to temperature are determined by the nature of both the asbestos and the rubber compound. For most services the natural or reclaimed rubber base is used; for oil and certain chemical services, special bases must be specified.

For continuous service, asbestos composition sheet is used at temperatures up to 850 deg. F. Rubber base materials used at high temperatures become very hard and brittle and they cannot be re-used.

Chemical Resistance of Gasket Materials

Resistance Ratings ¹ A = Good F = Fair C = Depends on conditions X = Unsuitable	Source of data ¹⁰	Metals										Asbestos						Rubber										Miscellaneous																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
		Metals										Asbestos						Rubber										Miscellaneous																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
												Comp., woven, ⁴ or woven ⁴		White (Buna-S) ⁵		White (neoprene) ⁵		Blue (butyl) ⁵		Blue (incaprene) ⁵		Blue (butyl) ⁵		GR-S	GR-S	GR-S	Neoprene	Neoprene	Buna-N	Buna-N	Butyl	Thiokol	Silicone ⁶	Glass fabric and silicone elastomer ⁷	Glass fabric and synthetic rubber ⁷	Cork composition	Plant-fiber sheet	Plant-fiber sheet	Teflon ⁸																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
		Lead	Copper	Aluminum	Nickel	Iron and Steel	Stainless 304	Stainless 316	Stainless 347	Others with good resistance ¹	G	G	G	G	G	J	J	U	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P

Chemical Resistance of Gasket Materials (Continued)

Resistance Ratings ¹ A = Good F = Fair C = Depends on conditions X = Unsuitable	Source of data ¹⁰	Metals										Asbestos				Rubber						Miscellaneous																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
		Lead	Copper	Aluminum	Monel	Nickel	Iron and Steel	Stainless 304	Stainless 316	Stainless 317	Others with good resistance ³	J	U	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P	P

DIRECTORY OF MATERIALS

For the Construction of Chemical Equipment

This portion of *Chemical Engineering's* Twelfth Report on Materials of Construction provides a quick means of identifying materials available for the construction of chemical plant equipment. Generous cooperation on the part of the manufacturers has made it possible to include nearly 600 items. Materials are arranged alphabetically within each of seven classes of material. Numbers in the first column are used to identify materials appearing in the Chemical Resistance table which follows this Directory.

No.	Material	Manufacturer	Essential Nominal Chemical Composition, Percent	Forms Available	Primarily for
METALS & ALLOYS					
1	Acipco Stainless	Amer. Cast Iron Pipe Co., Birmingham, Ala.	Various standard stainless steels; see Nos. 275-360	C, T (centrifugal)	
2	Admiralty	Generally available ¹	70 Cu; 1 Sn; 29 Zn	CR, D, E, P, S, T, R, W	C
3	Admiralty, Antimonial	Chase Brass & Copper Co., Waterbury, Conn.	71 Cu; 27.95 Zn; 1 Sn; 0.05 Sb	T, W	C
4	Admiralty, Arsenical	Amer. Brass Co., Waterbury, Conn.	70 Cu; 28.95 Zn; 1 Sn; 0.05 As	T	C
5	Admiralty, Phosphorized	Secoville Mfg. Co., Waterbury, Conn.	70 Cu; 29 Zn; 1 Sn; 0.03 P		C
6	Admic	Secoville Mfg. Co., Waterbury, Conn.	70 Cu; 29 Ni; 1 Sn	S	C, A
7	Advance	Driver Harris Co., Harrison, N. J.	55 Cu; 45 Ni	B, CR, HR, P, R, S, W	H
8	Alchrome 3	Wilbur B. Driver Co., Newark, N. J.	Fe; 20 Cr; 3 Al	R, W	H
9	Alchrome 6	Wilbur B. Driver Co., Newark, N. J.	Fe; 20 Cr; 6 Al	R, W	H
10	Alcoa Alclad 35	Aluminum Co. of Amer., Pittsburgh, Pa.	Surface layer of Al alloy which is anodic to core and therefore protects it electrolytically.	CR, HR, P, S, T	C
11	Alcoa Alloy 43	Aluminum Co. of Amer., Pittsburgh, Pa.	Al; 5 Si	C	C
12	Alcoa Alloy B214	Aluminum Co. of Amer., Pittsburgh, Pa.	Al; 1.8 Si; 3.8 Mg	C	C
13	Alcoa Alloy 356-T4	Aluminum Co. of Amer., Pittsburgh, Pa.	Al; 7 Si	C	C
14	Alcoa 25	Aluminum Co. of Amer., Pittsburgh, Pa.	99 min. Al	B, CR, HR, D, E, F, P, S, R, T, W	C
15	Alcoa 35	Aluminum Co. of Amer., Pittsburgh, Pa.	Al; 1.2 Mn	CR, HR, D, E, P, S, T	C
16	Alcoa 525	Aluminum Co. of Amer., Pittsburgh, Pa.	Al; 2.5 Mg; 0.25 Cr	D, E, P, S, T	C
17	Alcoa 615	Aluminum Co. of Amer., Pittsburgh, Pa.	Al; 1 Mg; 0.6 Si; 0.25 Cr; 0.25 Cu	B, CR, HR, D, E, F, P, S, R, T, W	C
18	Allegheny Metal	Allegheny Ludlum Steel Corp., Brackenridge, Pa.	Various standard stainless steels; see Nos. 275-360	B, C, CR, P, S, R, T, W	C, H, A
19	Alloyco-20	Alloy Steel Products Co., Linden, N. J.	Fe; 19-21 Cr; 28-30 Ni; 4.0-4.5 Cu; 2.5-3.0 Mo; 1.5 max. Si; 0.65-0.85 Mn; 0.07 max. C	C	C
20	Alray D	Alloy Metal Wire Co., Prospect Park, Pa.	Fe; 35 Cr; 15 Ni	W	H
21	Alumel	Hoskins Mfg. Co., Detroit, Mich.	94 Ni; 4 Al; 1 Si; 1 Mn	CR, W	H
22	Ambraley 901	Amer. Brass Co., Waterbury, Conn.	95 Cu; 9 Al	B, P, S, R, T, W	C
23	Ambraley 917	Amer. Brass Co., Waterbury, Conn.	82 Cu; 9 1/2 Al; 5 Ni; 2 1/2 Fe; 1 Mn	B, P, R	C
24	Ambraley 927	Amer. Brass Co., Waterbury, Conn.	76 Cu; 21.95 Zn; 2 Al; 0.05 As	T	C
25	American Stainless	Amer. Steel Castings Co., Newark, N. J.	Various standard stainless steels; see Nos. 275-360	C, H	C
26	American AW	Amer. Steel Castings Co., Newark, N. J.	Fe; 23.5 Ni; 19 Cr; 0.07 max. C	C	C
27	A Metal	Midvale Co., Philadelphia, Pa.	Fe; 19 Cr; 35 Ni; 0.35 C; 1 Si; 0.5 Mn	C	H
28	AMP	Midvale Co., Philadelphia, Pa.	Fe; 46-50 Ni; 0.1-0.2 C; 1-2 Mn	C	C
29	Ampeco 8	Ampeco Metal, Inc., Milwaukee, Wis.	Cu; 7 1/2 Al; 2-2 1/2 Fe	B, CR, HR, D, P, S, R, T, W	C, A
30	Ampeco 12	Ampeco Metal, Inc., Milwaukee, Wis.	Cu; 8.5-9.3 Al; 2.5-3.25 Fe	C	C, A
31	Ampeco 15	Ampeco Metal, Inc., Milwaukee, Wis.	Cu; 9-10 Al; 2.75-3.75 Fe	B, CR, HR, D, P, S, R, T	C, A
32	Ampeco 16	Ampeco Metal, Inc., Milwaukee, Wis.	Cu; 9.6-10.3 Al; 3-4 Fe	C	C, A
33	Ampeco 18	Ampeco Metal, Inc., Milwaukee, Wis.	Cu; 10.3-11 Al; 3.0-4.25 Fe	B, C, D, R, T	C, A
34	Ampecoley 40	Ampeco Metal, Inc., Milwaukee, Wis.	Cu; 9.5-10.5 Al; 0.20 max. Fe	C	C, A
35	Ampecoley 45	Ampeco Metal, Inc., Milwaukee, Wis.	Cu; 9.7-10.9 Al; 2.0-3.5 Fe; 4.5-5.5 Ni; 1.5 max. Mn	B, C, D, R, T	C, A

¹"Generally available" copper alloys may be obtained from such companies as the following: American Brass Co., Waterbury, Conn.; Bridgeport Brass Co., Bridgeport, Conn.; Bristol Brass Co., Bristol, Conn.; Chase Brass & Copper Co., Waterbury, Conn.; Mueller Brass Co., Huron, Mich.; New England Brass Co., Taunton, Mass.; Phelps Dodge Copper Products Corp., New York, N. Y.; Revere Copper & Brass, Inc., New York, N. Y.; Riverside Metal Co., Riverside, N. J.; Scovill Mfg. Co., Waterbury, Conn.; Seymour Mfg. Co., Seymour, Conn.; Wolverine Tube Co., Detroit, Mich.

NOTE: Primarily for: C, corrosion; H, heat; A, abrasion. Forms available: B, bars; C, castings; CR, cold rolled; D, drawn; E, extrusions; F, forgings; HR, hot rolled; P, plates; R, rods; S, sheets; T, tubes; W, wire.

No.	Material	Manufacturer	Essential Nominal Chemical Composition, Percent	Forms Available	Primarily for
36	Ampcoloy 49	Ampco Metal, Inc., Milwaukee, Wis.	Cu; 6½-9 Al; 4 max. Fe; 2 max. Mn	B, D, R, T, W	C, A
37	Ampcoloy 62	Ampco Metal, Inc., Milwaukee, Wis.	55-60 Cu; 0.5-1.5 Al; 0.4-2.0 Fe; 1.5 max. Mn; 1.0 max. Sn; 0.4 max. Pb; 0.5 max. Ni; bal. Zn	C	C, A
38	Ampcoloy 66	Ampco Metal, Inc., Milwaukee, Wis.	60-68 Cu; 3-7 Al; 2-4 Fe; 2.5-5 Mn; 0.5 max. Sn; 0.2 max. Pb; 0.5 max. Ni; bal. Zn	C	C, A
39	Ampcoloy A3	Ampco Metal, Inc., Milwaukee, Wis.	Cu; 9-10 Al; 1.25 max. Fe	B, C, D, R, T	C, A
40	Ampcoloy E123	Ampco Metal, Inc., Milwaukee, Wis.	Cu; 9.5-11 Al; 1.5 max. Fe	C	C, A
41	Amsco Alloys	Amer. Manganese Steel Div., Amer. Brake Shoe Co., Chicago Heights, Ill.	Now produced under tradename Thermalloy by Electro Alloys Div.		
42	Antaciron	Worthington Pump & Machinery Corp., Harrison, N. J.	Fe; 14.5 Si	C	CA
43	Armco & Rustless Stainless	Amer. Rolling Mill Co., Middletown, Ohio	Various standard stainless steels; see Nos. 275-360	B, CR, HR, D, P, S, W, strip	C, H, A
44	Armco Aluminized Steel	Amer. Rolling Mill Co., Middletown, Ohio	Hot-dip Al coating on mild & Cu-bearing steel	S, strip	C, H
45	Armco Galvanized Paintgrip	Amer. Rolling Mill Co., Middletown, Ohio	Bonderized galvanized sheets	S, strip	C
46	Armco Galvanized Steel or Ingot Iron	Amer. Rolling Mill Co., Middletown, Ohio	Hot-dip galvanized on mild or Cu-bearing steel or Armco Ingot Iron	S, strip	C
47	Armco Zincgrip	Amer. Rolling Mill Co., Middletown, Ohio	Galvanized steel	S, strip	
48	Armco Zincgrip Paintgrip	Amer. Rolling Mill Co., Middletown, Ohio	Bonderized galvanized steel	S, strip	
49	Aaraco Lead	Amer. Smelting & Ref. Co., New York, N. Y.	Pb; 0.06 Cu; 0.02 Bi	C, CR, R, S, T, W	C
50	Beraloy	Wilbur B. Driver Co., Newark, N. J.	Cu; 1.9 Be; 0.5 max. Co; 0.5 max. Ni	B, CR, D, HR	
51	Berylo 25	Beryllium Corp., Reading, Pa.	Cu; 1.9-2.15 Be; 0.05-0.4 Co; 0.1 max. Fe; 0.15 max. Si	B, C, CR, HR, P, S, R, T, W	C
52	Bored	Stoddy Co., Whittier, Calif.	60 tungsten carbide; 40 steel	Welding rod	A
53	Brass, Aluminum	Generally available ¹	76 Cu; 21.5-22 Zn; 2-2.5 Al	CR, D, T	
54	Brass, Cartridge	Generally available ¹ (Corrosion data by Amer. Brass)	66.5-69.5 Cu; 30.5-33.5 Zn	B, P, S, R, T, W	C
55	Brass, Forging	Scoville Mfg. Co., Waterbury, Conn.	59 Cu; 2 Pb; bal. Zn	R, W	C
56	Brass, Free Cutting	Scoville Mfg. Co., Waterbury, Conn.	61.5 Cu; 3 Pb; bal. Zn	R, W	C
57	Brass, High	Generally available ¹	66 Cu; 34 Zn		C
58	Brass, Low Loaded	Scoville Mfg. Co., Waterbury, Conn.	65 Cu; 0.5 Pb; bal. Zn	S, T, W	C
59	Brass, Med. Loaded	Scoville Mfg. Co., Waterbury, Conn.	65 Cu; 0.9 Pb; bal. Zn	S, R, W	C
60	Brass, High Loaded	Scoville Mfg. Co., Waterbury, Conn.	63 Cu; 1.75 Pb; bal. Zn	S, R, W	C
61	Brass, Naval	Generally available ¹ (Corrosion data by Amer. Brass)	60 Cu; 39.25 Zn; 0.75 Sn	B, P, S, R, W, D, R, T	C
62	Brass, Naval, Low Loaded	Scoville Mfg. Co., Waterbury, Conn.	61 Cu; 0.75 Sn; 0.75 Pb; bal. Zn (Corrosion resistance same as 61)	R, W	C
63	Brass, Red	Generally available ¹ (Corrosion data by Chase, Amer. Brass)	85 Cu; 15 Zn	B, S, R, T, W, P	C
65	Bronze, Aluminum	Generally available ¹	82-95 Cu; 5-10 Al; Fe; Mn; Ni; Sn	C, CR, F, HR, P, R, S, T, W	C
66	Bronze, Commercial	Chase Brass & Copper Co., Waterbury, Conn.	90 Cu; 10 Zn	P, S, T, W	C
67	Bronze, 600 Forgeable Bearing	Mueller Brass Co., Port Huron, Mich.	58 Cu; 2.5 Mn; 1.5 Al; 0.7 Si; bal. Zn	B, D, R, F	C, A
68	Bronze, Gilding 95%	Scoville Mfg. Co., Waterbury, Conn.	95 Cu; 5 Zn (Corrosion resistance same as commercial bronze)	S, R, T, W	C
69	Bronze, Hardware	Scoville Mfg. Co., Waterbury, Conn.	89 Cu; 8 Zn; 2 Pb; 1 Ni	D, R, W	C
70	Bronze, High Loaded Tin	Mueller Brass Co., Port Huron, Mich.	80 Cu; 10 Pb; 10 Sn	C	C
71	Bronze, Manganese	Mueller Brass Co., Port Huron, Mich.	58 Cu; 1 Sn; 1.4 Fe; 0.25 Mn; bal. Zn	B, D, R, F	C
72	Bronze, High Strength Manganese	Mueller Brass Co., Port Huron, Mich.	65 Cu; 3 Fe; 4 Mn; 5 Al; bal. Zn		
73	Bronze, Phosphor, 5% A	Generally available ¹ (Corrosion data by Amer. Brass)	94.8-95.5 Cu; 4.3-5 Sn; P	B, S, R, W, P, CR, D, T	C
74	Bronze, Phosphor, 8% C	Generally available ¹ (Corrosion data by Amer. Brass)	Cu; 7-9 Sn; 0.03-0.25 P	B, S, R, T, W, P, CR, D	C
75	Bronze, Phosphor, 10% D	Generally available ¹ (Corrosion data by Amer. Brass)	89.5-90 Cu; 10-10.5 Sn; P	B, S, R, T, W, P, CR, D	C
76	Bronze, Phosphor, Special Free Cutting	Amer. Brass Co., Waterbury, Conn.	88 Cu; 4 Zn; 4 Sn; 4 Pb	B, S, R, P	C
77	Bronze, Tobin	Amer. Brass Co., Waterbury, Conn.	60 Cu; 39.25 Zn; 0.75 Sn	B, S, R, T, W, P, D, HR, CR	C
78	Bronze, Tobin	Mueller Brass Co., Port Huron, Mich.	60 Cu; 1 max. Sn; bal. Zn		C
79	Buffblast Gray Iron	Bufflovak Equipment Div., Blaw-Knox Co., Buffalo, N. Y.	Fe; 3.2-3.6 C; 2 max. Ni; 1-2 Si; 0.6-0.9 Mn	C	
80	CA Stainless	Cooper Alloy Fdry. Co., Hillside, N. J.	Various standard stainless steels; see Nos. 275-360	C	C
81	CA-FA20	Cooper Alloy Fdry. Co., Hillside, N. J.	Fe; 19-21 Cr; 28-30 Ni; 3.5 Mo; 4-4½ Cu; 0.07 max. C	C	C
82	CA-MM	Cooper Alloy Fdry. Co., Hillside, N. J.	67 Ni; 30 Cu; 1.4 Fe; 0.1 Si; 0.15 C	C	C
83	Calite A	Calorizing Co., Wilkesburg, Pa.	Fe; 35 Ni; 15 Cr	B, C, P, S, R, W	H
84	Calite B25	Calorizing Co., Wilkesburg, Pa.	Fe; 25 Cr; 10 Ni; 1 Mo	C	H
85	Cast Iron	Corrosion data from <i>Standards of Hydraulic Institute</i> , Section G, 1941, Hydraulic Inst., New York	All-cast-iron pumps		
86	Cast Iron	Corrosion data from <i>Circular No. 312</i> , 1939, Crane Co., Chicago	Cast iron valves		
87	Causal Metal	Lunkenheimer Co., Cincinnati, Ohio	Fe; 19 Ni; 2.2-2.8 C; 4 Cu; 1.5 Cr	C	C
88	Chlorimet 2	Duriron Co., Dayton, Ohio	63 Ni; 32 Mo; 3 max. Fe; 0.15 max. C; 1 Si; 1 Mn	C	C
89	Chlorimet 3	Duriron Co., Dayton, Ohio	60 Ni; 18 Mo; 18 Cr; 2 Fe; 0.07 max. C; 1 Si; 1 Mn	C	C
90	Chromax	Driver Harris Co., Harrison, N. J.	Fe; 19 Cr; 35 Ni	B, CR, HR, P, R, S, W	H
91	Chromel A	Hoskins Mfg. Co., Detroit, Mich.	80 Ni; 20 Cr	B, CR, HR, D, R, W	H
92	Chromel C and D	Hoskins Mfg. Co., Detroit, Mich.	35-61 Ni; 16-18½ Cr; 23-46½ Fe		
93	Chromel P	Hoskins Mfg. Co., Detroit, Mich.	90 Ni; 10 Cr	CR, W	H
94	Circle L Stainless	Lebanon Steel Fdry., Lebanon, Pa.	Various standard stainless steels; see Nos. 275-360	C	C, A
95	Circle L 13	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 13 Cr; 0.25 max. C; 0.75 Mn; 0.75 max. Ni; 0.4 Mo	C	C, A

No.	Material	Manufacturer	Essential Nominal Chemical Composition, Percent	Forms Available	Primarily for
96	Circle L 21	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 19 Cr; 9 Ni; 0.07 max. C; 0.75 Mn; 0.75 Cu	C	C
97	Circle L 22M	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 19 Cr; 9 Ni; 0.07 max. C; 0.75 Mn; 1.75 Mo; 0.25 Si	C	C
98	Circle L 22XM	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 20 Cr; 10 Ni; 0.07 max. C; 0.75 Mn; 3 Mo	C	C
99	Circle L 23XM	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 19 Cr; 9 Ni; 0.2 max. C; 0.75 Mn; 3 Mo	C	C
100	Circle L 24	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 10 Cr; 20 Ni; 0.2 max. C; 0.75 Mn	C	C
101	Circle L 30H	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 24 Cr; 12 Ni; 0.5 max. C; 0.75 Mn	C	H
102	Circle L 31	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 29 Cr; 9 Ni; 0.3 max. C; 0.75 Mn	C	C
103	Circle L 31H	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 29 Cr; 9 Ni; 0.5 max. C; 0.75 Mn	C	H
104	Circle L 32	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 15 Cr; 35 Ni; 0.5 max. C; 0.75 Mn	C	H
105	Circle L 32XMC	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 15 Cr; 35 Ni; 0.07 max. C; 3.25 Mo; 2.25 Cu; 0.75 Mn	C	C
106	Circle L 34	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 21 Cr; 20 Ni; 0.07 max. C; 3.25 Mo; 0.75 Mn	C	C
107	Circle L 41	Lebanon Steel Fdry., Lebanon, Pa.	Fe; 15 Cr; 65 Ni; 0.5 max. C; 0.5 Mn	C	H
108	Colmonoy	Wall-Colmonoy Corp., Detroit, Mich.	68-80 Ni; 7-19 Cr; 2-4 B; Fe; Si	B, C, R	C, H, A
109	Colonial 618	Vanadium Alloys Steel Co., Latrobe, Pa.	Fe; 16-18 Cr; 1 Ni; 0.12 max. C; 8 (optional)	B, D, HR, P, R, S, W	C
110	Cupal	Hoskins Mfg. Co., Detroit, Mich.	55 Cu; 45 Ni	B, CR, HR, D, P, W	C, H
111	Copper	Generally available ¹ (Corrosion data by Chase)	99.9+ Cu	B, P, S, R, T, W	C
112	Copper, Beryllium	Generally available ¹	97.5 Cu; 2.15 Be; 0.35 Ni	B, C, CR, D, HR, P, R, S, W	C
113	Copper, Cadmium	Phelps Dodge Copper Prod. Corp., New York, N. Y.	99 Cu; 1 Cd	B, CR, D, HR, R, W	
114	Copper, Deoxidized	Generally available ¹ (Corrosion data by Amer. Brass)	99.9+ Cu; 0.01-0.03 P	B, C, CR, D, HR, P, R, S, T	C
115	Copper, O.F.H.C.	Amer. Metal Co., New York, N. Y.	99.9+ Cu	B, C, CR, D, HR, P, R, S, T, W	C
116	Copper, P.D.C.P.	Phelps Dodge Copper Prod. Corp., New York, N. Y.	99.9+ Cu	B, C, D, CR, HR, R, T, W	C
117	Copper, Phosphorized	Mueller Brass Co., Port Huron, Mich.	99.9 Cu; trace P	T	C
118	Copper, Tellurium	Chase Brass & Copper Co., Waterbury, Conn.	99.5 Cu; 0.5 Te	B, R, T, W	C
119	Corrosion	Pacific Fdry. Co. Ltd., San Francisco, Calif.	Fe; 14.5 Si	C	C
120	Croloy Stainless	Babcock & Wilcox Tube Co., Beaver Falls, Pa.	Various standard stainless steels; see Nos. 275-360	T	C, H
121	Cupaloy	Westinghouse Electric Corp., Pittsburgh, Pa.	99.4 Cu; 0.1 Ag; 0.5 Cr	B, C, R	C
122	Cupron	Wilbur B. Driver Co., Newark, N. J.	Cu; 45 Ni	B, CR, D, HR	
123	Cupro-Nickel, 20%	Generally available ¹ (Corrosion data by Amer. Brass)	70 Cu; 30 Ni	B, P, S, R, T, W	C
124	Cupro-Nickel, 30%	Generally available ¹ (Corrosion data by Chase)	70 Cu; 30 Ni	B, C, CR, D, HR, P, R, S, T, W	C
125	Dixton Stainless	Henry Dinton & Sons Inc., Philadelphia, Pa.	Various standard stainless steels; see Nos. 275-360	B, HR, P	C, H, A
126	Duploy 30	Bowers Mfg. Co., Buffalo, N. Y.	Fe; 18.5 Ni; 2.35 Cr; 2.85 C; 1 Mn	C	C
127	Dowmetal C	Dow Chemical Co., Midland, Mich.	Mg; 9 Al; 2 Zn; 0.1 Mn	C (perm. mold)	C
128	Dowmetal FS-1	Dow Chemical Co., Midland, Mich.	Mg; 3 Al; 1 Zn; 0.3 Mn	B, E, P, S, R, T	C
129	Dowmetal H	Dow Chemical Co., Midland, Mich.	Mg; 6 Al; 3 Zn; 0.2 Mn	C (sand)	C
130	Dowmetal J-1	Dow Chemical Co., Midland, Mich.	Mg; 6.5 Al; 1 Zn; 0.2 Mn	B, E, P, S, R, T, F	C
131	Dowmetal M	Dow Chemical Co., Midland, Mich.	Mg; 1.5 Mn	B, E, P, S, R, T, F	C
132	Dowmetal O-1	Dow Chemical Co., Midland, Mich.	Mg; 8.5 Al; 0.5 Zn; 0.2 Mn	B, E, R, F	C
133	Dowmetal R	Dow Chemical Co., Midland, Mich.	Mg; 9 Al; 0.6 Zn; 0.2 Mn	C (die)	C
134	Duraloy Stainless	Duraloy Co., Scottsdale, Pa.	Various standard stainless steels; see Nos. 275-360	C, T (centrifugal)	C, H, A
135	Duraloy	Duraloy Co., Scottsdale, Pa.	Fe; 26-30 Cr; 3 Ni; 2.75 C	C, T (centrifugal)	A
136	Duraloy HCA	Duraloy Co., Scottsdale, Pa.	Fe; 26-30 Cr; 1 C	C, T (centrifugal)	C, A
137	Duraloy HCN	Duraloy Co., Scottsdale, Pa.	Fe; 25 Cr; 12 Ni; 1 C	C, T (centrifugal)	C, H, A
138	Durco Stainless	Duriron Co., Dayton, Ohio	Various standard stainless steels; see Nos. 275-360	C	C, H, A
139	Durco D-10	Duriron Co., Dayton, Ohio	57 Ni; 23 Cr; 8 Cu; 4 Mo; 2 W; 1 Mn	C	C
140	Durichlor	Duriron Co., Dayton, Ohio	Fe; 0.85 C; 14.5 Si; 3 Mo; 0.35 Mn	C	C
141	Durimet 20	Duriron Co., Dayton, Ohio	Fe; 20 Cr; 29 Ni; 0.07 max. C; 2 Mo; 4 Cu; 1 Si	C	C
142	Durimet T	Duriron Co., Dayton, Ohio	Fe; 19 Cr; 22 Ni; 0.07 max. C; 2 Mo; 1 Cu; 1 Si	C, HR, B	C
143	Duriron	Duriron Co., Dayton, Ohio	Fe; 0.80 C; 14.5 Si; 0.35 Mn	C	C
144	Elverite A	Babcock & Wilcox Co., New York, N. Y.	Fe; 3-3.5 C; 0.35 Mn; 0.25-1 Si	C	A
145	Elverites B and C	Babcock & Wilcox Co., New York, N. Y.	Fe; 3-3.5 C; 1-1.8 Cr; 3.75-4.75 Ni; 0.25-1 Si	C	A
147	Enduro Stainless	Republic Steel Corp., Cleveland, Ohio	Various standard stainless steels; see Nos. 275-360	B, HR, D, CR, S, C, P, R, T, W, strip	C, H
148	Everdur 1000	Amer. Brass Co., Waterbury, Conn.	94.9 Cu; 4 Si; 1.1 Mn	Casting ingots	C
149	Everdur 1010	Amer. Brass Co., Waterbury, Conn.	95.8 Cu; 3.1 Si; 1.1 Mn	B, P, S, R, T, W	C
150	Everdur 1015	Amer. Brass Co., Waterbury, Conn.	98.25 Cu; 1.5 Si; 0.25 Mn	B, P, S, R, T, W	C
151	Fahrte Stainless	Ohio Steel Fdry. Co., Cincinnati, Ohio	Various standard stainless steels; see Nos. 275-360	C	C, H, A
152	Frontier S	Frontier Bronze Corp., Niagara Falls, N. Y.	89 Cu; 10 Al; 1 Fe	C	C
153	Frontier 11	Frontier Bronze Corp., Niagara Falls, N. Y.	88 Cu; 5 Ni; 5 Sn; 2 Zn	C	C
154	Frontier 40	Frontier Bronze Corp., Niagara Falls, N. Y.	Cu; 5 Zn; 0.5 Mg; 0.5 Cr; 0.2 Ti	C	C
155	Geneose Stainless	Symington-Gould Corp., Rochester, N. Y.	Various standard stainless steels; see Nos. 275-360	C	C, H, A
156	Gold	Baker & Co. Inc., Newark, N. J.	99.99 Au	B, C, CR, HR, D, P, S, R, T, W	C
157	Gun Metal	Mueller Brass Co., Port Huron, Mich.	88 Cu; 10 Sn; 2 Zn	C	C
158	Haycrome	Haynes Stellite Co., Kokomo, Ind.	Fe; 10-14 Cr; 0.8-1.2 C; 3-5 Mn	C, R (rolled, extruded)	H, A
159	Hastelloy A	Haynes Stellite Co., Kokomo, Ind.	Ni; 17-21 Mo; 17-21 Fe	B, C, CR, HR, D, P, S, R, T, W	C, H
160	Hastelloy B	Haynes Stellite Co., Kokomo, Ind.	Ni; 24-32 Mo; 3-7 Fe; 0.02-0.12 C	B, C, CR, HR, D, P, S, R, T, W	C, H
161	Hastelloy C	Haynes Stellite Co., Kokomo, Ind.	Ni; 14-19 Mo; 4-8 Fe; 0.04-0.15 C; 12-16 Cr; 3-5.5 W	B, C, CR, HR, D, P, S, R, T, W	C, H, A
162	Hastelloy D	Haynes Stellite Co., Kokomo, Ind.	Ni; 8-11 Si; 2-5 Cu; 1 max. Al	C, R	C, H, A

No.	Material	Manufacturer	Essential Nominal Chemical Composition, Percent	Forms Available	Primarily for
163	Haynes Stellite 1	Haynes Stellite Co., Kokomo, Ind.	Co; 28-34 Cr; 11-15 W	R (cast)	C, H, A
164	Haynes Stellite 3	Haynes Stellite Co., Kokomo, Ind.		C	C, H, A
165	Haynes Stellite 6	Haynes Stellite Co., Kokomo, Ind.	Co; 25-31 Cr; 3-6 W	C, S, R (cast)	C, H, A
166	Haynes Stellite 12	Haynes Stellite Co., Kokomo, Ind.	Co; 26-32 Cr; 6-10 W	C, R (cast)	C, H, A
167	Haynes Stellite 21	Haynes Stellite Co., Kokomo, Ind.	Co; 25-30 Cr; 4.5-6.5 Mo; 1.5-3.5 Ni; 2 max. Fe; 0.2-0.35 C	C, S	C, H
168	Haynes Stellite 23	Haynes Stellite Co., Kokomo, Ind.	Co; 0.35-0.5 C; 23-29 Cr; 1.5 max. Ni; 4-7 W; 2 max. Fe	C, S	C, H
169	Haynes Stellite 27	Haynes Stellite Co., Kokomo, Ind.	Ni; 0.35-0.5 C; 23-29 Cr; 5-7 Mo; 2 max. Fe; 30 min. Co	C, S	C, H
170	Haynes Stellite 30	Haynes Stellite Co., Kokomo, Ind.	Co; 3.5-5 C; 23-29 Cr; 13-17 Ni; 5-7 Mo; 2 max. Fe	C, S	C, H
171	Haynes Stellite 31	Haynes Stellite Co., Kokomo, Ind.	Co; 0.45-0.6 C; 23-28 Cr; 9-12 Ni; 6-9 W; 1.5 max. Fe	C, S	C, H
173	Haynes Stellite 93	Haynes Stellite Co., Kokomo, Ind.	Fe; 15-19 Cr; 4-7 Co; 0.5-3 V; 13-17 Mo	C, R	H, A
174	Haynes Stellite 98M2	Haynes Stellite Co., Kokomo, Ind.	Co; 27-31 Cr; 16-19 W	C	C, H, A
175	Haynes Stellite Multimet	Haynes Stellite Co., Kokomo, Ind.	20 Cr; 20 Co; 20 Ni; 3 Mo; 2 W; 1 Cb; 0.14 N; 0.1-0.35 C	B, C, CR, HR, D, P, S, R, T, W	C, H
176	Haynes Stellite Stainless	Haynes Stellite Co., Kokomo, Ind.	Various standard stainless steels; see Nos. 275-360	C	C, H, A
177	Haynes Stellite Star J	Haynes Stellite Co., Kokomo, Ind.	Co; 29-34 Cr; 15-19 W	C	C, H, A
178	Haystellite, Hard Grade	Haynes Stellite Co., Kokomo, Ind.	90-96 W; 0.5-2 Co; 3.5-4.5 C	R, crushed grains	A
179	Haystellite, Tough Grade	Haynes Stellite Co., Kokomo, Ind.	79-85 W; 8-11 Co; 3.5-4.5 C	Cast inserts, crushed grains	A
180	Herculey A and B	Revere Copper and Brass, New York, N. Y.	96-98 Cu; 1.75-3 Si; 0.25-0.5 Sn	B, C, CR, D, HR, P, R, S, T, W	C
181	Hytenal	Amer. Manganese Bronze Co., Philadelphia, Pa.	63 Cu; 23 Zn; 4 Al; 3 Fe; 3 Mn	B, C, HR, R	C, A
182	Ilium G	Burgess-Parr Co., Freeport, Ill.	56 Ni; 22 Cr; 6 Mo; 6 Fe; 6 Cu; Mn; Si; C	C	
183	Ilium R	Burgess-Parr Co., Freeport, Ill.	55-60 Ni; 18-24 Cr; 5-8 Mo; 5-8 Fe; 2-6 Cu; 0.5-1.75 Mn; Si; C	B, C, CR, P, R, S, T, W	
184	Inconel	International Nickel Co., New York, N. Y.	79.5 Ni; 13 Cr; 6.5 Fe; 0.08 C; 0.2 Cu; 0.25 Mn	B, C, CR, HR, D, P, S, R, T, W	C, H
185	Inconel-Clad Steel	Lukens Steel Co., Coatesville, Pa.	Steel sheet clad on one or both sides.	HR, P, heads	C
186	Indium Metal	Amer. Smelting and Ref. Co., New York, N. Y.	In	B, C, CR, R, S, T, W	C
187	Ingersoll Stainless	Ingersoll Steel Div., Borg-Warner Corp., Chicago, Ill.	Various standard stainless steels; see Nos. 275-360	P, S	C, H
188	Iso Cast Stainless	Empire Steel Castings, Inc., Reading, Pa.	Various standard stainless steels; see Nos. 275-360	C	C, H, A
189	K42R	Westinghouse Electric Corp., Pittsburgh, Pa.	42 Ni; 22 Co; 18 Cr; 14 Fe; 2.2 Ti	B, CR, R, W, F	H
190	Kanthal Alloys	C. O. Jelliff Mfg. Corp., Southport, Conn.	Fe; 20-25 Cr; Co; Al	W, ribbon	H
191	Lead	Eagle-Picher Co., Cincinnati, Ohio	99.9+ Pb	B, C, CR, S, R, T, W	C
192	Lead, Antimonial	Amer. Smelting & Ref. Co., New York, N. Y.	94 Pb; 6 Sb	C, CR, D, R, S, T, W	C
193	Lead, Antimonial	National Lead Co., New York, N. Y.	Pb; 4-12 Sb	B, C, CR, S, R, T, W, pipe	C
194	Lead, Antimonial	Northwest Lead Co., Seattle, Wash.	93.45 Pb; 6.5 Sb; 0.04-0.08 Cu	C, S, T, W	C
195	Lead, Chemical	Amer. Smelting & Ref. Co., New York, N. Y.	99.93 Pb; 0.06 Cu	B, C, CR, R, S, T, W	C
196	Lead, Chemical	National Lead Co., New York, N. Y.	99.93 Pb; 0.06 Cu	B, C, CR, S, R, T, W, pipe	C
197	Lead, Chemical	Northwest Lead Co., Seattle, Wash.	99.95 Pb; 0.04-0.08 Cu	C, S, T, W	C
198	Lead, Chemical Tellurium	Northwest Lead Co., Seattle, Wash.	99.9 Pb; 0.02-0.06 Te; 0.04-0.08 Cu	C, S, T, W	C
199	Lead, Tellurium	Amer. Smelting & Ref. Co., New York, N. Y.	99.98 Pb; 0.045 Te; 0.06 Cu	B, C, CR, R, S, T, W	C
200	Lead, Tellurium	National Lead Co., New York, N. Y.	99.98 Pb; 0.045 Te; 0.06 Cu	B, C, CR, R, S, T, W, pipe	C
201	Lukens CrCuNi Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.1 max. C; 0.4-0.6 Mn; 0.4-0.6 Cr; 0.4-0.6 Cu; 0.4-0.8 Ni	HR, P, heads	C
202	Lukens CrNiMo Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.25 max. C; 0.7-0.9 Mn; 0.8-1 Ni; 0.3-0.5 Mo	HR, P, heads	H, A
203	Lukens CrMn Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.45 max. C; 0.8-1 Mn; 0.3-0.5 Cr	HR, P, heads	H, A
204	Lukens CrMo Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.45 max. C; 0.3-0.6 Mn; 0.4-0.6 Cr; 0.3-0.6 Mo	HR, heads	H
205	Lukens MnMo Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.2 max. C; 1.2-1.5 Mn; 0.4-0.6 Mo	HR, P, heads	H, A
206	Lukens MnV Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.2 max. C; 1-1.4 Mn; 0.12 max. V	HR, P, heads	H
207	Lukens 1/2Mo Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.2 max. C; 0.6-0.9 Mn; 0.4-0.6 Mo	P, heads	H
208	Lukens 8 1/3 Ni Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.12 max. C; 0.5-0.8 Mn; 8-9 Ni	HR, P, heads	C
209	Lukens NiCr Steel	Lukens Steel Co., Coatesville, Pa.	Fe; 0.2 max. C; 0.4-0.6 Mn; 1-1.2 Ni; 0.4-0.6 Cr	HR, P, heads	H, A
210	Mayari R	Bethlehem Steel Co., Bethlehem, Pa.	Fe; 0.12 max. C; 0.2-1 Cr; 0.25-0.75 Ni; 0.5-0.7 Cu; 0.5-1 Mn	B, CR, HR, P, R, S, T, W	A
211	Michiana Stainless	Michiana Products Corp., Michigan City, Ind.	Various standard stainless steels; see Nos. 275-360	C	H
212	Midvale Stainless	Midvale Co., Philadelphia, Pa.	Various standard stainless steels; see Nos. 275-360		
213	Milwaukee Stainless	Milwaukee Steel Fdry., Milwaukee, Wis.	Various standard stainless steels; see Nos. 275-360	C	C, H, A
214	Misco Stainless	Michigan Steel Casting Co., Detroit, Mich.	Various standard stainless steels; see Nos. 275-360	C	C, H, A
215	Miscrome Stainless	Michigan Steel Casting Co., Detroit, Mich.	Various standard stainless steels; see Nos. 275-360	C	C, H, A
216	Musiel	International Nickel Co., New York, N. Y.	67 Ni; 30 Cu; 1.4 Fe; 0.1 Si; 0.15 C	B, C, CR, D, HR, P, R, S, T, W	C
217	Monel-Clad	Lukens Steel Co., Coatesville, Pa.	Steel sheet clad on one or both sides.	HR, P, heads	C
218	Mueller 85-5-5-5	Mueller Brass Co., Port Huron, Mich.	85 Cu; 5 Zn; 5 Sn; 5 Pb	C	C
219	Muntz Metal	Generally available ¹ (Corrosion data by Amer. Brass)	60 Cu; 40 Zn	B, P, S, R, T, W	C
220	National Al Alloys	National Smelting Co., Cleveland, Ohio	Al; 0-4 Cu; 0-4 Mg; 0-7.5 Si; 0-0.6 Mn; 0-1.5 Ni	C	C
221	Niag	Mueller Brass Co., Port Huron, Mich.	46 Cu; 10 Ni; 2.5 Pb; bal. Zn	B, D, R, F	C
222	Nichrome	Driver Harris Co., Harrison, N. J.	60 Ni; 15 Cr; Fe	B, CR, HR, P, R, S, T, W	H
223	Nichrome V	Driver Harris Co., Newark, N. J.	80 Ni; 20 Cr	B, CR, D, HR, P, R, S, T, W	H
224	Nickel	International Nickel Co., New York, N. Y.	99.4 Ni; 0.2 Mn; 0.1 Cu; 0.15 Fe; 0.05 Si	B, C, CR, HR, D, P, R, S, T, W	C, H
225	Nickel-Clad	Lukens Steel Co., Coatesville, Pa.	Steel sheet clad on one or both sides.	HR, P, heads	C
226	Nickel Silver, 18% A	Generally available ¹ (Corrosion data by Amer. Brass)	65 Cu; 18 Ni; 17 Zn	B, C, CR, D, P, R, S, T, W	C

No.	Material	Manufacturer	Essential Nominal Chemical Composition, Percent	Forms Available	Primarily for
227	Nickel Silver, 18% B	Generally available ¹	55 Cu; 18 Ni; 27 Zn	B, C, CR, D, P, R, S	C
228	Nicloy	Babcock & Wilcox Tube Co., Beaver Falls, Pa.	Fe; 31.5, 5, or 9 Ni	T (seamless)	C
229	Ni-Hard	International Nickel Co., New York, N. Y.	Fe; 3.4 C; 1.5 Cr; 4.5 Ni; 0.6 Si	C	A
230	Nidastin	Wilbur B. Driver Co., Newark, N. J.	Fe; 18-20 Cr; 8-10 Ni; 0.2 max. C; 2 max. Mn	D, HR, R, W	C
231	Ni-Resist	International Nickel Co., New York, N. Y.	Fe; 2.8 C; 14 or 20 Ni; 6 Cu (optional); 2 Cr; 2 Si	C	C, H
232	Nirox	Driver-Harris Co., Harrison, N. J.	80 Ni; 14 Cr; 6 Fe	B, CR, HR, P, R, S, W	H
233	NS-S Alloy	Lunkenheimer Co., Cincinnati, Ohio	50 Ni; 46 Cu; 2.4 Si; 1.6 Mn	C (valve seats, discs)	C, H, A
234	Olympic Bronze, Type A	Chase Brass & Copper Co., Waterbury, Conn.	96 Cu; 3 Si; 1 Zn	P, S, R, T, W	C
235	Olympic Bronze, Type B	Chase Brass & Copper Co., Waterbury, Conn.	97.5 Cu; 1.5 Si; 1 Zn	P, S, R	C
236	Palladium	Baker & Co., Newark, N. J.	99.991 Pd	B, C, CR, HR, D, P, S, R, T, W	C, H
237	Pennalloy	Pennsylvania Elec. Steel Casting Co., Hamburg, Pa.		C	A
238	Permite Al Alloys	Aluminum Industries, Cincinnati, Ohio	Al; 0-5 Cu; 1.5-7.5 Si; 0-1 Fe; 0-0.4 Mg	C	C
239	Pioneer	Pioneer Alloy Products Co., Cleveland, Ohio	65 Ni; Cr; Mo; Fe	C	C
240	Platinum	Baker & Co., Newark, N. J.	99.99 Pt	B, C, CR, HR, D, P, S, R, T, W	C, H
241	Platinum	J. Bishop & Co., Malvern, Pa.	99.95 Pt	B, C, CR, HR, D, P, S, R, T, W	C, H
242	Platinum, Iridio	Baker & Co., Newark, N. J.	Pt; 5-30 Ir	B, CR, HR, C, D, P, S, R, T, W	C, H
243	Platinum, Iridium	J. Bishop & Co., Malvern, Pa.	Pt; 10-30 Ir	B, CR, HR, C, D, P, S, R, T, W	C, H
244	Platinum, Rhodio	Baker & Co., Newark, N. J.	Pt; 5-40 Rh	B, C, CR, HR, D, P, S, R, T, W	C, H
245	PyraSteel	Chicago Steel Fdry. Co., Chicago, Ill.	Fe; 25-27 Cr; 12-14 Ni; 0.1-0.35 C; Mo, Nb, Se (optional)	C	C, H
246	Pyrocast	Pacific Fdry. Co. Ltd., San Francisco, Calif.	Fe; 22-30 Cr	C	H
247	Pyrocast Stainless	Pacific Fdry. Co. Ltd., San Francisco, Calif.	Various standard stainless steels; see Nos. 275-300	C	H
248	Resistac	Amer. Manganese Bronze Co., Philadelphia, Pa.	88 Cu; 10 Al; 2 Fe	B, C, HR, R	C, H
250	Reynolds 25	Reynolds Metals Co., Louisville, Ky.	99 Al; 1 max. Fe + Si; 0.2 max. Cu	B, R, W	C
251	Reynolds 35	Reynolds Metals Co., Louisville, Ky.	Al; 1-1.5 Mn; 0.7 max. Fe; 0.6 max. Si; 0.2 Cu	B, R, W	C
252	Reynolds 145	Reynolds Metals Co., Louisville, Ky.	Al; 3.9-5 Cu; 0.5-1.2 Si; 1 max. Fe; 0.4-1.2 Mn; 0.2-0.8 Mg	B, R, W	C
253	Reynolds 175	Reynolds Metals Co., Louisville, Ky.	Al; 3.5-4.5 Cu; 0.8 max. Si; 1 max. Fe; 0.4-1 Mn; 0.2-0.8 Mg	B, R, W	C
254	Reynolds 185	Reynolds Metals Co., Louisville, Ky.	Al; 3.5-4.5 Cu; 1.7-2.3 Ni; 0.9 max. Si; 1 max. Fe; 0.45-0.9 Mg	B, R, W	C
255	Reynolds 245	Reynolds Metals Co., Louisville, Ky.	Al; 3.8-4.9 Cu; 1.2-1.8 Mg; 0.5 max. Si	B, R, W	C
256	Reynolds 245 Pureclad	Reynolds Metals Co., Louisville, Ky.	Al 24S core covered with Al of high purity	S, P	C
257	Reynolds 255	Reynolds Metals Co., Louisville, Ky.	Al; 3.9-5 Cu; 0.5-1.2 Si; 1 max. Fe	B, R, W	C
258	Reynolds 325	Reynolds Metals Co., Louisville, Ky.	Al; 11-13.5 Si; 0.5-1.3 Cu; 1.0 max. Fe; 0.8-1.3 Mg; 0.5-1.3 Ni	B, R, W	C
259	Reynolds A515	Reynolds Metals Co., Louisville, Ky.	Al; 0.6-1.2 Si; 1 max. Fe; 0.35 Cu; 0.45-0.8 Mg	B, R, W	C
260	Reynolds 525	Reynolds Metals Co., Louisville, Ky.	Al; 2.2-2.8 Mg; 0.45 max. Fe + Si; 0.1 max. Cu	B, R, W	C
261	Reynolds 535	Reynolds Metals Co., Louisville, Ky.	Al; 0.35 max. Fe; 1.1-1.4 Mg; 0.15-0.35 Cr	B, R, W	C
262	Reynolds 615	Reynolds Metals Co., Louisville, Ky.	Al; 0.4-0.8 Si; 0.7 max. Fe; 0.8-1.2 Mg	B, R, W	C
263	Reynolds R301	Reynolds Metals Co., Louisville, Ky.	High strength Al alloy core clad with corrosion resistant Al alloy of intermediate strength.	S, P	C
264	Resistal Stainless	Crucible Steel Co. of Amer., New York, N. Y.	Various standard stainless steels; see Nos. 275-300	B, CR, HR, D, P, S, R, W	C, H, A
265	Rusfloy	Amer. Smelting & Ref. Co., New York, N. Y.	Pb; 0.25 Sn; 0.02 Mg; 0.02 Bi	CR, IL, T	C
266	St. Joe Lead	St. Joseph Lead Co., New York, N. Y.	99.90 + Pb; 0.04-0.08 Cu; 0.002-0.02 Ag; 0.002 max. Fe; 0.001 max. Zn; 0.002 max. As, Sb, Sn	Figs	C
267	Silfram	Stoddy Co., Whittier, Calif.	Fe; 30 Cr; 10 Ni	C, welding rod	A
268	Silver	Baker & Co. Inc., Newark, N. J.	99.9 + Ag	B, C, CR, HR, D, P, S, R, T, W	C
269	Silver	Handy & Harman, New York, N. Y.	99.9 + Ag	B, C, CR, D, P, R, S, T, W	C
270	Stainless-Clad 304	Lukens Steel Co., Coatesville, Pa.	Sheet steel clad on one or both sides.	HR, P, heads	C
271	Stainless-Clad 316	Lukens Steel Co., Coatesville, Pa.	Sheet steel clad on one or both sides.	HR, P, heads	C
272	Stainless-Clad 347	Lukens Steel Co., Coatesville, Pa.	Sheet steel clad on one or both sides.	HR, P, heads	C
273	Stainless-Clad 410	Lukens Steel Co., Coatesville, Pa.	Sheet steel clad on one or both sides.	HR, P, heads	C
274	Stainless-Clad 430	Lukens Steel Co., Coatesville, Pa.	Sheet steel clad on one or both sides.	HR, P, heads	C
275	Stainless Type 301		Fe; 16-18 Cr; 6-8 Ni; 0.08-0.15 C	B, CR, D, HR, P, S, W	C
276	Stainless Type 302		Fe; 17-19 Cr; 8-10 Ni; 0.08-0.15 C	B, CR, D, HR, P, S, W, T, R	C
277	Stainless Type 302B		Fe; 17-19 Cr; 8-10 Ni; 0.08-0.15 C; 2-3 Si	B, CR, D, HR, P, S, W	C, H
278	Stainless Type 303		Fe; 17-19 Cr; 8-10 Ni; 0.15 max. C; 0.07 min. P, S, Se; 0.6 max. Zr, Mo; 2 max. Mn	B, CR, D, HR, P, S, W	C
279	Stainless Type 304		Fe; 18-20 Cr; 8-11 Ni; 0.08 max. C; 2 max. Mn	B, CR, D, HR, P, R, S, T, W	C
280	Stainless Type 308		Fe; 19-21 Cr; 10-12 Ni; 0.08 max. C	B, CR, D, HR, P, R, S, T, W	C
281	Stainless Type 309		Fe; 22-24 Cr; 12-15 Ni; 0.2 max. C	B, CR, D, HR, P, R, S, W, H, C	C, H
282	Stainless Type 310		Fe; 24-26 Cr; 19-22 Ni; 0.25 max. C	B, CR, D, HR, P, R, S, T, W	C, H
283	Stainless Type 316		Fe; 16-18 Cr; 10-14 Ni; 0.1 max. C; 1.75-2.75 Mo	B, CR, D, HR, P, R, S, T, C, W	C, H
284	Stainless Type 317*		Fe; 17.5-20 Cr; 10-14 Ni; 0.1 max. C; 3-4 Mo	B, CR, HR, P, R, S, T, W	C, H
285	Stainless Type 321		Fe; 17-19 Cr; 8-11 Ni; Ti, 5xC min.	B, CR, D, HR, P, R, S, T, C, W	C, H
286	Stainless Type 347		Fe; 17-19 Cr; 9-12 Ni; Nb, 10xC min.	B, CR, D, HR, P, R, S, T, C, W	C, H

NOTE: Listed below are the producers of standard stainless steels (Nos. 275-305) for which type analyses have been established by the Amer. Iron and Steel Inst. The designations are intended to apply only to wrought products, but are so commonly applied to castings as well that they have been adopted by many foundries to identify comparable casting alloys. Types marked * are no longer in force but occasional reference is still made to them. Numbers in () are the number of standard A.I.S.I. alloys for which the manufacturer has provided corrosion data; they are solely to acknowledge cooperation in the preparation of these tables and have no reference to the number of steels produced by any company.

Allegany Ludlum Steel Corp., Pittsburgh, Pa. (25)
 Alloy Metal Wire Co., Prospect Park, Pa.
 Amer. Chain & Cable Co., Bridgeport, Conn.
 Amer. Rolling Mill Co., Middletown, Ohio (4)
 Babcock & Wilcox Tube Co., Beaver Falls, Pa. (7)
 Bethlehem Steel Co., Bethlehem, Pa.

No	Material	Manufacturer	Essential Nominal Chemical Composition, Percent	Forms Available	Primarily for
287	Stainless Type 403	A. M. Byers Co., Pittsburgh, Pa. Carnegie-Illinois Steel Co., Pittsburgh, Pa. (4)	Fe; 11.5-13 Cr; 0.15 max. C; (turbine quality)	B, CR, D, HR, P, R, S, T, W	C, A
288	Stainless Type 405	Carpenter Steel Co., Reading, Pa. Cooper Alloy Fdry. Co., Elizabeth, N. J. (3)	Fe; 11.5-13.5 Cr; 0.08 max. C; 0.1-0.3 Al	B, CR, D, HR, P, S, W	C, H
289	Stainless Type 406	Copperweld Steel Co., Warren, Ohio	Fe; 12-14 Cr; 0.15 max. C; 3.5-4.5 Al	B, CR, D, HR, P, S, W	C
290	Stainless Type 410	Crucible Steel Co. of America, New York, N. Y. (4) Wilbur B. Driver Co., Newark, N. J.	Fe; 11.5-13.5 Cr; 0.15 max. C	B, CR, D, HR, P, R, S, T, W	C, A, H
291	Stainless Type 414	Eastern Stainless Steel Corp., Baltimore, Md.	Fe; 11.5-13.5 Cr; 1.25-2.5 Ni; 0.15 max. C	B, D, HR, P, R, S, W	C, A
292	Stainless Type 416	Firth Sterling Steel Co., McKeesport, Pa. Globe Steel Tubes Co., Milwaukee, Wis. Henry Diston & Sons, Philadelphia, Pa.	Fe; 12-14 Cr; 0.15 max. C; 0.07 min. P, S, Se; 0.6 max. Zr, Mo	B, CR, D, HR, P, R, S, T, W	C, A
293	Stainless Type 418*	Ingersoll Steel Div., Borg-Warner Corp., New Castle, Ind.	Fe; 12-14 Cr; 0.15 max. C; 2.5-3.5 W		C, H
294	Stainless Type 420	Jenop Steel Co., Washington, Pa.	Fe; 12-14 Cr; 0.15 min. C	B, CR, D, HR, P, R, S, W	C, A
295	Stainless Type 430	Joslyn Mfg. & Supply Co., Chicago, Ill.	Fe; 14-18 Cr; 0.12 max. C	B, CR, HR, P, R, S, T, W	C, H
296	Stainless Type 430F	Latrobe Electric Steel Co., Latrobe, Pa. McLouth Steel Corp., Detroit, Mich. Michiana Products Corp., Michigan City, Ind.	Fe; 14-18 Cr; 0.12 max. C; 0.07 min. P, S, Se; 0.6 max. Zr, Mo	B, CR, D, HR, R, W	C, H
297	Stainless Type 431	Midvale Co., Philadelphia, Pa.	Fe; 15-17 Cr; 1.25-2.5 Ni; 0.2 max. C	B, CR, D, HR, P, S, W	C, A, H
298	Stainless Type 440A	Pittsburgh Steel Co., Pittsburgh, Pa.	Fe; 16-18 Cr; 0.6-0.75 C; 0.75 max. Mo	B, CR, HR, D, P, S, R, W	C, A
299	Stainless Type 440B	Timken Roller Bearing Co., Canton, Ohio	Fe; 16-18 Cr; 0.75-0.95 C; 0.75 max. Mo	B, CR, HR, D, P, S, R, W	C, A
300	Stainless Type 440C	Republic Steel Corp., Cleveland, Ohio	Fe; 16-18 Cr; 0.95-1.2 C; 0.75 max. Mo	B, CR, HR, D, P, S, R, W	C, A
301	Stainless Type 442	Rotary Electric Steel Corp., Detroit, Mich. Sharon Steel Corp., Sharon, Pa.	Fe; 18-23 Cr; 0.25 max. C	B, CR, D, HR, P, R, S	H, C
302	Stainless Type 443	Stanley Works, New Britain, Conn. Sumnerill Tubing Co., Bridgeport, Pa. Superior Steel Corp., Carnegie, Pa.	Fe; 18-23 Cr; 0.2 max. C; 0.9-1.25 Cu	B, CR, D, HR, P, R, S, T, W	C
303	Stainless Type 446	Universal Cyclops Steel Corp., Bridgeville, Pa. Vanadium Alloys Steel Co., Latrobe, Pa. (5) Wallingford Steel Co., Wallingford, Conn.	Fe; 23-27 Cr; 0.35 max. C; 0.25 max. N	B, CR, D, HR, P, R, S, T, W	C, H
304	Stainless Type 501		Fe; 4-6 Cr; 0.1 min. C	B, CR, D, HR, P, R, S, T, W	C
305	Stainless Type 502		4-6 Cr; 0.1 max. C	B, CR, D, HR, P, R, S, T, W	C
306	Stainless Type CA-15	NOTE: Listed below are the producers of standard cast stainless steel (Nos. 306-381) for which type analyses have been established by the Alloy Casting Institute. Designations marked * are no longer in force but occasional reference is still made to them. Numbers in () are the number of standard A.C.I. alloys for which the company has provided corrosion data; they are solely to acknowledge cooperation in the preparation of these tables and have no reference to the number of steels produced by any company.	Fe; 11-14 Cr; 1 max. Ni; 0.15 max. C	C	C
307	Stainless Type CA-40		Fe; 11-14 Cr; 1 max. Ni; 0.2-0.4 C	C	C
308	Stainless Type CB-30		Fe; 18-22 Cr; 2 max. Ni; 0.3 max. C	C	C
309	Stainless Type CC-35*		Fe; 26-30 Cr; 4 max. Ni; 0.35 max. C	C	C
310	Stainless Type CC-50		Fe; 26-30 Cr; 4 max. Ni; 0.5 max. C	C	C
311	Stainless Type CD-10M*		Fe; 27-30 Cr; 3-6 Ni; 0.1 max. C; 2 max. Mo	C	C
312	Stainless Type CE-30		Fe; 26-30 Cr; 8-11 Ni; 0.3 max. C	C	C
313	Stainless Type CF-7		Fe; 18-20 Cr; 8-10 Ni; 0.07 max. C	C	C
314	Stainless Type CF-10		Fe; 18-20 Cr; 8-10 Ni; 0.1 max. C	C	C
315	Stainless Type CF-16		Fe; 18-20 Cr; 8-10 Ni; 0.16 max. C	C	C
316	Stainless Type CF-20		Fe; 18-20 Cr; 8-10 Ni; 0.2 max. C	C	C
317	Stainless Type CF-25a		Fe; 18-20 Cr; 8-10 Ni; 0.07 max. C; 0.2-0.35 Se	C	C
318	Stainless Type CF-7C		Fe; 18-20 Cr; 8-10 Ni; 0.07 max. C; 8xC-1 Cb	C	C
319	Stainless Type CF-7M		Fe; 18-20 Cr; 8-10 Ni; 0.07 max. C; 1.5-3.5 Mo	C	C
320	Stainless Type CF-10M		Fe; 18-20 Cr; 8-10 Ni; 0.1 max. C; 1.5-3.5 Mo	C	C
321	Stainless Type CF-16M		Fe; 18-20 Cr; 8-10 Ni; 0.16 max. C; 1.5-3.5 Mo	C	C
322	Stainless Type CF-7MC*		Fe; 18-20 Cr; 8-10 Ni; 0.07 max. C; 1.5-3.5 Mo; 8xC-1 Cb	C	C
323	Stainless Type CG-7	Amer. Cast Iron Pipe Co., Birmingham, Ala. American Manganese Steel Div., American Brake Shoe & Fdry. Co., Chicago Heights, Ill.	Fe; 20-22 Cr; 10-12 Ni; 0.07 max. C	C	C
324	Stainless Type CG-10	Atlas Fdry. Co., Irvington, N. J.	Fe; 20-22 Cr; 10-12 Ni; 0.1 max. C	C	C
325	Stainless Type CG-16	Babcock & Wilcox Co., Barborton, Ohio Calorizing Co., Wilkesburg, Pa.	Fe; 20-22 Cr; 10-12 Ni; 0.16 max. C	C	C
326	Stainless Type CG-16Se	Chicago Steel Fdry., Chicago, Ill.	Fe; 20-22 Cr; 10-12 Ni; 0.07 max. C; 1.5-3.5 Mo; 8xC-1 Cb	C	C
327	Stainless Type CG-7C	Cooper Alloy Fdry. Co., Elizabeth, N. J. Crane Co., Chicago, Ill.	Fe; 20-22 Cr; 10-12 Ni; 0.07 max. C	C	C
328	Stainless Type CG-7M	Driver Harris Co., Harrison, N. J.	Fe; 20-22 Cr; 10-12 Ni; 0.1 max. C	C	C
329	Stainless Type CG-10M	Duraloy Co., Scottsdale, Pa. (9)	Fe; 20-22 Cr; 10-12 Ni; 0.16 max. C	C	C
330	Stainless Type CG-16M	Duriron Co., Inc., Dayton, Ohio	Fe; 20-22 Cr; 10-12 Ni; 0.16 max. C; 0.2-0.35 Se	C	C
331	Stainless Type CG-7MC*	Electric Steel Fdry. Co., Portland, Ore. Electro-Alloys Div., Amer. Brake Shoe Co., Elyria, Ohio	Fe; 20-22 Cr; 10-12 Ni; 0.07 max. C; 8xC-1 Cb	C	C
332	Stainless Type CH-10	Empire Steel Castings, Inc., Reading, Pa.	Fe; 20-22 Cr; 10-12 Ni; 0.07 max. C; 1.5-3.5 Mo	C	C
333	Stainless Type CH-20	General Alloys Co., Boston, Mass.	Fe; 20-22 Cr; 10-12 Ni; 0.1 max. C; 1.5-3.5 Mo	C	C
334	Stainless Type CH-10C	General Metals Corp., Oakland, Calif.	Fe; 20-22 Cr; 10-12 Ni; 0.16 max. C; 1.5-3.5 Mo	C	C
335	Stainless Type CH-10M	Grede Foundries, Milwaukee, Wis.	Fe; 20-22 Cr; 10-12 Ni; 0.16 max. C; 1.5-3.5 Mo	C	C
336	Stainless Type CH-20M*	Haynes Stellite Co., Kokomo, Ind. Hoskins Mfg. Co., Detroit, Mich.	Fe; 20-22 Cr; 10-12 Ni; 0.07 max. C; 1.5-3.5 Mo; 8xC-1 Cb	C	C
337	Stainless Type CH-10MC*	Key Co., East St. Louis, Ill. Lebanon Steel Fdry., Lebanon, Pa.	Fe; 22-26 Cr; 12-15 Ni; 0.1 max. C	C	C
338	Stainless Type CK-25	Michiana Products Corp., Michigan City, Ind.	Fe; 22-26 Cr; 12-15 Ni; 0.2 max. C	C	C
339	Stainless Type CM-25	Michigan Steel Casting Co., Detroit, Mich.	Fe; 22-26 Cr; 12-15 Ni; 0.1 max. C; 8xC-1 Cb	C	C
340	Stainless Type CN-7	Midvale Co., Philadelphia, Pa. Milwaukee Steel Fdry., Milwaukee, Wis.	Fe; 22-26 Cr; 12-15 Ni; 0.1 max. C; 1.5-3.5 Mo	C	C
341	Stainless Type CN-25*	National Alloy Div., Blaw-Knox Co., Blaw-Knox, Pa.	Fe; 22-26 Cr; 12-15 Ni; 0.2 max. C; 1.5-3.5 Mo	C	C
342	Stainless Type CS-25*	Ohio Steel Fdry. Co., Cincinnati, Ohio	Fe; 22-26 Cr; 12-15 Ni; 0.1 max. C; 1.5-3.5 Mo; 8xC-1 Cb	C	C
343	Stainless Type CT-7	Otis Elevator Co., Buffalo, N. Y. Pacific Fdry. Co., L.A., San Francisco, Calif.	Fe; 23-27 Cr; 19-22 Ni; 0.25 max. C	C	C
344	Stainless Type CT-25*	Shawinigan Chemicals, Ltd., Montreal, Que. Sivyer Steel Casting Co., Milwaukee, Wis.	Fe; 8-11 Cr; 19-22 Ni; 0.25 max. C	C	C
345	Stainless Type HB	Standard Alloy Co., Cleveland, Ohio	Fe; 18-22 Cr; 20-30 Ni; 0.07 max. C; may contain others	C	C
346	Stainless Type HC	Sterling Alloys Inc., Woburn, Mass.	Fe; 18-22 Cr; 20-30 Ni; 0.25 max. C; may contain others	C	C
347	Stainless Type HD	Symington-Gould Corp., Rochester, N. Y. (1)	Fe; 18-22 Cr; 20-30 Ni; 0.25 max. C	C	C
348	Stainless Type HE	Taylor Wharton Iron & Steel Co., High Bridge, N. J.	Fe; 8-12 Cr; 20-32 Ni; 0.25 max. C	C	C
349	Stainless Type HF	Utility Electric Steel Fdry., Los Angeles, Calif.	Fe; 13-17 Cr; 34-37 Ni; 0.07 max. C; may contain others	C	C
350	Stainless Type HH	Warman Steel Casting Co., Huntington Park, Calif.	Fe; 13-17 Cr; 34-37 Ni; 0.25 max. C; may contain others	C	C
351	Stainless Type HI		Fe; 13-17 Cr; 34-37 Ni; 0.25 max. C; may contain others	C	C
352	Stainless Type HK		Fe; 18-22 Cr; 2 max. Ni	C	H
353	Stainless Type HL		Fe; 26-30 Cr; 4 max. Ni	C	H

No.	Material	Manufacturer	Essential Nominal Chemical Composition, Percent	Forms Available	Primarily for
354	Stainless Type HN		Fe; 18-22 Cr; 23-26 Ni	C	H
355	Stainless Type HP		Fe; 28-32 Cr; 29-31 Ni	C	H
356	Stainless Type HS		Fe; 8-12 Cr; 29-32 Ni	C	H
357	Stainless Type HT		Fe; 13-17 Cr; 33-37 Ni	C	H
358	Stainless Type HU		Fe; 17-21 Cr; 37-41 Ni	C	H
359	Stainless Type HW		Fe; 10-14 Cr; 58-62 Ni	C	H
360	Stainless Type HX		Fe; 15-19 Cr; 64-68 Ni	C	H
362	Still Metal	Amer. Manganese Bronze Co., Philadelphia, Pa.	Cu; Sn	C	C
363	Stoodie	Stoodie Co., Whittier, Calif.	Fe; 33 Cr; 4.5 Mn; 2 Si; 4C	Welding rod	A
364	Stoodie 1	Stoodie Co., Whittier, Calif.	Co; 25 Cr; 13 W; 2 C	C, welding rod	C, H, A
365	Stoodie 6	Stoodie Co., Whittier, Calif.	Co; 25 Cr; 5.5 W; 1 C	C, welding rod	C, H, A
366	Stoodie Self Hardening	Stoodie Co., Whittier, Calif.	Fe; 6 Cr; 2.5 Mn; 1.5 Si; 1 C	Welding rod	A
367	Super Nickel	Amer. Brass Co., Waterbury, Conn.	70 Cu; 30 Ni	B, S, R, T, W, P	C
368	Tantalum	Fansteel Metallurgical Corp., North Chicago, Ill.	99.9+ Ta	B, CR, D, S, R, T, W	C
369	Tehnic Bronze	Chase Brass and Copper Co., Waterbury, Conn.	98.3 Cu; 1 Ni; 0.2 P; 0.5 Te	R	C
370	Thermalloy Stainless	Electro Alloys Div., Amer. Brake Shoe Co., Elyria, Ohio	Various standard stainless steels; see Nos. 275-360	C	H
371	Timken Stainless	Steel and Tube Div., Timken Roller Bearing Co., Canton, Ohio	Various standard stainless steels; see Nos. 275-360	B, CR, HR, R, T, W	C, H
372	Tisco 150 Alloy	Taylor-Wharton Iron and Steel Co., Easton, Pa.	Fe; 2.5-3 C; 2 Si; 1-1.5 Ni; 28-32 Cr	C	A, C
373	Tisco Timang MnNi Steel	Taylor-Wharton Iron and Steel Co., Easton, Pa.	Fe; 0.6-0.8 C; 12-15 Mn; 3 Ni	P, R	A
374	Tisco Mn Steel	Taylor-Wharton Iron and Steel Co., Easton, Pa.	Fe; 12 Mn (Hadfield type)	C	A
375	Toncon Cu Mo Iron	Republic Steel Corp., Cleveland, Ohio		B, CR, HR, P, S	C
376	Tophet A	Wilbur B. Driver Co., Newark, N. J.	60 Ni; 20 Cr	D, HR, R, W	H
377	Tophet C	Wilbur B. Driver Co., Newark, N. J.	Fe; 60 Ni; 15 Cr	D, HR, R, W	H
378	Tophet D	Wilbur B. Driver Co., Newark, N. J.	Fe; 35 Ni; 18.5 Cr	B, CR, D, HR, R, W	H
379	Tube Borium	Stoodie Co., Whittier, Calif.	60 tungsten carbide; 40 steel	Welding rod	A
380	Tuf-Stuf	Mueller Brass Co., Port Huron, Mich.	85.9 Cu; 10 Al; 3 Fe; 0.1 Mn	B, D, R, F	C, H, A
381	U. S. S. Stainless	Carnegie-Illinois Steel Corp., Pittsburgh, Pa.	Various standard stainless steels; see Nos. 275-360	B, CR, HR, P, S, R, strip	C, H
382	U. S. S. Cor-Ten	Carnegie-Illinois Steel Corp., Pittsburgh, Pa.	Fe; 0.12 max. C; 0.25-0.55 Cu; 0.5-1.25 Cr; 0.65 max. Ni	B, HR, P, S, R, strip	C, A
383	U. S. S. Man-Ten	Carnegie-Illinois Steel Corp., Pittsburgh, Pa.	Fe; 0.25 max. C; 1.1-1.6 Mn; 0.2 min. Cu	B, HR, P, S, R, strip	C, A
384	U. S. S. A-R	Carnegie-Illinois Steel Corp., Pittsburgh, Pa.	Fe; 0.35-0.5 C; 1.5-2 Mn; 0.15-0.3 Si	B, HR, P, S, strip	A
385	Utley Stainless	Utility Electric Steel Fdry., Los Angeles, Calif.	Various standard stainless steels; see Nos. 275-360	C	C, H
386	Vanadium Stainless	Vanadium Alloys Steel Co., Latrobe, Pa.	Various standard stainless steels; see Nos. 275-360	B, HR, D, P, R, W	C, H, A
387	Vanadium Stainless B	Vanadium Alloys Steel Co., Latrobe, Pa.	Fe; 14-18 Cr; 0.12 min. C	B, HR, D, P, R, W	C, A
388	Vanadium Stainless 795	Vanadium Alloys Steel Co., Latrobe, Pa.	Fe; 14-18 Cr; 2 max. Ni; 0.15 min. C	B, HR, P, R, W	C, A
389	Vanadium Stainless U	Vanadium Alloys Steel Co., Latrobe, Pa.	Fe; 17-19 Cr; 7-9.5 Ni; 0.15 max. C; 1-1.5 Cu; 1-1.5 Mo	B, HR, P, R, W	C, H
390	Worthite	Worthington Pump and Machinery Corp., Harrison, N. J.	Fe; 20 Cr; 24 Ni; 0.07 max. C; 3.25 Si; 3 Mo; 1.75 Cu; 0.5 Mn	B, C, HR, R, W	C
391	Wrought Iron, Genuine	A. M. Byers Co., Pittsburgh, Pa.	Fe; 0.02 C; 0.03 Mn; 0.12 P; 0.15 Si; 0.02 S	B, HR, P, R, S, T	C
392	Wyndaloy	Wyndale Mfg. Corp., Indianapolis, Ind.	60 Cu; 20 Ni; 20 Mn	B, CR, HR, D, P, R, T, F	C, A

No.	Material	Manufacturer	Description
CARBON & GRAPHITE			
400	International	International Graphite and Electrode Corp., St. Mary's, Pa.	Graphite. Electrodes and various shapes.
401	Karbato (Carbon)	National Carbon Co., Cleveland, Ohio	Impervious carbon.
402	Karbato (Graphite)	National Carbon Co., Cleveland, Ohio	Impervious graphite.
403	National Kompuf	National Carbon Co., Cleveland, Ohio	Carbon.
404	National Acheson	National Carbon Co., Cleveland, Ohio	Graphite.
405	Speer	Speer Carbon Co., St. Mary's, Pa.	Carbon and graphite.
406	Stackpole	Stackpole Carbon Co., St. Mary's, Pa.	Carbon and graphite.
			Impervious graphite. Pipe, fittings, pumps, valves, towers and auxiliary parts, tanks, heat exchangers, brick, raschig rings, plates, rods, etc.
			Brick, plates, blocks, tubes, cylinders, bushings, shapes.
			Tubes, pipe, rods, plates, bearings, seal rings, crucibles, heat treating boxes and molds.
			Pipe, bearings, seal rings, special shapes (injector body and nozzles.)

CEMENT, MORTAR, PUTTY

500	Sul. Cement	Generally available	Sulphur cement, silica aggregate, plasticized with Thiokol.	NOTE: Nos. 500-507 are the eight standard types of cement, or mortar, that predominate in chemical construction. Each has been rated against 55 chemicals by C. R. Payne, vice president and technical director of Atlas Mineral Products Co., who, rather than speak only for his own company's products, has consented to provide this comprehensive treatment of cements according to type. His ratings are on the conservative side.
501	Sul. Cement	Generally available	Sulphur cement, carbon aggregate, plasticized with Thiokol.	
502	Furan Cem.	Generally available	Furan derivative, silica aggregate, sets by chemical reaction.	
503	Furan Cem.	Generally available	Furan derivative, carbon aggregate, sets by chemical reaction.	
504	Phen. Cem.	Generally available	Phenol-formaldehyde, silica aggregate, sets by chemical reaction.	
505	Phen. Cem.	Generally available	Phenol-formaldehyde, carbon aggregate, sets by chemical reaction.	
506	Silicate Cem.	Generally available	Sodium silicate, silica aggregate, slow setting.	
507	Silicate Cem.	Generally available	Sodium silicate, silica aggregate, sets by chemical reaction.	
508	Acidlar	Pecora Paint Co., Philadelphia, Pa.	Firm putty.	
509	Acidlar	The Sullivan Co., Memphis, Tenn.	Pouring cements.	
510	Acidlar	Pecora Paint Co., Philadelphia, Pa.	Ready mixed cement; troweling.	
511	Alkor	Atlas Mineral Products Co., Mertztown, Pa.	Furan derivative; carbon aggregate.	
512	Alkor-S	Atlas Mineral Products Co., Mertztown, Pa.	Furan derivative; silica aggregate.	
513	Aspiz	Pennsylvania Salt Mfg. Co., Philadelphia, Pa.	Chemical hardening resin cement.	
514	Aspiz F	Pennsylvania Salt Mfg. Co., Philadelphia, Pa.	Chemical hardening resin cement.	

No.	Material	Manufacturer	Description
515	Basolit	Nukem Products Corp., Buffalo, N. Y.	Sulphur-silicate cement.
516	Carbo Korex	Atlas Mineral Products Co., Mertztown, Pa.	Phenol-formaldehyde; carbon aggregate.
517	Carboline	Carboline Co., St. Louis, Mo.	Carbonaceous resin cement.
518	Carbon Basolit	Nukem Products Corp., Buffalo, N. Y.	Sulphur-carbon cement.
519	Carbo Vitrobond	Atlas Mineral Products Co., Mertztown, Pa.	Sulphur cement; carbon aggregate.
520	Carolina	Charlotte Chemical Laboratories, Charlotte, N. C.	Acid proof cement.
521	Causplit	Pennsylvania Salt Mfg. Co., Philadelphia, Pa.	Chemical hardening resin cement.
522	Charlab	Charlotte Chemical Laboratories, Charlotte, N. C.	Chemical putty.
523	Duralon	U. S. Stoneware Co., Akron, Ohio	Furan base resin cements.
524	Durasite	U. S. Stoneware Co., Akron, Ohio	Furan base resin cements.
525	Fairprene	E. I. du Pont de Nemours & Co., Wilmington, Del.	Synthetic elastomer cement.
526	Filtros	Filtros, Inc., East Rochester, N. Y.	Acid proof cement.
527	Haveg 41-G	Haveg Corp., Newark, Del.	Quick setting, phenolic resin grouting cement.
528	Haveg 41-R	Haveg Corp., Newark, Del.	Quick setting phenolic resin cement for Haveg 41.
529	Haveg 43-HF	Haveg Corp., Newark, Del.	Quick setting phenolic resin cement for Haveg 43.
530	Haveg 60-R	Haveg Corp., Newark, Del.	Quick setting furane resin cement for Haveg 60.
531	Korex	Atlas Mineral Products Co., Mertztown, Pa.	Phenol-formaldehyde; silica aggregate.
532	Lumnite	Lumnite Div., Universal Atlas Cement Co., New York	Hydraulic cement; powder for mixing with aggregate and water to make concrete.
533	N-380 Silicate	Philadelphia Quarts Co., Philadelphia, Pa.	Sodium silicate; to be combined with special proprietary quick-setting cements at time of use.
534	N-Series	Union Bay State Chemical Co., Cambridge, Mass.	Neoprene base cements to be used as lining for tanks, etc.
535	Nukem All-Purpose	Nukem Products Corp., Buffalo, N. Y.	Resinous cement.
536	Nukem Silicate	Nukem Products Corp., Buffalo, N. Y.	Silicate cement.
537	Pecomastic	Pecora Paint Co., Philadelphia, Pa.	Putty; troweling; brushing.
538	Penchlor Acid-Proof	Pennsylvania Salt Mfg. Co., Philadelphia, Pa.	Quick setting silicate cement.
539	Penchlor Acid-Proof S25	Pennsylvania Salt Mfg. Co., Philadelphia, Pa.	Quick setting silicate cement.
540	Penchlor Fire-Proof	Pennsylvania Salt Mfg. Co., Philadelphia, Pa.	Quick setting silicate cement.
541	Pennsalt PRF	Pennsylvania Salt Mfg. Co., Philadelphia, Pa.	Chemical hardening resin cement.
542	Permanite	Maurice A. Knight, Akron, Ohio	Furane base resin cement.
543	Plastikon	B. F. Goodrich Rubber Co., Akron, Ohio	Rubber-base putty.
544	Plastite	U. S. Stoneware Co., Akron, Ohio	Calking putty.
545	Plasul Basolit	Nukem Products Corp., Buffalo, N. Y.	Plasticized sulphur-silicate cement.
546	Perox	Patterson Fdry. & Machine Co., East Liverpool, Ohio	Silicate cement.
547	Quigley	Quigley Co., New York, N. Y.	Acidproof cement.
548	Reardon	Reardon Industries, Cincinnati, Ohio	Acidproof cement.
549	Redux	Resinous Products & Chemicals Co., Philadelphia, Pa.	Metal-to-metal resin adhesive.
550	Sauereisen 31	Sauereisen Cements Co., Pittsburgh, Pa.	Acidproof cement.
551	Sauereisen 44	Sauereisen Cements Co., Pittsburgh, Pa.	Plastic; acid tank sealer.
552	Sauereisen 48	Sauereisen Cements Co., Pittsburgh, Pa.	Joint compound.
553	Silicate	Philadelphia Quarts Co., Philadelphia, Pa.	Sodium silicate; to be used with silica for acid resistant cements.
554	Silastic 121	Dow Corning Corp., Midland, Mich.	Silicone elastomers in putty form for calking.
555	Stackpole	Stackpole Carbon Co., St. Mary's, Pa.	Carbonaceous cements for carbon, graphite, and carbon-to-metal joints.
556	Stamnite	Robinson Clay Product Co., Akron, Ohio	Acidproof cement.
557	Sulsid	The Sullivan Co., Memphis, Tenn.	Pre-mixed silicate cement.
558	Tegul Vitrobond	Atlas Mineral Products Co., Mertztown, Pa.	Sulphur cement; silica aggregate.
559	Thiokol	Thiokol Corp., Trenton, N. J.	Liquid (100% solids) rubber polymers.
560	Vitrex	Atlas Mineral Products Co., Mertztown, Pa.	Sodium silicate; sets by chemical reaction.

CERAMICS

600	Acidproof Brick	Generally available *	Brick, stone, tile, rings, plates, cylinders, tower packing, tower linings, etc.
601	Alsep Glass Lining	Alsep Engineering Co., Milldale, Conn.	Glass-lined tanks, mixers and filters.
602	Ameril Fused Silica	Ameril Co., Inc., Hillside, N. J.	Fused silica ware. Pans, pipes, gas condensers, absorbers, insulators, tubes, plates.
603	Carrara	Pittsburgh Plate Glass Co., Pittsburgh, Pa.	Structural glass, flat or bent.
604	Caratherm	U. S. Stoneware Co., Akron, Ohio	Ceramic ware. Process equipment.
605	Fiberglas	Owens-Corning Fiberglass Corp., Toledo, Ohio	Fibrous glass cloth and mat. Air filters, thermal insulation, tower packing, filter cloth.
606	"General" Chemical Stoneware	General Ceramics & Steatite Corp., Keasbey, N. J.	Chemical stoneware. Tanks, kettles, pipe, fittings, valves, pumps, coils, filters, etc.
607	Glascote Glass Lining	Glascote Products, Inc., Cleveland, Ohio	Glass lined tanks and processing equipment.
608	Hanovia Fused Quarts	Hanovia Chemical & Mfg. Co., Newark, N. J.	Transparent fused quarts in all shapes.
609	Illinois Chemical Porcelain	Illinois Electric Porcelain Co., Macomb, Ill.	Ceramic chemical porcelain. Pipes, valves, fittings.
610	Knight-Ware	Maurice A. Knight, Akron, Ohio	Chemical stoneware. Tanks, kettles, pipe, fittings, valves, pumps, coils, filters, etc.
611	Lapp Porcelain	Lapp Insulator Co., Le Roy, N. Y.	Chemical porcelain. Pipe, fittings, valves, plug cocks, towers, tower packing, special shapes.
612	Pennvernon	Pittsburgh Plate Glass Co., Pittsburgh, Pa.	Window glass, flat.
613	Permaglas	A. O. Smith Corp., Milwaukee, Wis.	Glass lined steel equipment.
614	Plaudler Glass Lining	The Plaudler Co., Rochester, N. Y.	Glass-lined steel equipment.
615	Pittsburgh Plate Glass	Pittsburgh Plate Glass Co., Pittsburgh, Pa.	Polished plate glass, flat or bent.
616	Pyrex	Corning Glass Works, Corning, N. Y.	Glass. Pipe, fittings, sight glasses, gage glasses, heat resistant plate.
617	"U. S." Chemical Stoneware	U. S. Stoneware Co., Akron, Ohio	Chemical stoneware. Tanks, kettles, pipe, fittings, valves, pumps, coils, filters, etc.

* Acidproof brick and stone products are available from the following (tradenames, where they differ from name of company, are in parentheses): Acme Brick Co., Fort Worth, Tex. (Acitex, Everlast, La Perla); Alabama Clay Products Co., Birmingham, Ala.; Alberene Stone Corp. of Va., New York, N. Y.; Atlas Mineral Products Co., Mertztown, Pa.; Belden Brick Co., Canton, Ohio; Charlotte Chemical Labs., Charlotte, N. C. (Carolina); Claycraft Co., Columbus, Ohio; Custodia Construction Co., New York, N. Y. (Aco); Electro-Chemical Supply & Engineering Co., Paoli, Pa.; Filtros Inc., East Rochester, N. Y.; General Refractories Co., Philadelphia, Pa. (Acido); Harbinson-Walker Refractories Co., Pittsburgh, Pa.; B. Miffin Hood Co., Daisy, Tenn.; Kogler Brick Co., Steubenville, Ohio; Kewanee Mfg. Co., Kewanee, Wis. (Karcite, Konarock); Metropolitan Paving Brick Co., Canton, Ohio; Parker-Russell Mining & Mfg. Co., St. Louis, Mo.; Patterson Fdry. & Machine Co., East Liverpool, Ohio; Quigley Co., New York, N. Y.; Robinson Clay Product Co., Akron, Ohio; Southern Clay Mfg. Co., Chattanooga, Tenn.; Thornton Firebrick Co., Clarkburg, W. Va.

No.	Material	Manufacturer	Description
618	Vitreo	Vitreous Steel Products Co., Cleveland, Ohio	Acid resisting porcelain enameled steel. Drying and evaporating trays, miscellaneous parts.
619	Vitreous	The Thermal Syndicate Ltd., New York, N. Y.	Vitreous silica. Pipes, tubes, rods, plates, dishes, retorts, stills, HCl acid plant, and apparatus for absorption, cooling, and condensing.
620	Vitreous Enamel	Vitreous Enameling & Stamping Co., New York, N. Y.	Enameled tanks and specialties.
621	Vycor	Corning Glass Works, Corning, N. Y.	96% Silica glass. Tubing, rods, flat ware, various shapes.

PLASTICS

700	Ace Saran	Amer. Hard Rubber Co., New York, N. Y.	Vinylidene chloride. Pipe, fittings, tubing.
701	Celcon	Celanese Plastics Corp., New York, N. Y.	Ethyl cellulose.
702	Celluloid	Celanese Plastics Corp., New York, N. Y.	Cellulose nitrate.
703	Compax	Resistoflex Corp., Belleville, N. J.	Solution of compounded polyvinyl alcohol. Solution for dipping or painting.
704	DC 801-804	Dow Corning Corp., Midland, Mich.	Solvent dispersed silicone resins for coatings.
706	Formica CHN-5	Formica Insulation Co., Cincinnati, Ohio	Reinforced phenol-formaldehyde. Sheet, tube, rod.
707	Formica CN-22	Formica Insulation Co., Cincinnati, Ohio	Reinforced phenol-formaldehyde. Sheet and rod.
708	Formica LN-41	Formica Insulation Co., Cincinnati, Ohio	Reinforced melamine. Sheet, tube, rod.
709	Fortical	Celanese Plastics Corp., New York, N. Y.	Cellulose propionate.
710	Geom	B. F. Goodrich Chemical Co., Cleveland, Ohio	Polyvinyl chloride plastic.
711	Haveg 41	Haveg Corp., Newark, Del.	Phenolic-asbestos plastic. Pipe, pumps, tanks, blowers, agitators, valves, towers, coolers, fume duct, hoods.
712	Haveg 43	Haveg Corp., Newark, Del.	Furane-asbestos plastic.
713	Haveg 60	Haveg Corp., Newark, Del.	Phenolic-graphite plastic.
714	Haveg 63	Haveg Corp., Newark, Del.	Furane-graphite plastic.
715	Heresite M66	Heresite and Chemical Co., Manitowoc, Wis.	Transparent molding powder.
716	Heresite MF 48	Heresite and Chemical Co., Manitowoc, Wis.	Black molding powder.
717	Insurok	Richardson Co., Melrose Park, Ill.	Molded and laminated plastics. Sheet, rod, tube, fabricated parts, special moldings.
718	Kewosol	B. F. Goodrich Chemical Co., Akron, Ohio	Plasticized polyvinyl chloride. Sheet lining for tanks and fume ducts.
719	Kriston	B. F. Goodrich Chemical Co., Cleveland, Ohio	Allyl ester thermosetting materials.
720	Lamicaid	Mica Insulator Co., Schenectady, N. Y.	Phenolic laminate, fabric base. Sheets.
721	Lumarith	Celanese Plastics Corp., New York, N. Y.	Cellulose acetate.
722	Micarta	Westinghouse Electric Corp., Pittsburgh, Pa.	Laminated plastics, fabric or kraft base. Sheets, channels, angles, molded shapes.
723	Nixon CA (Nixonite)	Nixon Nitration Works, Nixon, N. J.	Cellulose acetate. Sheets, rods, molding powders.
724	Nixon CN (Nixonoid)	Nixon Nitration Works, Nixon, N. J.	Cellulose nitrate. Sheets, rods, tubes.
725	Nixon EC	Nixon Nitration Works, Nixon, N. J.	Ethyl cellulose. Molding powders.
726	Nukemite	Nukem Products Corp., Buffalo, N. Y.	Synthetic resin sheet and coating.
727	Nylon FM-1	E. I. du Pont de Nemours & Co., Wilmington, Del.	Injection moldings. Heat resistant injection molded parts.
728	Nylon FM-3	E. I. du Pont de Nemours & Co., Wilmington, Del.	Injection and extrusion moldings. Wire covering.
729	Nylon FM-4	E. I. du Pont de Nemours & Co., Wilmington, Del.	Injection, compression, and extrusion moldings.
730	Nylon FM-100	E. I. du Pont de Nemours & Co., Wilmington, Del.	Injection and extrusion moldings.
731	Nylon FM-101	E. I. du Pont de Nemours & Co., Wilmington, Del.	Injection, compression, and extrusion moldings. Tubing, sheeting, wire covering, gasketing.
732	Nylon FM-102	E. I. du Pont de Nemours & Co., Wilmington, Del.	Injection and extrusion moldings. Wire covering.
733	Permanite	Maurice A. Knight, Akron, Ohio	Furane base resin. Laminates, fabricated shapes.
734	Phenolite	National Vulcanized Fibre Co., Wilmington, Del.	Laminated phenolics. Sheet, tube, rod.
735	Polythene	E. I. du Pont de Nemours & Co., Wilmington, Del.	Polyethylene. Sheet, rod, tube, molding powders, film, filament. Pipe, pipe lining, gaskets, etc.
736	Pyroflex Construction	Maurice A. Knight, Akron, Ohio	Thermoplastic resin lining plus steel, brick, etc. to make a functional unit.
737	Resilon	U. S. Stoneware Co., Akron, Ohio	Bituminous linings and membranes.
738	Resistoflex	Resistoflex Corp., Belleville, N. J.	Compounded polyvinyl alcohol extruded tubing. Fiber or wire braided hose.
739	Resistoflex Compar	Resistoflex Corp., Belleville, N. J.	Compounded polyvinyl alcohol molded. Molded shapes; abrasion resistant gaskets, pump diaphragms, sand blasting mats, rollers, etc.
740	Saran	Dow Chemical Company, Midland, Mich.	Vinyl chloride-vinylidene chloride copolymer. Pipe, pipe fittings, tube, tube fittings.
741	Sealon	Maurice A. Knight, Akron, Ohio	Polyvinyl chloride elastomer. Tank linings, sheets, gaskets.
742	Teflon	E. I. du Pont de Nemours & Co., Wilmington, Del.	Polymerized tetrafluoroethylene. Rods, tubes, sheets, bradings, gaskets, thin tapes.
743	Textolite 1422	General Electric Co., Pittsfield, Mass.	Rods and plates.
744	Textolite 2001	General Electric Co., Pittsfield, Mass.	Graphited phenolic laminate. Sheet, rod, tube.
745	Textolite 2013	General Electric Co., Pittsfield, Mass.	Fabric base, phenolic laminate. Sheet, rod, tube.
746	Tygon	U. S. Stoneware Co., Akron, Ohio	Synthetic compounds. Linings, tubing, protective coatings, etc.
747	Vinlite	Celanese Plastics Corp., New York, N. Y.	Mesh reinforced plastic.
748	Vulcanized Fibre	National Vulcanized Fibre Co., Wilmington, Del.	Sheets, tubes, rod.
749	Zerok	Atlas Mineral Products Co., Mertstown, Pa.	Polyvinyl chloride. Tank linings and coatings.

RUBBER

800	Ace Hard Rubber	Amer. Hard Rubber Co., New York, N. Y.	Vulcanized rubber. Rod, sheet, tube, molded parts, linings, pipe, fittings, etc.
801	Acidseal E	B. F. Goodrich Co., Akron, Ohio	Hard rubber. Sheet lining for tanks and miscel. metal parts.*
802	Acidseal MA and PA	B. F. Goodrich Co., Akron, Ohio	Soft rubber. Sheet lining for tanks and miscel. metal parts.*
803	Armstrong	Armstrong Cork Co., Lancaster, Pa.	Gaskets.
804	Boston	Boston Woven Hose & Rubber Co., Boston, Mass.	Conveyor and transmission belt, hose, mechanical goods.
805	Butyl (GR-J)	Stanco Distributors, Inc., New York, N. Y.	Solid copolymer of isobutylene and isoprene.
806	Crane	Crane Packing Co., Chicago, Ill.	Packing and mechanical seals.
807	Custoplast	Custodis Construction Co., New York, N. Y.	Soft rubber and neoprene tank linings.
808	Dayton	Dayton Rubber Mfg. Co., Dayton, Ohio	Oilproof rubber belt, transmission belt.
809	Fairprene	E. I. du Pont de Nemours & Co., Wilmington, Del.	Sheet and coated fabric made from vulcanized neoprene. Linings, diaphragms, gaskets, packing.

No.	Material	Manufacturer	Description
810	Firestone	Firestone Tire & Rubber Co., Akron, Ohio	Vibration dampeners, adhesives, sheet, tape, hose, belting, fabric, moldings, extrusions.
812	Garlock	Garlock Packing Co., Palmyra, N. Y.	Gaskets, packings, moldings, Klosure oil seals.
813	Gates	Gates Rubber Co., Denver, Colo.	Belts, hose, moldings.
814	G. E. Silicone Rubber	General Electric Co., Pittsfield, Mass.	Sheets, extruded shapes, molded parts, coating pastes.
816	Greene-Tweed	Greene, Tweed & Co., New York, N. Y.	Packing, gaskets, sheet.
817	Heresite Rubber	Heresite & Chemical Co., Manitowoc, Wis.	Synthetic rubber coatings.
818	Hewitt	Hewitt Rubber Corp., Buffalo, N. Y.	Hose, belting, packing, moldings, extrusions.
820	Hycar (GR-A)	B. F. Goodrich Chemical Co., Cleveland, Ohio	Nitrile type synthetic rubber.
821	Jenkins	Jenkins Bros. Rubber Div., Bridgeport, Conn.	Mechanical goods, packing, valve discs, tape, moldings, extrusions.
822	Johns-Manville	Johns-Manville Sales Corp., New York, N. Y.	Gaskets.
825	Linear	Linear Packing & Rubber Co., Philadelphia, Pa.	Packing.
826	Luzerne	Luzerne Rubber Co., Trenton, N. J.	Hard rubber pipe, fittings, valves, shapes, tanks, rayon equipment.
827	Manhattan	Manhattan Rubber Mfg. Div., Passaic, N. J.	Belting, blocks, hose, pipe, rolls.
828	Neolon	Atlas Mineral Products Co., Merstoun, Pa.	Neoprene-base lining for tanks, fans, fume ducts, etc.
829	Neoprene	E. I. du Pont de Nemours & Co., Wilmington, Del.	Polymer of chloroprene. Crude neoprene for compounding and curing.
830	Parakote	Paramount Rubber Co., Detroit, Mich.	Plating rack insulation for racks to be coated at Paramount plant.
831	Paramount	Paramount Rubber Co., Detroit, Mich.	Neoprene, buna-S, natural rubber. Sheets for tank lining.
834	Parlon	Hercules Powder Co., Wilmington, Del.	Chlorinated rubbers. Used as a base for concrete paints.
835	Perbunan (GR-A)	Stanco Distributors, Inc., New York, N. Y.	Copolymer of butadiene and acrylonitrile. Solid sheets.
836	Permbond Natural (soft)	U. S. Rubber Co., New York, N. Y.	Linings for tanks, pipes, fittings, valves.
837	Permbond Natural (hard)	U. S. Rubber Co., New York, N. Y.	
838	Permbond GR-S (soft)	U. S. Rubber Co., New York, N. Y.	
839	Permbond GR-S (hard)	U. S. Rubber Co., New York, N. Y.	
840	Permbond GR-A (soft)	U. S. Rubber Co., New York, N. Y.	
841	Permbond GR-A (hard)	U. S. Rubber Co., New York, N. Y.	
842	Permbond GR-M (soft)	U. S. Rubber Co., New York, N. Y.	
843	Permbond GR-P (soft)	U. S. Rubber Co., New York, N. Y.	
844	Permbond GR-I	U. S. Rubber Co., New York, N. Y.	Rubber-lined tanks, pipe, etc.*
845	Pliowald	Goodyear Tire & Rubber Co., Akron, Ohio	
846	Saniprene	B. F. Goodrich Co., Akron, Ohio	
847	Self Vulcanizing	Self Vulcanizing Rubber Co., Chicago, Ill.	
848	Silastic 181	Dow Corning Corp., Midland, Mich.	
849	Superflexite	B. F. Goodrich Co., Akron, Ohio	
850	Stokes	Jos. Stokes Rubber Co., Trenton, N. J.	
851	Tenagrip	Amer. Winger Co., Woonsocket, R. I.	
852	Thermoid	Thermoid Rubber Div., Trenton, N. J.	Hard rubber. Sheet lining for tanks and miscel. metal parts.*
853	Thiokol (GR-P)	Thiokol Corp., Trenton, N. J.	
854	Thiokol	Thiokol Corp., Trenton, N. J.	
855	Triflex	B. F. Goodrich Co., Akron, Ohio	
856	Vistanex	Stanco Distributors, Inc., New York, N. Y.	
857	Vulcanized	Vulcanized Rubber Co., New York, N. Y.	

* In addition to the lining material named, this company produces most of the following: hose, belt, packing, gaskets, moldings, extrusions, vibration dampeners, rubber-metal bonded products, hard rubber pipe and fittings.

WOOD

900	Eastern red cedar	Following is a list of producers of wooden tanks, towers, pipe, and culverts. Companies in <i>italics</i> are members of the National Wood Tank Institute, Chicago, whose executive director, S. E. Chaney, provided all data on wood's resistance to chemicals.
901	Port Orford cedar	
902	Western red cedar	
903	White cedar	
904	Southern tidewater cypress	
905	Douglas fir (Coast type)	
906	Hard maple	
907	White oak	
908	Southern long-leaf pine	
909	Southern short-leaf pine	
910	Northern white pine	
911	Red pine	
912	Yellow poplar	
913	California redwood	
914	Spruce	

ALABAMA: Hightower Box & Tank Co., Birmingham. ARKANSAS: Fordyce-Crossett Sales Co., Fortsee; Leidl Lumber Co., Little Rock; Smith Fabricating Shop, Hot Springs. CALIFORNIA: Acme Tank Mfg. Co., Los Angeles; C. F. Braun Co., Los Angeles; Fluor Corp., Los Angeles; W. D. Hall Co., El Cajon; Hammond Lumber Co., San Francisco; Industrial Manufacturers Ltd., Los Angeles; Inman Tank, Pipe & Crossarm Co., San Leandro; Pacific Tank & Pipe Co., Oakland; Pacific Wood Tank Corp., San Francisco; Pope & Talbot Inc., San Francisco; Redwood Manufacturers Co., San Francisco; San Mateo Planing Mill, San Mateo; Union Lumber Co., San Francisco. COLORADO: Plattner Co., Denver; Stearns-Roger Mfg. Co., Denver. CONNECTICUT: G. H. Manville Pattern & Model Co., Waterbury. FLORIDA: G. M. Davis & Sons, Palatka; Timber Fabrications, Miami. GEORGIA: McCarr-Turner Co. ILLINOIS: Batavia Metal Products Co., Batavia; Benson Cooling Tower Co., Chicago; Blinks Mfg. Co., Chicago; California Redwood Distributors, Chicago; U. S. Challenge Co., Batavia; Chicago Wooden Tank Co., Chicago; J. P. Devine Mfg. Co., Mt. Vernon; Eagle Tank Co., Chicago; Johnson & Carlson, Chicago; C. Jacobson & Co., Chicago; Lord & Bushnell Lumber Co., Chicago; McKee Bros. Co., Chicago; E. W. Schmeling & Sons, Chicago; Technical Plywoods, Chicago; Wendnagel & Co., Chicago; Whyte-Coleman Co., Chicago. IOWA: Beckman Bros., Des Moines; Dultmeier Tank Co., Manning; Iowa Wind Mill & Pump Co., Cedar Rapids; Kretschmer Mfg. Co., Council Bluffs; Storm Lake Tank & Silo Co., Storm Lake; Wheeler Lumber, Bridge & Supply Co., Des Moines. KANSAS: Perdue Tank Co., Wichita; J. F. Pritchard & Co., Kansas City; Scherer Mfg. Co., Kansas City; Souder Tank Co., Madison; Stevens Tank Co., Wichita. KENTUCKY: W. E. Caldwell Co., Louisville. LOUISIANA: Lincoln Tank Co., Shreveport; McGuffin Tank Co., Shreveport; Moran Tank Co., Shreveport. MAINE: Stevens Tank & Tower Co., Auburn. MARYLAND: Baltimore Cooperage Tank & Tower Co., Baltimore; Economy Silo & Mfg. Co., Frederick; John Eppler Co., Baltimore; Maryland Engineering Co., Pikesville. MASSACHUSETTS: Rodney Hunt Machine Co., Orange; James Hunter Machine Co., North Adams; E. D. Jones & Sons Co., Pittsfield; New England Tank & Tower Co., Everett; Plymold Corp., Lawrence; Riggs

& Lombard Inc., Lowell; J. C. Roy Lumber Co., Chicopee; A. T. Stearns Lumber Co., Boston. MICHIGAN: Kalamazoo Tank & Silo Co., Kalamazoo; Michigan Pipe Co., Bay City. MINNESOTA: Midway Lumber Co., St. Paul; Terminal Mfg. Co., St. Paul; Twin City Tank, Silo, & Specialty Co., Minneapolis. MISSOURI: Lillie-Hoffman Cooling Towers Inc., St. Louis; Schubert-Christy Corp., Afton; Water Cooling Equipment Corp., St. Louis. NEBRASKA: Nebraska Bridge Supply & Lumber Co., Omaha. NEW HAMPSHIRE: Improved Paper Machinery Corp., Nashua; Nashua Milling Corp., Nashua. NEW JERSEY: Acme Tank Co., Jersey City; Atlantic Tank Corp., North Bergen; A. J. Corcoran Inc., Jersey City; General Tank Works Inc., Kearney; Hanson-Van Winkle-Manning Co., Matawan. NEW YORK: Arrow Tank Co., Buffalo; M. C. Bascom & Co., Bolivar; Carley Heater Co., Olean; J. Holland & Sons, Brooklyn; Howard Wood Tank Co., Brooklyn; F. E. Hudson & Sons, Buffalo; Hydro & Chemical Tank Co., New York; David Isaacs & Sons, Brooklyn; O. G. Kelley & Co., New York; Mayer Tank Mfg. Co., Brooklyn; Market Mfg. Co., Syracuse; Noble & Wood Machine Co., Hoosick Falls; Peerless Tank & Tower Co., New York; Phillips Cooling Tower Co., New York; Sandy Hill Iron & Brass Works, Hudson Falls; U. S. Plywood Corp., New York; Wenneis Tank Co., New York; Wilcox-Johnson Tank Co., Victor; A. Wyckoff & Son Co., Elmira. OHIO: Black-Clawson Co., Hamilton; Brown Lumber Co., Massillon; Hausser-Stander Tank Co., Cincinnati; Harvey Locher Lumber Co., Canton; Shurtle Bros. Machine Co., Middletown. OKLAHOMA: Black, Sivalis & Bryson Inc., Oklahoma City; National Tank Co., Tulsa; Parkersburg Rig & Reel Co., Tulsa; Producers Tank Co., Seminole. OREGON: Beall Pipe & Tank Corp., Portland; Cottage Grove Lumber Co., Cottage Grove; National Pipe & Tank Co., Portland. PENNSYLVANIA: Downingtown Mfg. Co., Downingtown; Eastern Wood Products Co., Williamsport; Everett Forest Products Co., Everett; Amos H. Hall & Sons, Philadelphia; H. K. Porter Co., Pittsburgh; E. F. Schlichter Co., Philadelphia; C. H. Wheeler Mfg. Co., Philadelphia; Woolford Wood Tanks, Darby. TENNESSEE: O. G. Kelley & Co., Johnson City; James E. Stark Co., Memphis. TEXAS: Axtell Co., Fort Worth; Cowser & Stark Co., Dallas; Drane Tank Co., Fort Worth; Federal Tank Co., Midland; Hayward Tank Co., Greggton; Hudson Engineering Corp., Houston; Martin Tank Co., Corsicana; M & V Tank Co., Wichita Falls; Alexander Schroeder Hardwood Lumber Co., Houston; Tex Well Equipment Mfg. Co., Fort Worth; Well Machinery & Supply Co., Fort Worth; Wilborne Bros. Co., Amarillo. WASHINGTON: American Wood Pipe Co., Tacoma; Brooks Lumber Co., Bellingham; Brooks Tank Co., Everett; Cascade Pipe & Flume Co., Seattle; Federal Pipe & Tank Co., Seattle; Horizontal Stave Tank Co., Seattle; Robinson Wood Tank Co., Bellingham; Weyerhaeuser Sales Co., Tacoma; Whatcom Falls Mill Co., Bellingham. W. VIRGINIA: Parkersburg Rig & Reel Co., Parkersburg. WISCONSIN: Beloit Iron Works, Beloit; Dunck Tank Works, Milwaukee; Frank Hamechek Machine Co., Keweenaw; Nekooza Foundry & Machine Works, Nekooza; Charles H. Stehling Co., Milwaukee; Stoelting Mfg. Co., Kiel.

CHEMICAL RESISTANCE

Of Construction Metals and Non-Metals

From data supplied by the manufacturers the editors of *Chemical Engineering* have compiled this table showing the resistance of materials to 24 common and troublesome chemicals. Also shown are some of the important applications in which the materials are being used. Now a word of caution. Corrosion involves many more variables than this or any table can possibly recognize. These data should never be construed as anything more than an aid in narrowing the field of materials that are worth investigation.

NO.	MATERIAL	RATINGS	EXPOSURE CONDITIONS	APPLICATIONS	No.	Material	Rating	Exposure Conditions	Applications
<p>Significance of Non.: 1-3xx Metals 4xx Carbon 5xx Cement 6xx Ceramics 7xx Plastics 8xx Rubber 9xx Wood To further identify material look up No. in Directory of Materials</p>									
<p>Ratings are those of materials manufacturers. A, good F, fair V, varies depending on conditions X, unsuitable</p>									
<p>* = Deg. F. % = Concentration Rm. = Room temp. Conc. = Concentrated Dil. = Dilute Sol. = Solution p.s.i. = lb./sq. in. —L = Lined</p>									
<p>B, Bodies of pumps and valves L, Impellers V, Valve trim P, Piping T, Tanks S, Shipping containers C, Condensing surfaces H, Heating surfaces D, Ducts for fumes F, Fans and blowers R, Tower packing</p>									
ACETIC ACID									
5	Admiralty	A			140	Durichlor	A	All %; any temp.	BIVPCHFR
4	Admiralty	V		CH	141	Durimet	A	All %; any temp.	BIVHF
6	Admic	A	All %; 70-212°		142	Durimet	A	All %; any temp.	BIVHF
10-17	Aluminum	A	All %; Rm.	BIPTSDF	143	Duriron	A	All %; any temp.	BIVPHFR
		A	Glacial; 212°	BIPTCHDF	148	Everdur	F		BIVFR
19	Alloyco	A	All to 100%; boil.	BV	149	Everdur	F		PTCHDR
		A	Vapors; 30, 100%; hot	BV	150	Everdur	F		PCH
22	Ambralloy	F		CH	156	Gold	A	0.5-100%; any temp.	
23	Ambralloy	F		CH	159	Hastelloy	A	All %; any temp.	BIVPTCH
24	Ambralloy	V		CH	160	Hastelloy	A	All %; any temp.	BIVPTCHDF
29-40	Ampco	A	All %; cold; crude or pure	BIVPTCHDF	161	Hastelloy	A	All %; any temp.	BIVPTCHDF
		V	Vapors		162	Hastelloy	A	All %; any temp.	BIVP
51	Berylo	A	Non-aerated		163	Stellite	A	All %; any temp.	BIV
54	Brass	X			165	Stellite	A	All %; any temp.	BIV
61	Brass	X			184	Inconel	F	5, 50%; aerated; 80°	C
63	Brass	A-F		PCH			F	5, 50%; unsaturated; boil.	
66	Brass	A					F	80%; storage	
73	Brass	F		VT	196, 200, 266	Lead	A	Glacial; boil.	C
74	Brass	F		V	216	Monel	V	Conc. or glacial; unsaturated	PT
75	Brass	F		VP			X	5%; aerated; 80°	
76	Brass	F		Instruments			A	5, 80%; unsaturated; boil.	BIVPTCH
77	Brass	X					A	80%; storage	
81	CA-FA20	A	Glacial; boil.	BIVP	219	Moniz	X	Glacial; boil.	
82	CA-MM	A	Glacial; boil.	BIVP	224	Nickel	X	5%; aerated; 80°	
86	Cast Iron	V	Crude				F	5, 80%; unsaturated; boil.	BVPTH
87	Cassul	F	150° max.	B			F	80%; storage	
88	Chlorimet	A	All %; any temp.	BIVCHF	225	Ni-Clad	A	Glacial; boil.	BTSC
89	Chlorimet	A	All %; any temp.	BIVCHF	226	Nick-Sil.	F		Instruments
111	Copper	A			231	Ni-Resist	X	5%; aerated; 80°	
114	Copper	F		PTCHR			X	5%, 80%; unsaturated; boil.	
117	Copper	V		S	233	NS-5	A	Dil.; impure; 150° max.	V
118	Copper	A			234	Olympic	A		
119	Corrosion	A	All %; Rm.	BIPHDF	235	Olympic	A		
123	Cupro-Ni	F		CH	236	Palladium	A	0.5-100%; any temp.	
124	Cupro-Ni	A			240	Platinum	A	0.5-100%; any temp.	
139	Darco	A	All %; any temp.	BIVHF	242	Ir-Plat.	A	0.5-100%; any temp.	
					244	Rh-Plat.	A	0.5-100%; any temp.	
					245	Pyrasteel	V		BIVPTSCHF
					249	Resistac	A	Glacial, conc. sol. only	BIVCHP
					266	Lead	V	In absence of oxygen	PT
					268	Silver	A	0.5-100%; any temp.	
					270	304-Clad	A	Over 15%; boil.	BTSC
							A	All %; 70°	
					271	316-Clad	A	All %; 70°	BTSC
					274	430-Clad	A	Over 15%; boil.	BTSC
							A	All conc.; 70°	
					275	St. 301	V	All %; Rm.	
					276	St. 302	V	All %; Rm.	

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
		A	All %; 70°	VTSCDF	403	Kempruf	A	All %; any temp.	PTDR
		X	Over 15%; boil.		404	Acheson	A	All %; any temp.	PTDR
		X	33%; 100% vapors; hot		500	Sul. cement	A	200° max.	D, T, towers, trenches, floors, pipe joints
		A	10%; 50%; 100%; boil.						
		F	80%; boil.		501	Sul. cement	A	200° max.	Same as above
		X	100%; 400°; at 150 p.s.i.		502	Furan cem.	A	360° max.	Same as above
		A	Weak or medium		503	Furan cem.	A	360° max.	Same as above
		A	Conc.; cold		504	Phen. cem.	A	360° max.	Same as above
278	St. 383	X	Conc.; boil.		505	Phen. cem.	A	360° max.	Same as above
279	St. 384	V	All %; Rm.		506	Silicate cem.	F	360° max.	Same as above
		V	All %; Rm.		507	Silicate cem.	A	360° max.	Same as above
		A	All %; 70°	VTSCDF	508	Acichlor	V	Dil. and conc.; 300° max.	
		X	Over 15%; boil.		510	Acitite	A	Dil. and conc.; 2,500° max.	
		A	20%; and 100%; 100°	P	513	Asplit	A	All %; 350° max.	
		F	Glacial; boil.	BIVP	514	Asplit-F	A	All %; 350° max.	
280	St. 388	V	All %; Rm.		515	Basolit	A	200° max.	T
281	St. 389	V	All %; Rm.		517	Carbolime	A		
282	St. 310	V	All %; Rm.		518	C-Basolit	A	200° max.	T
		A	5-100%; 70°	P	521	Causplit	A	All %; 350° max.	
		A	20%; and 100%; 100°	P	523	Duralon	A	350° max.	BIPTCHDF
283	St. 316	V	All %; boil. (total immersion)	BIVPTCHDF	524	Durisite	A	350° max.	BIPTCHDF
		A	All %; 70°		535	Nukem	A	350° max.	T
		A	Over 15%; boil.		536	Nukem	A		T
		A	33% vapors; hot		537	Pecomastic	F	Dil. and conc.; 300° max.	F
		X	100% vapors; hot		538	Penchlor	A	All %; 750° max.	
		A	20%; and 100%; 100°		539	Penchlor	A	All %; 750° max.	
		A	Glacial; boil.	BIVP	540	Penchlor	A	All %; 500°-2,000°	
		A	All %; 70° and boil.		541	Pennsalt	A	All %; 350° max.	
284	St. 317	A	100%; 400°; at 150 p.s.i.		542	Permanite	A	360° max.	TD
		V	All %; boil. (total immersion)	BIVPTCHDF	544	Plastite	F	175° max.	PTSD
		A	5-100%; 70°	P	545	P-Basolit	A	200° max.	T
		A	20%; and 100%; 100°	P	554	Silastic	A	(ASTM D-543-43)	
285	St. 321	V	All %; Rm.		556	Staminite	A	All %; any temp.	TD
286	St. 347	V	All %; Rm.	PT	559	Thiokol	V	150° max.	
287	St. 403	V	Glacial, 10%; Rm.		600	Acid Brick	A	1,200° max.	TDR
288	St. 405	V	Glacial, 10%; Rm.		603, 612, 615	Glass	A		THDR
290	St. 410	V	Glacial, 10%; Rm.		604	Ceratherm	A	200-400° depending on design	BIPTSCHDFR
		F	Glacial; boil.	BIVP	606	Stoneware	A	All conditions	BIVPTCHDFR
		A	10%; 70°		607	Glass-L	A	600° max.	PTCH
		A	All %		610	Stoneware	A	All %; any temp.	BIVPTCHDR
291	St. 414	V	Glacial, 10%; Rm.		611	Porcelain	A	All %; any temp.	BIPFDR
292	St. 416	V	Glacial, 10%; Rm.		614	Glass-L	A	All %; boil.; agitated	BTCH
		A	All %		616	Pyrex	A		
293	St. 418	V	Glacial, 10%; Rm.		617	Stoneware	A	140-160°	BIPTSCHDFR
294	St. 420	V	Glacial, 10%; Rm.		618	Vitreo	A	1,000° max.	
		A	All %		619	Vitreasil	A		
295	St. 430	V	Glacial; boil. (total immersion)		621	Vycor	A		
		V	35%; Rm.		700	Ace Saran	A		P
		A	All %; 70°	VTSCHDFP	703	Compac	X		
		X	Over 15%; boil.		704	DC Silicone	A	ASTM D-543-43	HD
		A	20%; and 100%; 100°	P	713	Haveg	A	All %; Rm. and boil.	BIVPTDFR
		A	100%; boil.		715	Heresite	A	200° max.	
		A	Weak		716	Heresite	A	200° max.	
		X	Medium or strong		720	Lamicaid	A		T
296	St. 430F	V	Glacial; boil. (total immersion)		723	Nixon	X	5%; 77°	
		V	33%; Rm.		724	Nixon	A	5%; 77°	S
297	St. 431	V	Glacial; boil. (total immersion)		725	Nixon	A	5%; 77°	S
		V	33%; Rm.		726	Nukemite	A	5%; Rm.	PTSDF
298	St. 440A	V	Glacial; boil. (total immersion)		727, 728	Nylon	A	Weak	
		V	33%; Rm.		729-732	Nylon	X		
300	St. 440C	V	Glacial; boil. (total immersion)		733	Permanite	A	360° max.	BVPTD
		V	33%; Rm.		736	Pyroflex	V		PTCHD
301	St. 442	V	Glacial; boil. (total immersion)		737	Resilon	F	175° max.	PTSD
		V	33%; Rm.		738	Resistoflex	X		
303	St. 446	V	Glacial; boil. (total immersion)		739	Resistoflex	X		
		V	33%; Rm.		740	Saran	A	77°	PD
309	St. CC-35	A	100%; Rm.-boil.		741	Sealon	A	Dil.; 160° max.	BPTDF
316	St. CF-20	A		BIV					
322	Still Met	A		BIVP					
324	Stoody	A	10%-conc.; boil.	VF	742	Teflon	A	Rm.	VP
325	Stoody	A	10%-conc.; boil.	IVF	743	Textolite	A	Dil.-conc.; Rm.	T
327	Super-Ni	F		PTCH	744, 745	Textolite	F	Dil.; 77-122°; total immersion	BI
328	Tantalum	A	All %; 392° max.	CH			X	Conc.; 77-122°; total immersion	
329	Telnic	A			746	Tygon	V	Low conc.	BIPTSCDF
330	Tuf-Stuf	F	Cold	BIV	800	Ace Hd. Rub.	A		BIVPTDF
337	Stainless	A	All %		802	Acidseal	A	All %; 150° max.	BIPTDF
338	Stainless	A	Weak; cold		805	Butyl	A	30%; Rm.	
		X	Weak; boil.		809	Fairprene	V		
		X	Medium or strong		814	GE Silicone	A	Dil.; Rm.	VIPT
339	Stainless	A	All %				X	Conc.; Rm.	
390	Worthite	A	All conditions	BIVPC	817	Heresite	A	Glacial to 86°	
392	Wyndaley	A	All %; 68°		836	Natural (S)	V		
401	Karbate	A	All %; to boil.	BIVPTCHDR	837	Natural (H)	A		
402	Karbate	A	All %; to boil.	BIVPTCHDR	838	GR-S (S)	V		

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
839	GR-S (H)	A			282	St. 310	V		
840	GR-A (S)	X			283	St. 316	A		BIVPTSCH
841	GR-A (H)	V					A	10%; any temp.	VTCHDF
842	GR-M (S)	X					A	10%; boil.	BIVP
843	GR-P (S)	X					A	Sat.; boil.	
844	GR-I	V			284	St. 316	A		BIVPTSCH
848	Silastic	A	(ASTM D-543-43)		285	St. 321	V		
853	Thiokol	V	150° max.	T	286	St. 347	V		
854	Thiokol	X			287	St. 403	V		
856	Triflex	A	30%; Rm.		288	St. 405	V		
913	Redwood	A	40-80%; Rm.; 45 yr.	T	290	St. 410	V		
		A	30-40%; Rm.; Shellacked; food	T			X	10%; boil.	
		A	2-20%; 36-165° max.; lithography	T	291	St. 414	V		
		A	10%; 68-110°; Asphalt-L; vinegar	T	292	St. 416	V		
		A	10%; 36-80°; Asphalt-L; vinegar	T	293	St. 418	V		
		A	10%; 75-120°; 23 yr.; food	T	294	St. 420	V		
		A	10%; 70°; 18 yr.; vinegar	T	295	St. 430	V		
		A	6-10%; 60-90°; 13 yr.; food	T			X	10%; any temp.	
		A	8-10%; 75°; Paraffined; 30 yr.; food	T			A	10%; 70°	
		A	2-5%; 36-80°; Painted; photo film	T			F	10%; boil.	
							X	Sat.; boil.	
					296	St. 430F	V		
					297	St. 431	V		
					298	St. 440A	V		
					300	St. 440C	V		
					301	St. 442	V		
					303	St. 446	V		
					316	St. CF-20	A		
					318	St. CF-7C	A	10%; Rm.-boil.	
					319	St. CF-7M	A	10%; Rm.-boil.	
					367	Super-Ni	A		PTCH
					368	Tantalum	A		Not used commer.
					369	Telnic	A		
					390	Worthite	A	All conditions	BIV
					401	Karbate	A	All %; to boil.	BIPH
					402	Karbate	A	All %; to boil.	BIPH
					403	Komprud	A	All %; any temp.	T
					404	Acheson	A	All %; any temp.	T
					500	Sul. cement	V	200° max.	D, T, towers trenches, floors, pipe joints.
					501	Sul. cement	V	200° max.	Same as 500
					502	Furan cem.	V	360° max.	Same as 500
					503	Furan cem.	V	360° max.	Same as 500
					504	Phen. cem.	V	360° max.	Same as 500
					505	Phen. cem.	V	360° max.	Same as 500
					506	Silicate cem.	V	1,600° max.	Same as 500
					507	Silicate cem.	V	1,600° max.	Same as 500
					513	Asplit	A	All %; 350° max.	
					514	Asplit-F	A	All %; 350° max.	
					515	Basolit	A	200° max.	T
					518	C-Basolit	A	200° max.	T
					521	Causplit	A	All %; 350°	
					523	Duralon	A	350° max.	BIPTCHDF
					524	Durisite	A	350° max.	BIPTCHDF
					532	Larmite	A	10% max.; 90° max.	TD
					534	N-Series	A	Sat.; 160°	BIVPTCDF
					535	Nukem	A	350° max.	T
					536	Nukem	F		T
					538	Penchior	A	All %; 750° max.	
					539	Penchior	A	All %; 750° max.	
					540	Penchior	A	All %; 800-2,000°	
					541	Pennsalt	A	All %; 350° max.	
					542	Permanite	A	300° max.	TD
					544	Plastite	A	175° max.	PTSD
					545	P-Basolit	A	200° max.	T
					559	Thiokol	A		
					600	Acid Brick	A	1,300° max.	
					603, 612, 615	Glass	A		THDR
					604	Ceratherm	A	200-400° depending on design	BIPTSCHDFR
					606	Stoneware	A	All conditions	BIVPTCHDFR
					607	Glass-L	A	600° max.	PTCH
					611	Porcelain	A	All %; any temp.	BIPTDR
					614	Glass-L	A	All conc.; 250° max.; agitated	BTCH
					616	Pyrex	A		
					617	Stoneware	A	140-460°	BIPTSCHDFR
					618	Vitreo	A	1,000° max.	
					621	Vycor	A		
					700	Ace Saran	A		P
					711	Harog	A	All %; 300° max.	BIVPTDFR
					713	Harog	A	All %; 300° max.	BIVPTDFR
					715	Heresite	A	300° max.	
					716	Heresite	A	300° max.	
					718	Koroseal	A	All %; 150° max.	TD

ALUM

3	Admiralty	A		
4	Admiralty	F		CH
6	Admic	A	70°	
10-17	Aluminum	AF	Rm.	BIPTSDF
19	Alloyco	A	10%; mt.; boil.	BV
22	Ambralay	F		CH
23	Ambralay	F		CH
24	Ambralay	F		CH
29-49	Ampco	A		BIVTCHDF
51	Beryles	A		
54	Brass	X		
61	Brass	X		
63	Brass	AF		FCH
66	Bronze	A		
73	bronze	F		VT
74	Bronze	F		V
75	Bronze	F		VP
76	Bronze	F		
77	Bronze	X		
81	CA-FA29	A	10%; boil.	BIVP
82	CA-MM	A	10%; boil.	BIVP
86	Cast Iron	X		
111	Copper	A		
114	Copper	F		PTCHR
118	Copper	A		
119	Corrosion	A	10%; Rm.	BIP
123	Cupro-Ni	A		CH
124	Cupro-Ni	A		
139	Durco	A	All %; any temp.	BIVHF
140	Durichlor	A	All %; any temp.	BIVPCHFR
141	Durimet	A	All %; any temp.	BIVHF
142	Durimet	A	All %; any temp.	BIVHF
143	Durimet	A	All % and temp.	BIVPHFR
148	Everdur	F		BIVR
149	Everdur	F		PTCHDR
150	Everdur	F		FCH
156	Gold	A	All %; any temp.	
194, 206, 266	Lead	A	All %	BIPTH
217	Monel-Clad	A		BTSCH
219	Muntz	X		
225	Ni-Clad	A		BTSCH
226	Nick-Sil	F		
234	Olympic	A		
235	Olympic	A		
236	Palladium	A	All %; any temp.	
240	Platinum	A	All %; any temp.	
242	Ir-Plat.	A	All %; any temp.	
244	Rh-Plat.	A	All %; any temp.	
245	Pyrasteel	A		BIVPTSCHDF
268	Silver	A	All %; any temp.	
270	304-Clad	A	10% max.	BTSCH
271	316-Clad	A	10% max.	BTSCH
275	St. 301	V		
276	St. 302	V		
		A	10%; any temp.	VTSCDF
		F	Sat.; boil.	
278	St. 303	V		
279	St. 304	V		
		A	10%; any temp.	VTSCDF
		A	10%; boil.	BIVP
280	St. 308	V		
281	St. 309	V		

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
720	Lamicaid	A		T	240	Platinum	A		
726	Nukemite	A	150° max.	PTSDF	242	Ir-Plat.	A		
733	Permanite	A	300° max.	BVPDT	244	Rh-Plat.	A		
737	Resilon	A	175° max.	PTSD	245	PyraSteel	X		
742	Teflon	A	Rm.	VP	249	Resistac	A		BIVCHF
746	Tygon	A	All %; 180° max.	BIPTSCDF	246	Lead	A		TO
800	Ace Hd. Rub.	A		BIVPTDF	268	Silver	A		
801	Acidseal	A	All %; 150° max.	BIPTSDF	275	St. 301	X		
802	Acidseal	A	All %; 150° max.	BIPTSDF	276	St. 302	X		
805	Butyl	A	Dry salt; aqueous sol. at Rm.		278	St. 303	X		
809	Fairprene	A			279	St. 304	X		
817	Heresite	A	Sat.; 212° max.		280	St. 305	X		
835	Perbunan	A	Dry salt; aqueous sol. at Rm.		281	St. 309	X		
836	Natural (S)	A			282	St. 310	X		
837	Natural (H)	A			283	St. 316	V		
838	GR-S (S)	A			284	St. 317	V		
839	GR-S (H)	A			285	St. 321	X		
840	GR-A (S)	A			286	St. 347	X		
841	GR-A (H)	A			287	St. 403	X		
842	GR-M (S)	A			288	St. 405	X		
843	GR-P (S)	X			290	St. 410	X		
844	GR-I	A			291	St. 414	X		
846	Saniprene	A	All %; 150° max.	BIPTSDF	292	St. 416	X		
849	Superflex.	A	All %; 150° max.	BIPTSDF	293	St. 418	X		
853	Thiokol	A	150° max.	T	294	St. 420	X		
854	Thiokol	A		PTSCDF	295	St. 430	X		
855	Triflex	A	All %; 150° max.	BIPTSDF	296	St. 430-F	X		
856	Triflex	A	Dry salt; aqueous sol. at Rm.		297	St. 431	X		
					298	St. 440-A	X		
					300	St. 440-C	X		
					301	St. 442	X		
					303	St. 446	X		
					316	St. CF-20	A		BIV
					319	St. CF-7M	A	Sat.; 100°	
					367	Super-Ni.	F		PTCH
					368	Tantalum	A		Not used commer.
					369	Telnic	V		
					390	Worthite	F	Cold, weak	BIV
					401	Karbate	A	All %; to boil.	BIVPH
					402	Karbate	A	All %; to boil.	BIVPH
					403	Kempul	A	All %; any temp.	TR
					404	Acheson	A	All %; any temp.	TR
					500	Sul. cement	A	Solutions; 200° max.	PT
					501	Sul. cement	A	Solutions; 200° max.	PT
					502	Furan cement	A	Solutions; 360° max.	PT
					503	Furan cement	A	Solutions; 360° max.	PT
					504	Phen. cement	A	Solutions; 360° max.	PT
					505	Phen. cement	A	Solutions; 360° max.	PT
					506	Silicate cement	A	Solutions; 1600° max.	PT
					507	Silicate cement	A	Solutions; 1600° max.	PT
					513	Asplit	A	All %; 350° max.	
					514	Asplit-F	A	All %; 350° max.	
					515	Basolit	A	200° max.	T
					517	Carbolime	A		
					518	C-Basolit	A	200° max.	T
					521	Causplit	A	All %; 350° max.	
					523	Duralon	A	350° max.	BIPTCHDF
					524	Durite	A	350° max.	BIPTCHDF
					534	N-Series	A	25%; Rm.	BIVPTCDF
					535	Nukem	A	350° max.	T
					536	Nukem	A		T
					538	Penchlor	A	All %; 750° max.	
					539	Penchlor	A	All %; 750° max.	
					540	Penchlor	A	All %; 500°-2,000°	
					541	Ponnsalt	A	All %; 350° max.	
					542	Permanite	A		TD
					544	Plastite	A	175° max.	PTSD
					545	P-Basolit	A	200° max.	T
					554	Silastic	A	ASTM D-543-43	
					556	Staminite	A	All %	TD
					559	Thiokol	X		
					600	Acid Brick	A	1,200° max.	TDR
					603, 612, 615	Glass	A		THDR
					604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR
					606	Stoneware	A	All conditions	BIVPTCHDFR
					607	Glass-L	A	600° max.	PTCH
					610	Stoneware	A	All %; any temp.	BIVPTCHDR
					611	Porcelain	A	All %; any temp.	BIPTDR
					614	Glass-L	A	All %; 250° max.; agitation	BTCH
					616	Pyrex	A		
					617	Stoneware	A	140°-160°	BIPTSCHDFR
					618	Vitreo	A	1,000° max.	
					619	Vitrosil	A		
					621	Vycor	A		

ALUMINUM CHLORIDE

3	Admiralty	V		
4	Admiralty	F		CB
6	Admic	A	70°	
10-17	Aluminum	V	Sol.; rm.	
22	Ambraloy	F		CH
23	Ambraloy	F		CH
24	Ambraloy	F		CH
29-40	Ampco	A		BIVPTCHDF
42	Antaciron	A	All conditions	BIV
54	Brass	X		
61	Brass	X		
63	Brass	FV		PCH
66	Bronze	V		
73	Bronze	F		VT
74	Bronze	F		V
75	Bronze	F		VP
76	Bronze	F		Instruments
77	Bronze	X		
88	Chlorimet	A	All % and temp.	BIVCHF
89	Chlorimet	A	All %; moderate temp.	BIVCHF
111	Copper	V		
114	Copper	F		PTCHR
118	Copper	V		
123	Cupro-Ni	F		CH
124	Cupro-Ni	V		
139	Durco	A	All % at moderate temp.	BIVHF
140	Durichlor	A	All % and temp.	BIVPCHFR
141	Durimet	A	All % at moderate temp.	BIVHF
142	Durimet	A	All % at rm.	BIVHF
143	Duriron	A	All % and temp.; 140 preferred	BIVPHFR
148	Everdur	F		BIVR
149	Everdur	F		PTCHDR
150	Everdur	F		PCH
156	Gold	A		
159	Hastelloy	A	All %; 160° max.	BIVPT
160	Hastelloy	A	All %; any temp.; also as dry catalyst with organics up to 300°	BIVPTCHDF
161	Hastelloy	A	All %; 125° max.	BIVPT
162	Hastelloy	A	Rm. max.	V
163	Stellite	A	Moist; rm. max.; dry; 300° max.	BIV
165	Stellite	F	Moist; rm. max.; dry; 300° max.	BIV
184	Inconel	V	26%; 65°	
196, 200, 266	Lead	A		TC
216	Monel	A	20%; 65°	VT
217	Monel-Clad	A		BTSCH
219	Muntz	X		
224	Nickel	A	65%; 65°	
226	Nick-Sil.	F		Instruments
231	Ni-Resist	F	26%; 65°	
234	Olympic	V		
235	Olympic	V		
236	Palladium	A		

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
700	Ace Saran	A		P	139	Durco	A	All % and temp.	BIVHF
704	DC Silicone	A	ASTM D-543-43	HD	140	Durichlor	A	All % and temp.	BIVPCHFR
711	Haveg	A	All %; 300° max.	BIVPTDFR	141	Durimet	A	All % and temp.	BIVHF
713	Haveg	A	All %; 300° max.	BIVPTDFR	142	Durimet	A	All % and temp.	BIVHF
715	Harosite	A	200° max.		143	Duriron	A	All % and temp.	BIVPHFR
716	Harosite	A	200° max.		148	Everdur	A	Dry	BIVR
718	Karocel	A	All %; 150° max.	TD			X	Moist	
720	Lamicaid	A		T	149	Everdur	A	Dry	PTCHDR
726	Nukemite	A	150° max.	PTSDF			X	Moist	
733	Permanite	A	300° max.	BVPDT	150	Everdur	A	Dry	PCH
736	Pyroflex	A		PTCHD			X	Moist	
737	Resilon	A	175° max.	PTSD	156	Gold	A	All % and temp.	
741	Suslon	A	100° max.	BPTDF	159	Hastelloy	A	Wet; any temp.	BIVYTCB
742	Teflon	A	Rm.	VP	160	Hastelloy	A	Wet; any temp.	BIVPTCH
746	Tygon	A	180° max.	BIPTSCDF	161	Hastelloy	A	Wet; any temp.	BIVPTCH
800	Ace Hd Rubber	A			162	Hastelloy	A	Wet; any temp.	BIVPS
801	Acidocel	A	All %; 150° max.	BIPTSDF	163	Stellite	A	Wet; any temp.	BIV
802	Acidocel	A	All %; 150° max.	BIPTSDF	165	Stellite	A	Wet; any temp.	BIV
805	Butyl	A	Dry salt; aqueous sol.; rm.		184	Inconel	A	All %; 70°	
809	Fairprene	A			185	Inc-Clad	A		BTSCH
817	Harosite	A	Sat.; 212° max.		216	Monel	A	2.7%; 70°; aerated	(VP, anhyd.) (V, aqua)
835	Perbunan	A	Dry salt; aqueous sol.; rm.				X	10%; 70°; aerated	
836	Natural (S)	A			217	Monel-Clad	A		BTSCH
837	Natural (H)	A			219	Muntz	A	Dry	CH
838	GR-S (S)	A					X	Moist	
839	GR-S (H)	A			224	Nickel	A	Hydioxide; 1.1%; 70°; aerated	P
840	GR-A (S)	A					X	Hydioxide; 2.7%; 70°; aerated	
841	GR-A (H)	A					X	Hydioxide; 10%; 70°; aerated	
842	GR-M (S)	A			225	Ni-Clad	A		BTSCH
843	GR-P (S)	X			226	Nick-Sil	A	Dry	Instruments
844	GR-I	A					X	Moist	
846	Saniprene	A	All %; 150° max.	BIPTSDF	231	Ni-Resist	A	All %; 70°	(BV, anhyd.) (BIV, aqua)
848	Silastic	A	ASTM D-543-43				X		
849	Superflex	A	All %; 150° max.	BIPTSDF	234	Olympic	X		
853	Thiokol	V	150° max.	T	235	Olympic	X		
854	Thiokol	V	150° max.	PTSCDF	236	Palladium	A	All % and temp.	
855	Triflex	A	All %; 150° max.	BIPTSDF	240	Platinum	A	All % and temp.	
856	Vistanex	A	Dry salt; aqueous sol.; rm.		242	Ir-Plat.	A	All % and temp.	
AMMONIA					244	Rh-Plat.	A	All % and temp.	
3	Admiralty	X			245	Pyrasteel	A		BIVPTSCHF
4	Admiralty	A	Dry	CH	268	Silver	A	Oxygen-free sol. to 100°	
		X	Moist				X	Over 100°; anhydrous	
6	Admic	V			279	304-Clad	A	All %; 70°	BTSCH
10-17	Aluminum	AV	All %; Rm., boil.	BIPTSCHDF	271	316-Clad	A	All %; 70°	BTSCH
		A	Dry	BIPTSCHDF	274	430-Clad	A	All %; 70°	BTSCH
22	Ambralay	A	Dry	CH	275	St. 301	A		BIVTSCB
		X	Moist		276	St. 302	A	All %; 70°	BIVTSCB
23	Ambralay	A	Dry	CH			X	Gas; hot	VTSCDF
		X	Moist				A	Sp. gr. 0.91; 70°; boil. gas liquor	
24	Ambralay	A	Dry	CH	278	St. 303	A		TV
		X	Moist		279	St. 304	A		BIVPTSCHDF
54	Brass	A	Dry	CH			A	All %; 70°	VTSCDF
		X	Moist				X	Gas; hot	
61	Brass	A	Dry	VCH			A	Conc.; 70°	BIVPT
		X	Moist		280	St. 308	A		BIVPTSCHDF
63	Brass	A	Dry	PCH	281	St. 309	A		BIVTSCBDF
		X	Moist		282	St. 310	A		BIVPTSCHDF
66	Bronze	X			283	St. 316	A		BIVPTSCHDF
73	Bronze	A	Dry	VT			A		VTCHDF
		X	Moist				A	Conc.; 70°	BIVPT
74	Bronze	A	Dry	V	284	St. 317	A		BIVPTSCHDF
		X	Moist		285	St. 321	A		BIVPT
75	Bronze	A	Dry	VP	286	St. 347	A		BIVPTSCHDF
		X	Moist		287	St. 403	A		IV
76	Bronze	A	Dry	Instruments	288	St. 405	A		BIVTSCBDF
		X	Moist		290	St. 410	A		BIVPTSCHDF
77	Bronze	A	Dry	PCH			A	Conc.; 70°	BIVP
		X	Moist		291	St. 414	A		IV
81	CA-FA20	A	Conc. sol.; 70°	BIVP	292	St. 416	A		IV
82	CA-MM	V	Conc. sol.; 70°	BIVP	293	St. 418	A		
85	Cast Iron	A	Aqua		294	St. 420	A		
86	Cast Iron	A			295	St. 430	A		BIVPTSCHDF
88	Chlorimet	A	All % and temp.	BIVCHF			X	Gas; hot	
89	Chlorimet	A	All % and temp.	BIVCHF			A	All %; 70°	VTSCBDF
111	Copper	X					A	Sp. gr. 0.91; 70°; boil. gas liquor	
114	Copper	A	Dry	PTCHR	296	St. 430-F	A		IV
		X	Moist		297	St. 431	A		IV
118	Copper	X			298	St. 440-A	A		
123	Cupro-Ni	A	Dry	CH	300	St. 440-C	A		IV
		X	Wet		301	St. 442	A		BIVTSCBDF
124	Cupro-Ni	F			303	St. 446	A		BIVPTSCHDF
127-133	Dowmetal	A	Liquid or hydrosol		313	St. CF-7	A	All %; Rm.-boil.	

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
318	St. CF-7C	A	All %; Rm.-boil.		849	Superflux	A	Up to sat.; 150° max.; in water	BIPTDF
319	St. CF-7M	A	All %; Rm.-boil.		853	Thiokol	V	150° max.	T
338	St. CK-25	A	All %; Rm.-boil.		854	Thiokol	A	150° max.	PTSCDF
367	Super-Ni	A	Dry	PTCH	AMMONIUM SULPHATE				
		V	Moist	PTCH	3	Admiralty	F		
368	Tantalum	X			4	Admiralty	V		CH
369	Telnic	X			6	Admic	V	All %; 70°	
401	Karbate	A	All %; to boil.	BIVPCHF	10-17	Aluminum	A	5% max.; Rm.	PT
402	Karbate	A	All %; to boil.	BIVPCHF			A	Dry powders	
403	Kempul	A	All %; any temp.		19	Alloyco	A	10% Sat.; boil.	BV
404	Acheson	A	All %; any temp.				A	Plus free H ₂ SO ₄ @ 150°	BV
500	Sul. cement	F	200° max.	T	22	Ambralay	V		CH
501	Sul. cement	F	200° max.	T	23	Ambralay	V		CH
502	Furan cement	A	300° max.	PT	24	Ambralay	V		CH
503	Furan cement	A	300° max.	PT	29-40	Amuco	A		BIVPTSCHDF
504	Phen. cement	A	300° max.	PT	54	Brass	X		
505	Phen. cement	A	300° max.	PT	61	Brass	X		
506	Silicate cement	X	1,600° max.		63	Brass	VF		FCH
507	Silicate cement	X	1,600° max.		66	Bronze	F		
508	Acichlor	A	Dilute and conc.; 300° max.		73	Bronze	V		VT
510	Acithe	V	Dilute and conc.; 250° max.		74	Bronze	V		V
513	Asplit	A	All %; 350° max.		75	Bronze	V		VP
514	Asplit-F	A	All %; 350° max.		76	Bronze	V		Instruments
515	Basolit	X			77	Bronze	X		
518	C-Basolit	X			81	CA-FA20	A	10%; boil.	BIVP
521	Causplit	A	All %; 350° max.		82	CA-MM	A	10%; boil.	BIVP
523	Duralon	A	350° max.	BIPTCHDF	85	Cast Iron	A		
524	Durisite	A	350° max.	BIPTCHDF	86	Cast Iron	A		
535	Nukem	A		T	88	Chlorimet	A	All % and temp.	BIVCHF
536	Nukem	A		T	89	Chlorimet	A	All % and temp.	BIVCHDF
539	Penchlor	A	All %; 750° max.		111	Copper	F		
541	Pennsalt	A	All %; 350° max.		114	Copper	V		PTCHR
542	Permanite	A		TD	117	Copper	V		P
544	Plastite	V	175° max.	PTSD	118	Copper	F		
545	P-Basolit	X			119	Corrosiron	A	25%; Rm.	BIP
554	Silastic	A	ASTM D-543-43		123	Cupro-Ni	V		CH
556	Staminit	X			124	Cupro-Ni	F		
559	Thiokol	A	150° max.		139	Durco	A	All % and temp.	BIVHF
600	Acid Brick	A		TDR	140	Durichlor	A	All % and temp.	BIVPCHFR
603, 612, 615	Glass	A		THDR	141	Durimet	A	All % and temp.	BIVHF
604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR	142	Durimet	A	All % and temp.	BIVHF
606	Stoneware	A	Not commonly used		143	Duriron	A	All % and temp.	BIVPHFR
607	Glass-L	V		PTCH	148	Everdur	V		BIVP
610	Stoneware	A	All %; any temp.	BIVPTCHDR	149	Everdur	V		PTCHDR
611	Porcelain	A	All % and temp.	BIPTDR	150	Everdur	V		PCH
614	Glass-L	V		BTCH	159	Hastelloy	A	All % to 180°	BIVPT
617	Stoneware	A	140°-160°	BIPTSCHDFR	160	Hastelloy	A	All % to boil.	BIVPTCH
618	Vitreo	V	1,000° max.		161	Hastelloy	A	All % to boil.	BIVPTCH
619	Vitrosil	A			162	Hastelloy	A	All % to boil.	BIVP
700	Ace Saran	X			163	Stellite	A	All %; Rm.	BIV
703	Compax	X			165	Stellite	A	All %; Rm.	BIV
704	DC Silicone	A	ASTM D-543-43	HD	184	Inconel	A	Sat. plus 5% sulphuric; 150°	
706	Ferunica	A	Conc.; Rm.	PTF	193, 196, 200, 266	Lead	A	Various %; Rm.	PT
713	Haveg	A	300° max.	BIVPTDFR	216	Monel	A	Sat. plus 5% sulphuric; 150°	BIVPTHDF
715	Heresite	A	200° max.		217	Monel-Clad	A		BTSCH
716	Heresite	A	200° max.		219	Muntz	X		
729	Lamicaid	A		T	224	Nickel	F	Sat. plus 5% sulphuric; 150°	PH
726	Nukemite	A		PTSDF	225	Ni-Clad	A		BTSCH
727	Nylon	A			226	Nick-Sil.	V		Instruments
728	Nylon	A			231	Ni-Resist	A	Sat. plus 5% sulphuric; 150°	BIV
729-732	Nylon	A			234	Olympic	F		
733	Permanite	A	260° max.	BVPDT	235	Olympic	F		
736	Pyroflex	A		PTCHD	245	PyraSteel	V		BIVPTSCHF
737	Resilon	V	175°	PTSD	249	Resistac	A		BIVCHF
738	Resistoflex	X			270	304-Clad	A	1, 5%; 70°	BTSCH
739	Resistoflex	X			271	316-Clad	A	1, 5%; 70°	BTSCH
740	Saran	X	77°		274	430-Clad	A	1, 5%; 70°	BTSCH
741	Sealon	A	160° max.	BPTDF	275	St. 301	A		BIVTSCH
742	Teflon	A	Rm.	VP	276	St. 302	A		BIVTSCH
746	Tygon	V	180° max.	BIPTSCDF			X	1%; 50%; 70°	VTSCDF
800	Ace Hd Rubber	A		BIVPTDF	278	St. 303	A	10% Sat.; boil.	
801	Acidseal	A	Up to sat.; 150° max.; in water	BIPTDF			A	10%; Sat. cold; boil.	IV
817	Heresite	A	Sat.; 212° max.; aqueous sol.		279	St. 304	A		BIVPTSCHDF
836	Natural (S)	A					A	1%; 5%; 70°	VTSCDF
837	Natural (H)	A					X	10% Sat.; boil.	
838	GR-S (S)	A					A	10%; boil.	BIVP
839	GR-S (H)	A			280	St. 308	A		BIVPTSCH
840	GR-A (S)	A			281	St. 309	A		BIVTSCH
841	GR-A (H)	A			282	St. 310	A		BIVPTSCH
842	GR-M (S)	A			283	St. 316	A		BIVPTSCH
843	GR-P (S)	X					X	10% Sat.; boil.	
844	GR-I	A							
846	Saniprene	A	Up to sat.; 150° max.; in water	BIPTDF					
848	Silastic	A	ASTM D-543-43						

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
		A	10%; Sat. cold; boiling		742	Teflon	A	Rm.	VP
		A	10%; boil.	BIVP	746	Tygon	A	180° max.	BIPTSCDF
284	St. 317	A		BIVPTSCH	800	Ace Hd. Rubber	A		BIVPTDF
285	St. 321	A		BIVPTSCH	801	Acidseal	A	All %; 150° max.	BIPTDF
286	St. 347	A		BIVPTSCH	802	Acidseal	A	All %; 150° max.	BIPTDF
287	St. 403	F	Rm.		809	Fairprene	A		
288	St. 405	F			817	Heresite	A	Sat.; 212° max.	
290	St. 410	F	Rm.		836	Natural (S)	A		
		X	10%; boil.		837	Natural (H)	A		
291	St. 414	F	Rm.		838	GR-S (S)	A		
292	St. 416	F	Rm.		839	GR-S (H)	A		
293	St. 418	F	Rm.		840	GR-A (S)	A		
294	St. 420	F	Rm.		841	GR-A (H)	A		
295	St. 430	A		BIVPTSCHDF	842	GR-M (S)	A		
		A	1%; 50%; 70°	VTSCHDF	843	GR-P (S)	X		
296	St. 430-F	A		IV	844	GR-I	A		
297	St. 431	A		IV	846	Saniprene	A	All %; 150° max.	BIPTDF
298	St. 440-A	A			848	Silastic	A	ASTM D-543-43	
300	St. 440-C	A		IV	849	Superflex	A	All %; 150° max.	BIPTDF
301	St. 442	A		BIVTSCH	853	Thiokol	A	150° max.	T
303	St. 446	A		BIVPTSCH	854	Thiokol	A	150° max.	PTSCDF
316	St. CF-20	A		BIV	855	Triflex	A	All %; 150° max.	BIPTDF
318	St. CF-7C	A	Conc.; Rm.-boil.						
319	St. CF-7M	A	Conc.; Rm.-boil.						
367	Super-Ni	F		PTCH					
368	Tantalum	A		Not used commer.					
369	Telair	F							
390	Worthite	A	All %; any temp.	BIV	3	Admiralty	A		
401	Karbato	A	All %; to boil.	BIVPH	4	Admiralty	A		CH
402	Karbato	A	All %; to boil.	BIVPH	6	Admic	A		
403	Kempul	A	All %; any temp.		10-17	Aluminum	A	Rm., boil.	BIPTSCHDF
404	Acheson	A	All %; any temp.		22	Ambralay	A		CH
500	Sul. cement	A	200° max.	PT	23	Ambralay	A		CH
501	Sul. cement	A	200° max.	PT	24	Ambralay	A		CH
502	Furan cement	A	360° max.	PT	29-40	Ampco	A		BIVPTCHDF
503	Furan cement	A	360° max.	PT	51	Berylico	A		
504	Phon. cement	A	360° max.	PT	54	Brass	A		CH
505	Phon. cement	A	360° max.	PT	61	Brass	A		VCH
506	Silicate cement	V	1,600° max.	T	63	Brass	A		PCH
507	Silicate cement	V	1,600° max.	T	66	Bronze	A		
513	Asplit	A	All %; 350° max.		73	Bronze	A		VT
514	Asplit-F	A	All %; 350° max.		74	Bronze	A		V
515	Basolit	A	200° max.	T	75	Bronze	A		VP
517	Carbolino	A			76	Bronze	A		Instruments
518	C-Basolit	A	300° max.	T	77	Bronze	A		PCH
521	Causplit	A	All %; 350° max.		85	Cast Iron	A		
523	Durinox	A	350° max.	BIPTCHDF	86	Cast Iron	A		
524	Durinox	A	350° max.	BIPTCHDF	87	Causal	A	All %; any temp.	R
532	Lumnite	A		TD	88	Chlorimet	A	All % and temp.	BIVCHF
535	Nukem	A		T	89	Chlorimet	A	All % and temp.	BIVCHF
536	Nukem	A		T	111	Copper	A		
539	Penchlor	A	All %; 750° max.		114	Copper	A		PTCHR
541	Pennsalt	A	All %; 350° max.		117	Copper	A		P
542	Permanite	A		TD	118	Copper	A		
544	Plastite	A	175° max.	PTSD	123	Capro-Ni	A		CH
545	P-Basolit	A	200° max.	T	124	Capro-Ni	A		
554	Silastic	A	ASTM D-543-43		127-133	Downmetal	A		
559	Thiokol	A	150° max.		139	Durco	A	All % and temp.	BIVHF
600	Acid Brick	A		TDR	140	Durichlor	A	All % and temp.	CHFR
603, 612, 615	Glass	A		THDR	141	Durimet	A	All % and temp.	BIVHF
604	Ceratherm	A	300°-400°, depending on design	BIPTSCHDFR	142	Durimet	A	All % and temp.	BIVHF
606	Stoneware	A	All conditions	BIVPTCHDFR	143	Duriron	A	All % and temp.	BIVPHFR
607	Glass-L	A	600° max.	PTCH	148	Everdur	A		BIVR
610	Stoneware	A	All %; any temp.	BIVPTCHDR	149	Everdur	A		PTCHDR
611	Porcelain	A	All % and temp.	BIPTDR	150	Everdur	A		PCH
614	Glass-I	A	All %; under 302°; agitation	BTCH	156	Gold	A	Any temp. to cracking temp.	
616	Pyrex	A			159	Hastelloy	A	All conc. to boil.	
617	Stoneware	A	140°-160°	BIPTSCHDFR	160	Hastelloy	A	All conc. to boil.	
618	Vitreo	A	1,000° max.		161	Hastelloy	A	All conc. to boil.	
621	Vycor	A			162	Hastelloy	A	All conc. to boil.	
700	Ace Saran	A		P	163	Stellite	A	All conc. to boil.	BIV
704	DC Silicone	A	ASTM D-543-43	HD	165	Stellite	A	All conc. to boil.	BIV
711	Haveg	A	All %; 300° max.	BIVPTDFR	184	Inconel	A	Boil.	
713	Haveg	A	All %; 300° max.	BIVPTDFR	216	Monel	A	Boil.	VC
715	Heresite	A	300° max.		216	Monel-Clad	A		BTSCH
716	Heresite	A	300° max.		219	Muntz	A		CH
718	Koresol	A	All %	TD	224	Nickel	A	Boil.	T
720	Lamicaid	A		T	225	Ni-Clad	A		BTSCH
726	Nukemite	A		PTSD	226	Nick-Sil	A		Instruments
733	Permanite	A	360° max.	BVPTD	231	Ni-Resist	A	Boil.	BI
736	Pyroflex	A		PTCHD	234	Olympic	A		
737	Resilon	A	175° max.	PTSD	235	Olympic	A		
740	Saran	A	77°		236	Palladium	A	Any temp. to cracking temp.	
741	Sealon	A	100° max.	BPTDF	240	Platinum	A	Any temp. to cracking temp.	
					245	Ir-Plat.	A	Any temp. to cracking temp.	
					246	Rh-Plat.	A	Any temp. to cracking temp.	

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
245	Pyrasteel	A		BIVPTSCHF	616	Pyrex	A		
268	Silver	A	Any temp. to cracking temp.		617	Stoneware	A	140°-160°	BIPTSCHDFR
270	304-Clad	A	All %; any temp.	BTSCH	618	Vitreo	A	1,000° max.	
271	316-Clad	A	All %; any temp.	BTSCH	621	Vycor	A		
274	430-Clad	A	All %; any temp.	BTSCH	700	Ace Saran	F		P
275	St. 301	A		BIVTSCHDF	703	Compax	A	Conc.; -40° to boils	TD
276	St. 302	A		BIVTSCHDF	704	DC Silicone	X	ASTM D-543-43	BIVPTDFR
		A	Hot		713	Haveg	A	All conditions	
		A	Any temp.	VTSCDF	715	Heresite	A	200° max.	
278	St. 303	A		IV	716	Heresite	A	200° max.	
279	St. 304	A		BIVPTSCHF	718	Karozeal	X		
		A	Any temp.	VTSCDF	720	Lamicaid	A		T
280	St. 308	A		BIVPTSCHF	723	Nixon	A	77°	
281	St. 309	A		BIVTSCHDF	724	Nixon	A	77°	S
282	St. 310	A		BIVPTSCHDF	733	Permanite	A	360° max.	BVPDT
283	St. 316	A		BIVPTSCHF	736	Pyroflex	V		PTCHD
		A	Hot		737	Resilon	X		
		A	Any temp.	VTCHDF	738	Resistoflex	A	Conc.; to boils	P
284	St. 317	A		BIVPTSCHF	739	Resistoflex	A	Conc.; 275° max.	IVP
285	St. 321	A		BIVPTSC	740	Saran	V	77°	
286	St. 347	A		BIVPTSCH	741	Sealon	X		
287	St. 403	A		IV	742	Teflon	A	Rm.	VP
288	St. 405	A		BIVTSC	744	Textolite	A	77°-122°	BI
290	St. 410	A		BIVPTSCHF	745	Textolite	A	77°-122°	BI
291	St. 414	A		IV	746	Tygon	X		
292	St. 416	A		IV	800	Ace Hd. Ru.	X		
293	St. 418	A			801	Acidseal	X		
294	St. 420	A			802	Acidseal	X		
295	St. 430	A		BIVPTSCHDF	805	Butyl	X		
		A	Any temp.	VTSCDF	817	Heresite	X		
296	St. 430-F	A		IV	835	Perbunan	V		
297	St. 431	A		IV	836	Natural (S)	X		
298	St. 440-A	A			837	Natural (H)	X		
300	St. 440-C	A		IV	838	GR-S (S)	X		
301	St. 442	A		BIVTSCHDF	839	GR-S (H)	X		
303	St. 446	A		BIVPTSCHF	840	GR-A (S)	X		
308	St. CB-36	A	High temp.		841	GR-A (H)	F		
367	Super-Ni	A		PTCH	842	GR-M (S)	X		
368	Tantalum	A		Not used commerc.	843	GR-P (S)	V		
369	Telnic	A			844	GR-I	X		
401	Karbate	A	All %; to boil.	BIVP	846	Saniprene	X		
402	Karbate	A	All %; to boil.	BIVP	848	Silastic	X		
403	Kemperul	A	All %; any temp.	T	849	Superflex	X		
404	Acheson	A	All %; any temp.	T	853	Thiokol	F	150° max.	T
500	Sul. cement	X			854	Thiokol	V	150° max.	PTSCHF
501	Sul. cement	X			855	Triflex	X		
502	Furan cement	A	360° max.	PTD	856	Vistanex	X		
503	Furan cement	A	360° max.	PTD					
504	Phen. cement	A	360° max.	PTD					
505	Phen. cement	A	360° max.	PTD					
506	Silicate cement	F	1,000° max.	TD					
507	Silicate cement	F	1,600° max.	TD					
508	Acichlor	X							
510	Acrite	F	Dilute and conc.; 250° max.						
513	Asplu	A	All %; 350° max.						
514	Asplu-F	A	All %; 350° max.						
515	Basolu	A		T					
517	Carbolino	A							
518	C-Basolu	A		T					
521	Causplu	A	All %; 350° max.						
523	Duralon	A	350° max.	BIPTCHDF					
524	Durite	A	350° max.	BIPTCHDF					
534	N-Series	X							
535	Nukem	A		T					
536	Nukem	A		T					
537	Pecomastic	X							
538	Penchlor	A	All %; 750° max.						
539	Penchlor	A	All %; 750° max.						
540	Penchlor	A	All %; 800°-2,000°						
541	Pennsalt	A	All %; 350° max.						
542	Permanite	A		TD					
544	Plaxite	X							
545	P-Basolu	A		T					
554	Silastic	X	ASTM D-543-43						
556	Staminite	A	All %	T					
559	Thiokol	X							
600	Acid Brick	A		TDR					
603, 612, 615	Glass	A		THDR					
604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR					
606	Stoneware	A	Not commonly used						
607	Glass-L	A	600° max.	PTCH					
610	Stoneware	A	All %; any temp.	BIVPTCHDR					
611	Porcelain	A	All % and temp.	BIPTDR					
614	Glass-L	A	Under 302°; agitation	BTCH					

BROMINE

3	Admiralty	A	Dry	
		V	Moist	
4	Admiralty	A	Dry	CH
		V	Moist	
6	Admic	A	Dry gas	
10-17	Aluminum	X		
22	Ambraloy	A	Dry	CH
		V	Moist	
23	Ambraloy	A	Dry	CH
		V	Moist	
24	Ambraloy	A	Dry	CH
		V	Moist	
29-40	Ampco	V		
54	Brass	A	Dry	CH
		X	Moist	
61	Brass	A	Dry	VCH
		X	Moist	
63	Brass	A	Dry	PCH
		V	Moist	
66	Bronze	A	Dry	
		V	Moist	
73	Bronze	A	Dry	VT
		V	Moist	
74	Bronze	A	Dry	V
		V	Moist	
75	Bronze	A	Dry	VP
		V	Moist	
76	Bronze	A	Dry	Instruments
		V	Moist	
77	Bronze	A	Dry	PCH
		X	Moist	
88	Chlorimet	A	Dry; all temp.	BIVCHF
		X	Wet	

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
89	Chlorimet	A	Dry; all temp.	BIVCHF	300	St. 440-C	X		
		X	Wet		301	St. 442	X		
111	Copper	A	Dry		303	St. 446	X		
		V	Moist	PTCHR	367	Super-Ni	A	Dry	PTCH
114	Copper	A	Dry				V	Moist	
		V	Moist		368	Tantalum	A	302° max.	CH
118	Copper	A	Dry		369	Telnic	A	Dry	
		V	Moist				V	Moist	
123	Cupro-Ni	A	Dry	CH	390	Worthite	X		
		V	Moist		401	Karbata	V		
124	Cupro-Ni	A	Dry		403	Kempul	V		
		V	Moist		500	Sul. cement	F	120° max.	T
127-133	Dowmetal	A*	Dry		501	Sul. cement	F	120° max.	T
139	Durco	X			502	Furan cement	F	360° max.	T
140	Durichlor	X			503	Furan cement	F	360° max.	T
141	Durimet	X			504	Phen. cement	F	360° max.	T
142	Durimet	X			505	Phen. cement	F	360° max.	T
143	Duriron	X			506	Silicate cement	F	1,600° max.	T
148	Everdur	A	Dry	BIVR	507	Silicate cement	F	1,600° max.	T
		V	Moist		513	Asplit	X		
149	Everdur	A	Dry	PTCHDR	514	Asplit-F	X		
		V	Moist		515	Basolit	A		T
150	Everdur	A	Dry	PCH	518	C-Basolit	A		T
		V	Moist		523	Duralon	X		
154	Gold	X			524	Durite	X		
159	Hastelloy	F	Dry only		535	Nukem	X		
160	Hastelloy	A	HBr; any temp.	BIVPTCH	536	Nukem	A		T
161	Hastelloy	A	Wet gas; Rm. only	BIVPTCH	538	Penchlor	A	All %; 750° max.	
162	Hastelloy	F	Dry only		539	Penchlor	A	All %; 750° max.	
163	Stellite	A	Wet gas; Rm. only	BIV	540	Penchlor	A	All %; 500°-2,000°	
165	Stellite	A	Wet gas; Rm. only	BIV	541	Pennsalt	X		
164	Inconel	A	Dry		542	Permanite	X		
		X	Wet		544	Plastite	V	175° max.	PTSD
216	Monel	A	Dry		545	P-Basolit	A		T
		X	Wet		554	Silastic	X	ASTM D-543-43	
219	Muntz	A	Dry	CH	559	Thiokol	X		
		X	Moist		600	Acid Brick	A		TDR
224	Nickel	A	Dry		603, 612, 615	Glass	A		THDR
		X	Wet		604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR
226	Nick-Sil.	A	Dry	Instruments	606	Stoneware	A	All conditions	BIVPTCHDFR
		V	Moist		607	Glass-L.	A	600° max.	PTCH
231	Ni-Resist	A	Dry		610	Stoneware	A	All %; any temp.	BIVPTCHDR
		X	Wet		611	Porcelain	A	All % and temp.	BIPTDR
234	Olympic	A	Dry		614	Glass-L.	V	Under 212°; small capacity units	BTCH
		V	Moist		616	Pyrex	A		
235	Olympic	A	Dry		617	Stoneware	A	140°-160°	BIPTSCHDFR
		V	Moist		618	Vitreo	V	1,000° max.	
240	Platinum	A	Rm.		619	Vitrosil	A		
		X	Elevated temp.		621	Vycor	A		
242	Ir-Plat.	A	Rm.		700	Aco Saran	X	Liquid	
		X	Elevated temp.		703	Compar	X		
244	Rh-Plat.	A	Rm.		704	DC Silicone	X	ASTM D-543-43	
		X	Elevated temp.		711	Haveg	X		
245	Pyrasteel	A		BIVPTSCHF	715	Heresite	A	200° max.	
268	Silver	X			716	Heresite	A	200° max.	
275	St. 301	X			729	Lamicaid	X		
276	St. 302	X			726	Nukemite	A		PTBDF
		X	70°		733	Permanite	X		
		X	70°; Bromine water		736	Pyroflex	V		PTCHD
278	St. 303	X			737	Resilon	V	173° max.	PTSD
279	St. 304	X			738	Resistoflex	X		
		X	70°; Bromine water		739	Resistoflex	X		
280	St. 308	X			740	Saran	X	77°	
281	St. 309	X			741	Sesalon	A	160° max.	BPTDF
282	St. 310	X			742	Teflon	A	Rm.	VP
283	St. 316	X			746	Tygon	V	180° max.	
		X	70°		805	Butyl	X		
		X	70°; Bromine water		809	Fairprene	X		
284	St. 317	X			817	Heresite	V	Sat.; 212° max.	
285	St. 321	X			835	Perbunan	X		
286	St. 347	X			836	Natural (S)	V		
287	St. 403	X			837	Natural (H)	V		
288	St. 405	X			838	GR-S (S)	V		
290	St. 410	X			839	GR-S (H)	V		
291	St. 414	X			840	GR-A (S)	V		
292	St. 416	X			841	GR-A (H)	V		
293	St. 418	X			842	GR-M (S)	V		
294	St. 429	X			843	GR-P (S)	X		
295	St. 430	X			844	GR-I	V		
		X	70°		848	Silastic	X		
		X	70°; Bromine water		853	Thiokol	X		
296	St. 436-F	X			854	Thiokol	X		
297	St. 431	X			856	Vistanex	X		
298	St. 440-A	X							

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
CALCIUM HYPOCHLORITE					292	St. 416	X		
3	Admiralty	V			293	St. 418	X		
4	Admiralty	F		CH	294	St. 420	X		
6	Admic	V	Dil. sol.; 70°		295	St. 430	X		
10-17	Aluminum	V	Rm.				A	2%; 70°	VTCHDF
22	Ambralay	F		CH	296	St. 430-F	X		
23	Ambralay	F		CH	297	St. 431	X		
24	Ambralay	F		CH	298	St. 440-A	X		
29-40	Ampro	F	May be erratic	BIVPTCHDF	300	St. 440-C	X		
42	Anticiron	A	All conditions		301	St. 442	X		
54	Brass	X			303	St. 446	X		
61	Brass	X			367	Super Ni	F		PTCH
63	Brass	FV		PCH	368	Tantalum	A		Not used commer.
66	Bronze	V			369	Telnic	V		
73	Bronze	F		VT	390	Worthite	A	All %; any temp.	BIV
74	Bronze	F		V	401	Karbate	A	70% max.	BIV
75	Bronze	F		VP	402	Karbate	A	70% max.	BIV
76	Bronze	F		Instruments	403	Kemprud	F	All %; any temp.	
77	Bronze	X			404	Acheson	F	All %; any temp.	
81	CA-FA20	A	2%; 70°	BIVP	500	Sul. cement	F	Dilute sol.; low temp. only	T
82	CA-MM	X	2%; 70°		501	Sul. cement	F	Dilute sol.; low temp. only	T
85	Cast Iron	A			502	Furan cement	F	Dilute sol.; low temp. only	T
86	Cast Iron	V			503	Furan cement	F	Dilute sol.; low temp. only	T
88	Chlorimet	X			504	Phen. cement	F	Dilute sol.; low temp. only	T
89	Chlorimet	A	All %; moderate temp.	BIVCHF	505	Phen. cement	F	Dilute sol.; low temp. only	T
111	Copper	V			506	Silicate cement	X		
114	Copper	F		PTCHR	507	Silicate cement	X		
117	Copper	V	Dil. sol.	P	513	Asplit	A	All %; 350° max.	
118	Copper	V			514	Asplit-F	A	All %; 350° max.	
123	Cupro-Ni	F		CH	515	Basolit	A		T
124	Cupro-Ni	V			518	C-Basolit	A		T
139	Duroc	V	All % and temp.	BIVHF	521	Causplit	A	All %; 350° max.	
140	Durichlor	A	All % and temp.	BIVPCHFR	523	Duralon	V	350° max.	BIPTCHDF
141	Durimet	V	All % and temp.	BIVHF	524	Duriste	V	350° max.	BIPTCHDF
142	Durimet	V	All % and temp.	BIVHF	535	Nukem	A	350° max.	T
143	Duriron	A	All % and temp. (140 preferred)	BIVPHFR	536	Nukem	A		T
148	Everdur	F		BIVR	538	Penchlor	A	All %; 750° max.	
149	Everdur	F		PTCHDR	539	Penchlor	A	All %; 750° max.	
150	Everdur	F		PCH	540	Penchlor	A	All %; 500°-2,000°	
159	Hastelloy	X			541	Pennsalt	A	All %; 350°	
160	Hastelloy	X			542	Permanite	V		TD
161	Hastelloy	A	Rm. only	BIVPTSC	544	Plastite	A	175° max.	TPSD
162	Hastelloy	X			545	P-Basolit	A		T
163	Stellite	A	Rm. only	BIV	554	Silastic	F	ASTM D-543-43	
165	Stellite	X			559	Thiokol	X		
184	Inconel	A	3 g.p.l. max. free Cl ₂ ; 70°		600	Acid Brick	A		TDR
		X	Over 3 g.p.l. free Cl ₂ ; 70°		603, 612, 615	Glass	A		THDR
216	Monel	A	3 g.p.l. max. free Cl ₂ ; 70°	V	604	Ceratherm	A	200°-400°, depending on design	BIPTCHDFR
		X	Over 3 g.p.l. free Cl ₂ ; 70°		606	Stoneware	A	All conditions	BIVPTCHDFR
219	Muntz	X			607	Glass-L	V		PTCH
224	Nickal	A	3 g.p.l. max. free Cl ₂ ; 70°		610	Stoneware	A	All %; any temp.	BIVPTCHDR
		X	Over 3 g.p.l. free Cl ₂ ; 70°		611	Porcelain	A	All % and temp.	BIPTDR
226	Nick-Sil.	F		Instruments	614	Glass-L	V	Under 77°; agitation	BTCH
231	Ni-Resist	A	0.07%; 60°	BIV	616	Pyrex	A		
		X	Over 3 g.p.l. free Cl ₂ ; 70°		617	Stoneware	A	140°-160°	BIPTSCHDFR
233	NS-5	A	Bleach liquor; cold	V	618	Vitreo	A	1,000° max.	
234	Olympic	V			621	Vycor	A		
235	Olympic	V			700	Ace Saran	A		P
240	Platinum	A	All temp.		704	DC Silicone	F	ASTM D-543-43	HD
242	Ir-Plat.	A	All temp.		713	Haveg	F	All conditions	BIVPTDFR
244	Rh-Plat.	A	All temp.		715	Heresite	A	5% at 70°	
245	Pyrasteel	V		BIVPTSCHF	716	Heresite	A	5% at 70°	
275	St. 301	V			720	Lamicaid	X		
276	St. 302	V			726	Nukemite	A		PTSDF
		A	2%; 70°	VTSCDF	733	Permanite	V	360° max.	BVPDT
278	St. 303	V			736	Pyroflex	A		PTCHD
279	St. 304	V			737	Resilon	A	175° max.	PTSD
		A	2%; 70°	VTSCDF	740	Saran	F	77°	
		V	2%; 70°	BIVP	741	Sealon	A	160° max.	BPTDF
280	St. 308	V			742	Teflon	A	Rm.	VP
281	St. 309	V			746	Tygon	A	180° max.	BIPTSCDF
282	St. 310	V			800	Ace Hd. Rub.	A		BIVPTDF
283	St. 316	A		BIPTS	801	Acidseal	A	All %; 150° max.	BIPTDF
		A	2%; 70°	VTCHDF	805	Butyl	V		
284	St. 317	A		VP	809	Fairprene	V		
285	St. 321	V			817	Heresite	A	Sat.; 212° max.	
286	St. 347	V			835	Perbunan	V		
287	St. 403	X			836	Natural (S)	V		
288	St. 405	X			837	Natural (H)	V		
290	St. 410	X			838	GR-S (S)	V		
		X	2%; 70°		839	GR-S (H)	V		
291	St. 414	X			840	GR-A (S)	V		
					841	GR-A (H)	V		
					842	GR-M (S)	X		

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
843	GR-P (S)	X			224	Nickel	A	Boil.	TCH
844	GR-I	V			225	Ni-Clad	A	Pure	BTSCH
846	Saniprene	A	All %; 150° max.	BIPTDF	226	Nick-Sil.	A	Dry	Instruments
848	Silastic	F	ASTM D-543-43				X	Moist	
849	Superflex	A	All %; 150° max.	BIPTDF	231	Ni-Resist	A	Boil.	BIV
853	Thiokol	X			233	NS-S	A	Any temp.	V
854	Thiokol	F	150° max.	PTSCDF	234	Olympic	A	Dry	
856	Vistana	V					V	Moist	
CARBON TETRACHLORIDE									
3	Admiralty	A	Dry		245	PyraSteel	V		BIVPTSCHF
		V	Moist		268	Silver	A	All temp.	
4	Admiralty	A	Dry	CH	270	304-Clad	A	Pure; 70°	BTSCH
		F	Moist		271	316-Clad	A	Pure; 70°	BTSCH
6	Admic	A			274	430-Clad	A	Pure; 70°	BTSCH
10-17	Aluminum	AF	Rm.	BIPTC	275	St. 301	V		
19	Alloyco	A	Boil.	BT	276	St. 302	V		
22	Ambralay	A	Dry	CH			A	Anhydrous; 70°; boil.	
		F	Moist				X	5%; 10%; 70°; aqueous sol.	
23	Ambralay	A	Dry	CH	278	St. 303	V	Pure; 70°	
		F	Moist		279	St. 304	V		
24	Ambralay	A	Dry	CH			X	5%; 10%; 70°; aqueous sol.	VTSCDF
		F	Moist				A	Pure; 70°	
29-40	Ampco	A		BIVPTCHDF	280	St. 308	V		
51	Beryles	A			281	St. 309	V		
54	Brass	A	Dry	CH	282	St. 310	V		
		V	Moist		283	St. 316	A		BIVPTS
61	Brass	A	Dry	VCH			A	Anhydrous; 70°	VTCHDF
		V	Moist				A	Pure; 70°	VP
63	Brass	A	Dry	PCH	284	St. 317	A		
		FV	Moist		285	St. 321	V		
66	Bronze	A	Dry		286	St. 347	V		
		V	Moist		287	St. 403	X		
73	Bronze	A	Dry	VT	288	St. 405	X		
		F	Moist		290	St. 410	X		
74	Bronze	A	Dry	V			A	Anhydrous; 70°	
		F	Moist		291	St. 414	X		
75	Bronze	A	Dry	VP	292	St. 416	X		
		V	Moist		293	St. 418	X		
76	Bronze	A	Dry	Instruments	294	St. 420	X		
		F	Moist		295	St. 430	F		
77	Bronze	A	Dry	PCH			A	Anhydrous; 70°	VTCHDF
		V	Moist				A	Pure; 70°	
85	Cast Iron	A			296	St. 430-F	F		
86	Cast Iron	V			297	St. 431	F		
87	Causal	A	Hot or cold	B	298	St. 440-A	F		
88	Chlorimet	A	All % and temp.	BIVCHF	300	St. 440-C	F		
89	Chlorimet	A	All % and temp.	BIVCHF	301	St. 442	F		
111	Copper	A	Dry		303	St. 446	F		
		V	Moist		308	St. CB-30	A	Boil.	
114	Copper	A	Dry	PTCHF	309	St. CC-35	A		
		F	Moist		367	Super-Ni	A	Dry	PTCH
118	Copper	A	Dry				F	Moist	
		V	Moist		368	Tantalum	A		Net used commer.
123	Cupro-Ni	A	Dry	CH	369	Telnic	A	Dry	
		F	Moist				V	Moist	
124	Cupro-Ni	A	Dry		390	Worthite	A	50%; 184°	BIV
		V	Moist		401	Karbate	A	All %; to boil	BIV
127-133	Dowmetal	A	Dry		402	Karbate	A	All %; to boil	BIV
139	Durco	A	All % and temp.	BIVHF	403	Kemprul	A	All %; any temp.	
140	Durichlor	A	All % and temp.	BIVPCHFR	404	Acheson	A	All %; any temp.	
141	Durimet	A	All % and temp.	BIVHF	500	Sul. cement	X		
142	Durimet	A	All % and temp.	BIVHF	501	Sul. cement	X		
143	Duriron	A	All % and temp.	BIVPHFR	502	Furan cement	A	360° max.	PT
148	Everdur	A	Dry	BIVR	503	Furan cement	A	360° max.	PT
		F	Moist		504	Phen. cement	A	360° max.	PT
149	Everdur	A	Dry	PTCHDR	505	Phen. cement	A	360° max.	PT
		F	Moist		506	Silicate cemen	F	1,600° max.	T
150	Everdur	A	Dry	PCH	507	Silicate cement	F	1,600° max.	T
		F	Moist		508	Acichlor	X		
159	Hastelloy	A	Any temp.		510	Acitite	F	Dilute and conc.; 250°	
160	Hastelloy	A	Any temp.		513	Asplit	A	All %; 350° max.	
161	Hastelloy	A	Any temp.		514	Asplit-F	A	All %; 350° max.	
162	Hastelloy	A	Any temp.	V	515	Basolit	X		
163	Stellite	A	Any temp.		518	C-Basolit	X		
165	Stellite	A	Any temp.		521	Causplit	A	All %; 350° max.	
184	Inconel	A	Boil.		523	Duralon	A	360° max.	BIPTCHDF
185	Inc-Clad	A	Pure	BTSCH	524	Durisite	A	360° max.	BIPTCHDF
216	Monel	A	Boil.	BIVPTCHDF	534	N-Series	X		
217	Monel-Clad	A	Pure	BTSCH	535	Nukom	A		T
219	Muntz	A	Dry	CH	536	Nukem	A		T
		V	Moist		537	Pecomastic	X		
					538	Penchlor	A	All %; 730° max.	

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
539	Penchla	A	All %; 750° max.		24	Ambraloy	A	Dry	CH
540	Penchlor	A	All %; 500°-2,000°				V	Moist	
541	Penusalt	A	All %; 350° max.		29-40	Ampco	F	Dry gas	BIVPTCHDF
542	Permanite	A		TD	54	Brass	A	Dry	CH
544	Plastite	X					X	Moist	
545	P-Basulit	X			61	Brass	A	Dry	VCH
554	Silastic	X	ASTM D-543-43				X	Moist	
556	Staminite	A	All %	T	63	Brass	A	Dry	PCH
559	Thiokol	F	150° max.				V	Moist	
600	Acid Brick	A		TDR	66	Bronze	A	Dry	
603, 612, 615	Glass	A		THDR			V	Moist	
604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR	73	Bronze	A	Dry	VT
606	Stoneware	A	All conditions	BIVPTCHDFR			V	Moist	
607	Glass-L	A	600° max.	PTCH	74	Bronze	A	Dry	V
610	Stoneware	A	All %; any temp.	BIVPTCHDFR			V	Moist	
611	Porcelain	A	All % and temp.	BIPTDR	75	Bronze	A	Dry	VP
614	Glass-L	A	Under 302°; agitation	BTCH			V	Moist	
616	Pyrex	A			76	Bronze	A	Dry	Instruments
617	Stoneware	A	140°-160°	BIPTSCHDFR			V	Moist	
618	Vitreo	A	1,000° max.		77	Bronze	A	Dry	PCH
619	Vitreosil	A					X	Moist	
621	Vycor	A			81	CA-FA20	A	Dry gas; 70°	BIVP
700	Ace Saran	A		P	82	CA-MM	A	Dry gas; 70°	BIVP
703	Compar	A	-40° to boil.	TD	86	Cast iron	A	Dry	
704	DC Silicone	X	ASTM D-543-43		88	Chlorimet	A	Dry to 1,000°	BIVCHF
706	Formica	A	Commercial	TD			X	Wet	
707	Formica	A	All %; 212° max.		89	Chlorimet	A	Dry; all % to 960°	BIVCHF
713	Haveg	A	All conditions	BIVPTDFR			A	Wet; all % at rm.	BIVCF
715	Heresite	A	200° max.		111	Copper	A	Dry	
716	Heresite	A	200° max.				V	Moist	
718	Kroco seal	X			114	Copper	A	Dry	PTCHR
720	Lamicaid	A					V	Moist	
723	Nixon	A	C. P.; 77°	S	116	Copper	A	Dry	
724	Nixon	A	77°	S			V	Moist	
725	Nixon	X			123	Cupro-Ni	A	Dry	CH
726	Nukemite	X					V	Moist	
733	Permanite	A	360° max.	BVPDT	124	Cupro-Ni	A	Dry	
735	Polythene	F	Rm.; swells slightly				V	Moist	
		X	176°		139	Durco	A	Dry to 600°	BIVCHF
736	Pyroflex	V		PTCHD	140	Durichlor	A	Wet; all %; rm.	BIVPCHFR
737	Resilon	X			141	Durimet	A	Dry to 500°	BIVHF
738	Resistoflex	A	Conc.; to boil.	P	142	Durimet	A	Dry to 500°	BIVHF
739	Resistoflex	A	Conc.; 275° max.	IVP	143	Duriron	X		
740	Saran	F	77°		146	Everdur	A	Dry	BIVR
741	Sealco	V	160° max.	BPTDF			V	Moist	
742	Teflon	A	Rm.	VP	149	Everdur	A	Dry	PTCHDR
746	Tygon	X					V	Moist	
800	Ace Hd. Rob.	X			150	Everdur	A	Dry	PCH
801	Acidseal	X					V	Moist	
802	Acidseal	X			184	Inconel	A	Dry; to 1,000°	
805	Butyl	X					X	Wet	
809	Fairprene	X			216	Monel	A	Dry; to 800°	BVPTSH
817	Heresite	X					X	Wet	
835	Perbunan	X			217	Monel-Clad	A	Dry gas	BTSCH
836	Natural (S)	X			219	Muntz	A	Dry	CH
837	Natural (H)	X					X	Moist	
838	GR-S (S)	X			224	Nickel	A	Dry; to 1,000°	VTHD
839	GR-S (H)	X					X	Wet	
840	GR-A (S)	X			225	Ni-Clad	A	Dry gas	BTSCH
841	GR-A (H)	X			226	Nick-Sil	A	Dry	Instruments
842	GR-M (S)	X					V	Moist	
843	GR-P (S)	V			231	Ni-Resist	X	Wet	
844	GR-I	X			234	Olympic	A	Dry	
846	Saniprene	X					V	Moist	
848	Silastic	X			235	Olympic	A	Dry	
849	Superflex	X					V	Moist	
853	Thiokol	A	150° max.	T	240	Platinum	A	480° max.	
854	Thiokol	A	150° max.	PTSCDF	242	Ir-Plat.	A	480° max.	
855	Triflex	X			244	Rh-Plat.	A	480° max.	
856	Vistanox	X			268	Silver	F	Rm.	
					271	316-Clad	A	Dry gas; 70°	BTSCH
					275	St. 301	X		
					276	St. 302	X		
							A	Gas, dry; 70°	
							F	Gas, moist; 70°	
							X	Gas, moist; 212°	
							X	Chlorinated water; sat.; 70°	
							X	Gas, dry; 70°	
					278	St. 303	X		
					279	St. 304	X		
							X	Chlorinated water; sat.; 70°	
							X	Gas, dry; 70°	
					280	St. 308	X		
					281	St. 309	X		

CHLORINE

3	Admiralty	A	Dry	
		V	Moist	
4	Admiralty	A	Dry	CH
		V	Moist	
6	Admic	A	Dry gas	
10-17	Aluminum	X		
22	Ambraloy	A	Dry	CH
		V	Moist	
23	Ambraloy	A	Dry	CH
		V	Moist	

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
282	St. 310	X			621	Vycor	A		
283	St. 316	X			700	Ace Saran	X	Liquid	
		A	Gas, dry; 70°		703	Compax	X		
		F	Gas, moist; 70°		704	DC Silicone	X		
		X	Gas, moist; 212°		711	Haveg	A	All conditions	BIVPTDFR
		X	Chlorinated water; sat.; 70°		713	Haveg	A	All conditions	BIVPTDFR
		V	Gas, dry; 70°	VTCHDF	715	Heresite	A	70° max.	
284	St. 317	X			716	Heresite	A	70° max.	
285	St. 321	X			720	Lamicaid	A		
286	St. 347	X			726	Nukemite	A		PTSDF
287	St. 403	X			733	Permanite	V	360° max.	BVPDT
288	St. 405	X			736	Pyroflex	V		PTCHD
290	St. 410	X			737	Resilon	A	175° max.	PTSD
		X	Dry gas; 70°		738	Resistoflex	X		
291	St. 414	X			739	Resistoflex	X		
292	St. 416	X			740	Saran	X	77°	
293	St. 418	X			741	Sealon	A	160° max.	BPTDF
294	St. 420	X			742	Teflon	A	Rm.	VP
295	St. 430	X			746	Tygon	F	180° max.	BIPTSCDF
		F	Gas, dry; 70°		801	Acidseal	A	Sat.; 1 atm. p.a.i.; 150° max. (wet only)	BIPTDF
		F	Gas, moist; 70°		805	Butyl	X		
		X	Gas, moist; 212°		809	Fairprene	X		
		X	Chlorinated water; sat.; 70°		817	Heresite	V	Sat.; 212° max.	
		X	Gas, dry; 70°		835	Perbunan	X		
296	St. 430-F	X			836	Natural (S)	V		
297	St. 431	X			837	Natural (H)	V		
298	St. 440-A	X			838	GR-S (S)	V		
300	St. 440-C	X			839	GR-S (H)	V		
301	St. 442	X			840	GR-A (S)	V		
303	St. 446	X			841	GR-A (H)	V		
364	Steady	A	Sat. vapor		842	GR-M (S)	X		
365	Steady	F	Sat. vapor		843	GR-P (S)	X		
367	Super-Ni	F	Moist	PTCH	844	GR-I	V		
368	Tantalum	A	302° max.; wet or dry	CH	846	Saniprene	A	Sat.; 1 atm. p.a.i.; 150° max. (wet only)	BIPTDF
369	Telnic	A	Dry		848	Silastic	X		
		V	Moist		849	Superflex	A	Sat.; 1 atm. p.a.i.; 150° max. (wet only)	BIPTDF
390	Worthite	X	Wet		853	Thiokol	X		
392	Wyndaloy	V	Aqueous sol.; 68°		854	Thiokol	F	150° max.	PTSCDF
401	Karbato	A	All %; dry; 338° max.	P	856	Vistanex	X		
		V	Moist						
402	Karbato	A	All %; dry; 338° max.	F					
		V	Moist						
403	Kempul	A	All %; any temp.						
404	Achason	A	All %; any temp.						
500	Sul. cement	A	200° max.	PT					
501	Sul. cement	A	200° max.	PT					
502	Furan cem.	A	360° max.	PT					
503	Furan cem.	A	360° max.	PT					
504	Phen. cem.	A	360° max.	PT					
505	Phen. cem.	A	360° max.	PT					
506	Silicate cem.	F	1,600° max.	T					
507	Silicate cem.	A	1,000° max.	PT					
513	Asplit	X							
514	Asplit-F	X							
515	Basolit	A		T					
517	Carbolime	A							
518	C-Basolit	A		T					
521	Causplit	X							
523	Duricon	V	350° max.	BIPTCHDF					
524	Durite	V	350° max.	BIPTCHDF					
535	Nukem	X							
536	Nukem	A		T					
538	Penchlor	A	All %; 750° max.						
539	Penchlor	A	All %; 750° max.						
540	Penchlor	A	All %; 500°-2,000°						
541	Pennsalt	X							
542	Permanite	V		TD					
544	Plastite	A	175° max.	PTSD					
545	P-Basolit	A		T					
554	Silastic	X	ASTM D-543-43						
559	Thiokol	X							
600	Acid Brick	A		TDR					
603, 612, 615	Glass	A		THDR					
604	Cerathum	A	200°-400°, depending on design	BIVPTSCHDFR	139	Durco	A	All % and temp.	BIVHF
606	Stoneware	A	All conditions	BIVPTCHDFR	140	Durichlor	A	All % and temp.	BIVPCHFR
607	Glass-L	A	900° max.	PTCH	141	Durimet	A	All % and temp.	BIVHF
610	Stoneware	A	All %; any temp.	BIVPTCHDR	142	Durimet	A	All % and temp.	BIVHF
611	Porcelain	A	All % and temp.	BIPTDR	143	Duriron	A	All % and temp.	BIVPHFR
614	Glass-L	V		BTCH	148	Everdur	X		
616	Pyrex	A			149	Everdur	X		
617	Stoneware	A	140°-100°	BIPTSCHDFR	150	Everdur	X	All % and temp.	
618	Vitreo	V	1,000° max.		159	Hastelloy	X	All % and temp.	
619	Vitreosil	A		PH	160	Hastelloy	X	All % and temp.	
					161	Hastelloy	A	All % to 160°	BIVPCH

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
162	Hastelloy	X	All % and temp.		505	Phen. com.	X		
163	Stellite	A	All % and temp.	BIV	506	Silicate com.	A	1,000° max.	PT
165	Stellite	F			507	Silicate com.	A	1,000° max.	PT
184	Inconel	A	5%; 80°		508	Acichlar	F	Dilute and conc.; 300°	
191, 193	Lead	A	Sat.; to boil.; aerated; agitated; commercial purity	PTH	510	Acikite	F	Dilute and conc.; 250°	
216	Monel	A	5%; 80°	VPTD	513	Asplit	X		
		X	Sat. aqueous sol.; 250°		514	Asplit-F	X		
217	Monel-Clad	A		BTSCH	515	Basolit	A	Rm.	T
219	Muntz	X			518	C-Basolit	A	Rm.	T
224	Nickel	A	5%; 80°		521	Causplit	X		
225	Ni-Clad	A		BTSCH	523	Duralon	X		
226	Nick-Sil	X			524	Duricite	X		
231	Ni-Resist	A	5%; 80°	BIV	532	Luminate	A	10% max.; 90°	
234	Olympic	X			535	Nukem	X		
235	Olympic	X			536	Nukem	A		T
240	Platinum	A			537	Pecomastic	A		
242	Ir-Plat.	A			538	Penchlar	A	All %; 750° max.	
244	Rh-Plat.	A			539	Penchlar	A	All %; 750° max.	
245	Pyrasteel	A		BIVPTSCHF	540	Penchlar	A	All %; 500°-2,000°	
270	304-Clad	A	5%; 70°	BTSCH	541	Pennsalt	X		
271	316-Clad	A	10%; C.P.; boil.	BTSCH	542	Permanite	X		
274	430-Clad	A	5%	BTSCH	544	Plastite	F	175° max.	TDSP
275	St. 301	X			545	P-Basolit	A	Rm.	T
276	St. 302	X			556	Stannite	F	Cold	T
		X	50%; not C.P., contains SO ₂ ; boiling		559	Thiokol	X		
		A	50%; not C.P., contains SO ₂ ; 70°		600	Acid Brick	A		TDR
		A	10%; C.P., free of SO ₂ ; 70°; boil.		603, 612, 615	Glass	A		THDR
		A	50%; C.P., free of SO ₂ ; 70°		604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR
		F	50%; C.P., free of SO ₂ ; boil.		606	Stoneware	A	All conditions	BIVPTCHDFR
		A	5%; 70°	VTSCDF	607	Glass-L	V		PTCH
		X	10% C.P.; boil.		610	Stoneware	A	All %; any temp.	BIVPCHDR
278	St. 303	X			611	Porcelain	A	All % and temp.	BIPTDR
279	St. 304	X			614	Glass-L	A	All %; under 302°; agitation	BTCH
		A	5%; 70°	VTSCDF	616	Pyrex	A		
		X	10%; C.P.; boil.		617	Stoneware	A	140°-160°	BIPTSCHDFR
280	St. 308	X			618	Vitreo	A	1,000° max.	
281	St. 309	X			619	Vitreosil	A		
282	St. 310	X			621	Vycor	A		
283	St. 316	X			703	Compax	X		
		X	50%; not C.P., contains SO ₂ ; boil.		704	DC Silicone	A	ASTM D-543-43	HD
		A	50%; not C.P., contains SO ₂ ; 70°		711	Haveg	X		
		A	10%; C.P., free of SO ₂ ; 70°; boil.		713	Haveg	X		
		A	50%; C.P., free of SO ₂ ; 70°		715	Heresite	A	200° max.	
		X	50%; C.P., free of SO ₂ ; boil.		716	Heresite	A	200° max.	
		A	5%; 70°	VTCHDF	718	Koroseal	F	35% max.; 130° max.	TD
		A	10%; C.P.; boil.	VTCHDF	720	Lamicaid	A		
284	St. 317	X			726	Nukemite	A	Rm.	PTSDF
285	St. 321	X			727	Nylon	X	Conc.	
286	St. 347	X			728	Nylon	X	Conc.	
287	St. 403	X			729-732	Nylon	X	Conc.	
288	St. 405	X			733	Permanite	X		
290	St. 410	X			736	Pyroflex	V		PTCHD
291	St. 414	X			737	Resilon	F	175° max.	PTSD
292	St. 416	X			738	Resistoflex	X		
293	St. 418	X			739	Resistoflex	X		
294	St. 420	X			741	Sealon	A	160° max.	BPTDF
295	St. 430	X			742	Teflon	A	Rm.	VP
		X	50%; not C.P., contains SO ₂ ; boil.		744	Textolite	X	Conc.; 77°-122°	BI
		A	5%; 70°	VTCHDF	745	Textolite	X	Conc.; 77°-122°	BI
		X	10%; C.P.; boil.		746	Tygon	A	180° max.	BIPTSCDF
296	St. 430-F	X			800	Acc Hd. Rub.	X		
297	St. 431	X			805	Butyl	F	20°; 140° max.	
298	St. 440-A	X			809	Fairprene	X		
300	St. 440-C	X			817	Heresite	X		
301	St. 442	X			836	Natural (S)	X		
303	St. 446	X			837	Natural (H)	V		
367	Super-Ni	X			838	GR-S (S)	X		
368	Tantalum	A		Not used commer.	839	GR-S (H)	V		
369	Telnic	X			840	GR-A (S)	X		
390	Warthite	A	Plating sol.; anodizing sol.; 150°	BIVP	841	GR-A (H)	V		
401	Karbate	X			842	GR-M (S)	X		
402	Karbate	X			843	GR-P (S)	X		
403	Kompruf	X			844	GR-I	A		
404	Acheson	X			848	Silastic	A	ASTM D-543-43	
500	Sul. cement	X			853	Thiokol	X		
501	Sul. cement	X			854	Thiokol	F	150° max.	PTSDF
502	Furan com.	X			856	Vistanex	F	20°; 140° max.	
503	Furan com.	X							
504	Phen. com.	X							

FATTY ACIDS

3	Admiralty	A		
4	Admiralty	A		CH
6	Admic	A		

No	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
10-17	Aluminum	A	Rm., boil.; moisture inhibits attack	PTCH	367	Super-Ni	A		PTCH
19	Alloyco	A	180°-550°	BT	368	Tantalum	A		Not used commer.
22	Ambraloy	A		CH	369	Telnic	A		
23	Ambraloy	A		CH	390	Warthite	A	All %; any temp.	BIV
24	Ambraloy	A		CH	392	Wyndaloy	AV	68°	
29-40	Ampco	AF	Depends on type and presence of oxygen	BIVPTCHDF	401	Karbate	A	All %; to boil.	BIVPTCHDF
54	Brass	F		CH	402	Karbate	A	All %; to boil.	BIVPTCHDF
61	Brass	F		VCH	403	Kemprul	A	All %; any temp.	PTDR
63	Brass	A		PCH	404	Acheson	A	All %; any temp.	PTDR
66	Bronze	A			500	Sul. cement	F	100° max.	T
73	Bronze	A		VT	501	Sul. cement	F	100° max.	T
74	Bronze	A		V	502	Furan com.	A	360° max.	PT
75	Bronze	A		VP	503	Furan com.	A	360° max.	PT
76	Bronze	A		Instruments	504	Phen. com.	A	360° max.	PT
77	Bronze	F		PCH	505	Phen. com.	A	360° max.	PT
87	Causal	A	Hot or cold	B	506	Silicate com.	F	1,600° max.	T
88	Chlorimet	A	All % and temp.	BIVCHF	507	Silicate com.	F	1,600° max.	T
89	Chlorimet	A	All % and temp.	BIVCHF	515	Basolit	A	200° max.	T
111	Copper	A			517	Carbolime	A		
114	Copper	A		PTCHR	518	C-Basolit	A	200° max.	T
117	Copper	V		P	523	Duralon	A	350° max.	BIPTCHDF
118	Copper	A			524	Durisite	A	350° max.	BIPTCHDF
123	Cupro-Ni	A		CH	532	Lumite	A	1° max.; 90°	TD
124	Cupro-Ni	A			535	Nukem	A	350° max.	T
139	Durez	A	All % and temp.	BIVHF	536	Nukem	A		T
140	Durichlor	A	All % and temp.	BIVPCHFR	542	Permanite	A		TD
141	Durimet	A	All % and temp.	BIVHF	544	Plasite	F	175° max.	TPSD
142	Durimet	A	All % and temp.	BIVHF	545	P-Basolit	A	200° max.	T
143	Duriron	A	All % and temp.	BIVPCHFR	554	Silastic	A	ASTM D-543-43	
148	Everdur	A		BIVR	556	Stamite	A	All %	T
149	Everdur	A		PTCHDR	559	Thiokol	A	150° max.	
150	Everdur	A		PCH	600	Acid Brick	A		TDR
156	Gold	A			603, 612, 615	Glass	A		THDR
159	Hastelloy	A	All % and temp.	BIVPTCH	604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR
160	Hastelloy	A	All % and temp.	BIVPTCH	606	Stoneware	A	All conditions	BIVPTCHDFR
161	Hastelloy	A	All % and temp.	BIVPTCH	607	Glass-L	A	600° max.	PTCH
162	Hastelloy	A	All % and temp.	BIVP	610	Stoneware	A	All %; any temp.	BIVPTCHDR
163	Stellite	A	All % and temp.	BIV	611	Porcelain	A	All % and temp.	BIPTDR
165	Stellite	A	All % and temp.	BIV	614	Glass-L	A	Under 302°; agitation	BTCH
184	Inconel	A	Boil.	BIVPTCHR	616	Pyrex	A		
185	Inc-Clad	A		BTSCH	617	Stoneware	A	140°-160°	BIPTSCHDFR
196, 200, 266	Lead	V	212° max. in absence of oxygen	PTH	618	Vitres	A	1,000° max.	
216	Monel	A	Boil.	BIVPTCH	621	Vycor	A		
217	Monel-Clad	A		BTSCH	700	Ace Saran	A	122°	P
219	Muntz	F		CH	703	Comar	A	200° max.	TD
224	Nickel	A	Boil.	PTH	704	DC Silicone	A	ASTM D-543-43	HD
225	Ni-Clad	A		BTSCH	706	Formica	A	All %; 212° max.	
226	Nick-Sil.	A		Instruments	711	Haveg	A	All conditions	BIVPTDFR
231	Ni-Resist	A	Boil.	BIVPH	713	Haveg	A	All conditions	BIVPTDFR
234	Olympic	A			715	Heresite	A	200° max.	
235	Olympic	A			716	Heresite	A	200° max.	
236	Palladium	A			718	Koroseal	F	All %; 100° max.	TD
240	Platinum	A			720	Lamicoid	A		
242	Ir-Plat.	A			726	Nukemite	V		PTSDF
244	Rh-Plat.	A			733	Permanite	A	360° max.	BVPDT
268	Silver	A			736	Pyroflex	V		PTCHD
275	St. 301	A		BIVTSCDF	737	Resilon	F	175° max.	PTSD
276	St. 302	A		BIVTSCDF	738	Resistoflex	A	Conc.; 275° max.	P
278	St. 303	A		IVF	739	Resistoflex	A	Conc.; 140° max.	IVP
280	St. 308	A		BIVPTSCDF	741	Seslon	A	100° max.	BPTDF
281	St. 309	A		BIVTSCDF	742	Teflon	A	Rm.	VP
282	St. 310	A		BIVPTSCHDF	743	Testolite	A	Dil.; Rm.	T
283	St. 316	A		BIVPTSCHDF	744	Testolite	F	Dil.; Rm.	BI
284	St. 317	A		BIVPTSCHDF	745	Testolite	F	Dil.; Rm.	BT
285	St. 321	A		BIVPTSCH	746	Tygon	A	180° max.	BIPTSCDF
286	St. 347	A		BIVPTSCDF	801	Acidusal	F	Any %; 100° max.	BIPTDF
287	St. 403	A		IV	805	Butyl	F	Rm.	
288	St. 405	A		BIVTSC	809	Fairprene	V		VPTDF
290	St. 410	A		BIVPTSCHDF	814	GE Silicone	A	Dil. Rm.	
291	St. 414	A		IV	817	Heresite	A	Sat.; 212° max.	
292	St. 416	A		IV	835	Perbunan	A	Rm.	
293	St. 418	A			836	Natural (S)	V		
294	St. 420	A			837	Natural (H)	V		
295	St. 430	A		BIVPTSCHDF	838	GR-S (S)	V		
296	St. 430-F	A		IV	839	GR-S (H)	V		
297	St. 431	A		IV	840	GR-A (S)	V		
298	St. 440-A	A			841	GR-A (H)	V		
300	St. 440-C	A		IV	842	GR-M (S)	X		
301	St. 442	A		BIVTSC	843	GR-P (S)	X		
303	St. 446	A		BIVPTSC	844	GR-I	F		
313	St. CF-7	A	Boil.		846	Saniprene	F	Any %; 100° max.	BIPTDF
319	St. CF-7M	A	Boil.		848	Silastic	A	ASTM D-543-43	
					849	Superflex	F	Any %; 100° max.	BIPTDF

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
853	Thiokol	A	180° max.	T	295	St. 430	X		
854	Thiokol	A	150° max.	PTSCDF			X	Dil.; 70°	
856	Vistanex	F	Rm.		296	St. 430-F	X		
913	Redwood	F	40°-220° max.; + 20% NaCl; soap plant		297	St. 431	X		
		A	75% + Dil. H ₂ SO ₄ ; 160° max.; reduction plant		298	St. 440-A	X		
		A	75% + Dil. H ₂ SO ₄ + Dil. NaOH; 160° max.; 10 yr		300	St. 440-C	X		
		A	5%; 40°-185°; 32 yr.; Packing plant		301	St. 442	X		
					303	St. 446	X		
					364	Stoody	A	10%; boil.; Rm.	
							A	25%; Rm.	
							F	25%; boil.	
					365	Stoody	A	10%; Rm.	
							F	10%; boil.	
							F	25%; Rm.	
							X	25%; boil.	
					367	Super-Ni	X		
					368	Tantalum	A	200° max.	H
					369	Telaic	X		
					390	Worthite	X		
					401	Karbate	A	All %; to boil.	BIVP
					402	Karbate	A	All %; to boil.	BIVP
					403	Kempul	V		T
					404	Archason	V		T
					500	Sul. cement	A	200° max.	PT
					501	Sul. cement	A	200° max.	PT
					502	Furan cement	A	300° max.	PT
					503	Furan cement	A	300° max.	PT
					504	Phen. cement	A	300° max.	PT
					505	Phen. cement	A	300° max.	PT
					506	Silicate cement	F	1,600° max.	T
					507	Silicate cement	A	1,600° max.	PT
					508	Acichlor	A	Dilute and conc.; 300°	
					510	Acithe	X		
					513	Asplit	A	All %; 350° max.	
					514	Asplit-F	A	All %; 350° max.	
					515	Basolit	A	80°	T
					517	Carbolino	A		
					518	C-Basolit	A	80°	T
					521	Causplit	A	All %; 350° max.	
					523	Duralon	A	350° max.	BIPTCHDF
					524	Duraisite	A	350° max.	BIPTCHDF
					534	N-Series	A	25%; Rm.	BIVPTCDFR
					535	Nukem	A	80%; 250° max.	T
					536	Nukem	A	80°	T
					537	Pecomastic	F	Dilute and conc.; 300°	
					538	Penchlor	A	All %; 750° max.	
					539	Penchlor	A	All %; 750° max.	
					540	Penchlor	A	All %; 500-2,000°	
					541	Pennsalt	A	All %; 350° max.	
					542	Permanite	A	300° max.	TD
					544	Plastite	A	175° max.	PTSD
					545	P-Basolit	A	80°	T
					554	Silastic	A	ASTM D-543-43	
					556	Staminit	F		T
					559	Thiokol	A	150° max.	
					600	Acid Brick	A		TDR
					603, 612, 615	Glass	A		THDR
					604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR
					606	Stoneware	A	All conditions	BIVPTCHDFR
					607	Glass-L	A	600° max.	PTCH
					610	Stoneware	A	All %; any temp.	BIVPTCHDR
					611	Porcelain	A	All %; any temp.	BIPTDR
					614	Glass-L	A	All %; under 302°; agitation	BTCH
					616	Pyrex	A		
					617	Stoneware	A	140-160°	BIPTSCHDFR
					618	Vitreo	A	1,000° max.	
					619	Vitrosail	A	Concentrating solutions	
					621	Vycor	A		
					700	Ace Saran	A		P
					704	DC Silicone	A		HD
					711	Haveg	A	All conditions	BIVPTDFR
					713	Haveg	A	All conditions	BIVPTDFR
					715	Heresite	A	200° max.	
					716	Heresite	A	200° max.	
					720	Lamicaid	A		
					726	Nukemite	A		PTSDF
					733	Permanite	A	300° max.	BVPDT
					736	Pyroflex	V		PTCHD
					737	Resilon	A	175° max.	PTSD
					740	Saran	F	77°	
					741	Sealon	A	160° max.	BPTDF
					742	Teflon	A	Rm.	VP
					746	Tygon	A	180° max.	BIPTSCHDF
					800	Ace Hd. Rah.	A		BIVPTDF

FERRIC CHLORIDE

3	Admiralty	X		
4	Admiralty	X		
6	Admic	X	Severe attack	
10-17	Aluminum	X		
22	Ambralay	X		
23	Ambralay	X		
24	Ambralay	X		
29	Ampco	X		
42	Antaciron	A	Cold	
51	Berylico	X	Hot	
54	Brass	X		
61	Brass	X		
63	Brass	X		
66	Bronze	X		
73	Bronze	X		
74	Bronze	X		
75	Bronze	X		
76	Bronze	X		
77	Bronze	X		
88	Chlorimet	V		
89	Chlorimet	V	All % and temp.	BIVCHF
111	Copper	X		
114	Copper	X		
118	Copper	X		
119	Corrosion	F	45%; Rm.; quiet; C. P	BIP
123	Cupro-Ni	X		
124	Cupro-Ni	X		
139	Durco	X		
140	Durichlor	V		BIVPCHFR
141	Durimet	X		
142	Durimet	X		
143	Duriron	V		
148	Everdur	X		
149	Everdur	X		
150	Everdur	X		
159	Hastelloy	X	All % and temp.	
160	Hastelloy	X	All % and temp.	
161	Hastelloy	A	10% to 160°	BIVPTCH
		A	45%; Rm. only	BIVPTCH
162	Hastelloy	X	All % and temp.	
163	Stellite	A	All %; Rm. only	BIV
165	Stellite	X	All % and temp.	
184	Inconel	X	10%; 70°	
216	Munsel	X	10%; 70°	
219	Munta	X		
224	Nickel	X	10%; 70°	
226	Nick-Sil.	X		
231	Ni-Resist	X	10%; 70°	
234	Olympic	X		
235	Olympic	X		
245	Pyrasteel	X		
268	Silver	F		
275	St. 301	X		
276	St. 302	X		
		X	Dil.; 70°	
278	St. 303	X		
279	St. 304	X		
280	St. 308	X		
281	St. 309	X		
282	St. 310	X		
283	St. 316	A		BIPT
		X	Dil.; 70°	
		X		
284	St. 317	A		PT
285	St. 321	X		
286	St. 347	X		
287	St. 403	X		
288	St. 405	X		
290	St. 410	X		
		X	Dil.; 70°	
291	St. 414	X		
292	St. 416	X		
293	St. 418	X		
294	St. 420	X		

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
801	Acidazol	A	All %; 150° max.	BIPTSDF	278	St. 303	A		IV
805	Butyl	A	Dry salt; aqueous sol.; Rm.		279	St. 304	A		BIVPTSCDF
809	Fairprene	A			280	St. 308	A		BIVPTSCDF
817	Herocite	A	Sat.; 212° max.		281	St. 309	A		BIVTSCDF
835	Perbunan	A	Dry salt; aqueous sol.; Rm.		282	St. 310	A		BIVPTSCDF
836	Natural (S)	A			283	St. 316	A		BIVPTSHD
837	Natural (H)	A			284	St. 317	A		BIVPTSCDF
838	GR-S (S)	A			285	St. 321	A		BIVPTSCDF
839	GR-S (H)	A			286	St. 347	A		BIVPTSCDF
840	GR-A (S)	A			287	St. 403	A		IV
841	GR-A (H)	A			288	St. 405	A		BIVTSC
842	GR-M (S)	A			290	St. 410	A		BIVPTSCDF
843	GR-P (S)	X			291	St. 414	A		IV
844	GR-I	A			292	St. 416	A		IV
846	Saniprene	A	All %; 150° max.	BIPTSDF	293	St. 418	A		
848	Silastic	A	ASTM D-543-43		294	St. 420	A		
853	Thiokol	A	150° max.	T	295	St. 430	A		BIVPTSCDF
854	Thiokol	A	150° max.	PTSCDF	296	St. 430-F	A		IV
855	Triflex	A	All %; 150° max.	BIPTSDF	297	St. 431	A		IV
856	Vistanox	A	Dry salt; aqueous sol.; Rm.		298	St. 440-A	A		
913	Redwood	F	20% + 5% HCl; 100-180°; 2 yr; T smelter	T	300	St. 440-C	A		IV
HYDROCARBONS (ALIPHATIC)					301	St. 442	A		BIVTSC
3	Admiralty	A			303	St. 446	A		BIVPTSCDF
4	Admiralty	A		CH	306	St. CA-15	A	High temp.	
6	Admic	A			350	St. HH	A	High temp.	
10-17	Aluminum	A		BIPTSCHDF	367	Super-Ni	A		PTCH
22	Ambralay	A		CH	368	Tantalum	A	Good for catalytic & chlorination reactions in liquid phase	CH
23	Ambralay	A		CH	369	Telnic	A		
24	Ambralay	A		CH	401	Karbato	A	All %; 338° max.	BIVP
29-40	Ampco	A	Depends on halogen acid content	BIVPTCHDF	402	Karbato	A	All %; 338° max.	BIVP
51	Berylico	A			403	Kempul	A	All %; any temp.	T
54	Brass	A		CH	404	Acheson	A	All %; any temp.	T
61	Brass	A		VCH	500	Sul. cement	X		
63	Brass	A		PCH	501	Sul. cement	X		
66	Bronzo	A			502	Furan cem.	A	360° max.	PTD
67	Bronzo	A		PIV	503	Furan cem.	A	360° max.	PTD
73	Bronzo	A		VT	504	Phen. cem.	A	360° max.	PTD
74	Bronzo	A		V	505	Phen. cem.	A	360° max.	PTD
75	Bronzo	A		VP	506	Silicate cem.	F	1,000° max.	PTD
76	Bronzo	A		Instruments	507	Silicate cem.	F	1,000° max.	PTD
77	Bronzo	A		PCH	508	Acichlor	X		
87	Causal	A		B	510	Acikite	A	Dilute and conc.; 250°	
88	Chlorimet	A	All % and temp.	BIVCHF	515	Basolit	X		
89	Chlorimet	A	All % and temp.	BIVCHF	517	Carbolino	A		
111	Copper	A			518	C-Basolit	X		
114	Copper	A		PTCHR	523	Duralon	A	350° max.	BIPTCHDF
117	Copper	A		P	524	Duralite	A	350° max.	BIPTCHDF
118	Copper	A			534	N-Series	V	Rm.	BIVPTCDFR
123	Cupro-Ni	A		CH	535	Nukem	A		T
124	Cupro-Ni	A			536	Nukem	A		T
127-133	Dowmetal	A	Dry		537	Pecomastic	X		
139	Duroc	A	All % and temp.	BIVHF	542	Permanite	A	360° max.	TD
140	Durichlor	A	All % and temp.	BIVPCHFR	544	Plastite	X		
141, 142	Durimet	A	All % and temp.	BIVHF	545	P-Basolit	X		
143	Durim	A	All % and temp.	BIVPHFR	554	Silastic	X	ASTM D-543-43	
148	Everdur	A		BIVR	559	Thiokol	A	150° max.	
149	Everdur	A		PTCHDR	606	Acid orick	A		TDR
150	Everdur	A		PCH	603, 612, 615	Glass	A		THDR
156	Gold	A			604	Ceratherm	A	200°-400°, depending on design	BIVPTCHDFR
159	Hastelloy	A	All % and temp.		606	Stoneware	A	Not commonly used	
160	Hastelloy	A	All % and temp.		607	Glass-L	A	600° max.	PTCH
161	Hastelloy	A	All % and temp.	BIVPTCH	610	Stoneware	A	All %; any temp.	BIVPTCHDR
162	Hastelloy	A	All % and temp.		611	Porcelain	A	All % and temp.	BIPTDR
163	Stellite	A	All % and temp.	BIV	614	Glass-L	A	Under 302°; agitation	BTCH
165	Stellite	A	All % and temp.	BIV	616	Pyrex	A		
184	Inconel	A	Boil.		617	Stoneware	A	140°-160°	BIPTSCHDFR
216	Monel	A	Boil.	BVPTCH	618	Vitro	A	1,000° max.	
219	Muntz	A		CH	619	Vitrosil	A		
224	Nickel	A	Boil.		621	Vycor	A		
226	Nick-Sil.	A		Instruments	700	Ace Saran	V		P
231	Ni-Rosist	A	Boil.	BIVP	703	Compac	A	Cane.; -43° to 200°	TD
233	NS-S	A	If low in sulphur		704	DC Silicone	V		HD
234	Olympic	A			706	Formica	A	All %; 212° max.	ID
235	Olympic	A			707	Formica	A	All %; 212° max.	I
236	Palladium	A			708	Formica	A	Ordinary conditions; 122° max.	
240	Platinum	A			711	Haveg	A	All conditions	BIVPTDFR
242	Ir-Plat.	A			713	Haveg	A	All conditions	BIVPTDFR
244	Rh-Plat.	A			715	Herocite	A	200° max.	
260	Silver	A			716	Herocite	A	200° max.	
275	St. 301	A		BIVTSCDF	718	Kerosol	V	All %; 100° max.	TD
276	St. 302	A		BIVTSCDF	720	Lamicaid	A		T
					723	Nixon	F	77°	S
					724	Nixon	A	77°	S

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
725	Nixon	X	77°		219	Muntz	A		CH
726	Nukemite	A		PTSDF	224	Nickel	A	Boil.	
733	Permanite	A	360° max.	BVPTD	226	Nick-Sil.	A		Instruments
735	Polythene	F	Rm.; swells slightly		231	Ni-Resist	A	Boil.	BIVP
		X	176°		233	NS-5	A	If low in sulphur	
736	Pyroflex	V		PTCHD	234	Olympic	A		
737	Resilon	X			235	Olympic	A		
738	Resistoflex	A	Conc.; -40° to 275°	P	236	Palladium	A		
739	Resistoflex	A	Conc.; -40° to 275°	PIV	240	Platinum	A		
741	Sealon	V	160° max.	BPTDF	242	Ir-Plat.	A		
742	Teflon	A	Rm.	VP	244	Rh-Plat.	A		
744	Testolite	A	77°-122°	BI	268	Silver	A		
745	Testolite	A		BI	275	St. 301	A		BIVPTSCDF
746	Tygon	V	180° max.	BIPTSCHDF	276	St. 302	A		BIVTSCDF
801	Acidseal	V	All %; 150° max.	BIPTSDF	278	St. 303	A		IV
805	Butyl	X			279	St. 304	A		BIVPTSCDF
809	Fairprene	A			280	St. 308	A		BIVPTSCDF
814	GE Silicone	V	Rm.	VPTDF	281	St. 309	A		BIVTSCDF
817	Heresite	A	Sat.; 86° max.		282	St. 310	A		BIVPTSCDF
835	Perbunan	A	To 300°; type hydrocarbon governs max. temp.		283	St. 316	A		BIVPTSHD
					284	St. 317	A		BIVPTSCDF
836	Natural (S)	X			285	St. 321	A		BIVPTSCDF
837	Natural (H)	V			286	St. 347	A		BIVPTSCDF
838	GR-S (S)	X			287	St. 403	A		IV
839	GR-S (H)	V			288	St. 405	A		BIVTSC
840	GR-A (S)	A			290	St. 410	A		BIVPTSCHDF
841	GR-A (H)	A			291	St. 414	A		IV
842	GR-M (S)	A			292	St. 416	A		IV
843	GR-P (S)	A			293	St. 418	A		
844	GR-I	X			294	St. 420	A		
846	Saniprene	V	All %; 150° max.	BIPTSDF	295	St. 430	A		BIVPTSCDF
848	Silastic	X	ASTM D-543-43		296	St. 430-F	A		IV
849	Superflex	V	All %; 150° max.	BIPTSDF	297	St. 431	A		IV
853	Thiokol	A	150° max.	T	298	St. 440-A	A		
854	Thiokol	A	150° max.	PTSCDF	300	St. 440-C	A		IV
856	Vistanex	X			301	St. 442	A		BIVTSC
					303	St. 446	A		BIVPTSCDF
					306	St. CA-15	A	High temp.	
					350	St. HH	A	High temp.	
					367	Super-Ni	A		PTCH
					368	Tantalum	A	Good for catalytic and chlorination reactions in liquid phase	CH
3	Admiralty	A			369	Telnic	A		
4	Admiralty	A		CH	401	Karbato	A	All %; 338° max.	BIVP
6	Admic	A			402	Karbato	A	All %; 338° max.	BIVP
10-17	Aluminum	A		BIPTSCHDF	403	Kempuf	A	All %; any temp.	T
22	Ambraloy	A		CH	404	Acheson	A	All %; any temp.	T
23	Ambraloy	A		CH	500	Sul. cement	X		
24	Ambraloy	A		CH	501	Sul. cement	X		
29-40	Ampco	A		BIVPTCHDF	502	Furan cem.	A	300° max.	PTD
54	Brass	A		CH	503	Furan cem.	A	300° max.	PTD
61	Brass	A		VCH	504	Phen. cem.	A	300° max.	PTD
63	Brass	A		PCH	505	Phen. cem.	A	300° max.	PTD
66	Bronze	A			506	Silicate cem.	F	1,000° max.	TD
67	Bronze	A		PIV	507	Silicate cem.	F	1,000° max.	TD
73	Bronze	A		VT	508	Acichler	X		
74	Bronze	A		V	510	Acithe	A	Dilute and conc.; 250°	
75	Bronze	A		VP	515	Basolit	X		
76	Bronze	A		Instruments	517	Carbolino	A		
77	Bronze	A		PCH	518	C-Basolit	X		
87	Causal	A	Hot or cold	B	523	Duralon	A	350° max.	BIPTCHDF
88	Chlorimet	A	All % and temp.	BIVCHF	524	Durisite	A	350° max.	BIPTCHDF
89	Chlorimet	A	All % and temp.	BIVCHF	534	N-Series	X		
111	Copper	A		PTCHR	535	Nukem	A		T
114	Copper	A		P	536	Nukem	A		T
117	Copper	A			537	Pecomastic	X		
118	Copper	A			542	Permanite	A	300° max.	TD
123	Cupro-Ni	A		CH	544	Plastite	X		
124	Cupro-Ni	A			545	P-Basolit	X		
127-133	Dowmetal	A	Dry		554	Silastic	X	ASTM D-543-43	
139	Durco	A	All % and temp.	BIVHF	559	Thiokol	F	130° max.	
140	Durichlor	A	All % and temp.	BIVPCHFR	600	Acid Brick	A		TDR
141, 142	Durimet	A	All % and temp.	BIVHF	603, 612, 615	Glass	A		THDR
143	Duriron	A	All % and temp.	BIVPHFR	606	Stoneware	A	Not commonly used	
148	Everdur	A		BIVR	607	Glass-L	A	000° max.	PTCH
149	Everdur	A		PTCHDR	610	Stoneware	A	All %; any temp.	BIPTCHDR
150	Everdur	A		PCH	611	Porcelain	A	All % and temp.	BIPTDR
156	Gold	A			614	Glass-L	A	Under 302°; agitation	BTCH
159	Hastelloy	A	All % and temp.	BIVPTCH	616	Pyrex	A		
160	Hastelloy	A	All % and temp.	BIVPTCH	617	Stoneware	A	140°-160°	BIPTSCHDFR
161	Hastelloy	A	All % and temp.	BIVPTCH	618	Vitron	A	1,000° max.	
162	Hastelloy	A	All % and temp.	BIVP	619	Vitrosil	A		
163	Stellite	A	All % and temp.	BIV	621	Vycor	A		
165	Stellite	A	All % and temp.	BIV	709	Ace Saran	V		
184	Inconel	A	Boil.						
216	Monel	A	Boil.	BVPTCH					

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
703	Compax	A	Conc.; -40° to 200°	TD	123	Cupro-Ni	V		CH
704	DC Silicone	X			124	Cupro-Ni	V		
706	Formica	A	All %; 212° max.	I	139	Durco	A	Dil.; Rm.	BIVHF
707	Formica	A	All %; 212° max.	I	140	Durichlor	A	All % and temp.	BIVPCHFR
708	Formica	A	Ordinary conditions; 122° max.		141, 142	Durimat	A	Dil.; Rm.	BIVHF
713	Harvey	A	All conditions	BIVPTDFR	143	Duriron	V	Low % and temp. (140 preferred)	BIVPHFR
715	Heresite	A	300° max.		146	Everdur	V		BIVR
716	Heresite	A	200° max.		149	Everdur	V		PTCHDR
718	Koroseal	X			150	Everdur	V		PCH
720	Lamicaid	A		T	156	Gold	A	In absence of oxidizing material	
723	Nixon	F	77°	S	159	Hastelloy	A	All % to 160°	BIVPTSCHDF
724	Nixon	A	77°	S	160	Hastelloy	A	All % to boil.	BIVPTSCHDF
725	Nixon	X			161	Hastelloy	A	All % to 125°	BIVPTCHDF
726	Nukemite	X			162	Hastelloy	A	All %; Rm. only	BIV
733	Permanite	A	300° max.	BVPTD	163	Stellite	A	All %; Rm. only	BIV
735	Polythene	V	Rm.; swells slightly		165	Stellite	X	All %; Rm.	
		X	176°		181	Hytonal	F	10% max.; cold	BIVHF
736	Pyroflex	V		PTCHD	184	Inconel	X	0.5% boil.	
737	Resilon	X					A	5% unacrated; 86°	
738	Resistoflex	A	Conc.; -40° to 273°	P			F	5% acrated; 86°	
739	Resistoflex	A	Conc.; -40° to 273°	IVP			X	5% unacrated; 158°	
741	Saalon	V	180° max.	BPTDF			F	20% unacrated; 86°	
742	Teflon	A	Rm.	VP	185	Inc-Clad	A	5% sol. sat. with N; 86°	BTSCH
744	Testolite	A	77°-122°	BI	216	Monel	A	0.5% boil.	BIVPTCHDFR
745	Testolite	A	77°-122°	BI			A	5% unacrated; 86, 158°	
746	Tygon	X					F	5% acrated; 86°	
801	Acidseal	X					F	20% unacrated; 86°	
802	Acidseal	X			217	Monel-Clad	A	5% sol. sat. with N; 86°	BTSCH
805	Butyl	X			219	Muntz	X		
809	Fairprene	X			224	Nickel	X	0.5% boil.	
814	GE Silicone	V	Rm.	VPTDF			A	5, 20% unacrated; 86°	BIVPTCH
817	Heresite	V	Sat.; 86°				F	5% acrated; 86°	
835	Perbunan	A	Type of hydrocarbon governs max. temp.				X	5% unacrated; 158°	
836	Natural (S)	X			225	Ni-Clad	A	5% sol. sat. with N; 86°	BTSCH
837	Natural (H)	X			226	Nick-Sil.	V		
838	GR-S (S)	X			231	Ni-Resist	A	5% unacrated; 86°	BIVR
839	GR-S (H)	X					X	5% acrated; 86°	
840	GR-A (S)	X					X	5% unacrated; 158°	
841	GR-A (H)	V					F	20% unacrated; 86°	
842	GR-M (S)	X			233	NS-5	F	Low %; cold	V
843	GR-P (S)	A			234	Olympic	V		
844	GR-I	X			235	Olympic	V		
846	Saniprene	X			236	Palladium	A	In absence of oxidizing material	
848	Silastic	X	ASTM D-543-43		240	Platinum	A	In absence of oxidizing material	
849	Superflex	X			242	Ir-Plat.	A	In absence of oxidizing material	
853	Thiakal	F	180° max.	T	244	Rh-Plat.	A	In absence of oxidizing material	
854	Thiakal	V	180° max.	PTSCDF	245	Pyrasteel	X		
856	Vistanex	X			268	Silver	A	In absence of oxidizing material	
					275	St. 301	X		
					276	St. 302	X		
							X	Diluted 1:85; boil.	
							A	Diluted 1:85; 70°	
							F	Diluted 1:10; 70°	
							X	Diluted 1:10; boil.	
							A	Vapors; 70°	
							X	Vapors; 212°; 425°	
							X	All %; any temp.	
					278	St. 303	X		
					279	St. 304	X		
							X	All %; any temp.	
							X	1% acrated and agitated; 70°	
							X	1% boil.	
					280	St. 308	X		
					281	St. 309	X		
					282	St. 310	X		
					283	St. 316	X		
							A	Diluted 1:85; 70°	
							X	Diluted 1:85; boil.	
							A	Diluted 1:10; 70°	
							X	Diluted 1:10; boil.	
							A	Vapors; 70°	
							X	Vapors; 212°; 425°	
							X	All %; any temp.	
							A	1% acrated and agitated; 70°	BIVP
							X	1% boil.	
					284	St. 317	X		
					285	St. 321	X		
					286	St. 347	X		
					287	St. 403	X		
					288	St. 405	X		
					290	St. 410	X		
							X	Diluted 1:85; boil.	
							X	Diluted 1:10; boil.	
							X	1% acrated and agitated; 70°	

HYDROCHLORIC ACID

3	Admiralty	V		
4	Admiralty	V		CH
6	Admic	V		
10-17	Aluminum	X		
22	Ambralay	V		CH
23	Ambralay	V		CH
24	Ambralay	V		CH
29-48	Ampco	V		BIVPTCHDF
42	Anticrom	A	All %; cold	PIV
51	Berylo	V		
54	Brass	X		
61	Brass	X		
63	Brass	V		PCH
66	Brass	V		
73	Bronze	V		VT
74	Bronze	V		V
75	Bronze	V		VP
76	Bronze	V		
77	Bronze	X		
81	CA-FA20	A	1, 5% acrated and agitated; 70°	BIVP
		A	1% boil.	BIVP
82	CA-MM	F	1, 5% acrated and agitated; 70°	BIVP
		X	1% boil.	
87	Causal	F	Dil.; cold	
89	Chlorimet	A	All % and temp.	BIVCHF
89	Chlorimet	A	All % to 170°	BIVCHF
111	Copper	V		
114	Copper	V		PTCHR
118	Copper	V		
119	Corrosion	F	5%; Rm.; unagitated; C. P.	BIPF
		V	25%; Rm.; unagitated; C. P.	BIPF
		V	37%; Rm.; unagitated; C. P.	BIPF

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
291	St. 414	X			703	Compas	X		
292	St. 416	X			704	DC Silicon	A		HD
		X	All %		706	Formica	F	All %; 212° max.	TD
293	St. 418	X			711	Haveg	A	All conditions	BIVPTDFR
294	St. 420	X			713	Haveg	A	All conditions	BIVPTDFR
		X	All %		715	Heresite	A	200° max.	
295	St. 430	X			716	Heresite	A	200° max.	
		X	Diluted 1:85; boil.		720	Lamicaid	X		
		X	Diluted 1:10; boil.		723	Nixon	X	10%; 77°	
		X	All %; any temp.		724	Nixon	A	10%; 77°	
296	St. 430-F	X			725	Nixon	A	10%; 77°	S
297	St. 431	X			726	Nukemite	A	150° max.	PTSDF
298	St. 440-A	X			727	Nylon	X	Conc.	
300	St. 440-C	X			728	Nylon	X	Conc.	
301	St. 442	X			729-732	Nylon	X		
303	St. 446	X			733	Permanite	A	360° max.	BVPTD
364	Stoody	A	10%; Rm.		735	Polythene	V	Rm.	
		F	10%; boil.; conc.		736	Pyroflex	A		PTCHD
365	Stoody	F	10%; Rm.; boil.		737	Resilon	A	60% max.; 175° max.	PTSD
		X	Conc.; boil.		738	Resistoflex	X		
367	Super-Ni	V		PTCH	739	Resistoflex	X		
368	Tantalum	A	662° max.	BPCH	740	Saran	A	77°	
369	Telnic	V			741	Sealon	A	100° max.	BPTDF
387	Stainless	X	All %		742	Teflon	A	Rm.	VP
388	Stainless	X	All %		743	Testolite	V		
389	Stainless	A	Weak		744	Testolite	V		BI
		X	Strong		745	Testolite	V		BI
390	Worthite	F	15%; 100°; without metal salts		746	Tygon	A	All %; 190° max.	BIPTSCHDF
		X	20° min.		800	Ace Hd. Rub.	A		BIVPTDF
392	Wyndaloy	V	Very dilute; 68°		801	Acidcoal	A	All %; 150° max.	BIPTSDF
		X	Moderate dilution; 68°		805	Butyl	F	Rm.	
		X	Conc.; 68°		809	Fairprene	A		
401	Karbate	A	All %; to boil.	BIVPTCHD	814	G.E. Silicone	X		
402	Karbate	A	All %; to boil.	BIVPTCHD	817	Heresite	A	Conc.; 122° max.	
403	Kemprul	A	All %; any temp.	PTDR	836	Natural (S)	A		
404	Acheson	A	All %; any temp.	PTDR	837	Natural (H)	A		
500	Sul. cement	A	200° max.	PTD	838	GR-S (S)	V		
501	Sul. cement	A	200° max.	PTD	839	GR-S (H)	V		
502	Furan cem.	A	360° max.	PTD	840	GR-A (S)	V		
503	Furan cem.	A	360° max.	PTD	841	GR-A (H)	V		
504	Phen. cem.	A	360° max.	PTD	842	GR-M (S)	V		
505	Phen. cem.	A	360° max.	PTD	843	GR-P (S)	X		
506	Silicate cem.	A	1,000° max.	PTD	844	GR-I	A		
507	Silicate cem.	A	1,000° max.	PTD	846	Saniprene	A	All %; 150° max.	BIPTSDF
508	Acichlor	A	Dilute and conc. 300°		848	Silastic	A	10%; ASTM D-543-43	
510	Acrite	A	Dilute and conc. 250°				A	Conc.; ASTM D-543-43	
513	Asplit	A	All %; 350° max.		849	Superflex	A	All %; 150° max.	BIPTSDF
514	Asplit-F	A	All %; 350° max.		853	Thiokol	X		
515	Basolit	A	200° max.	T	854	Thiokol	F	150° max.	PTSCDF
517	Carbolite	A			855	Triflex	A	All %; 150° max.	BIPTSDF
518	C-Basolit	A	200° max.	T	856	Vistanex	F	Rm.	
521	Causplit	A	All %; 350° max.		913	Redwood	X	18-20° Be.; 60-120°; Failed in 3 mo.	T
523	Duralon	A	350° max.	BIPTCHDF			A	18° Be.; 60-120°; asphalt + tar-L; 12 yr.; chem. plant	T
524	Durite	A	350° max.	BIPTCHDF			A	15%; 36-180°; 5 yr.; steel pick-ling	T
534	N-Series	V		BIVPTCDFR			F	5%; 36-90°; 3 yr.; Petroleum byproducts plant	T
		X	Conc.				A	1 1/2% + 2% H ₂ SO ₄ ; 40-180°F; 21 yr.; chem. plant	T
535	Nukem	A	350° max.	T			A	0.5% + Glycerine; 40-150°; 2 yr.; soap plant	T
536	Nukem	A		T					
537	Pecomatic	A	Dilute and conc.; 300°						
538	Penchlor	A	All %; 750° max.						
539	Penchlor	A	All %; 750° max.						
540	Penchlor	A	All %; 500°-2,000°						
541	Pennsalt	A	All %; 350° max.						
542	Permanite	A	360° max.	TD					
544	Plastite	A	60% max.; 175° max.	PTSD					
545	P-Basolit	A	200° max.	T					
554	Silastic	A	10%; ASTM D-543-43						
		X	Conc.; ASTM D-543-43						
556	Staminite	A	All %	T					
559	Thiokol	X							
600	Acid Brick	A		TDR					
603, 612, 615	Glass	A		THDR					
604	Ceratherm	A	200°-400°, depending on design	BIPTCHDFR					
606	Stoneware	A	All conditions	BIVPTCHDFR					
607	Glass-L	A	600° max.	PTCH					
610	Stoneware	A	All %; any temp.	BIPTCHDR					
611	Pierclain	A	All % and temp.	BIPTDR					
614	Glass-L	A	All %; under 302°; agitation	BTCH					
616	Pyrex	A							
617	Stoneware	A	140°-160°	BIPTCHDFR					
618	Vitreo	A	1,000° max.						
619	Vitreosil	A		PCH					
621	Vycor	A							
700	Ace Saran	A		P					

HYDROFLUORIC ACID

3	Admiralty	V		
4	Admiralty	V		CH
6	Admic	V		
10-17	Aluminum	X		
22	Ambraley	V		CH
23	Ambraley	V		CH
24	Ambraley	V		CH
29-40	Ampco	A	15% max.; cold; anhydrous	BIVPTCHDF
54	Brass	X		
61	Brass	X		
63	Brass	V		PCH
66	Bronze	V		
73	Bronze	V		VT
74	Bronze	V		V
75	Bronze	V		VP
76	Bronze	V		
77	Bronze	X		

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
81	CA-FA20	A	48%: 70°	BIVP	367	Super-Ni	F		PTCH
		X	48%: 170°		368	Tantalum	X		
82	CA-MM	A	48%: 70°	BIVP	369	Telnic	V		
		A	48%: 170°	BIVCHF	390	Worthite	A	Cold, 0.5% in 4% H ₃ PO ₄	BIV
88	Chlorimet	A	All % at Rm.	BIVCHF			F	175°, 0.5% in 4% H ₃ PO ₄	BIV
89	Chlorimet	A	All % and temp.	BIVCHF	392	Wyndaley	V	68°	
111	Copper	V			401	Karbato	A	60% max.; 185° max.	BIVPCHD
114	Copper	V		PTCHR	402	Karbato	A	60% max.; 185° max.	BIVPCHD
118	Copper	V			403	Kemprul	A	All %; to boil.	PTR
123	Cupro-Ni	V		CH	404	Acheson	A	All %; to boil.	PTR
124	Cupro-Ni	V			503	Sul. cement	X		
127-133	Dowmetal	A	Over 5%		501	Sul. cement	A	200° max.	PTD
139	Durco	F	Low %; Rm.	BIVHF	502	Furan cem.	X		
140	Durichlor	X			503	Furan cem.	A	360° max.	PTD
141, 142	Durimet	F	Low %; Rm.	BIVHF	504	Phen. cem.	X		
143	Duriron	X			505	Phen. cem.	A	360° max.	PTD
148	Everdur	V		BIVR	506	Silicate cem.	X		
149	Everdur	V		PTCHDR	507	Silicate cem.	X		
150	Everdur	V		PCH	513	Asplit	X		
156	Gold	A			514	Asplit-F	A	All %; 350° max.	
159	Hastelloy	A	All %; Rm. only		515	Basolit	X		
160	Hastelloy	A	All % to boil.		517	Carboline	A		
161	Hastelloy	A	All % to boil.		518	C-Basolit	A	200° max.	T
162	Hastelloy	X	All % to boil.		521	Causplit	X		
163	Stellite	A	All %; Rm. only	BIV	523	Duralon	V	350° max.	BIPTCHDF
165	Stellite	A	All %; Rm. only	BIV	524	Durisoit	V	350° max.	BIPTCHDF
181	Hytanal	A	90% max.; cold	BIVHF	535	Nukem	A	50% max.	T
184	Inconel	A	10%: 70°		536	Nukem	X		
		X	6%: 170°		538	Penchlor	X		
		X	38%: 230°		539	Penchlor	X		
		A	100% to 900°		540	Penchlor	X		
210	Monel	A	10%: 70°	BIVPTCHDFR	541	Pennsalt	A	All %; 350° max.	
		A	6%: 170°		542	Permanite	A	360° max.	TD
		A	38%: 230°		544	Plastite	V	175° max.	PTSD
		A	100% to 1,100°		545	P-Basolit	X		
		A	60%: Rm.		556	Staminit	X		
217	Monel-Clad	X		BTSCH	559	Thiokol	X		
219	Muntz	X			600	Acid Brick	X		
224	Nickel	A	10%: 70°	VPTC	603, 612, 615	Glass	X	All % and temp.	
		X	6%: 170°		604	Cerathorm	X	All %	
		X	38%: 230°		606	Stoneware	X		
		A	100% to 1,2		607	Glass-L	X		
226	Nick-Sil.	V			610	Stoneware	X		
231	Ni-Resist	A	10%: 70°	BIVP	611	Porcelain	X		
		X	6%: 170°		614	Glass-L	X		
		X	38%: 230°		616	Pyrex	X		
233	NS-5	A	Dil. or conc	V	617	Stoneware	A	All %	BIPTSCHDFR
234	Olympic	V			618	Vitreo	X		
235	Olympic	V			619	Vitrosil	X		
236	Palladium	A			621	Vycor	X		
240	Platinum	A			700	Ace Saran	A		P
242	Ir-Plat.	A			703	Compar	X		
244	Rh-Plat.	A			712	Haveg	A	All conditions	BIVPTDFR
245	Pyrasteel	X			714	Haveg	A	All conditions	BIVPTDFR
268	Silver	A			715	Heresite	A	20%: 70°	
275	St. 301	X			716	Heresite	A	20%: 70°	
276	St. 302	X			718	Koroseal	A	60%: 100°	TD
		A	Vapors; 212°		720	Lamicaid	X		
		X	All %; any temp.		726	Nukemite	A	150° max.	PTSDF
278	St. 303	X			727	Nylon	X	Cont.	
279	St. 304	X			728	Nylon	X	Cont.	
		X	All %; any temp.		729-732	Nylon	X		
280	St. 308	X			733	Permanite	A	300° max.	BVPTD
281	St. 309	X			735	Polythene	A	45%: Rm.	
282	St. 310	X			736	Pyroflex	V		PTCHD
283	St. 316	X			737	Resilon	V	175° max.	PTSD
		A	Vapors; 212°		738	Resistoflex	X		
		X	All %; any temp.		739	Resistoflex	X		
284	St. 317	X			740	Saran	A	77°	
285	St. 321	X			741	Sealon	A	160° max.	BPTDF
286	St. 347	X			742	Teflon	A	Rm.	VP
287	St. 403	X			746	Tygon	F	Dil.; 180° max.	BIPTSCHDF
288	St. 405	X			800	Ace Hd. Rub.	A		BIVPTDF
290	St. 410	X			802	Acidseal	A	50% max.; 100°	BIPTSDF
291	St. 414	X			805	Butyl	A		
292	St. 416	X			809	Fairprene	A		
293	St. 418	X			814	GE Silicone	X		
294	St. 420	X			817	Heresite	A	48%: 77° max.	
295	St. 430	X			836	Natural (S)	V		
296	St. 430-F	X			837	Natural (H)	V		
297	St. 431	X			838	GR-S (S)	V		
298	St. 440-A	X			839	GR-S (H)	V		
300	St. 440-C	X			840	GR-A (S)	V		
301	St. 442	X			841	GR-A (H)	V		
303	St. 446	X							

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
842	GR-M (S)	A			279	St. 304	A	All %; Rm.	BIVPTSCHDF
843	GR-P (S)	X					A	65%; boil.	BIVPTSCHDF
844	GR-I	V					A	50% max.; boil.	VTSCDF
853	Thiokol	X					A	All %; 70°	VTSCDF
854	Thiokol	F	150° max.	PTSCDF			X	Conc.; boil.	DF
856	Viatanex	A	Rm.				A	65%; boil.	BIVP
913	Redwood	A	3½-5%; 36-90°; Pitch + asphalt-L; Airplane mfg.	T	280	St. 308	A	All %; Rm.	BIVPTSCH
		A	3%; 36-90°; 5 yr.; steel plant	T			A	65%; boil.	BIVPTSCH
NITRIC ACID					281	St. 309	A	All %; Rm.	BIVTSCHDF
3	Admiralty	X					A	65%; boil.	BIVTSCHDF
4	Admiralty	X			282	St. 310	A	All %; Rm.	BIVPTSCHDF
6	Admic	X	Severe attack				A	65%; boil.	BIVPTSCHDF
10-17	Aluminum	A	Over 80%	BIPTSCHDF	283	St. 316	A	All %; Rm.	BIVPTSCHDF
		FX	Under 80%				A	65%; boil.	BIVPTSCHDF
22	Ambralay	X					A	Diluted 1:10; 70°; boil.	
23	Ambralay	X					A	Diluted 1:1; 70°; boil.	
24	Ambralay	X					A	Sp. gr. 1.40; conc.; 70°; boil.	
29-40	Ampco	X					A	Sp. gr. 1.52; conc. fuming; 70°	
51	Beryco	X					F	Sp. gr. 1.52; conc. fuming; boil.	
54	Brass	X					A	80% max.; boil.	VTCHDF
61	Brass	X					A	65%; boil.	VTCHDF
63	Brass	X					A	All %; boil.	VTCHDF
66	Bronze	X					X	Conc.; boil.	
73	Bronze	X					F	65%; boil.	BIVP
74	Bronze	X			284	St. 317	A	All %; Rm.	BIVPTSCHDF
75	Bronze	X					A	65%; boil.	
76	Bronze	X			285	St. 321	A	All %; Rm.	BIVPTSCHDF
77	Bronze	X					A	65%; boil.	BIVPTSCHDF
81	CA-FA20	A	65%; boil.	BIVP	286	St. 347	A	All %; Rm.	BIVPTSCHDF
82	CA-MM	X	65%; boil.				A	65%; boil.	
88	Chlorimet	X			287	St. 403	V	All %; Rm.	
89	Chlorimet	V		BIVHF	288	St. 405	V	All %; Rm.	
111	Copper	X			290	St. 410	V	All %; Rm.	
114	Copper	X					A	Diluted 1:10; 70°	
118	Copper	X					A	Diluted 1:1; 70°	
119	Corrosion	A	10, 25, 70%; Rm.; unagitated; C.P.	BIVPTCHDFR			A	All %	
							X	65%; boil.	
123	Cupro-Ni	X			291	St. 414	V	All %; Rm.	
124	Cupro-Ni	X			292	St. 416	V	All %; Rm.	
130	Durco	V	All % (except strong) and temp.	BIVHF			A	All %	
140	Durichlor	A	All % and temp.	BIVPCHFR	293	St. 418	V	All %; Rm.	
141, 142	Durimet	A	All % and temp.	BIVHF	294	St. 420	V	All %; Rm.	
143	Duriron	A	All % and temp.	BIVPHFR			A	All %	
148	Everdur	X			295	St. 430	V	All %; 70°	BIVPTSCHDF
149	Everdur	X					A	Diluted 1:10; 70°; boil.	
150	Everdur	X					A	Diluted 1:1; 70°; boil.	
156	Gold	A	To boil.				A	Sp. gr. 1.40; conc.; 70°	
159	Hastelloy	X	All % and temp.				F	Sp. gr. 1.40; conc.; boil.	
160	Hastelloy	X	All % and temp.				A	80% max.; boil.	VTCHDF
161	Hastelloy	A	All % to 150°	BIV			X	65%; boil.	
162	Hastelloy	X	All % and temp.				A	All %; boil.	VTCHDF
163	Stellite	A	All % to 150°	BIV			X	Conc.; boil.	
165	Stellite	A	All % to 150°	BIV			A	All %	
184	Inconel	F	5%; 70°; aerated		296	St. 430-F	V		
		A	65%; 70°		297	St. 431	V	Sp. gr. 1.42; all %; 70°	
216	Monel	X	5%; 70°; aerated				V	65%; boil.	
219	Muntz	X			298	St. 440-A	V	Sp. gr. 1.42; all %; Rm.	
224	Nickel	X	5%; 70°; aerated		300	St. 440-C	V	Sp. gr. 1.42; all %; Rm.	
226	Nick-Sil.	X			301	St. 442	V	Sp. gr. 1.42; all %; Rm.; 65%; boil.	BIVTSCH
231	Ni-Resist	X	5%; 70°; aerated				V	Sp. gr. 1.42; all %; Rm.; 65%; boil.	BIVPTSCHDF
234	Olympic	X			313	St. CF-7	A	All %; boil.	
235	Olympic	X			316	St. CF-20	A		BIV
240	Platinum	A	To boil.		319	St. CF-7M	A	All %	
242	Ir-Plat.	A	To boil.		364	Stoody	A	10%; boil.	
244	Rh-Plat.	A	To boil.				F	Conc.; boil.	
245	Pyrasteel	V			365	Stoody	A	10%; boil.	
275	St 301	A	All %; Rm.	BIVTSCHDF			F	Conc.; boil.	
		A	65%; boil.	BIVTSCHDF	367	Super-Ni	X		
		A	All %; Rm.	BIVTSCHDF	368	Tantalum	A	All %; 392° max.	BCH
		A	65%; boil.	BIVTSCHDF	369	Telmic	V		
		A	Diluted 1:10; 70°; boil.		387	Stainless	A	A1 %	
		A	Diluted 1:1; 70°; boil.		388	Stainless	X	All %	
		A	Sp. gr. 1.40; conc.; 70°; boil.		389	Stainless	A	All %	
		A	Sp. gr. 1.52; conc.; fuming 70°; boil.		390	Worthite	A	All %; 175°	BIV
		A	50% max.; boil.	VTSCDF	392	Wyndaley	V	Very dilute; 65°	
		A	65%; boil.	VTSCDF			X	Moderate dilution; 65°	
		A	All %; 70°	VTSCDF			X	Conc.; 65°	
		X	Conc.; boil.		401	Karbate	V	40% max.	BIVPTCH
		A	All %		402	Karbate	V	40% max.	BIVPTCH
		A	All %; Rm.	IVF	403	Komprud	V	40%; max. 1	T
		A	65%; boil.	IVF	404	Acheson	V	40% max.	T
278	St. 303				500	Sul. cen.ent	A	30% max.; 200° max.	PTD

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
501	Sul. cement	A	30% max.; 300° max.	PTD	848	Silastic	A	10%; ASTM D-543-43	
502	Furan com.	X					A	Conc.; ASTM D-543-43	
503	Furan com.	X			849	Superflex	A	20% max.; 70° max.	BIPTSDF
504	Phen. com.	X			853	Thiokol	X		
505	Phen. com.	X			854	Thiokol	V	150° max.	PTSCDF
506	Silicate com.	A	1,000° max.	PTD	856	Vistanex	V	35%; Rm.	
507	Silicate com.	A	1,000° max.	PTD	913	Redwood	A	5-8% + Dil. H ₂ SO ₄ ; asphalt-L; 21 yr.; explosives mfg.	T
508	Acichlor	F	Dilute and conc.; 300°				A	1%; 40°-90°; Acid res. brick-L; chemical plant	T
510	Acithe	F	Dilute and conc.; 250°				A	Very dil.; 70°-80°; 19 yr.; explosives mfg.	T
513	Asplit	X		T	OXALIC ACID				
514	Asplit-F	X		T	3	Admiralty	A		
515	Basolit	A			4	Admiralty	A		CH
518	C-Basolit	A			6	Admic	A		
521	Causplit	X			10-17	Aluminum	V		
523	Duralon	X		T			A	Dry powders	
524	Durinite	X			22	Ambraley	A		CH
534	N-Series	X			23	Ambraley	A		CH
535	Nukem	X			24	Ambraley	A		CH
536	Nukem	A			29-40	Ampco	A		BIVPTCHDF
537	Pecomastic	V	Dilute and conc.; 300°		51	Berylo	A	Cold	
538	Penchlor	A	All %; 750° max.		54	Brass	X		
539	Penchlor	A	All %; 750° max.		61	Brass	X		
540	Penchlor	A	All %; 500°-2,000°		63	Brass	A		PCH
541	Pennsalt	X			66	Bronze	A		
542	Permanite	X			73	Bronze	A		VT
544	Plastite	F	Dil.; 125° max.	PTSD	74	Bronze	A		V
545	P-Basolit	A		T	75	Bronze	A		VP
554	Silastic	A	10%; ASTM D-543-43		76	Bronze	A		Instruments
		X	Conc.; ASTM D-543-43		77	Bronze	X		
556	Staminite	A	All %	T	96	Cast Iron	V		
559	Thiokol	X			99	Chlorimet	A		BIVHF
600	Acid Brick	A		TDR	111	Copper	A		
603, 612, 615	Glass	A		THDR	114	Copper	A		PTCHR
604	Cerathorm	A	200°-400°, depending on design	BIPTSCHDFR	117	Copper	V		P
606	Stoneware	A	All conditions	BIVPTCHDFR	118	Copper	A		
607	Glass-L	A	600° max.	PTCH	119	Corrosion	A	2.1, 7.9%; Rm.; unagitated; C.P.	BIPF
610	Stoneware	I	All %; any temp.	BIVPTCHDR	123	Cupro-Ni	A		CH
611	Porcelain	A	All % and temp.	BIPTDR	124	Cupro-Ni	A		
614	Glass-L	A	All %; under 302°; agitation	BTCH	139	Darco	A	All % and temp.	BIVHF
616	Pyrex	A			140	Durichlor	A	All % and temp.	BIVPCHFR
617	Stoneware	A	140°-160°	BIPTSCHDFR	141, 142	Durimet	A	All % and temp.	BIVHF
618	Vitreo	A	1,000° max.		143	Duriron	A	All % and temp.	BIVPHFR
619	Vitresail	A		PCH	148	Everdur	A		BIVR
621	Vycor	A			149	Everdur	A		PTCHDR
700	Ace Saran	A	77°	P	150	Everdur	A		PCH
703	Compac	X			156	Gold	A		
704	DC Silicone	A	10%		159	Hastelloy	A	All % and temp.	
707	Formica	F	5% max.; Rm.		160	Hastelloy	A	All % and temp.	
708	Formica	X	All %		161	Hastelloy	A	All % and temp.	
711	Havug	V	5%; 125° max.	BIVPTDFR	162	Hastelloy	A	All % and temp.	
715	Heresite	A	200° max.		163	Stellite	A	All % and temp.	BIV
718	Keweenaw	A	35% max.; 70° max.	TD	165	Stellite	A	All % and temp.	BIV
		A	10% max.; 150°	TD	184	Inconel	A	20-50%; 100°-175°	
720	Lamicaid	X			216	Monel	A	20-50%; 100°-175°	VPT
723	Nixon	X	10%; 77°		217	Monel-Clad	A	5%; any temp.	BTSCH
724	Nixon	A	10%; 77°		219	Muntz	X		
725	Nixon	A	10%; 77°		224	Nickel	F	20-50%; 100°-175°	
723	Permanite	X			226	Nick-Sil.	A		Instruments
735	Polythene	X	Conc.; hot		231	Ni-Resist	X	20-50%; 100°-175°	
736	Pyroflex	V		PTCHD	234	Olympic	A		
737	Resilon	F	Dil.; 125° max.	PTSD	235	Olympic	A		
738	Resistoflex	X			236	Palladium	A		
739	Resistoflex	X			240	Platinum	A		
740	Saran	F	77°		242	Ir-Plat.	A		
741	Saalon	A	160° max.	BPTDF	244	Rh-Plat.	A		
742	Teflon	A	Rm.	VP	270	304-Clad	A	10%; 70°	BTSCH
744, 745	Testolite	V		BI			A	5%; any temp.	BTSCH
746	Tygon	F	35% max.; 140° max.	BIPTSCHDF	271	316-Clad	A	10%; 70°	BTSCH
800	Ace Hd. Rub.	A	16° Be; Rm.	BIVPTDF			A	5%; any temp.	BTSCH
801	Acidseal	A	30% max.; 70° max.	BIPTSDF	274	430-Clad	A	5%; any temp.	BTSCH
805	Butyl	V	35%; Rm.		275	St. 301	V		
809	Fairprene	X			276	St. 302	A	10%; 70°	
814	GE Silicone	X	Conc.	VPTDF			F	10%; boil.	
817	Heresite	A	20% max.; 77° max.				F	25%; boil.	
836	Natural (S)	X					F	50%; boil.	
837	Natural (H)	V					A	5%; any temp.	VTSCDF
838	GR-S (S)	X					A	10%; 70°	VTSCDF
839	GR-S (H)	V					X	10%; boil.	
840	GR-A (S)	X							
841	GR-A (H)	V							
842	GR-M (S)	X							
843	GR-P (S)	X							
844	GR-I	A							
846	Saniprene	A	20% max.; 70° max.	BIPTSDF					

No.	Material	Rating	Exposure Conditions	Applications
278	St. 303	V		
279	St. 304	V		
		A	5%; any temp.	VTSCDF
		A	10%; 70°	VTSCDF
		X	10%; boil.	
280	St. 308	V		
281	St. 309	V		
282	St. 310	V		
283	St. 316	V		
		A	10%; 70°	
		F	10%; boil.	
		F	25%; boil.	
		F	50%; boil.	
		A	5%; any temp.	VTCHDF
		A	10%; 70°	VTCHDF
		X	10%; boil.	
284	St. 317	V		
285	St. 321	V		
286	St. 347	V		
287	St. 403	V		
288	St. 405	V		
290	St. 410	V		
291	St. 414	V		
292	St. 416	V		
293	St. 418	V		
294	St. 420	V		
295	St. 430	V		
		A	5%; any temp.	VTSCDF
		A	10%; 70°	VTSCDF
		X	10%; boil.	
296	St. 430-F	V		
297	St. 431	V		
298	St. 440-A	V		
300	St. 440-C	V		
301	St. 442	V		
303	St. 446	V		
319	St. CF-7M	A	10%; 212°	
367	Super-Ni	A		PTCH
368	Tantalum	A		Not used comm.
369	Telnic	A		
390	Worthite	A	178°	BIV
401	Karbate	A	All %; to boil.	PS
402	Karbate	A	All %; to boil.	PS
403	Kempul	A	All %; any temp.	
404	Acheam	A	All %; any temp.	
500	Sul. cement	A	200° max.	PT
501	Sul. cement	A	200° max.	PT
502	Furan cem.	A	360° max.	PT
503	Furan cem.	A	360° max.	PT
504	Phen. cem.	A	360° max.	PT
505	Phen. cem.	A	360° max.	PT
506	Silicate cem.	A	1,600° max.	PT
507	Silicate cem.	A	1,600° max.	PT
508	Acichlor	A	Dilute and conc.; 300°	
510	Acithe	A	Dilute and conc.; 350°	
513	Asplit	A	All %; 350° max.	
514	Asplit-F	A	All %; 350° max.	
515	Basolit	A	200° max.	T
517	Carbolime	A		
518	C-Basolit	A	200° max.	T
521	Causplit	A	All %; 350° max.	
523	Durifon	A	350° max.	BIPTCHDF
524	Durisite	A	350° max.	BIPTCHDF
535	Nukem	A	350° max.	T
536	Nukem	A		T
537	Pecomastic	X		
538	Penchlor	A	All %; 750° max.	
539	Penchlor	A	All %; 750° max.	
540	Penchlor	A	All %; 500°-2,000°	
541	Pennsall	A	All %; 350° max.	
542	Permanite	A	360° max.	TD
544	Plastite	A	175° max.	PTSD
545	P-Basolit	A	200° max.	T
554	Silastic	A	ASTM D-543-43	
556	Staminite	A	All %	T
559	Thiokol	A	150° max.	
609	Acid Brick	A		TDR
603, 612, 615	Glass	A		THDR
604	Coratherm	A	200°-400°, depending on design	BIPTSCHDFR
606	Stoneware	A	All conditions	BIVPTCHDFR
607	Glass-L	A	600° max.	PTCH
610	Stoneware	A	All %; any temp.	BIVPTCHDR
611	Porcelain	A	All % and temp.	BIPTDR
614	Glass-L	A	All %; 77° max.; agitation	BTCH

No.	Material	Rating	Exposure Conditions	Applications
616	Pyrex	A		
617	Stoneware	A	140°-160°	BIPTSCHDFR
618	Vitreo	-A	1,000° max.	
619	Vitreasil	A		
621	Vycor	A		
700	Ace Saran	A		P
704	DC Silicone	A		
706	Formica	A	All %; 122° max.	PT
707	Formica	V	All %	
708	Formica	F	All %; Rm.	
711	Haveg	A	All conditions	BIVPTDFR
713	Haveg	A	All conditions	BIVPTDFR
715	Heresite	A	200° max.	
720	Lamicoid	A		T
726	Nukomite	A	150° max.	PTSCDF
727	Nylon	A	Dilute	
728	Nylon	A	Dilute	
729-732	Nylon	X		
733	Permanite	A	360° max.	FVBTD
736	Pyroflex	V		PTCHD
737	Resilon	A	178° max.	PTSD
741	Sealon	A	160° max.	BPTDF
742	Teflon	A	Rm.	VP
744, 745	Textolite	V		BI
746	Tygon	A	180° max.	BIPTSCHDF
800	Ace Hd. Rub.	A		BIVPTDF
809	Fairprene	V		
814	GE Silicone	V	Rm.	VPTDF
817	Heresite	A	Sat.; 212°	
836	Natural (S)	V		
837	Natural (H)	V		
838	GR-S (S)	V		
839	GR-S (H)	V		
840	GR-A (S)	V		
841	GR-A (H)	V		
842	GR-M (S)	V		
843	GR-P (S)	X		
844	GR-I	V		
848	Silastic	A	ASTM D-543-43	
853	Thiokol	A	150° max.	T
854	Thiokol	A	160° max.	PTSCDF

PHENOL

3	Admiralty	V		
4	Admiralty	F		CH
6	Admic	A		
10-17	Aluminum	A	Rm.-212°; moisture inhibits action	VPTSCHD
22	Ambraloy	F		CH
23	Ambraloy	F		CH
24	Ambraloy	F		CH
29-40	Ampeco	A	If contamination is no factor	BIVPTCHDF
54	Brass	F		CH
61	Brass	F		VCH
63	Brass	FV		FCH
66	Bronze	V		
73	Bronze	F		VT
74	Bronze	F		V
75	Bronze	F		VP
76	Bronze	F		
77	Bronze	F		FCH
85	Cast Iron	A	Conc.	
88	Chlorimet	A	All % and temp.	BIVCHF
89	Chlorimet	A	All % and temp.	BIVHF
111	Copper	V		
114	Copper	F		PTCHR
117	Copper	V		P
118	Copper	V		
123	Cupro-Ni	F		CH
124	Cupro-Ni	V		
127-133	Dowmetal	A	248°	
		X	350°	
139	Durco	A	All % and temp.	BIVHF
140	Durichlor	A	All % and temp.	BIVPCHFR
141, 142	Durimet	A	All % and temp.	BIVHF
143	Duriron	A	All % and temp.	BIVPHFR
148	Everdur	F		BIVR
149	Everdur	F		PTCHDR
150	Everdur	F		PCH
156	Gold	A		
159	Hastelloy	A	All % and temp.	
160	Hastelloy	A	All % and temp.	

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
161	Hastelloy	A	All % and temp.		542	Permanite	A	360° max.	TD
162	Hastelloy	A	All % and temp.		544	Plastite	F	175° max.	PTSD
163	Stellite	A	All % and temp.	BIV	545	P-Basolit	A	200° max.	T
165	Stellite	A	All % and temp.	BIV	554	Silastic	X	ASTM D-543-43	
184	Inconel	A	90%; boil.	PTCH	559	Thiokol	X		
185	Inc-Clad	A	All %; any temp.	BTSCH	600	Acid Brick	A		TDR
216	Monel	A	90%; boil.	VPT	603, 612, 615	Glass	A		THDR
217	Monel-Clad	A	All %; any temp.	BTSCH	604	Cerathorm	A	200°-400°, depending on design	BIPTSCHDFR
219	Muntz	F		CH	606	Stoneware	A	Not commonly used	
224	Nickel	A	90%; boil.	BIVPTSCH	607	Glass-I.	A	600° max.	PTCH
225	Ni-Clad	A	All %; any temp.	BTSCH	610	Stoneware	A	All %; any temp.	BIVPTCHDR
226	Nick-Sil.	F		Instruments	611	Porcelain	A	All % and temp.	BIPTDR
231	Ni-Resist	A	90%; boil.	BIVP	614	Glass-I.	A	Under 302°; agitation	BTCH
234	Olympic	V			616	Pyrex	A		
235	Olympic	V			617	Stoneware	A	140°-180°	BIPTSCHDFR
236	Palladium	A			618	Vitreo	A	1,000° max.	
240	Platinum	A			621	Vycor	A		
242	Ir-Plat.	A			700	Ace Saran	A	Crystals; 77°	P
244	Rh-Plat.	A			703	Compac	V		
268	Silver	A			704	DC Silicone	X		
270	304-Clad	A	All %; any temp.	BTSCH	713	Harog	V	Satisfactory for water sol.	BIVPTDFR
271	316-Clad	A	All %; any temp.	BTSCH	715	Heresite	A	200° max.	
275	St. 301	V			718	Koroseal	A		TD
276	St. 302	V			720	Lamicaid	A		T
		A	C.P.; boil.		726	Nukemite	A	150° max.	PTSDF
		A	Raw; boil.; 212°		727	Nylon	X		
278	St. 303	V			728	Nylon	X		
279	St. 304	V			729-732	Nylon	X		
280	St. 308	V			733	Permanite	A	360° max.	FVBTD
281	St. 309	V			736	Pyroflex	A		PTCHD
282	St. 310	V			737	Resilon	F	175° max.	PTSD
283	St. 316	A		VP	738	Resistoflex	V		
		A	C.P.; boil.		739	Resistoflex	V		
		A	Raw; boil.; 212°		740	Saran	F	77°	
284	St. 317	A		PT	741	Sealon	A	100° max.	BPTDF
285	St. 321	V			742	Teflon	A	Rm.	VP
286	St. 347	V			746	Tygon	V	180° max.	BIPTSCHDF
287	St. 403	V			801	Acidseal	A		BIPTSDF
288	St. 405	V			802	Acidseal	A		BIPTSDF
290	St. 410	V			805	Butyl	A	Rm.	
291	St. 414	V			809	Fairprene	F		
292	St. 416	V			817	Heresite	A	Sat.; 122° max.	
293	St. 418	V			835	Perbunan	F	Rm.	
294	St. 429	V			836	Natural (S)	X		
295	St. 430	V			837	Natural (H)	V		
296	St. 430-F	V			838	GR-S (S)	X		
297	St. 431	V			839	GR-S (H)	V		
298	St. 440-A	V			840	GR-A (S)	V		
300	St. 440-C	V			841	GR-A (H)	V		
301	St. 442	V			842	GR-M (S)	X		
303	St. 446	V			843	GR-P (S)	X		
306	St. CA-15	A	Conc.; boil.		844	GR-I	X		
313	St. CF-7	A	Conc.; boil.		846	Saniprene	A		BIPTSDF
367	Super-Ni	F		PTCH	848	SElastic	X	ASTM D-543-43	
368	Tantalum	A		Not used commer.	849	Suporflex	A		BIPTSDF
369	Telnic	V			853	Thiokol	A		
390	Worthite	A	370°	BIV	854	Thiokol	A	150° max.	PTSCDF
401	Karbato	A	All %; to boil.	PH	856	Triflex	A		
402	Karbato	A	All %; to boil.	PH		Vistanex	A	Rm.	
403	Kompruf	A	All %; any temp.						
404	Acheson	A	All %; any temp.						
500	Sul. cement	A	Dilute sol.; low temp. only	PT					
501	Sul. cement	A	Dilute sol.; low temp. only	PT					
502	Furan cem.	A	Phenol sol.; 230° max.	PT					
503	Furan cem.	A	Phenol sol.; 230° max.	PT					
504	Phen. cem.	A	Phenol sol.; 230° max.	PT					
505	Phen. cem.	A	Phenol sol.; 230° max.	PT					
506	Silicate cem.	A	1,000° max.	PT					
507	Silicate cem.	A	1,000° max.	PT					
503	Asplit	X							
514	Asplit-F	X							
515	Basolit	A	200° max.	T					
517	Carbolite	A							
518	C-Basolit	A	200° max.	T					
521	Causplit	A	All %; 350° max.						
523	Duralon	A	350° max.	BIPTCHDF					
524	Duralite	A	350° max.	BIPTCHDF					
534	N-Series	X	Above Rm.						
535	Nukem	A	350° max.	T					
536	Nukem	A		T					
538	Penchlor	A	All %; 750° max.						
539	Penchlor	A	All %; 750° max.						
540	Penchlor	A	All %; 800°-2,000°						
541	Pensoak	A	All %; 350° max.						

PHOSPHORIC ACID

3	Admiralty	V		
4	Admiralty	V		CH
6	Admic	F	Attacked	
10-17	Aluminium	X		
19	Alloyca	A	25%; boil.	BV
		A	45%; 70°	BV
22	Ambraloy	V		CH
23	Ambraloy	V		CH
24	Ambraloy	V		CH
29-40	Ampco	F	Up to 85%; pure	BIVPTCHDF
54	Brass	X		
61	Brass	X		
63	Brass	V		PCH
66	Bronze	V		
73	Bronze	V		VT
74	Bronze	V		V
75	Bronze	V		VP
76	Bronze	V		
77	Bronze	X		
81	CA-FA28	A	85% aerated and agitated; 70°	BIVP
		A	85%; boil.	BIVP

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
82	MM	A	85% aerated and agitated; 70°	BIVP			A	80%; 140°	
		F	85%; boil.	BIVP			F	80%; 230°	
86	Cast Iron	V	Crude				A	5% max.; 70°	VTCHDF
88	Chlorimet	A	All % to 170°	BIVCHF			A	10%; 70°	VTCHDF
89	Chlorimet	A	All % to 170°	BIVHF			A	85%; aerated and agitated; 70°	BIVP
111	Copper	V			284	St. 317	A		BIVPTSCH
114	Copper	V		PTCHR	285	St. 321	A		BIVPTSCH
117	Copper	V	Dilute	P	286	St. 347	A		BIVPTSCH
118	Copper	V			287	St. 403	V		
119	Corrosion	A	10, 25, 87%; Rm.; unagitated; C.P.	BIVPF	288	St. 405	V		
					290	St. 410	V		
123	Capro-Ni	V		CH			A	1%; 70°	
124	Capro-Ni	V					X	All %	
139	Durco	A	All % and temp. except conc. boil.	BIVHF			A	85% aerated and agitated; 70°	BIVP
140	Durichlor	A	All % and temp. (except crude)	BIVPCHFR	291	St. 414	V		
141, 142	Durimet	A	All % to 176°	BIVHF	292	St. 416	V		
143	Duriron	A	All % and temp. (except crude)	BIVPHFR			X	All %	
148	Everdur	V		BIVR	293	St. 418	V		
149	Everdur	V		PTCHDR	294	St. 420	X	Medium and strong	
150	Everdur	V		PCH			V		
156	Gold	A	All %; any temp.				A	Weak	
159	Hastelloy	A	All % to 180°	BIVPTCHDF	295	St. 430	V		
160	Hastelloy	A	All % to boil.	BIVPTCHDF			A	1%; 70°	
161	Hastelloy	A	All % to boil.	BIVPTCHDF			A	5% max.; 70°	VTSCDF
162	Hastelloy	A	All % to boil.	BIVP			X	10%; 70°	
163	Stellite	A	All % to boil.	BIV			X	All %	
165	Stellite	A	All % to boil.	BIV	296	St. 420-F	V		
181	Hytensal	A	10% max.; cold	BIVF	297	St. 431	V		
184	Inconel	A	12%; 212°; un aerated		298	St. 440-A	V		
		A	57%; 70°		300	St. 440-C	V		
		X	90%; 230°		301	St. 442	V		
196, 200, 266	Lead	A	80% max.; 212° max.; 85% max. with crude	BIPTSCH	303	St. 446	V		
216	Monel	A	12%; 212°; un aerated	BIVPTCHDF	309	St. CC-35	A	85%; 130°	
		A	57%; 70°		316	St. CF-20	A		BIV
		A	90%; 230°		367	Super-Ni	V		PTCH
217	Monel-Clad	A	5% max.; 70°	BTSCH	368	Tantalum	V	All % (fluorine below 10 p.p.m.), to 392°	CH
219	Muntz	X							
224	Nickel	A	12%; 212°; un aerated	BVPT	369	Telnic	V		
		X	57%; 70°		387	Stainless	A	Weak	
		F	90%; 230°				X	Medium and strong	
225	Ni-Clad	A	5% max.; 70°	BTSCH	388	Stainless	X	All %	
226	Nick-Sil.	V			389	Stainless	A	All %	
231	Ni-Resist	F	12%; 312°; un aerated	BIVP	390	Worthite	A	5%; boil.	BIV
		F	57%; 70°				A	70%; 178°; with slurry & HF to 0.5%	BIV
		X	90%; 230°				A	85%; 270°	BIV
234	Olympic	V			392	Wyndaley	A	60°	
235	Olympic	V			401	Karbato	A	85% max.; to boil.	BIVPTH
240	Platinum	A	All %; any temp.		402	Karbato	A	85% max.; to boil.	BIVPTH
242	Ir-Plat.	A	All %; any temp.		403	Kemprud	A	All %; any temp.	PTDR
244	Rh-Plat.	A	All %; any temp.		404	Acheson	A	All %; any temp.	PTDR
245	Pyrasteel	V			500	Sul. cement	A	85% max.; 200° max.	PT
268	Silver	A	Under 365°		501	Sul. cement	A	85% max.; 200° max.	PT
		F	Over 365°		502	Furan cem.	A	85% max.; 360° max.	PT
270	304-Clad	A	Under 5%; 70°	BTSCH	503	Furan cem.	A	85% max.; 360° max.	PT
271	316-Clad	A	10%	BTSCH	504	Phen. cem.	A	85% max.; 360° max.	PT
274	430-Clad	A	Under 5%; 70°	BTSCH	505	Phen. cem.	A	85% max.; 360° max.	PT
275	St. 301	A		BIVTSC	506	Silicate cem.	A	85% max.; 1,600° max.	PT
276	St. 302	A		BIVTSC	507	Silicate cem.	A	85% max.; 1,600° max.	PT
		A	1%; 70°; boil.		513	Asplit	A	All %; 350° max.	
		A	1% at 45 lb. pressure; 275°		514	Asplit-F	A	All %; 350° max.	
		A	10%; boil.		515	Basolit	A	70%	T
		A	45%; boil.		517	Carbolino	A		
		A	80%; 140°		518	C-Basolit	A	70%	T
		X	80%; 230°		521	Causplit	A	All %; 350° max.	
		A	5%; max.; 70°	VTSCDF	523	Duralon	A	350° max.	BIPTCHDF
		X	10%; 70°		524	Darisite	A	350° max.	BIPTCHDF
		A	Weak or medium		532	Lumnite	A	1% max.; 90° max.	TD
		X	Boil.; strong		535	Nukem	A	70%; 350° max.	T
		A	Cold; strong		536	Nukem	A	70%	T
278	St. 303	A		IV	538	Penchlor	A	All %; 750° max.	
279	St. 304	A		BIVPTSCH	539	Penchlor	X		
		A	5% max.; 70°	VTSCDF	540	Penchlor	X		
		X	10%; 70°		541	Pennsalt	A	All %; 350° max.	
		A	85%; aerated and agitated; 70°	BIVP	542	Permanite	A	360° max.	TD
280	St. 308	A		BIVPTSCH	544	Plastite	A	175° max.	PTSD
281	St. 309	A		BIVTSC	545	P-Basolit	A	70%	T
282	St. 310	A		BIVPTSCH	554	Silastic	A	ASTM D-543-43	
283	St. 316	A		BIVPTSCH	556	Staminite	V	Cold	T
		A	1%; 70°; boil.		559	Thiokol	V	150° max.	
		A	1% at 45 lb. pressure; 275°		600	Acid Brick	A	Dil.; cold	TDR
		A	10%; boil.				X	Conc.; hot	
		A	45%; boil.		603, 612, 615	Glass	V	Better at low % and temp.	THDR
					604	Certherm	A	200°-400°, depending on design	BIPTSCHDFR

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
606	Stoneware	F	Under 176°		88	Chlorimet	A	All % and temp.	BIVCHF
607	Glass-L	V		PTCH	89	Chlorimet	A	All % and temp.	BIVHF
610	Stoneware	A	All %; any temp.	BIVPTCHDR	111	Copper	A		
611	Porcelain	V	Dil.; cold	BIPTDR	114	Copper	F		PTCHR
614	Glass-L	A	40% max.; 212° max.; agitation	BTCH	117	Copper	V		P
616	Pyrex	X	Glacial		118	Copper	A		
617	Stoneware	A	140-160°	BIPTSCHDR	119	Corrosion	A	25%; Rm.; unagitated; C.P	BIVP
618	Vitreous	V	1,000° max.		123	Cupro-Ni	A		CH
619	Vitreous	V			124	Cupro-Ni	A		
621	Vycor	X	Glacial		139	Darco	A	All % and temp.	BIVHF
700	Ace Saran	A		P	140	Durichlor	A	All % and temp.	BIVPCHFR
703	Compur	X			141, 142	Durimet	A	All % and temp.	BIVHF
704	DC Silicone	A			143	Duricon	A	All % and temp. (140 preferred)	BIVPHFR
707	Formica	F	All %; 122°		148	Everdur	F		BIVR
711	Haveg	A	All conditions	BIVPTDFR	149	Everdur	F		PTCHDR
715	Heresite	A	300° max.		150	Everdur	F		PCH
718	Koroseal	X			157	Gun Metal	A	Seawater	BIV
720	Lanicaid	A		T	159	Hastelloy	A	All % to boil.	
726	NuKemite	A	180° max.	PTSDF	160	Hastelloy	A	All % to boil.	
727	Nylon	X	Conc.		161	Hastelloy	A	All % to boil.	BIVPH
728	Nylon	X	Conc.		162	Hastelloy	A	All % to boil.	
729-732	Nylon	X			163	Stellite	A	All %; Rm.	BIV
733	Permanite	A	300° max.	BVPTD	165	Stellite	A	All %; Rm.	BIV
736	Pyroflex	A		PTCHD	181	Hytelal	A		BIVHF
737	Resilon	A	175° max.	PTSD	184	Inconel	A	Sat.; 200°	
738	Resistoflex	X			185	Inc-Clad	A	Sat. sol. mixed with steam and air; 200°	BTSCH
739	Resistoflex	X			193, 196, 200, 266	Lead	A	Dil. sol.; seawater; brine	BIPT
740	Saran	A	77°		216	Monel	A	Sat.; 200°	BIVPTCHDF
741	Saxlon	A	100° max.	BPTDF	217	Monel-Clad	A	Sat. sol. mixed with steam and air; 200°	BTSCH
742	Teflon	A	Rm.	VP	219	Muntz	V		CH
744-745	Testolite	V		BI	224	Nickel	A	Sat.; 200°	BV
746	Tygon	A	180°	BIPTSCHDF	225	Ni-Clad	A	Sat. sol. mixed with steam and air; 200°	BTSCH
800	Ace Hd. Rub.	A	93%	BIVPTDF	226	Nick-Sil.	A		Instruments
801	Acidseal	X			231	Ni-Resist	A	Sat.; 200°	BIVP
802	Acidseal	X			233	NS-5	A	All % and temp.	V
805	Butyl	A	85%; Rm.		234	Olympic	A		
809	Fairprene	A			235	Olympic	A		
814	GE Silicone	V		VPTDF	245	Pyrasteel	V		
817	Heresite	A	Sat.; 104° max.		249	Resistac	A		BIVCHF
836	Natural (S)	A			270	304-Clad	A	Sat.; boil.	BTSCH
837	Natural (H)	A			271	316-Clad	A	8%; 150°	BTSCH
838	GR-S (S)	A			274				
839	GR-S (H)	A			275	St. 301	V		
840	GR-A (S)	A			276	St. 302	V		
841	GR-A (H)	A					V	Cold saturated solution; 70°	
842	GR-M (S)	A					X	Hot saturated at 212°	
843	GR-P (S)	X					X	8%; 150°	
844	GR-I	A					X	Saturated; boil.	
846	Saniprene	X			278	St. 303	V		
848	Silastic	A	ASTM D-543-43		279	St. 304	V		
849	Superflex	X					X	8%; 150°	
853	Thiokol	V	150° max.	T			X	Saturated; boil.	
854	Thiokol	A	150° max.	PTSCDF	280	St. 308	V		
855	Triflex	X			281	St. 309	V		
856	Vistanex	A	85%; Rm.		282	St. 310	V		
913	Redwood	V	30%; 36-90°; 1-3 yr.; Airplane	T	283	St. 316	V		
			infr.				V	Cold saturated solution; 70°	
							A	Hot saturated at 212°	
							A	8%; 150°	VTCHDF
							A	Saturated; boil.	VTCHDF
					284	St. 317	V		
					285	St. 321	V		
					286	St. 347	V		
					287	St. 403	V		
					288	St. 405	V		
					290	St. 410	V		
					291	St. 414	V		
					292	St. 416	V		
					293	St. 418	V		
					294	St. 420	V		
					295	St. 430	V		
							X	8%; 150°	
					296	St. 430-F	V		
					297	St. 431	V		
					298	St. 440-A	V		
					300	St. 440-C	V		
					301	St. 442	V		
					303	St. 446	V		
					316	St. CF-20	A		BIV
					367	Super-Ni	A		PTCH
					368	Tantalum	V	Water sol. only; 212° max.	Not used comm.

SODIUM CHLORIDE

3	Admiralty	A		
4	Admiralty	A		CH
6	Admir	A		
10-17	Aluminum	AF	Rm.-boil.; Alclad alloys best	PTSCH
		A	Dry powders	
22	Ambralay	A		CH
23	Ambralay	A		CH
24	Ambralay	A		CH
29-40	Ampco	A		
51	Berylex	A		
54	Brass	V		CH
61	Brass	V		VCH
63	Brass	AF		PCH
66	Bronze	A		
67	Bronze	A	Seawater	BIV
71	Bronze	A	Seawater	BIV
72	Bronze	A	Seawater	BIV
73	Bronze	F		VT
74	Bronze	F		V ₂
75	Bronze	A		VP
76	Bronze	F		
77	Bronze	V		PCH
85	Cast Iron	A		
86	Cast Iron	A		
87	Causal	A		B

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
369	Telnic	A			SODIUM HYDROXIDE				
390	Worthite	A	All %; any temp.	BIV	3	Admiralty	V		
392	Wyndaloy	AV	Moderate dilution; 68°; sea-water and brines		4	Admiralty	F		CH
		AV	Conc.; 68°; seawater and brines		6	Admic	A		
401	Karbato	A	All %; to boil.	BIVPH	10-17	Aluminum	X		
402	Karbato	A	All %; to boil.	BIVPH	19	Alloyco	F	35%; boil.	BV
403	Kompruf	A	All %; any temp.				F	Molten; 600°	BV
404	Acheson	A	All %; any temp.		22	Ambralay	F		CH
500	Sul. cement	A	200° max.	PTD	23	Ambralay	F		CH
501	Sul. cement	A	200° max.	PTD	24	Ambralay	F		CH
502	Furan cem.	A	360° max.	PTD	29-40	Ampco	F	0.5% sol.; max.	
503	Furan cem.	A	360° max.	PTD	54	Brass	V		CH
504	Phen. cem.	A	360° max.	PTD	61	Brass	V		VCH
505	Phen. cem.	A	360° max.	PTD	63	Brass	VF		PCH
506	Silicate cem.	X			66	Bronze	V		
507	Silicate cem.	V	1,600° max.	TD	73	Bronze	F		VT
600	Acid Brick	A		TDR	74	Bronze	F		V
603, 612, 615	Glass	A		THDR	75	Bronze	F		VP
604	Ceratherm	A	200°-400°, depending on design	BIPTSCHDFR	76	Bronze	F		
606	Stoneware	A	Not commonly used		77	Bronze	V		PCH
607	Glass-L	A	600° max.	PTCH	81	CA-FA20	A	Under 20%; boil.	BIVP
610	Stoneware	A	All %; any temp.	BIVPTCHR			F	Molten; 600°	BIVP
611	Porcelain	A	All % and temp.	BIPTDR	82	CA-MM	A	Under 20%; boil.	BIVP
614	Glass-L	A	All %; 302° max.; agitation	BTCH			A	Molten; 600°	BIVP
616	Pyrex	A			85	Cast Iron	A		
617	Stoneware	A	140°-160°	BIPTSCHDFR	86	Cast Iron	A		
618	Vitreo	A	1,000° max.		87	Causal	A	40% max.; 230°	B
621	Vycor	A			88	Chlorimet	A	All % and temp.	BIVCHF
700	Acc Saran	A		P	89	Chlorimet	A	All % and temp.	BIVHF
704	DC Silicane	A			111	Copper	V		
706	Formica	A	All %; 212° max.	T	114	Copper	F		PTCHR
707	Formica	A	All %; 212° max.		117	Copper	V		P
708	Formica	F	All conc.		118	Copper	V		
711	Haveg	A	All conditions	BIVPTFDR	123	Cupro-Ni	A		CH
713	Haveg	A	All conditions	BIVPTFDR	124	Cupro-Ni	A		
715	Heresite	A	200° max.		127-133	Dowmetal	V	3%	
718	Koroasal	A	Any %; 150° max.	TD	139	Durco	A	All % and temp.	BIVHF
720	Lamicaid	A		T	140	Durichlor	A	All % and temp. (except boil.)	BIVPCHFR
723	Nixon	A	10%	S	141, 142	Durimet	A	All % and temp.	BIVCH
724	Nixon	A	10%	S	143	Durimet	A	All % and temp. (except boil.)	BIVPHFR
726	Nukemite	A		PTSDF	145	Everdur	F		BIVR
733	Permanite	A	360° max.	PVBDT	149	Everdur	F		PTCHDR
736	Pyroflex	A		PTCHD	150	Everdur	F		PCH
737	Resilon	A	175° max.	PTSD	156	Gold	A	All %	
741	Sealon	A	160° max.	BPTDF	159	Hastelloy	A	All % to boil.	BIV
742	Teflon	A	Rm.	VP	160	Hastelloy	A	All % to boil.	BIV
746	Tygon	A	180° max.	BIPTSCHDF	161	Hastelloy	A	All % to boil.	BIV
800	Acc Hd. Rub.	A		BIVPTDF	162	Hastelloy	A	All % to boil.	
801	Acidseal	A	All %; 150° max.	BIPTSDF	163	Stellite	A	All % to boil.	BIV
802	Acidseal	A	All %; 150° max.	BIPTSDF	165	Stellite	A	All % to boil.	BIV
805	Butyl	A	Dry salt; aqueous sol.; Rm.		184	Inconel	A	50%; 180°	
809	Fairprene	A					A	75%; 275°	
817	Heresite	A	Sat.; 212° max.		185	Inc-Clad	A		BTSCH
835	Perbunan	A	Dry salt; aqueous sol.; Rm.		216	Monel	A	50%; 180°	BIVPTCHDF
836	Natural (S)	A					A	75%; 275°	
837	Natural (H)	A			217	Monel-Clad	A		BTSCH
838	GR-S (S)	A			219	Munta	V		CH
839	GR-S (H)	A			224	Nickel	A	50%; 180°	BIVPTSCHDF
840	GR-A (S)	A					A	75%; 275°	
841	GR-A (H)	A			225	Ni-Clad	A	70% max.	BTSCH
842	GR-M (S)	A			226	Nick-Sil.	A		Instruments
843	GR-P (S)	A			231	Ni-Rosist	A	50%; 180°	BIVPH
844	GR-I	A					A	75%; 275°	
846	Saniprene	A	All %; 150° max.	BIPTSDF	233	NS-5	A	All % and temp.	
848	Silastic	A	ASTM D-543-43		234	Olympic	V		
849	Superflex	A	All %; 150° max.	BIPTSDF	235	Olympic	V		
853	Thiokol	A	150° max.	T	236	Palladium	A	All %	
854	Thiokol	A	150° max.	PTSCDF	240	Platinum	A	Any temp.	
855	Triflex	A	All %; 150° max.	BIPTSDF	242	Ir-Plat.	A	Any temp.	
856	Vistanex	A	Dry salt; aqueous sol.; Rm.		244	Rh-Plat.	A	Any temp.	
913	Redwood	A	25%; 30°-70°; 22 yr.; Tanks always full; chem. plant	T	245	Pyrasteel	V		
		F	20%; 40°-220°; 5 yr.; Soap plant	T	249	Resistac	A		BIVCHF
		A	2½%; 130°-200°; Packing plant	T	268	Silver	A	Any temp.	
		A	36,000 ppm.; 40°-100°; 4 yr.; Petroleum plant	T	270	304-Clad	A	20% max.; 70°	BTSCH
		A	1-2%; 75°; 18 yr.; Olive cannery	T	271	316-Clad	A	20% max.; 70°	BTSCH
		A	8½% + 0.5% Acetic acid; 36°-110°; paraffin-L; olives	T	274	430-Clad	A	20% max.; 70°	BTSCH
		A	Seawater; 30°-70°; 28 yr.; Tannery	T	275	St. 301	A	Solutions	BIVTSCH
		A	Seawater; 70°; 8 yr.; Fish cannery	T	276	St. 302	A	Solutions	BIVTSCH
							A	20%; 230°	
							A	Melting; 610°	
							A	20% max.; 70°	VTSCDF
							A	Weak or medium	
							X	Strong	

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
278	St. 303	A	Solutions	IV	535	Nukem	A	50%	T
279	St. 304	A	Solutions	BIVPTSCH	536	Nukem	X		
		A	20% max.; 70°	VTSCDF	538	Penchlor	X		
		A	Under 20%; boil.	BIPT	539	Penchlor	X		
		X	Molten; 600°		540	Penchlor	X		
280	St. 308	A	Solutions	BIVPTSCH	541	Pemsalt	A	All %; 350° max.	
281	St. 309	A	Solutions	BIVTSCH	542	Permanite	A	380° max.	TD
282	St. 310	A	Solutions	BIVPTSCH	544	Plastite	A	175° max.	PTSD
283	St. 316	A	Solutions	BIVPTSCH	545	P-Basolite	X		
		A	Melting; 610°		554	Silastic	F	10%; ASTM D-543-43	
		A	20% max.; 70°	VTCHDF			A	50%; ASTM D-543-43	
		A	Under 20%; boil.	BIPT	556	Staminite	X		
		X	Molten; 600°		559	Thiokol	F	150° max.	
284	St. 317	A	Solutions	BIVPTSCH	600	Acid Brick	A	Dil.	TDR
285	St. 321	A	Solutions	BIVPTSCH			V	Conc.	
286	St. 347	A	Solutions	BIVPTSCH	603, 612, 615	Glass	V	Better at low % and temp.	
287	St. 403	A		IV	604	Ceratherm	X	Conc.; hot	
288	St. 405	A		BIVTSCH	606	Stoneware	V	Under 10% at 77°	BIVPTDFR
290	St. 410	A		BIVPTSCH	607	Glass-L	V		PTCH
		X	Cold; strong		610	Stoneware	X		
		X	All %; boil.		611	Porcelain	V	Dil.; cold	BIPTDR
		A	Cold; weak or medium	BIVP	614	Glass-L	V	Not recommended	BTCH
		A	Under 20%; boil.		616	Pyrex	X	Conc.	
		X	Molten; 600°		617	Stoneware	X	Conc.; hot	
291	St. 414	A		IV	618	Vitro	X		
292	St. 416	A		IV	621	Vycor	X	Conc.	
		A	Cold; weak or medium		700	Ace Saran	A	50%; 77°	P
		X	Cold; strong		703	Compur	X		
		X	All %; boil.		704	DC Silicone	A		
293	St. 418	A			706	Fernica	F	10%; Rm.	f
294	St. 420	A					F	5%; 170°	F
		A	Weak and medium		707	Fernica	F	20%; boil.	T
		X	Strong				F	50%; Rm.	T
295	St. 430	A		BIVPTSCH	708	Fernica	A	10% max.; 122°	P
		A	20% max.; 70°	VTSCDF	713	Haveg	A	All conditions	
		A	Weak or medium		715	Heresite	V	5%; 70°	
		X	Strong		718	Kerosene	A	35%; 90°	TD
296	410-F	A		IV			A	10%; 130°	TD
297	St. 431	A		IV	720	Lamicaid	X		
298	St. 440-A	A			723	Nixen	X		
300	St. 440-C	A		IV	724	Nixen	X		
301	St. 442	A		BIVTSCH	726	Nukemite	A	50%; Rm.	PTSDF
303	St. 446	A		BIVPTSCH	727	Nylon	A		
313	St. CF-7	A	50%; boil.		728	Nylon	A		
316	St. CF-20	A		BIV	729-732	Nylon	A		
319	St. CF-7M	A	70%; boil.		733	Permanite	A	360° max.	BVPTD
344	Steady	A	25%; boil.		735	Polythene	A	50%	
365	Steady	F	25%; boil.		736	Pyroflex	A		PTCHD
367	Super-Ni	A		PTCH	737	Resilon	A	175° max.	PTSD
368	Tantalum	X			738	Resistoflex	X		
369	Telnic	V			739	Resistoflex	X		
377	Stainless	A	Weak and medium		740	Saran	F	77°	
		X	Strong		741	Seslon	A	100° max.	BPTDF
388	Stainless	A	Weak or medium; strong, cold		742	Teflon	A	Rm.	VP
		X	Strong; boil.		744, 745	Textolite	V		BI
389	Stainless	A	Weak; medium, cold		746	Tygon	A	190° max.	BIPTSCHDF
		X	Strong; medium, boil.		800	Ace Hd. Rub.	A		BIVPTDF
390	Worthite	A	50%; 200°	BIV	801	Acidseal	A	All %; 150° max.	BIPTSDF
		A	70%; 200°	BIV	802	Acidseal	A	All %; 150° max.	BIPTSDF
392	Wyndaley	A	Very dilute; 68°		805	Butyl	A	Rm.	
		AV	Moderate dilution; 68°		809	Fairprene	A		
		AV	Conc.; 68°		814	GE Silicone	V		VPTDF
401	Karbato	A	All %; to boil.	BIVPH	817	Heresite	A	70%; 150° max.	
402	Karbato	A	All %; to boil.	BIVPH	836	Natural (S)	A		
403	Kompruf	A	All %; any temp.	TR	837	Natural (H)	A		
404	Archemo	A	All %; any temp.	TR	838	GR-S (S)	A		
500	Sul. cement	X			839	GR-S (H)	A		
501	Sul. cement	X			840	GR-A (S)	A		
502	Furan cem.	X			841	GR-A (H)	A		
503	Furan cem.	A	360° max.	PT	842	GR-M (S)	A		
504	Phon. cem.	X			843	GR-P (S)	X		
505	Phon. cem.	X			844	GR-I	A		
506	Silicate cem.	X			846	Saniprene	A	All %; 150° max.	BIPTSDF
507	Silicate cem.	X			848	Silastic	A	10%; ASTM D-543-43	
508	Acichlor	F	Dilute and conc.; 300°				A	50%; ASTM D-543-43	
510	Acichlor	X	Dilute and conc.; 250°		849	Superflex	A	All %; 150° max.	BIPTSDF
513	Asplit	X			853	Thiokol	F	150° max.	T
514	Asplit	X			854	Thiokol	A	150° max.	PTSCDF
515	Basolit	X			855	Trilox	A	All %; 150° max.	BIPTSDF
518	C-Basolit	X			856	Vistanex	A	Rm.	
521	Causplit	A	All %; 350° max.		913	Redwood	A	3 1/4%; 75°; 15 yr.; Olive cannery	
523	Duralum	A	350° max.	BIPTCHDF			A	1-2% + dil. H ₂ SO ₄ ; 40°-212°	
524	Duralite	A	350° max.	BIPTCHDF				Soap plant	
534	N-Series	A	70% max. at 100°	BIVPTCDFR					

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
SULPHURIC ACID					193, 196, 200, 266	Lead	A	Under 96% to 60°; under 85% to 428° (No. 193, 245° max.)	BIPTSCHDF
3	Admiralty	V			216	Monel	A	5%; 80°; un aerated	BIVPTCHDF
4	Admiralty	V		CH			F	5%; 86°; aerated	
6	Admic	V	0.5-2.5%; 50%, 95%				A	19%; boil.	
10-17	Aluminium	A	Fuming; Rm.	S			A	45, 60%; 140°; un aerated	
		FX	Dil.; Rm.				A	80%; 86°	
19	Alloyco	A	All %; 70°	BV	217	Monel-Clad	A	Conc.; 70°	BTSCH
		A	50% max.; boiling	BV	219	Muntz	X		
		A	50%-93%; 150°	BV	224	Nickel	A	5%; 86°; un aerated	VP TH
		A	93% sulphuric to 65% oleum; 150°	BV			X	5%; 86°; aerated	
22	Ambraloy	V		CH			X	19%; boil.	
23	Ambraloy	V		CH	225	Ni-Clad	A	Conc.; 70°	BTSCH
24	Ambraloy	V		CH	226	Nick-Sul.	V		
29-40	Ampco	A	To 10%; 212° max.	BIVPTCHDF	231	Ni-Resist	A	5%; 86°; un aerated	BIVP
		V	10-75%; depends upon conditions	BIVPTCHDF			X	5%; 86°; aerated	
							X	19%; boil.	
42	Antaciron	A	All conditions, with slurry, reducing or oxidizing	BIV	233	NS-S	A	Under 60° Be.; hot or cold	V
51	Berylo	A	Cold		234	Olympic	V	95%	
54	Brass	X			235	Olympic	V	95%	
61	Brass	X			240	Platinum	A	To boil.	
63	Brass	V		PCH	242	Ir-Plat.	A	To boil.	
65	Bronze	V			244	Rh-Plat.	A	To boil.	
67	Bronze	A	Dil.; hot and cold	BIV	245	Pyra steel	V		
73	Bronze	V		VT	249	Resistac	A	66° Be. max.	BIVCHF
74	Bronze	V		V	270	304-Clad	A	Conc.; 70°	BTSCH
75	Bronze	V		VP	271	316-Clad	A	5%; 10%; fuming; 70°	BTSCH
76	Bronze	V			274	430-Clad	A	Conc.; 70°	BTSCH
77	Bronze	X			275	St. 301	V	Conc.; Rm.	
81	CA-FA20	A	5%; aerated and agitated; 70°		276	St. 302	V	Conc.; Rm.; 60° Be. min.; 180° F max.	
		A	5%; aerated and agitated; 176°				A	Diluted 1:20; 70°	
		A	75% aerated and agitated; 176°				X	Diluted 1:20; boil.	
		A	93% aerated and agitated; 70°				A	Diluted 1:10; 70°	
82	CA-MM	A	5%; aerated and agitated; 70°				X	Diluted 1:10; boil.	
		F	5%; aerated and agitated; 176°				A	Diluted 1:1; 70°	
		X	73% aerated and agitated; 176°				X	Diluted 1:1; boil.	
		F	93% aerated and agitated; 70°				A	Conc.; 1:0; 70°	
85	Cast Iron	A	Over 77%				F	Conc.; 1:0; 212°	
86	Cast Iron	A	75-95%; 98%-fuming				X	Conc.; 1:0; 300°	
		X	To 75%				A	Fuming, 11% free SO ₂ ; 212°	
87	Causal	A	Cold or hot to 60° Be.; Cold above 60° Be.	B	278	St. 303	V	Fuming, 60% free SO ₂ ; 70°, 100°	
88	Chlorimet	A	All % and temp. except hot over 80%	BIVCHF			V	Conc.; Rm.; 60° Be. min.; 180° F max.	
89	Chlorimet	A	Dil. all temp.; strong moderate temp.	BIVHF	279	St. 304	V	Conc.; Rm.; 60° Be. min.; 180° F max.	
		F	Intermediate %	BIVHF			A	5%; aerated and agitated; 70°	BIVP
111	Copper	V					X	5%; aerated and agitated; 176°	
114	Copper	V		PTCHR			X	75%; aerated and agitated; 176°	
118	Copper	V	95%				A	93%; aerated and agitated; 70°	BIVT
119	Corrosion	A	25, 87, 95%; Rm.; unagitated; C.P.	BIVPTCHDFR	280	St. 308	V	Conc.; Rm.; 60° Be. min.; 180° F max.	
123	Cupro-Ni	V		CH	281	St. 309	V	Conc.; Rm.; 60° Be. min.; 180° F max.	
124	Cupro-Ni	V	95%		282	St. 310	V	Conc.; Rm.; 60° Be. min.; 180° F max.	
139	Durco	A	All % to 176°	BIVHF	283	St. 316	V	Conc. or 16° Be.; Rm.	
		A	Under 45% to boil.	BIVHF			V	5% at 120° F max.; 60° Be. min., 200° max.	
140	Durichlor	A	All % and temp.	BIVPTCHFR			A	Diluted 1:20; 70°	
141	Durimet	A	All % to 176°	BIVCHF			F	Diluted 1:20; boil.	
		A	Under 25% boil.	BIVHF			A	Diluted 1:10; 70°	
		F	78% hot	BIVHF			X	Diluted 1:10; boil.	
142	Durimet	A	Under 10% boil; all % to 176° except near 60° Be. (141 preferred)	BIVHF			A	Diluted 1:1; 70°	
							X	Diluted 1:1; boil.	
143	Duriron	A	All % and temp.	BIVPHFR			A	Conc., 1:0; 70°	
148	Everdur	V		BIVR			F	Conc., 1:0; 212°	
149	Everdur	V		PTCHDR			X	Conc., 1:0; 300°	
150	Everdur	V		PCH			A	Fuming 11% free SO ₂ ; 212°	
156	Gold	A	To boil.				A	Fuming 60% free SO ₂ ; 70°, 160°	
159	Hastelloy	A	Under 50%; to boil.	BIVPTCHDF	284	St. 317	V	Over 15° Be.; Rm.	
		A	Over 50%; to 160°	BIVPTCHDF	285	St. 321	V	Conc.; Rm.	
160	Hastelloy	A	Under 60%; to boil.	BIVPTCHDF			V	Over 60° Be.; 180° F max.	
		A	Over 60%; to 160°	BIVPTCHDF	286	St. 347	V	Conc.; Rm.	
161	Hastelloy	A	Under 80%; to boil.	BIVPTCHDF			V	Over 60° Be.; 180° F max.	
		A	Over 50%; to boil.	BIVPTCHDF	287	St. 463	V	Conc.; Rm.	
162	Hastelloy	A	All % (except 55%) to boil.	BIVP	288	St. 405	V	Conc.; Rm.	
163	Stellite	A	All %; Rm. only	BIV	290	St. 410	V	Conc.; Rm.	
165	Stellite	A	All %; Rm. only	BIV			X	5%; aerated and agitated; 176°	
184	Inconel	A	5%; 86°; un aerated				X	78%; aerated and agitated; 176°	
		X	5%; 86°; aerated				A	93%; aerated and agitated; 70°	BIVP
		X	19%; boil.				V	Conc.; Rm.	
185	Inc-Clad	A	Conc.; 70°	BTSCH	291	St. 414	V	Conc.; Rm.	
191	Lead	A		PTH					

No.	Material	Rating	Exposure Conditions	Applications	No.	Material	Rating	Exposure Conditions	Applications
292	St. 416	V	Conc.; Rm.		617	Stoneware	A	140°-160°	BIPTSCHDFR
293	St. 418	V	Conc.; Rm.		618	Vitreo	A	1,000° max.	
294	St. 428	V	Conc.; Rm.		619	Vitreosil	A		PCH
295	St. 436	V	Conc.; Rm.		621	Vycor	A		
		F	Diluted 1:20, 70°		700	Ace Saran	A	60%; 122°	P
		X	Diluted 1:20, boil.		704	DC Silicone	V		
		F	Diluted 1:10, 70°		706	Formica	F	25% max.; Rm.	
		X	Diluted 1:10, boil.		707	Formica	F	25% max.; Rm.	T
		A	Conc. 1:0, 70°		708	Formica	X	All %	
		F	Conc. 1:0, 212°		711	Haveg	V	75%; cold	BIVPTFDR
		X	Conc. 1:0, 300°				V	50%; 300° max.	BIVPTFDR
296	St. 438-F	V	Conc.; Rm.		718	Kerosal	A	50%; 150°	TD
297	St. 431	V	Conc.; Rm.				A	60%; 100°	TD
298	St. 440-A	V	Conc.; Rm.		729	Lamicaid	X		
300	St. 440-C	V	Conc.; Rm.		723	Nixon	A	3%	S
301	St. 442	V	Conc.; Rm.				F	30%	S
303	St. 446	V	Conc.; Rm.		724	Nixon	A	3-30%	S
316	St. CF-20	A		BIV	726	Nukemite	A	40%; Rm.	PTSDF
344	Steady	A	10%; Rm.; boil.		727	Nylon	X	Conc.	
345	Steady	A	10%; Rm.		728	Nylon	X	Conc.	
		X	10%; boil.		729-732	Nylon	X		
347	Super-Ni	V		PTCH	733	Permanite	V	Dil.; cold	PVJDT
348	Tantalum	V	96% max.; 347° max. at 96%; avoid free SO ₂	H			X	Conc.; hot	
							X	Conc.; hot	
349	Telnic	V	95% and under		735	Polythene	V	Rm.	
357	Stainless	X	All %				V		
358	Stainless	X	All %		736	Pyroflex	V		PTDCH
359	Stainless	A	Weak; strong		737	Reazon	F	175° max.	PTSD
		X	Medium		740	Saran	F	77°	
					741	Sealon	A	100° max.	BTPDF
398	Worthite	A	All %; 125°	BIV	742	Tufcon	A	Rm.	VP
		A	1-50%; aerated; 175°	BIV	744, 745	Textolite	V		BI
		A	96-100%; aerated; 175°	BIV	746	Tygon	V	Dil. to med. conc.; 180° max.	BIPTSCHDF
		A	100-110%; 200°	BIV	800	Ace Hd. Rub.	A	50%	BIVPTDF
		F	50-83%; aerated; 140°	BIV	801	Acidseal	A	50%; 150° max.	BIPTSDF
392	Wyndalay	A	Very dilute				A	60%; 100° max.	BIPTSDF
		V	Other %		802	Acidseal	A	50%; 150° max.	BIPTSDF
401	Karbate	V	96% max.; 338° max.	BIVPTCHD			A	60%; 100° max.	BIPTSDF
402	Karbate	V	96% max.; 338° max.	BIVPTCHD	805	Butyl	V	70%; 140° max.	
403	Kempul	A	100% max. to boil.	PTDR	809	Fairprene	V		
		A	115% max. to 158°	PTDR	814	GE Silicone	V		VPTDF
404	Acheson	A	50% max.; to boil.	PTDR	817	Hereaite	A	50%; 122° max.	
500	Sul. cement	A	50% max.; 200° max.	PTD	836	Natural (S)	V		
501	Sul. cement	A	50% max.; 200° max.	PTD	837	Natural (H)	V		
502	Furan com.	A	50% max.; 360° max.	PTD	838	GR-S (S)	V		
503	Furan com.	A	50% max.; 360° max.	PTD	839	GR-S (H)	V		
504	Phen. com.	A	50% max.; 360° max.	PTD	840	GR-A (S)	V		
505	Phen. com.	A	50% max.; 360° max.	PTD	841	GR-A (H)	V		
506	Silicate com.	A	Strong sol. only; 1,000° max.	PTD	842	GR-M (S)	V		
507	Silicate com.	A	Strong sol. only; 1,600° max.	PTD	843	GR-P (S)	X		
508	Arichlor	V	Dilute and conc.; 300°		844	GR-I	V		
510	Archite	A	Dilute and conc.; 250°		846	Saniprene	A	50%; 150° max.	BIPTSDF
513	Asplit	A	All %; 350° max.				A	60%; 100° max.	BIPTSDF
514	Asplit-F	A	All %; 350° max.		848	Silastic	A	10%-30%; ASTM D-543-43	
515	Basolit	A	Diluted; 200° max.	T			X	Conc.; ASTM D-543-43	
517	Carbolime	A	50% max.		849	Superflex	A	50%; 150° max.	BIPTSDF
518	C-Basolit	A	Diluted; 200° max.	T			A	60%; 100° max.	BIPTSDF
521	Causplit	A	All %; 350° max.		853	Thiokol	X	150° max.	
523	Duralon	F	Sp. gr. 1.5; 350° max.	BIPTCHDF	854	Thiokol	F	150° max.	PTSCDF
524	Durite	F	Sp. gr. 1.5; 350° max.	BIPTCHDF	855	Triflex	A	50%; 150° max.	BIPTSDF
532	Lumite	A	1% max.; 90° max.	TD			A	60%; 100° max.	BIPTSDF
535	Nukem	A		T	856	Vistanex	V	70%; 140° max.	
536	Nukem	A		T	913	Redwood	A	5-12%; 36°-190°; Falsewood-L; steel pickle	T
537	Pecomastie	A	Dilute and conc.; 300°				A	8-8% + Dil. HNO ₃ ; 36°-90°; asphalt-L; explosives mfr.	T
538	Penchlor	A	All %; 750° max.				A	pH4.1; 36°-80°; 17 yr.; Plating works	T
539	Penchlor	A	All %; 750° max.				A	pH5.8; 36°-80°; 20 yr.; Plating works	T
540	Penchlor	A	All %; 600°-2,000°				A	4-5%; 36°-140°; 37 yr.; Armor plate pickling	T
541	Pennsalt	A	All %; 350° max.				A	3%; 36°-90°; 7 yr.; Plating works	T
542	Permanite	V	Dil.; cold	TD			A	2% + 1.5% HCl; 40°-180°; 21 yr.; Chemical plant	T
		X	Conc.; hot				A	1.5%; 36°-120°; 27 yr.; Tannery	T
544	Plastite	F	175° max.	PTSD			A	1% + 1-5% CuSO ₄ ; 36°-170°; 13 yr.; Chemical plant	T
545	P-Basolit	A	Dil.; 200° max.	T			A	0.5% + dil. NaOH; 40°-115°; 2 yr.; Soap specialties	T
554	Silastic	A	10%-30%; ASTM D-543-43				A	Dil. + dil. HCl + dil. lead acetate; 40°-150°; 13 yr.; paint	T
		X	Conc.; ASTM D-543-43				A	Dil.; 60°-200°; 2 yr.; Petroleum refinery	T
556	Staminite	A	All %	T					
559	Thiokol	X							
600	Acid Brick	A		TDR					
603, 612, 615	Glass	A		THDR					
604	Ceratherm	A	300°-400°, depending on design	BIPTSCHDFR					
606	Stoneware	A	All conditions	BIVPTCHDFR					
607	Glass-L	A	600° max.	PTCH					
610	Stoneware	A	All %; any temp.	BIVPTCHDR					
611	Porcelain	A	All % and temp.	BIPTDR					
614	Glass-L	A	All %; 325° max.; agitation	BTCH					
616	Pyrex	A							

Practical Aspects in Design of LIQUID AGITATORS

Despite all that has been written on the design of agitators for liquids, and mixtures of liquids with solids or gases, the subject is still far from exact and there is still room for practical information that will in most cases insure a correct design without resort to theories and formulas of doubtful validity. The author presents such a system, which has had the benefit of much actual and successful use.—*Editors*

AGITATION or mixing is perhaps one of the most important, but least understood, unit operations in chemical engineering. There is scarcely a vessel in a chemical plant which does not require some form of agitation, be it simply for suspending solids in a slurry or—the more difficult case—the dispersion of gas in a liquid. In certain chemical reactions the rate depends immeasurably upon the degree of agitation. The dissolving of solids, and the heating and/or cooling of liquids in tanks is influenced by agitation. Chemical engineers are discovering every day, to an always increasing extent, the importance of agitation as a critical variable in chemical processes.


The subject of agitation has been investigated quite thoroughly in the laboratory and reported by A. W. Hixson¹ in a recent article which gave 127 references to various publications in this field. These publications represent considerable work and the expenditure of a large amount of time and effort. However, an air of mystery still surrounds this unit operation and, so far, a straight-forward method for the selection and design of liquid agitators has not been published. In the majority of cases the design chemical engineer seeks the advice of the agitator equipment companies but, despite this, a need is felt for a simple procedure whereby efficient liquid agitators

can be designed with assurance, or proposed designs can be checked.

The author is familiar with an agitator design, and the subsequent equipment installation by a large mixing company, where a 15-hp. motor was used to drive the agitator impeller. As the agitation appeared ineffective, a power test was made using a recording wattmeter and it was found that the agitator impeller was actually consuming only a little over 1 hp. In all honesty, perhaps the complete facts were not given to the designer, but an error of this magnitude should have been discoverable with available design methods.

Until sufficient performance data on pilot plant mixers have been accumulated and correlated, it will probably always be necessary to resort to small-scale experiments to obtain design data for specifying certain agitators to meet the unusual conditions occasionally encountered in complex chemical reactions. However, certain data are now available for the design of liquid agitators, and the design does not involve the application of numerous theories and formulas. With the help of these data, large-scale agitators can be designed from pilot plant experiments with some degree of confidence.

Fig. 1—Agitators of these four types suffice for 95 percent of liquid mixing problems; modifications handle most others






Fig. 2—Approximate relation of degree of agitation and power input per 1,000 gal. of solution

AGITATOR IMPELLER TYPES

Selection of the proper agitator impeller is the first consideration in the design of a liquid agitation unit. There are four main types of agitator impellers, including:

- a. Propellers
- b. Flat-bladed paddles
- c. Turbines
- d. Anchors.

The general types of impellers, well-known to all engineers, are illustrated in Fig. 1a to d. Besides these types, there are many tricky designs which are variations of those mentioned, some of which have advantages for certain special uses. In 95 percent of the mixing problems encountered, one of the standard types properly designed will perform the required mixing adequately. Each of these standard impellers has its proper place when agitators are used for liquid-liquid mixing, liquid-solid mixing, liquid-gas contacting, and liquid-gas-solid contacting.

Propellers are principally used as high-speed mixers for some cases of liquid-solid mixing and liquid-liquid mixing and, as such, have a definite place in the liquid agitator field. In mixing operations requiring mechanical cutting and shearing, propellers have proved most satisfactory. Their power consumption is low, together with a low initial capital investment. They are useful mainly in small-capacity vessels; however, in the case of large-diameter and large-capacity storage or blending tanks, propeller agitators have been used successfully by installing two or more units around the circumference of the tank near ground level. A propeller agitator is not basically effective in a highly viscous or dense solution, and care must be taken to install the propeller in the tank off-center either horizontally or vertically to prevent vortexing and swirling of the entire contents of the

Fig. 3—Power consumption of propeller type agitators (from Badger et al, *Chem. & Met.*, 27, 1176, 1922)

vessel. A very good article on the use of the marine-type propeller and the so-called "radial" propeller was recently published.

The flat-bladed paddle agitator having two, three, or four blades has been used extensively in the chemical industry. Agitators of this type have usually been recommended for use at low speeds only, but with proper design they can be used at speeds up to 180 r.p.m. Paddle agitators are of low initial cost, easily fabricated or modified in the field, and are useful in nearly all types of mixing. In considering a mixing problem, careful thought should be given to the use of a paddle-type impeller as it is highly effective over a wide range of solution viscosities and densities.

Turbine-type agitators, with both open and shrouded impellers, are likewise popular in the industry and can be used for nearly all types of mixing. Turbine impellers are expensive and care must be taken in fabrication to obtain good balance; however, a properly designed turbine impeller is well-suited for the difficult job of dispersing gases in a liquid. A few years ago* a modification of the conventional turbine impeller known as the "dispenser-type" turbine was introduced for liquid-gas contacting and has proved to be very effective.

Anchor-type impellers are mainly used in glass-lined vessels where their shape leads to ease of enameling operations. They are most helpful where viscous materials or liquids containing a high percentage of solids are agitated. This type of agitator, slightly modified, is used in Dopp kettles to prevent a build-up of solids on the sides of the kettle because such a build-up lowers over-all heat transfer rates. Anchor-type agitators are used for conditions requiring a low degree of agitation, and operate at speeds under 120 r.p.m.

One of the most difficult problems in designing an agitator is what criterion to

use in describing the desired degree of agitation and how to translate this criterion into design terms.

Agitation is usually spoken of in terms of "vigorous" or "mild" or some other such nonspecific term. A single quantitative term which can be applied to mixing and agitation has not, as yet, been found. The design engineer is faced with the problem of furnishing "good agitation" because the operating or research group usually specifies "good agitation" as very necessary for carrying out the proposed chemical reaction; or sometimes, he has to design an agitator which will "just keep the solids in uniform suspension."

The criterion of power input per unit volume is recommended for the present state of the art as one means of specifying the degree of agitation. It is realized that this procedure is only qualitative, but the results obtained have been proved to be reliable and adequate in most cases. Fig. 2 shows the relationship of degree of agitation and horsepower input per unit volume with solutions similar to water. When this chart is used for solutions having high viscosities and densities, the indicated power input should be increased 25 to 50 percent to obtain the same degree of agitation. This plot, based on the experience of the author and others, is intended only as a guide since, as mentioned previously, the terms "mild agitation" and "vigorous agitation" have little value and must be viewed in the light of experience.

POWER CONSUMPTION

Once the proper agitator impeller has been selected and the power input to give the required degree of agitation determined, it is necessary to calculate the size and speed of the impeller to obtain the correct power input.

A nomograph shown in Fig. 3 has been developed for calculating the power requirements for propeller-type impellers of certain pitch and diameter at various speeds. This nomograph is based on agitation in solutions of the viscosity of water. The power consumption is the power actually consumed by the propeller and not the size of the motor for the agitator unit. However, since the nomograph is based on the assumption that the propeller is 100 percent efficient (whereas efficiency is actually about 60 percent), the power figure obtained will be conservative. With this factor of safety already incorporated in the power figure no additional increase is necessary when agitating fluids having a viscosity up to 100 centipoises.

For flat-bladed paddles power requirements may be estimated by the use of the following equation developed by White et al¹:

$$P = 0.00013L^{2.72}Z^{0.54}N^{2.84}\rho^{0.59}D^{1.4}W^{0.3}H^{0.4}$$

where: P = horsepower; L = paddle

length (ft.); Z = Absolute viscosity (lb. per sec.-ft.); N = Revolutions per second; ρ = Density (lb. per cu. ft.); D = Tank diameter (ft.); W = Paddle width (ft.); and H = Liquid depth (ft.).

Experimental work on which this equation is based covered a wide range of paddle sizes, speeds, etc., and the final correlation included some data on four-bladed as well as two-bladed paddles. This formula is fairly reliable, but should be carefully interpreted by the designer and when applied for three- and four-bladed paddles the power computed should be increased by approximately 25 and 50 percent, respectively.

In Fig. 4 the power consumption as a function of speed is given for a number of standard-size turbine-type impellers. This power is the net power delivered to the turbine when agitating a solution of the viscosity of water. The effect of viscosity on the power requirements of turbine impellers is shown in Fig. 5. The power values obtained from these figures are reliable and can be used safely.

Very few data are available on the power consumption of anchor-type agitators, probably because of their limited use. However, as a rough estimate the power can be computed using the formula for flat-bladed paddles by assuming the paddle length to be the horizontal width of the agitator, and increasing this power value by the ratio of the total surface of the agitator to the surface used in the calculation.

DESIGN DETAILS

In the actual design of an agitator unit, careful consideration should be given to the design of the mixing vessel. For effective agitation, that is, the proper degree of agitation required by any one job, the vessel should have a ratio of height to diameter of from 1.0 to 1.5. Whenever good and effective agitation is desired, the mixing vessel should be baffled in order to increase the turbulence which, incidentally, will increase the power consumption from 10 to 25 percent and should be allowed for in selecting the drive motor. These baffles can consist of three or four equally spaced vertical members fastened to the side of the vessel. They should extend from above the liquid level down to a point below the location of the agitator impeller and should have a width about one-tenth the vessel diameter.

The selection of the diameter of a liquid impeller agitator is always something of a problem, but its solution for turbine impellers is made relatively easy by the fact that in most cases the range of standard sizes available limits the choice. As a starter, an impeller diameter one- to two-thirds the tank diameter may be chosen; then this size should be matched with the standard impellers available.

There are some data which indicate that

the length of a paddle-type impeller blade should be approximately equal to the radius of the mixing vessel. Another limiting factor when closed vessels are agitated is to select an impeller that will go through the manhole. The width of a liquid impeller agitator must be balanced against the diameter and speed to obtain the proper power input. A turbine impeller usually has a width about one-tenth of the diameter, while the width of a paddle-type impeller should be from one-eighth to one-quarter the length. The blades of a standard turbine impeller are usually inclined at an angle of 45 deg. Experience of the author indicates that the blades of the paddle-type impeller should be inclined at 30 to 45 deg. from the vertical.

The exact location of the impeller agitator in the mixing vessel has been a subject of controversy for many years. Some designers place the impeller one-third of the distance up from the bottom of the tank to the liquid level. Others place the impeller at a distance from the bottom of the tank equal to the impeller width, whereas still others place the impeller approximately one-half of the diameter of the impeller from the bottom of the tank. The author's experience indicates that for commercial installations the impeller should be placed approximately 4 to 8 in. above the bottom of the tank. However, this rule should not be followed too rigidly as, for example, in the agitation of liquids in extremely deep vessels or where heavy solids might collect on the bottom.

In the majority of cases, the impeller should rotate in such a direction as to push the liquid downward over the bottom of the tank. There may be a few cases where it will be more advantageous to have the impeller push upward, but

these should be determined by experimentation. Several years ago an agitator was installed in a jacketed tank used for cooling a reactor charge from approximately 450 deg. F. to 200 deg. F. By mistake, the turbine impeller was installed to push upward and the rate of cooling was found to be quite low. As soon as the error was discovered and the impeller rotation reversed, the cooling rate increased considerably. This was merely a matter of increasing the turbulence and the velocity of the liquid past the tank walls in order to increase the heat transfer coefficient. In the case of dispersing gases in a liquid where the gas is introduced under the outer edge of the impeller, it has likewise been noted that greatly increased results are obtained with the impeller pushing the liquid downward. In some deep vessels, best agitation may be obtained by use of two impellers on a common shaft rotating so that the lower impeller pushes the liquid downward and the upper impeller pushes upward.

Design details which should be given careful consideration include the diameter of the shaft, power losses in the stuffing box, inefficiencies of the reduction gears, maximum shaft length, and others more or less of a mechanical nature. The answer to these details can best be obtained from the mixing equipment manufacturer.

REFERENCES

1. Hixson, A. W., *Ind. Eng. Chem.*, 36, 488 (1944).
2. Brumagim, I. S., *Chem. & Met.*, 53, 110 (1946).
3. Rushton, J. H., *Ind. Eng. Chem.*, 37, 422 (1945).
4. White et al., *Trans. A.I.Ch.E.*, 30, 585 (1934).
5. Brothman, A., *Product Eng.*, April (1940).
6. Brothman, A., *Product Eng.*, Sept. and Nov. (1940).

Fig. 4—Power consumption of standard size turbine type liquid-mixing impellers (Courtesy of New England Tank & Tower Co.)





Fig. 5—Effect of viscosity on power consumption of turbine-type impellers ("Chemical Engineers' Handbook," 2nd ed., p. 1554)



1946 CHEMICAL INDUSTRY MEDAL

On November 8 the American Section of the Society of Chemical Industry honored Dr. Willard H. Dow, president of the Dow Chemical Co., by awarding him the Chemical Industry Medal for 1946. Dr. William J. Hale, research consultant for the Dow company and brother-in-law of the medallist, served as personal sponsor while the professional sponsor was Major General Alden H. Waitt, chief of the Army's Chemical Corps. Highlights of the three addresses of the occasion are presented here.—Editors



William J. Hale



Alden H. Waitt

The Man

IN THE FALL OF 1918, it fell to my lot to repair to Midland and organize organic chemical research of the Dow Chemical Co. In the summer of 1919, Mr. Willard Dow returned to his native city and took up work at the chemical plant. It was as my assistant that he decided to serve for a few months and learn the ways of organic chemicals.

To my way of thinking the most outstanding characteristic of Willard Dow is his inventiveness, coupled with perseverance. Everything that meets his attention stirs up quandaries within him as to how best it may be improved. But along with his inventiveness there is also that urge for preparedness. His general aim seems to concern itself with the appointment of assistants to positions such that will guarantee a maximum performance for the whole.

In this chemical age all further advance must be chemically sound, otherwise it becomes labor lost. It is here that Dr. Dow has bent his best efforts to prepare for enormous production of chemicals from the sea, especially bromine and magnesium; but he has plans for many more from this same source.

Utilization of everything to the best interests of society and to the highest degree has become the incentive of Dow Chemical and its entire personnel. When Dr. Dow

once perceives the possibility of a lowering in cost of any chemical of our manufacture his ready mind is alert and pointed to some new adaptation lurking just around the corner. Truly he delights in reconnoitering untrodden paths.

The greatest forward strides of Dow Chemical have followed directly the rise to its presidency of Dr. Willard Henry Dow. His courage and driving force have never faltered.

His Accomplishments

AFTER WORLD WAR I, Dow and other companies continued to develop production of magnesium, but the others finally abandoned their efforts, convinced it was impossible to produce at a competitive price. Willard[®] Dow pushed research on magnesium recovery, and for more than 15 years chased molecules of magnesium around the brine, sometimes in the red financially, but always in the black technically. The military services reaped the full benefit of these years of research.

Dr. Dow's love of doing the impossible contributed no small part in winning the battle of transportation in World War II. With the spiralling demand for lead tetraethyl in the late 20's and early 30's, many concerns had been attracted by the unlimited supply of bromine in seawater but had abandoned their development

efforts as uneconomical. Dow had been producing bromine from the Midland brine since the establishment of the concern. With the experience thus gained, Dow tackled the problem of extracting bromine from the seawater successfully. The ethylene dibromide plant at Kure Beach gave our army the finest motorized equipment of any army.

When our supply of rubber was suddenly shut off after Pearl Harbor, another pioneer development by Dow became vital to our war effort. Styrene furnished the quickest process for the production of synthetic rubber. Dow had been producing styrene commercially since 1937 and was the sole producer at the outbreak of the war. Dow's know-how was made available to the government, and they not only expanded their own production but also assisted competitor-operated plants by furnishing engineering service and in training their operating personnel.

In addition, Dow has pioneered work in production of butadiene, on which they had started development work in the late 30's.

A byproduct of Dow's early research on production of ethyl cellulose and styrene played an important role in the development of certain wartime applications that have been secret until very recently. Their polyfiber radomes were used extensively. From this same polyfiber came a new type of separator for storage batteries.

One of the major developments of the war was the radio proximity fuze. The pioneering work of Dow in molding ethyl cellulose provided the solution which permitted early production of this fuze.

A little publicized side of Dr. Dow's technical achievements is in the field of human engineering. This sympathetic interest had much to do with the fact that during all the war years no Dow plant, and no Dow operated plant, lost a day's production because of strikes or work stoppages.

Another little publicized side of Dr. Dow's technical ability is in the field of

therapeutic agents. He has deep personal interest, and supports extensive research in the development of new treatments for tuberculosis and cancer.

The many sided technical training of Dr. Dow was utilized to the utmost by the government during the war. His counsel was given as a member of a large number of technical advisory committees. The Chemical Advisory Committee of the Army and Navy Munitions Board, The Chemical Warfare Advisory Committee, The Quartermaster Advisory Board, The Rubber Reserve Corporation—these are just a few of his wartime activities.

The American Section of the Society of Chemical Industry is honoring an outstanding American in awarding its Chemical Industry Medal to Dr. Willard Dow. His record before and during the war has been outstanding. It is to such men as he that we must now look in the winning of the peace.

Salts of the Earth

Ours is a scientific company by whose ideals and harmonious cooperation the salts of the earth, the water and the air have been utilized to give man's daily life new meaning. It is the vital constructive force of all industry that has made America great, an example to the people of the world who would attain that same measure of life. This constructive force has issued from a free people—free in their thoughts, in their work and in their ventures. From these salts of the earth has sprung the chemical industry.

When we consider chlorine chemistry, or the chemistry of salt, starting with the electrolytic decomposition of salt into chlorine and caustic soda, we cannot but be astounded at the effect of electricity and electrochemistry upon our lives. These products of the electrochemistry of salt or their diverse compounds are vital to the petroleum, lumber, automobile and textile industries. They go into hundreds of medicinal compounds, fumigants and insecticides to protect our health and our food, as well as being key factors in water purification and sewage treatment. They hold a dominant position in the making of rayon and practically all plastics—in dry cleaning fluids, refrigeration media and fire extinguishers. They are so much a part of us that we can scarcely touch an object that has not in some way been benefited by the chemistry of salt.

Too seldom do we stop to glorify our stupendous industrial successes. Or perhaps we have dwelt too much and too long on success in terms of the dollar—too little in terms of the humanities. We have judged the merit of a company by the extent of its physical assets rather than by the number of human beings with which its operations provide the comforts of life—by the magnitude of its sales rather than

the degree to which its products have made life finer and fuller.

Looking back over a number of decades, we can see how each new advance could have been used to wreck and destroy, or to give unwarranted power to one group or another. But the reassuring, the inspiring part of it is that our great advances have come through great men with the vision to see beyond the nearest street corner.



Willard H. Dow

Altogether too many people these days are taking the attitude that they have no responsibility, yet there is not a single man who can honestly say he does not enjoy the benefits of modern society. All benefits, no matter how small, create responsibility, and only by accepting responsibility can we hope to realize the benefits of further progress.

Because the chemical industry, and all industry, has been mindful of its responsibility to civilization, we have in this country an exceedingly high standard of living. Work and more work and hard work has been the means to this end. No Aladdin's Lamp or magic carpet has lifted us to that present plane of living—nor will it carry us to further heights. The blessing of hard work is what we must glorify and live by, and the satisfaction and pleasure of a job well done is a reward no one will ever measure in dollars. Industrial success breeds progress, and the dollar is only the clothing—not the flesh and blood and soul of the offspring.

It is a strange commentary on the intelligence of our people that they so readily forget that we had an economy in our country before we had economists. True principles of economics cannot be discovered by experimentation because of the human factor. And when we try to make an exact science out of the actions of human nature, with the dollar motive the paramount issue, we must necessarily meet with one failure after another. Human nature and its reactions cannot be made into exact science.

The measure of industry's responsibility rests on finding the proper type of man

for every job and conversely the proper job for every man. The average man must see his responsibility as well as the industrialist; when these responsibilities are recognized and accepted, then most of our problems are over. In place of such folderol as "the world owes a man a living," we shall hear from every honest citizen, "Every man owes the world something in return for the blessings so freely offered." Each individual in every walk of life must justify that right. There are no rights without responsibility, and conversely, since acceptance of responsibility grants rights.

The ability of the human race to work together to solve a problem by the use of combined intellectual brainpower is the very foundation of our many successes. Therefore it is incumbent on each one of us to apply that brainpower to the solution of our many problems. Nearly everything has a simple solution and any problem should be reduced to its simple fundamentals. For example, if you wish to produce magnesium, you must have an abundant source of raw material. The natural reaction is to consider dolomite or some other magnesium bearing ore, but this is not the truly simple solution. Why mine rock when it is so much easier and cheaper to mine ocean water? And then again, sea water is available to all.

As a large producer of magnesium, it was logically our responsibility to go to the largest source of supply of raw material for its production. As we had commercially demonstrated the practical extraction of bromine in a concentration of 65 parts per million parts of ocean water, so surely the extraction of magnesium, with a concentration of 1,200 parts per million, was feasible. This accomplishment is a matter of record, but its greatest significance may yet lie beyond the horizon. After sodium chloride, magnesium as magnesium chloride is the next most abundant mineral in sea water, and along with it can be accumulated trace elements such as manganese, iron, copper, boron and others. Here then is offered a means of returning these ingredients to the soil for use as soil enrichers and fertilizers.

We see the continents of the world well blessed with the rich resources of the oceans—resources containing recoverable quantities of the order of 4,500,000 tons of magnesium, 85,000,000 tons of sodium chloride and 230,000 tons of bromine per cubic mile, not to mention many thousands more tons of elements of perhaps greater value. The industries of the world are standing ready to offer their every assistance.

Nature offers the opportunity to advance. Our civilization is enlightened chemically, physically and mechanically, but not spiritually. Is it not high time to forsake false issues and return to fundamental thinking—fundamentals that nake for a full life, liberty and the pursuit of happiness?

What Readers Think About Equipment Cost Data Plan

Here are a few of the letters that readers have sent to *Chemical Engineering*, commenting on the plan proposed by Henry Eckhardt on page 104 of our September issue. Chemical engineers are badly in need of standard cost estimating data for both chemical equipment and chemical process operation. Past efforts at securing such data have been largely unproductive. Mr. Eckhardt suggests a new type of approach through the cooperative efforts of those who would be most benefited — that is, the engineers whose files already contain data of this sort, but to whom a complete compilation would be of enormous benefit. The editors are enthusiastically behind the plan and will gladly serve as the correlating agency. If you have not read the Eckhardt plan we urge you to do so and let us have the benefit of your opinions.

THE EDITORS

CHARLES OWEN BROWN
CHEMICAL ENGINEER
SPECIALIST IN
HIGH PRESSURE PROCESSES
HYDROGEN FLUORIDE
PLANTS

33 MADISON AVENUE
NEW YORK
UNIVERSITY 4-1115

October 3, 1946

Mr. S. D. Kirkpatrick, Editor,
Chemical Engineering,
330 West 42nd Street
New York 18, New York

My dear Sir:

I have read with a great deal of interest the article by Henry Eckhardt that appeared in your September issue. I think it would be an excellent idea of making a major piece of work out of this suggestion. I believe that it warrants another handbook of the order of Perry's.

Although I have been thinking of devoting a number of articles to an exposition of chemical plant cost data and similar data on operating costs for chemical processes, I think this idea is not as good as the suggestion of Eckhardt, and that it would be much better if a cooperative effort were made to produce a real handbook. Such a book, I think, should be published by McGraw-Hill in view of their excellent past record.

Eckhardt has made a very excellent contribution. It was interesting to me to note his list of seven references on cost data. They emphasize the paucity of this information and confirm the records I have in my office concerning the standard tests available on this subject. Fortunately, my files are a much better source for such information.

COB:sw

Very truly yours,

Shas O'Brien

SOUTHERN ALKALI CORPORATION

CORPUS CHRISTI, TEXAS
October 9, 1946

Mr. Sidney Kirkpatrick
Chemical Engineering
330 W. 42nd St.
New York 18, N. Y.

Subject: Article on Cost Estimating

Dear Sir:

Mr. Eckhardt has done an excellent job of presenting the problem in the September issue. We are looking forward to a series of articles presenting the solution of the problem. You may as well set them up as to run reprints of the series as they are likely to be one of your most popular items.

Mr. Eckhardt's suggestion of tying price estimates to commodity index or something of the sort is very good, but to show up regional inequalities it might be desirable to tie it back to base metal prices and man hours or sell as to the commodity or wage scale index.

Since manufacturers are so reluctant to give out prices, you will no doubt be put to some little expense securing satisfactory personnel to get the data; however, we believe the interest would justify all the difficulties encountered.

Very truly yours,
Clayton Thompson
Chemical Engineer

COB:j

WAR ASSETS ADMINISTRATION
WASHINGTON 25 D. C.

October 2, 1946

Mr. S. D. Kirkpatrick, Editor
Chemical Engineering,
McGraw-Hill Building,
330 West 42nd Street,
New York, N. Y.

Dear Sir,

The article commencing on Page 104 of your September issue, together with the Editor's invitation for correspondence (and contribution of data), was very interesting to me.

As the author, Mr. Henry Eckhardt, pointed out, the assembly of such data would be extremely valuable, but it does present considerable difficulty.

I would suggest that JMW & N&T ought to encourage such an undertaking and should work out with the author of the article some practicable means of publishing a book or manual.

Is it possible that the American Institute of Chemical Engineers might consider underwriting such a project, after due evaluation of its tremendous worth to the profession and the industry?

Very truly yours,

George Walker
GEORGE WALKER

JOHN H. PERRY, JR.
EDITOR-IN-CHIEF

CHEMICAL ENGINEERS' HANDBOOK

SHIPLEY ROAD
WILMINGTON, DEL.

October 4, 1946

Mr. S. D. Kirkpatrick, Editor,
Chemical Engineering,
330 West 42nd St.,
New York, N. Y.

Dear Sid:

I was mighty glad to see the Eckhardt article in your September issue and find that you are trying to do something about this important matter of cost data for process equipment. It is true as Mr. Eckhardt says that we have been able to get data of this sort into some of the sections of the "Chemical Engineers' Handbook" but it is also true that the data are limited.

It is hardly possible to exaggerate the importance of having available accurate cost information for use in estimates dealing with design, construction and operation in the process field. The assembly of truly useful cost data presents great difficulty but I do not believe the difficulties are insurmountable. The goal should be to obtain cost data that can readily be tied to current costs in the same way that general over all construction costs are related by using the well-known construction indices.

In fact, it would be well to consider the possibility of developing a quarterly or annual index (or indices) for chemical process equipment and operating costs. Equipment manufacturers should back such a study while engineers with process engineering experience should be the source of operating data and methods for handling such data.

Very truly yours,

John H. Perry
Editor,
Chemical Engineers' Handbook

Shipley Road,
Wilmington,
Delaware

GENERAL AMERICAN PROCESS EQUIPMENT

DIVISION OF GENERAL AMERICAN TRANSPORTATION CORPORATION
400 LEXINGTON AVENUE
NEW YORK 17, NEW YORK

October 3, 1946

Mr. S. D. Kirkpatrick,
Editor,
Chemical Engineering,
330 West 42nd Street,
New York 18, N. Y.

Dear Sid:

I was very much interested in Mr. Eckhardt's article in the September issue of CHEM & MET and I think it is a fine idea and that you should get behind it and make a start at least toward collecting such data. I shall be glad to be of any possible help.

You will remember that about ten years ago Harrison Howe suggested something of the sort be done and he attempted to collect the costs of various items of equipment and the cost of their operation. Some manufacturers resisted giving out any costs of the various sizes of equipment they build. I imagine many did the same but I cannot see why and I think you should be able to get something together now.

I am sure that when you first started putting out flowcharts there must have been a good deal of objection on the part of many companies to giving you the needed information, but this seems to have been all forgotten and the flowcharts are now a valuable part of our chemical engineering data. I think you will find the same thing true on the cost of pieces of equipment and their cost of operation and if you make a start you will probably find that everyone will fall in line, including the equipment manufacturers.

Sincerely,

GENERAL AMERICAN TRANSPORTATION CORP.

C. H. Knowles
C. H. Knowles, Technical Director
Process Equipment Division

CLK:WJ

Company
Equipment

THE TUBULO-JOBBER CORP.
Tanks and
Process Heaters

Tanks and
Process Heaters

LOUVELLE DRYING MACHINERY CO.
Drying Drums and Conveyors

AMERICAN MACHINE CO.
Dust Cyls.

Laboratories
BROOKLYN N. Y.
NEW BRUNSWICK, N. J.
CHEMICAL
PHARMACEUTICAL
BUILDING
AL

1946
NEW YORK

GENERAL ANILINE WORKS

ENGINEERING DEPARTMENT
Grasselli, Union County
NEW JERSEY
TELEPHONE: LINCOLN 8-8000

Factory
GRASSLETTON N. J.

October 24, 1946

Mr. S. D. Kirkpatrick,
Chemical Engineering,
330 West 42nd Street
New York 18, New York

Dear Mr. Kirkpatrick:

The statement by Mr. Henry Eckhardt in the September issue of "Chemical Engineering" that there is need for "Standard Cost Estimating Data for the Process Industries" and his suggestion that something be done to meet that need are both very much to the point. If you can interest others in such an undertaking I am sure that we shall be glad to cooperate.

Sincerely yours,

GENERAL ANILINE WORKS,
Engineering Department
D. E. Pierce
D. E. Pierce
Chief Engineer

DEP:ma

E. R. SQUIBB & SONS

MANUFACTURING CHEMISTS
TO THE MEDICAL PROFESSION SINCE 1838

General Offices
SQUIBB BUILDING, 261 FIFTH AVENUE, NEW YORK 20
AT FORTY-NINTH STREET
Please address your reply to
22 Columbia Heights, BOSTON 17, N. Y.

Branches
CHICAGO
SAN FRANCISCO
PHILADELPHIA
ATLANTA - HOUSTON
BOSTON - CLEVELAND
KANSAS CITY
LOS ANGELES
SEATTLE
PORTLAND

October 23, 1946.

Mr. S. D. Kirkpatrick, Editor,
Chemical Engineering,
330 West 42nd Street,
New York, 18, N. Y.

Dear Mr. Kirkpatrick:

I am gratified by the response to my suggestion in your September issue that a standard cost hand book for the process industries should be established by the cooperative work of all who are interested in this subject.

I note with interest that one manufacturer is willing to cooperate in compiling the proposed standard cost data source. This is progress which should be followed further, since the manufacturers are the primary source for equipment cost data. Perhaps other manufacturers will reconsider their stand on the policy of withholding general price information, in view of the good beginning made in this project.

I am eager to cooperate individually or collectively with those interested in this project, and I look forward to the immediate developments on which we can base our first efforts.

Very truly yours,

Henry Eckhardt
Henry Eckhardt,
Design Engineer,
Engineering Design Dept.

"The Priceless Ingredient of every product is the honor and integrity of its maker."

PLASTIC MATERIALS

Review of Supply Outlook

Production of plastics by last August was running about 48 percent above the 1945 rate. Current output of thermoplastic molding powders, not including vinyls, tops that of last year by about 60 percent with thermosetting types increased around 40 percent. Completion of new planned facilities will bring capacities to three and one-half times the 1945 volume.—Editors

SINCE THE original forecasts made to the Society of the Plastics Industry in April of this year and in December 1945, many things have happened in the industrial economy which have changed the original plans, delayed expansion programs, and, in a few cases, even required complete alterations in long term constructions. As this is being prepared, labor disputes are causing acute shortages in supply of certain basic raw materials and plastics. The cumulative effects on production since August are extremely serious; even though the labor difficulties are resolved in the near future, the total production lost will not be made up for some time.

In December the Association, speaking for its members, announced a long range expansion program in plastics materials manufacturing in the amount of \$107 million to be completed by the middle of 1947. In April of this year a brief review of the situation by Mr. Landes indicated considerable delay in completion of these programs, and it was estimated that increased costs, with which everyone is familiar, make this original estimate of \$107 million somewhere around \$125 million. Due to strikes in other industries, progress has been disappointingly slow in

Based on paper delivered by Mr. Carman before the New England Section meeting, Society of the Plastics Industry, at Manchester, Vt., on Oct. 18, 1946.

many cases; costs of construction have become alarmingly high. Nothing has happened since that time to permit earlier completion of these facilities; they have been delayed further. Members report an average delay of four to six months in the original plans; some facilities due early in 1946 will not come in until late in the year and many of the expansions which were to have been completed in 1947 will not be available until 1948.

Increase in costs of many constructions has already been mentioned, the extent over the original \$107 million is not available at this time. A number of PMMA members have announced additional expansion programs not previously included in industry estimates. These include certain new materials, additions to existing plants, and will provide further growth of plastics expanded during the war. Roughly these new programs involve expenditures amounting to \$21,850,000.

RAW MATERIAL SUPPLIES

Strikes in the coal, steel, and chemical industries have severely curtailed the supply of many basic materials for the plastics industry. Some of the present or pending shortages include:

Phenol—In short supply prior to existing strikes and is now exceedingly tight. Even with elimination of these difficulties, it is estimated the shortage will not be entirely eliminated for six months to a year.

Cresols and Creylic Acid—Certain pricing policies on coal-tar do not encourage production and, if continued, future supplies will be even less plentiful.

Phthalic Anhydride—Strikes earlier in the year and others now in force affect supply of this chemical in the same manner as phenol production.

Urea and Formaldehyde—There was no surplus of these chemicals before the coal strike which aggravated the situation. During 1947 it is anticipated the availability of urea and formaldehyde is likely to be a limiting factor in plastics production rather than supply of labor or

manufacturing capacity. New production units for both these chemicals should eventually improve this situation.

Glycerine—There is little prospect for supplies easing up before the end of 1947 or even later. The shortage is due primarily to the international shortage of fats and oils and the absence of a normally large supply of copra from the South Pacific.

Plasticizers—Severely curtailed by the aforementioned strikes. Other industries competing for chemicals used in manufacturing the better plasticizers further aggravate the situation. The shortage of good plasticizers actually prevents certain desirable uses of some plastics and diverts the material to less important products. Some manufacturers are prone to resort to inferior plasticizers which may affect the reputation of the industry. Plans are going forward to increase production of certain plasticizer chemicals by the end of 1947. Some industry members predict supplies will be even more critical during 1947 when increased resin production comes in.

Benzol and Alcohol—Important basic materials required by many industries. Benzol supply at the present time is not too plentiful because of lower steel mill operations. As large amounts are required for both phenol and styrene and increased amounts will be needed, it is becoming ever more important for plastics. Alcohol supply has been mentioned as possibly affecting production of certain cellulose plastics.

Cotton Linters—A large portion of the cellulose plastics production is still dependent on cotton. Even with pending price increases, the supply may still be short especially in view of plastics and rayon expansions.

Pigments and Lubricants—Shortages are presently affecting vinyl plastics production.

NITROCELLULOSE PLASTICS

Production in 1945 was 15,235,676 lb. and the 1946 production rate has been 18,400,000 lb. Census reports for the first

eight months of 1946 indicate this material is being produced at a rate 20 percent greater than in 1945. Incidentally this is the highest rate for pyroxylin plastics since 1937. Even though this was the first plastic material and newer ones have been developed and expanded enormously, the high production rate maintained for this plastic has surprised many in the industry. PMMA members report that availability of nitrocellulose is about equal to demand and it is anticipated there will be little change in this position.

CELLULOSE ESTER PLASTICS

Government reports now indicate that production of sheets, rods, tubes and film in the first eight months is running at a rate 21 percent in excess of 1945 production. Demand for these materials, particularly for continuous sheeting, continues at a high rate. Producers report demand is substantially in excess of supply, with estimates running as high as 3:1 for certain types of material. In the December survey, a short term increase in continuous sheeting was not forecast. However, production now has been increased to the extent already indicated. Consumers can anticipate even better availability of film through expansions to be completed in 1947. Compared with the 1945 rate, PMMA members anticipate an increase amounting to approximately 100 percent.

CELLULOSE ESTER MOLDING POWDER

In 1945 production was 61,123,000 lb. and based on eight months, the 1946 rate is 82,000,000 lb. or an increase of 34 percent. Demand for flake of this type still is in excess of supply with the ratio roughly estimated at 24:1. Members report the ratio of demand to supply of molding powder is approximately 3:1.

All Cellulose Molding Powders

Production data are shown as percentages of 1939, 1941, and 1945. Last December a short term increase of 6-10 percent and long range increase of 53 percent was forecast.

Base Year	Base Year as 100		Estimated Rate After Expansion
	1945 Rate	August 1946 Estimated Rate	
1939.....	484	570	745
1941.....	198	234	305
1945.....	...	118	154

POLYSTYRENE PLASTICS

Bureau of Census shows 1945 production as 23,500,000 lb. and based on seven months, 1946 rate is 53,700,000 lb. or an increase of 128 percent. Figures already presented to the Society indicate the 1945 production rate was 32 times that of 1939.

Polystyrene Molding Material

Base Year	Base Year as 100		Estimated Rate After Expansion
	1945 Rate	August 1946 Estimated Rate	
1939.....	3,260	11,130	31,200
1941.....	388	1,040	3,705
1945.....	...	268	955

The estimated rate by January 1, 1947 is 374 percent of 1945 actual production. Consumers can anticipate increased availability from month to month.

VINYL RESIN PLASTICS

Producers report capacity production on most of the vinyl plastics. Demand for vinylidene chloride, polyvinyl chloride, and copolymer resins and compounds, especially the elastomeric type, are approximately three times the available supply. During the latter part of 1945 full capacity of the industry was not utilized because of reconversion problems. With the change from war to civilian production, the end use pattern changed extensively. Based on Census' reports for seven months the increase this year over the last five months of 1945 is roughly estimated at 50 percent. Other vinyl plastics such as polyvinyl butyral and polyvinyl acetate, although running at higher production rates are believed to be in sufficient supply.

Base Year	Base Year as 100		Estimated Rate After Expansion
	1945 Rate	August 1946 Estimated Rate	
1939.....	1,280	1,438	3,000
1941.....	373	429	895
1945.....	...	115	240

Since earlier reports on expansion plans, further increases have been announced for certain vinyl resins.

AMINO MOLDING POWDERS

Producers report near capacity operations for these materials with demand almost four times the availability. Substantial increases in production over 1945 already have been made and further expansions are under way for completion in the latter part of 1947. In December 1945, a forecast of 25 percent increase by April and 80 percent by the latter part of 1946 was made. It is believed the short term expansion has been achieved and that the long term increase will be exceeded.

PHENOLIC MOLDING MATERIALS

Based on the last six months, the 1945 annual rate for production was 119,000,000 lb. while based on seven months, 1946 rate is 151,000,000 lb. and the July 1946 rate is 43 percent over the average for the last half of 1945. These figures show that forecasts made earlier in the year are being exceeded. Acute shortage of materials and labor troubles indicate

a decided drop can be anticipated over the remainder of the year.

Base Year	Base Year as 100		Estimated Rate After Expansion
	1945 Rate	August 1946 Estimated Rate	
1939.....	185	267	334
1941.....	107	154	193
1945.....	...	144	180

MISCELLANEOUS PLASTICS

Production of synthetic resin adhesives, both phenolic and urea, currently is going ahead considerably in excess of 1945. PMMA members report present operations increased from 25 percent to 90 percent over the former period and demand is about one and one-half the supply. Some expansion in manufacturing capacity has been made although definite information is not available. Because of these and additional facilities under contemplation, the industry can rest assured that manufacturing capacity will not seriously curtail production.

Members of the Association report production of acrylic, nylon, polyethylene and other miscellaneous plastics well in excess of 1945 rates. A four-fold expansion has been possible for certain molding materials and substantial capacity brought into operation for other newer materials.

Demands for laminating and industrial resins are somewhat in excess of current supplies even though producers are operating at rates substantially above 1945.

Summary of Plastics Production

Molding Powders Base year as 100			
	1945 Rate	August 1946 Estimated Rate	Estimated Rate After Expansion
Thermoplastics			
Vinyls not included			
Based on 1939.....	652	1,040	3,340
Based on 1941.....	230	360	826
Based on 1945.....	...	160	360
Based on Aug. 1946..	224
Thermosetting			
Based on 1939.....	187	262	357
Based on 1941.....	110	157	214
Based on 1945.....	...	140	192
Based on Aug. 1946..	137
All Molding Powders			
Vinyls not included			
Based on 1939.....	261	386	667
Based on 1941.....	140	208	358
Based on 1945.....	...	148	256
Based on Aug. 1946..	173

Data for thermoplastics molding powders include all materials currently produced by PMMA members with the exception of vinyls.

All Plastics Materials*

Base Year	Base Year as 100		Rate 1945
	1941 Production	1946 Rate	
1939.....	200	364	364
1941.....	182

* Based on government reports. Includes certain synthetic resins for protective coatings and coumarone indene resins.

PMMA Estimates

Base Year	Base Year as 100		Estimated Rate After Expansion
	1945 Rate	August 1946 Estimated Rate	
1939.....	335	458	656
1941.....	174	238	342
1945.....	...	140	200

FROM THE VIEWPOINT OF THE EDITORS

S. D. KIRKPATRICK, Editor • JAMES A. LEE, Managing Editor • THEODORE R. OLIVE, J. R. CALLAHAN, Associate Editors • H. M. BATTERS, Market Editor
L. B. POPE, R. W. PORTER, J. V. HIGHTOWER, E. C. FETTER, R. F. WARREN, Assistant Editors • R. S. McBRIDE, Consulting Editor

AT LAST AN A.E.C.

PRESIDENT TRUMAN's appointment on October 28 of the men to constitute the new Atomic Energy Commission came as welcome news to those who feel it is high time to transfer such activities from military to civilian control. Those selected for these heavy responsibilities are earnest patriotic citizens who may be expected to take seriously their assignments. That only Chairman Lilienthal and Professor Bacher are intimately acquainted with the problems of atomic energy is not a valid criticism of the Board. The point of view of the lay public should be the controlling interest rather than the viewpoints of the scientist or of the military. The job calls for statesmanship of high order and also a lot of hard, conscientious work.

INTER-INDUSTRY COMPETITION

MORE serious competition often comes to many companies in the process industries from outside their own line of business than is encountered from contemporary firms making identical or similar goods. This is true in other business affairs, also. The railroads worry about waterways and air competition. The coal industry is terrified at the prospect of huge natural gas movement. Inter-industry competition is the order of the day.

Within the field of chemical enterprise we have currently an outstanding set of problems of just this sort. They relate to industrial alcohol. They deserve study far outside the alcohol industry because the problems of that industry can be an object lesson for many others.

Industrial alcohol in the past has been based largely on molasses as a raw material. Now the molasses supply is wholly inadequate, with no attractive prospect for the near future. Substitution of corn or granular wheat flour, practiced during the war period, is closely regulated now, and will probably be unattractive economically for many years to come.

And the alcohol producers are finding that they no longer command the major markets formerly dominated. Methanol is successfully promoted as an anti-freeze. Isopropyl alcohol promises formidable competition. And synthetic ethanol is made not only as an incident to organic chemical business but also as a byproduct of petroleum refining and as a potential co-product of synthetic liquid fuel made from natural gas.

The "natural" industries in the chemical process field have no assurance of permanence. Let us not forget natural indigo, natural camphor, and numerous other natural products no longer important industrially. The executive or engineer who worries about competition from solely within his own industry is not worrying on a large enough scale to keep up with all the headaches of the times.

MILITARY RESEARCH vs. OBSOLESCENT WEAPONS

LAST spring General Eisenhower enunciated a new War Department policy on research and development. He wanted to make certain that this country would not make the same mistake we made after World War I of sitting back on a stockpile of obsolescent fighting equipment. "The Armed Forces," he said, "could not have won the war alone. Scientists and business men contributed techniques and weapons which enabled us to outwit and overwhelm the enemy.... This pattern of integration must be translated into a peacetime counterpart which will not merely familiarize the Army with the progress made in science and industry, but draw into our planning for national security all the civilian resources which can contribute to the defense of the country." To carry out this policy of integrating civilian and military resources, the War Department created a Research and Development Division on the highest level of its General Staff with Major General Henry S. Aurand as director.

Some idea of the magnitude of the research and development programs of the Army and Navy may be gained from the fact that the funds available this year are nearly half as great as the funds for actual procurement of weapons and equipment—comparable in total to the entire prewar outlay for industrial expenditures in this field. Furthermore, when recent economy moves were forced by the White House, the services invariably chose to take the cut from the production side rather than in their research programs. Today the limit on developmental contracting is not the availability of funds as much as it is the reluctance of industry to tie up research facilities and personnel on government work.

No one can say today exactly how much "leftover" money the Army and Navy have available to spend on research. Presumably this is one of the motivating considerations behind the appointment on October 17 of a Presidential Research Board with Reconversion Director John R. Steelman as chairman, and to which was given broad instructions "to coordinate and improve the efficiency of all federal research." In President Truman's accompanying statement it was apparent that he is beginning to have some qualms about "the share of our national income which can be devoted to research." He warns "there must be no duplication, overlapping or inefficiency to hamper federal research. In view of the current level of federal expenditures, our research activities must be conducted with minimum expenditures consistent with the essential objectives of a federal program." He expressed his concern "over the current shortage of scientific personnel," and asked the Board to make a careful inquiry into this phase of the national research program.

Undoubtedly there is need for an over-all study of the problems being created by the overlapping programs of the Armed Services. Whether or not the Presidential Research Board, as now constituted can arrive at the right answer is open to serious doubt. It is dominated by five cabinet members and the non-technical heads of four or five other governmental agencies. There are only two representatives whose work deals intimately with research. Such a Board may produce little more than some generalizations on which the White House can base its further demands for economy through curtailment of activities for which appropriations have been made. Some corrections of excesses may be necessary, but too drastic action could prove dangerously shortsighted if the Armed Forces are not to be handicapped in their efforts to join military and civilian science for safeguarding national security in this atomic age.

COOPERATION WITH REGULATORS

NOT LONG AGO the Civilian Production Administration announced that an Industry Advisory Committee had "adjourned its meeting and requested that no future meetings be called until 'Government pricing inaction on urgently needed raw materials' was ended."

Industry Advisory Committees are supposed to be, as their name implies, advisory to the government organizations which they serve. They are composed of members of industry, presumably representative of the entire cross section of their own fields. Companies not specifically represented by membership on the Committee have ready access to the committee members and certainly every right to present their minority opinions.

Whatever we may think of the action or inaction of any government agency, it seems to us that little is to be gained by deliberately breaking contact with that agency. While we do not know exactly who was involved in the incident that came to our attention, and we have no desire to know their names and connections, we feel that intensified "advice" would perhaps have accomplished more than adjournment. This advice, in the form of factual evidence, should be presented as forcefully and as persuasively as any committee report can be made. It should be documented completely and with care for its accuracy and authority. Decisions of the regulating agency may not follow in exactly the desired pattern, but industry's best advice is then on record.

ELECTION IS OVER

DURING the next twelve months is the time in which to get government action on business matters. During the rest of this year and most of 1947, Congress and the Executive Departments will be largely free from the urgency of political pressures. They will not be just approaching either primary, Congressional, or Presidential balloting. Thus they can give more fair and factual attention to the decisions which they must make and to the influences which they can properly exert.

If a process industry needs to get clearances or approvals it will be wise to get them soon. Freedom of action by politicians will end a year from now, when they begin to worry about 1948.

CHEMURGIC PLANS BROADENED

AGRICULTURAL research on a much broader basis than ever before practiced is authorized by Public Law 733 which was signed by the President during August of this year. This law provides the authority for new appropriations of large magnitude to support the development of industrial products from agricultural materials.

It is expected that nearly \$10,000,000 will be appropriated for new projects of this sort to begin in 1947. The principal objective is to anticipate the time when agricultural surpluses may again plague Washington and be ready to afford new industrial outlets that will be sound and constructive, not mere makeshifts or unsound subsidies.

Permitted fields of research include improved farm production methods which may lower costs, development of new crops, studies of human nutrition, and a great variety of other studies long recognized as fundamental for scientific agriculture. Enterprising industry can well take part by encouraging the most promising of the chemurgic studies which are not yet adequately supported or prosecuted. Sooner or later there can be established profitable enterprises based on chemical processing of farm products. The sooner this is done the better for all industries.

The next six months offers an opportunity to exert constructive influence with the Department of Agriculture, and later with Congress, for stimulation of the most promising project of this sort.

ANOTHER "PLUS" FOR THE PACIFIC

FOR more than twenty years this magazine has maintained active editorial representation on the Pacific Coast. Readers there have reason to remember the long and unselfish services of Dr. Paul D. V. Manning who succeeded Arthur W. Allen in 1926. Hal Smith, now of Bonneville, carried on for a time from Los Angeles until Jan. 1, 1945 when John R. Callahan, associate editor, was transferred to our San Francisco office. Now, as is announced elsewhere in this issue, his hand is to be strengthened by the employment of James Cosgrave as his editorial assistant. All this is in anticipation of additional services and coverage of the rapidly developing West.

Beginning next January the section of *Chemical Engineering* which since 1945 has been called "Pacific Process Industries" will concentrate on news of local events and regional developments of primary interest to western readers while trends and progress of national concern will be reported more adequately in articles and the other departments of the magazine. Thus there will be a "plus value" of editorial service in the Pacific Edition to subscribers residing in the eleven western states, at the same time the National Edition will be strengthened by increased coverage and more comprehensive reporting of developments that affect the economy and profession as a whole. If the program succeeds, as we believe it will, we may well look forward to additional opportunities in the future to serve other rapidly developing areas in which special attention to local and regional news will help to advance the common interests and objectives of all American chemical engineers.

CHEMICAL ENGINEERING PLANT NOTEBOOK

THEODORE R. OLIVE, Associate Editor

\$50 CASH PRIZE FOR A GOOD IDEA!

Until further notice the editors of *Chemical Engineering* will award \$50 cash each month to the author of the best short article received that month and accepted for publication in the "Chemical Engineering Plant Notebook." The winner each month will be announced in the issue of the next month: e.g., the November winner will be announced in December, and his article published in January. Judges will be the editors of *Chemical Engineering*. Non-winning articles submitted for this contest will be published if acceptable, in that case being paid for at applicable space rates. (Right is reserved to make no award if no article received is of award status.)

Any reader of *Chemical Engineering*,

other than a McGraw-Hill employee, may submit as many entries for this contest as he wishes. Acceptable material must be previously unpublished and should be short, preferably not over 300 words, but illustrated if possible. Neither finished drawings nor polished writing are necessary, since only appropriateness, novelty and usefulness of the ideas presented are considered.

Articles may deal with any sort of plant or production "kink" or shortcut that will be of interest to chemical engineers in the process industries. In addition, novel means of presenting useful data, as well as new cost-cutting ideas, are acceptable. Address Plant Notebook Editor, *Chemical Engineering*, 330 West 42nd St., New York 18, N. Y.

September Contest Prize Winner

DYE INSOLUBLE IN ONE COMPONENT PERMITS VISUAL STUDY OF PACKING CHANNELING

G. V. O'CONNOR

Evans Chemetics, Inc.
Watertown, N. Y.


IN EVALUATING various types of packing for distillation and extraction columns the question of possible channeling is always present and may introduce an error that cannot be measured. In a recent problem in extraction the extent of the channeling was of prime importance and it was necessary to choose the type of packing which would minimize this effect.

Since both the solvent used and the liquid to be extracted were colorless, visual inspection of the Pyrex glass laboratory column would give no inkling of the behavior of the packing in question. However, the problem was quickly and easily solved by adding a dye that was insoluble in water, but was soluble in the solvent employed. By this device it was possible not only to observe the dispersion of the solvent through the raffinate at all points in the tower, but also to study the behavior of the solvent as it emerged from the spargers. Thus types of both spargers and packing could be varied until the optimum conditions were obtained.

The same scheme could also be used, of course, with a water-soluble, solvent-insoluble dye. In addition, it is possible to make use of the opacity of the dye-containing solvent for photo-electric control. For example, a bullseye can be installed in the solvent discharge line and a light source and photo-cell arranged to actuate a valve. Here, if the raffinate level in the tower should increase until clear liquid rather

than opaque solvent ran from the discharge line, then the photo-cell would operate to close a valve and ring a warning.

Use of a dye soluble in the solvent but not in the raffinate enables channeling to be studied visually



OCTOBER WINNER!

A prize of \$50 in cash
will be issued to

A. A. LYNCH and
M. W. ROSCH

American Cyanamid Co.
Stamford, Conn.

For an article dealing with a method of avoiding heat loss from a process vessel jacket that has been judged the winner of our October contest.

This article will appear in our December issue. Watch for it!

HOW A GAS HOLDER WAS PATCHED DURING USE

R. H. SCHALLER
Aliquippa, Pa.

THE METHOD described here for welding a patch on to a gas holder while the holder is in operation has been used successfully by the writer in putting three patches on one holder.

First test the holder plate around the leak with a small hammer to determine the plate thickness, so that the proper size of patch can be judged. Then cut a patch to fit over the leak, shaping it to a slightly smaller radius than the holder so the edges will pull up tight. The patch should then be provided with a $\frac{1}{2}$ -in. pipe connection at its center which is used to bleed away the leaking gas during welding, and is afterwards plugged. This can best be made by cutting a $\frac{1}{2}$ -in. pipe coupling in half and welding it to the outer side of the patch plate concentric with a hole drilled through the center of the plate. Care should be taken to see that the threads are in good condition.

It is now necessary to provide a gas-tight gasket near the outer edge of the patch. For this purpose apply a strip of thick shellac to the back side of the patch and place a strip of lamp wick over the shellac, shellacing over the wick.

To hold the patch in place while it is being welded, stretch a small cable around the holder horizontally at leak level, providing it with a turnbuckle to supply tension. Place the patch on the holder under the cable, tighten the turnbuckle and drive two wooden wedges, one from the bottom

and one from the top, between the patch and the cable. This should give a tight joint around the outer edge of the patch, bleeding the leaking gas out through the pipe coupling. To remove the gas, screw a pipe nipple into the coupling and attach a 20-25 ft. length of hose to the nipple to lead the leaking gas to a safe distance.

The patch is now ready to weld. It should first be task welded, then welded all the way around. To complete the job, remove the cable, hose and nipple, screw in a pipe plug, saw off the part of the plug that projects beyond the coupling and finally paint the patch.

NOMOGRAPH FINDS PROPORTIONS FOR ETHANOL-WATER MIXES

WILLIAM C. FRISHE

Professor of Chemical Engineering & Metallurgy
Grove City College
Grove City, Pa.

ETHANOL-WATER solutions are ordinarily made up by pumping 95 percent ethanol from storage tank or drum into the makeup tank which contains water or a dilute solution of ethanol in water. The determination of the final volume of solution for a given final concentration requires temperature and gravity measurements and looking up densities in a handbook. By means of the nomograph given here, however, one can determine quickly the final volume of solution if he knows (1) the initial volume of weak solution; (2) the weak solution concentration; and (3) the final concentration to be made up.

In the example shown on the chart: If 95 percent ethanol is to be added to 50 gal. of water (0 percent ethanol) and the final

solution concentration is to be 75 percent ethanol, what will the final volume be?

Connect the initial concentration (C_1) at 0 with final concentration (C_2) at 75. Connect the intersection on the pivot line Z with 50 on the initial volume (V_1) scale. Read the answer, 277 gal., on the final volume (V_2) scale.

It is assumed that mixing will be complete and that the initial and final temperatures will be the same between 10 and 30 deg. C. Obviously the chart can be used also to find the final concentration if the final volume, initial volume and the initial concentration are known.

The chart is based on data for 20 deg. C. from Perry's "Chemical Engineers' Handbook," 2nd edition, p. 441 (McGraw-Hill Book Co., New York, 1941).

CHART FOR CRITICAL PRESSURE OF ANY SUBSTANCE

I. J. HOOKS and FRANK KERZE, JR.

Department of Chemical Engineering
New York University
New York 53, N. Y.

CRITICAL pressure of any substance may be estimated by the equation¹

$$P_c = \frac{20.8 T_c}{v_c - 8}$$

where P_c = critical pressure in atmospheres; T_c = critical temperature, deg. K.; and v_c = critical volume, cc. per gram mol.

For most non-associated substances the calculated values for P_c are within 10 percent of the experimental values and the deviation ranges to about 15 percent for associated substances. Use of the nomograph is illustrated for diethylamine, where

$T_c = 496.6$ deg. K. and $v_c = 297$ cc. per gram mol. The line through these points gives $P_c = 35.8$ atm., which is close to the experimental value of 36.2 atm.

If v_c is not known it may be obtained by the equation¹

$$v_c = (0.377 \bar{P} + 11.0)^{1.25}$$

where \bar{P} is Sugden's parachor, liquid mol volume at standard surface tension. This equation is solved by the double scales at the right of the nomograph, so that the parachor value may be used instead of v_c . The calculated v_c values are generally within 5 percent of the experimental values except for water and diphenyl.

The parachor may be estimated from the table appearing in the upper part of the nomograph by summation of the fundamental values listed. For illustration, we will use the same compound mentioned above. Here, from the table, if the value for $C_1 = 19.2$; for $H_{11} = 188.1$; and for $N = 12.5$, then the parachor for diethylamine = the sum, or 219.8.


The adjacent scale value $v_c = 292$ compares favorably with the experimental value given above. In the case of associated liquids the parachor should be based on the non-associated structure. Use of the table is not recommended for the simpler gases.

If T_c is not known it may be obtained readily by several methods for which nomographs² are available.


REFERENCES

1. Meissner, H. P., and Redding, E. M., *Ind. Eng. Chem.*, **34**, 521 (1942).
2. *Chem. & Met.* "Plant Notebook," June 1945, May 1946.

Nomograph solves volume-concentration relations for ethanol-water solutions



Nomograph permits estimation of critical pressure for any substance



PROCESS EQUIPMENT NEWS

THEODORE R. OLIVE, Associate Editor

ALL-METAL THERMOMETER

INDICATION of the maximum or minimum temperatures reached is possible with the new all-metal Max-Min thermometer now being offered by Weston Electrical Instrument Corp., Newark, N. J. Although it is similar in other respects to this company's standard all-metal thermometers, the new type has an auxiliary red index which is manually set by a finger knob protruding from the center of the scale glass. If a record of the lowest temperature reached is desired, this index is placed to the low side of the temperature pointer and the pointer will move the index to the lowest temperature reached. It then remains there until manually re-set. Similarly, for a record of highest temperature reached, the index is set at the high side of the pointer. This thermometer is available in two types having scale diameters of 3 and 5 in., respectively, and is built in all the usual ranges offered by this company.

HOT-PROCESS SOFTENER

DEVELOPED by the Permutit Co., 330 West 42d St., New York 18, N. Y., a new type of hot-process water softener incorporating a sludge blanket design is said to improve boiler feed water and at the same time give substantial savings in chemicals. Other advantages claimed for the four models of the new softener are reduction in turbidity of soft water, reduced load on the filters, less backwashing, and less silica left in the water.

In the tank, suspended sludge forms a bed which acts as a filter screen for fine particles. Action of this bed, coupled with the slow rate of upward flow of treated water throughout the full cross section of the settling tank, is said to give an effluent lower in turbidity than is obtainable in older types of softeners. Furthermore, when water is softened in two stages, the lower turbidity of the first-stage product reduces phosphate consumption in the second stage. The sludge blanket also decreases lime requirements since the unconsumed lime is retained in the blanket until it reacts

with water hardness. Finally, the sludge blanket (when it has considerable oxide or hydroxide of magnesium) gives a higher degree of silica removal than formerly possible owing to increased time and intimacy of contact of silica particles with the magnesium. The height of the sludge blanket is automatically controlled by a photoelectric turbidity detector which automatically blows the unit down through a desludging valve as often as may be needed.

TEMPERATURE CONTROLLER

ON-AND-OFF temperature control, with variation as low as 0.2 deg. F., and power "on-off" cycles as short as three seconds is claimed for the new Xactline temperature controller made by Claud S. Gordon Co., 3000 South Wallace St., Chicago 16, Ill. The unit, which is of the electronic type, employs no cams, motors, bearings, shafts, gears or other rotating mechanical parts and can be employed for all types of electric furnaces, ovens, or injection molding machines employing conventional millivoltmeter and potentiometer type controller pyrometers. It also is applicable to gas-fired equipment employing solenoid-controlled or motor-operated valves.

LIQUID SEPARATOR


FOLLOWING several years of experimental work, the Selas Corp. of America, Erie Ave. and D St., Philadelphia 34, Pa., has now introduced a pilot plant and small production model of its phase separator for immiscible liquids. A device of this type, shown used in connection with a steam distillation operation, appears in the accompanying illustration. The device has no moving parts, no packing glands, no space-consuming settling tank, yet is said to be

successful in breaking emulsions on steam distillation streams, on phase separation of water from carbon tetrachloride, gasoline, fuel oil, benzol and other organic liquids.


Essentially the separator consists of two parts, a coalescing chamber which houses the coalescing medium, and a separatory chamber in which the separatory membranes are contained. The feed stream first enters the coalescing chamber, shown at the right in the illustration, where its velocity is greatly reduced, allowing finely dispersed particles to coalesce into droplets and settle into the outlet leg for discharge. Coalescence is accelerated by a coalescing medium through which the liquid mixture must flow before it can reach the separatory chamber.

In the separating chamber the remaining aqueous phase is completely separated from the continuous hydrocarbon phase as the latter passes through a preferentially-wetted membrane which is impervious to the aqueous phase. To secure maximum separating area, the membranes are arranged in multiple, much like the chambers of a filter press. The water-repellant character of the membranes is said to be such that a single membrane will effect complete separation, so that all membranes operate in parallel, discharging to a single manifold and then to a discharge chamber and out of


Phase separator for liquids



Sludge-blanket hot process water softener



Electronic temperature controller



Thermometer shows maximum or minimum temperature



the apparatus. The aqueous phase settles into a second outlet leg. Other arrangements are available in case the ejected phase is the lighter liquid, rather than the heavier as described.

GRAVITY CONVEYOR SWITCH

Known as the "Y" Flipswitch, a new switching device for gravity conveyors of the ball-bearing wheel type has been announced by Speedways Conveyors, Inc., 1261 Niagara St., Buffalo 13, N. Y. The new device not only speeds up loading and unloading of materials by making double production lines easy to use and control, but it requires no power and is said to minimize upkeep and maintenance. The principle is clearly evident from the accompanying illustration which shows a curved section of conveyor hinged in such a manner in the center of the switch section that it can be flipped to form a continuous path to either branch of the Y. The device, which weighs only 35 lb., is available for 12, 15 or 18 in. wide standard conveyors made by this company.

HIGH VACUUM GAGE

Ability to cover the vacuum range from millimeters to microns, without danger of burning out the measuring instruments, is incorporated in a new vacuum measuring gage designed for continuous operation at pressures as low as 0.1 micron and introduced by the Scientific Instrument Section of RCA Victor Division, Radio Corporation of America, Camden, N. J. Designated as Type EMG, the instrument incorporates two types of gage, a thermocouple gage for the higher pressure range, and a discharge gage for the lower. The thermocouple gage is housed in an all-metal inclosure to prevent accidental mechanical damage. The discharge gage is of

a novel cold-cathode type operating on the ionization principle to give current indications proportional to very low pressures. It contains no filament to burn out. The tube is inclosed in an oval shell. A permanent magnet surrounding the unit induces a strong magnetic field along the minor diameter of the shell, establishing it as the cathode of the gage. The anode consists of a rectangular loop of wire embracing the maximum position of the magnetic field.

These sensitive elements are shown in the foreground of the accompanying view, with the thermocouple gage at the left and the discharge gage at the right.

INTERPOLATING CHARTS

Four loose-leaf sheets of durable material, $8\frac{1}{2} \times 11$ in., and punched to fit all binders, are being provided by F. R. Gerber, 1305 S. W. 12th Ave., Portland 1, Ore., to provide automatic interpolation as well as short-cut calculating machine methods of single and double interpolating; condensed seven-place tables of trigonometric functions; and a variety of tables of physical constants, equivalents, etc. The only auxiliary is a carefully calibrated "interpolating tape." Two methods of interpolating are covered, the ordinary "straight-line" method, which, however, is accomplished without any need for calculation; and interpolation in curved functions where ordinary straight-line interpolation is insufficient due to rapidly changing tabular differences. By this method a straight-line interpolation is corrected by means of an alignment chart by applying the method of point second differences. The charts are said to be particularly useful to anyone who uses or constructs numerical tables.

ELECTRONIC HEATER

EXPERIMENTAL work is facilitated by a new electronic heating generator known as Ther-Monic M 285C, now being offered by the Induction Heating Corp., 389 Lafayette St., New York 3, N. Y. The unusual feature of this generator is that it is suitable for providing heat either by the dielectric method or by the induction

method. The generator is provided with two separate, interchangeable oscillator sections to permit the two types of heating, changeover from one section to the other being a simple job which is accomplished by removing one oscillator section and replacing it with the other.

The unit operates on 205-245 volts, single-phase a.c., and has a full load input of 12 kva. At 90 percent power factor, its full load output is 285 B.t.u. per min. or approximately 5 kw. at nominal frequencies of 375,000 cycles per second for induction heating and 20,000,000 cycles per second for dielectric heating operations. When operating as a dielectric unit, the device heats non-conducting materials whereas, used as an induction unit, it heats conductors such as metals. Weight of the generator is 1,400 lb. and its dimensions are $36 \times 28 \times 62\frac{1}{2}$ in. high.

HEATING SYSTEM

FOR HEATING applications requiring the high temperatures and close control obtainable with Dowtherm, but which do not justify the installation of a Dowtherm boiler, Blaw-Knox Division of Blaw-Knox Co., Box 1198, Pittsburgh, Pa., has developed the Electro-Vapor system. In this system the process vessel is provided with an over sized jacket which serves as a Dowtherm boiler; and a number of electric bayonet heaters which serve to boil the Dowtherm. The system is said to provide uniform heat which can be closely controlled at any temperature between 100 and 700 deg. F. Explosion resistant construction is employed which is said to be safe in hazardous atmospheres.

IMPULSE SCALER

FOR THE COUNTING of beta particles and gamma rays in radioactivity work, Instrument Development Laboratories, 817 East 55th St., Chicago 15, Ill., has introduced the new Model 161 impulse scaler which operates on impulses from a Geiger-Mueller tube and actuates an external register once for each 64 impulses it receives. The instrument has a self-contained high voltage supply and requires no pre-amplifier for use with a Geiger-Mueller tube. This high voltage power supply is electronically regu-

New "Y" Flipswitch for gravity conveyors



Non-burn-out high vacuum gage



Mines Florida Phosphate

This huge Bucyrus-Erie walking dragline excavator, which is being used in the Peace Valley phosphate operations of the International Minerals & Chemical Corp. at Mulberry, Fla., is capable of excavating nearly 2,000 tons of overburden per hour. It can dig to a depth of about 130 ft. and can carry its 64,200-lb. rock load 420 ft. to the dumping spot, each cycle requiring only one minute. It is powered with 46 Westinghouse motors totalling 2,100 hp., variable voltage d.c. drive being used for its drag, hoist and swing motions. Employing a Rototrol rotating type regulator for these motions, the machine has extremely rapid acceleration and deceleration.



Combination induction and dielectric generator



lated to better than 0.01 percent, per 1 percent change in line voltage. The instrument is said to be simple to operate, either by trained or inexperienced personnel.

OXYGEN INDICATOR

NEWEST in the line of gas-detecting and measuring instruments made by Mine Safety Appliances, Co., Braddock, Thomas and Meade Sts., Pittsburgh 8, Pa., is the Type C oxygen indicator designed for indication and control in chemical and petroleum processes and in gas transmission and distribution. The device employs an electrolytic detector cell made up of a plastic container with a hollow carbon tube and metallic plate serving as electrodes in about 1 oz. of liquid electrolyte. Polarization in the cell causes hydrogen to be deposited on the carbon pole. When a gas sample containing oxygen is passed through the hollow carbon electrode, diffusion through the porous carbon causes the oxygen to combine with the hydrogen on the carbon, reducing the internal resistance of the cell and causing its current and voltage output to be increased. A direct reading meter having a linear scale indicates the percentage of oxygen in the sample.

The device is available for full-scale ranges of zero to 0.5, zero to 5, zero to 10, and zero to 25 percent. An adjustable high-point contacting device can be used for automatic operation of warning signals or control circuits.

A sample flow of 25-75 c.c. per min. propelled by an external motor-driven pump operates the instrument. Provision is made for both calibration and zero-adjusting circuits, independent of each other, while an electronic recorder or galvanometer potentiometer recorder can be added if needed.

FLUE GAS RECORDER

CHANGES in CO₂ content of flue gases can be recorded within 3½ seconds after the changed gas reaches the analyzing cell in the new Davis-Hebler recorder announced by Davis Emergency Equipment Co., 98 Halleck St., Newark 4, N. J. In order still further to increase the speed with which changes are detected, the analyzing cell is located close to the stack so that the changed percentage is indicated almost as soon as it occurs in the stack, according to the manufacturer. In addition to this extreme sensitivity, the new instrument embodies other important features. Operating on the thermal conductivity principle, the instrument eliminates continuously operating suction pumps, employing a flow rate through the gas sampling line of not more than 250 c.c. per min. Filtering trains and dryers are eliminated, with condensate and other harmful substances automatically expelled from the sampling line. Flow through the analyzing cell is produced by the pressure differential between the last pass of the boiler and the stack.

IMPROVED ABRASIVE PUMP

SEVERAL improvements in its Hydrosal centrifugal pump for the handling of abrasive materials have been introduced by Allen-Sherman-Hoff Co., 1439 Locust St., Philadelphia 2, Pa. Among these are new

heavy-duty, antifriction radial and thrust bearings which are interchangeable and are now standard with these pumps. A new means of axial adjustment for the shaft bearing assembly is provided and a new pump shell which is now supported from the bearing housing in such a way as to permit the pump discharge to be placed in any of three positions including vertical upward, horizontal at top, or horizontal at bottom. This feature usually simplifies installation of discharge piping and eliminates the need for special pump construction. The pump retains its Hydrosal principle and Maximix rubber lining.

NEW CENTRIFUGAL PUMP

TWO NEW lines of pumping equipment developed recently by Warren Steam Pump Co., Warren, Mass., include the Type DBL single-stage, double-suction centrifugal pump, and the Type CH two-stage, high-head, close-coupled centrifugal pump, known as the Compacunit. The first of these is available in capacities from 50 to 600 g.p.m. for heads of 120 to 260 ft., and discharge sizes from 1½ to 3 in. The pump is normally bronze fitted but may be supplied in special metals if desired. The design is said to minimize maintenance and to emphasize accessibility, without the use of special tools. The second type of pump, produced in capacities of from 5 to 300 g.p.m., for heads from 225 to 500 ft., is available for either motor or turbine drive, with either open or closed impellers. The unit is said to be as compact as practicable.

DRY PRODUCT WEIGHER

AN IMPROVED line of automatic and semi-automatic machines for weighing and filling dry products into containers has been announced by Triangle Package Machinery Co., 906 North Spalding Ave., Chicago 51, Ill. Known as the Triangle Model A Elec-Tri-Pak vibratory feed weighers, these devices are said to be not only more accurate but to package 25 to 50 percent faster than earlier models. The production range is from 15 to 20 packages per minute to as high as 120, depending on the machine and the product. Weighing and discharge of material are automatic except that in the case of bags, rather than rigid containers, an operator must place each bag on the filling spout. The material to be packaged is discharged by electrically vibrated feed plates into a power-rotated weighing receptacle which discharges into the container as soon as

the load reaches correct weight. Feeding speed is regulated readily. Some models will weigh as little as ¼ oz. up to 8 oz., with others ranging from 4 oz. to 5 lb. Weight adjustments can readily be made, with minor corrections during operation.

HIGH PRESSURE PUMP


APPLICATIONS such as power transmission and materials handling, requiring small fluid displacement capacities at high pressure, are the field for the Series 700 pump recently announced by the McIntyre Co., Newton, Mass. This is a direct-driven spur-gear pump said to have a volumetric efficiency in excess of 90 percent and a mechanical efficiency in excess of 80 percent. Four models are available, displacing from 0.4 to 9.6 g.p.m. at speeds ranging up to 1,750 r.p.m., against working pressures up to 1,000 psi. Power requirements range from fractional to 6½ hp. The pump body is constructed of aluminum with nitrided Nitralloy gears.

CARTON PRINTER


READY imprinting of corrugated cartons, wooden boxes or barrel tops is possible with the new Markomatic industrial printer developed by Adolph Gottscho, Inc., 1 Hudson St., New York 13, N. Y. The device is adjustable to handle several carton sizes and may mark up to 6x9 in. or 5x13. It is manually operated and can mark 300 cases or more per hour, depending on case size and the ability of the operator. Several different models are available to handle different kinds of package.

Correction: In the description of the low-speed tachometer given on p. 138 of our October 1946 issue the name of the manufacturer was inadvertently omitted. The instrument is offered by Metron Instrument Co., 432 Lincoln St., Denver 9, Colo.

High pressure gear pump



Weigher-filler for dry products



Industrial printer for cartons





1. Maximum Capacity when needed most
2. Accurate Pressure Control under toughest working conditions
3. Trouble-free Service
4. Smooth Operation
5. Tight Closure
6. Accurate Regulation
7. Speedier Production Results
8. Elimination of Failures
9. Constant Delivery Pressure
10. Cost Saving Operation
11. No Spoilage
12. Practically zero in maintenance costs

CASH STANDARD
CONTROLS..
VALVES

A. W. CASH COMPANY
DECATUR, ILLINOIS

The trouble makers you see above are literally being blasted out of a plant immediately upon the installation of a CASH STANDARD Streamlined "type 1000" Pressure Reducing Valve. And they are out permanently.


When they go out the 12 points listed come in.

It happens every time because these cost raisers who relentlessly interfere with production can't do their stuff when the "1000" valve is put on the job.


WRITE FOR BULLETIN "962"—read about the construction, the operation, and the effectiveness of the "1000" in plants like yours in bettering operation and decidedly cutting costs.

**BULLETINS
AVAILABLE
ON OTHER
CASH STANDARD
VALVES**


Send for them



Bulletin 950—features the CASH STANDARD Type D Single Seat Pressure Reducing and Regulating Valves for use with most fluids. Shows simple inner working parts that save in maintenance. Diagram explains how valve works. Blueprint shows simplicity of installation.



Bulletin 956—features the CASH STANDARD Type 4030 Back Pressure Valve—designed to automatically maintain a constant pressure in the evaporator corresponding to a constant temperature desired. Shows an Ammonia and Freon Gas Capacity Chart based on ABSOLUTE pressures.



Bulletin 966—features the CASH STANDARD Self-Contained, Pilot Operated Type 10 Pressure Reducing and Regulating Valve for use with water or air; with any gas or oil that is non-corrosive; and with refrigerating fluids such as Ammonia and Freon. Many interesting particulars explained such as: how valve works, tight seating, large capacity, no waste, no water hammer or chatter.

CONTINUOUS SEPARATION OF FATTY ACIDS

A PROCESS for the continuous separation of distilled fatty acids into solids and liquid components has been developed by Emery Industries, Inc., of Cincinnati, Ohio, and has been designated as the Emersol Process. Three commercial plants are now being operated by the Ohio organization, the most recent of which was designed and constructed by the Blaw Knox Co. of Pittsburgh.

The process may be used to separate the solid and liquid fatty acids from almost any fat or oil. By paying particular attention to the type of feed stock and its preliminary treatment, the plant can operate continuously and produce the products of a desired grade. Typical of the fatty acids which are processed through this equipment are tallow, grease, stearine, and garbage grease. The resulting stearic and oleic acids from any of these fatty acids have similar iodine values and titers but the percentages of stearic and oleic acids resulting, of course depend upon the percentages of the fats in the feed.

The Emersol Process consists essentially of controlled crystallization of solid fatty acids from polar solvent medium, permitting a sharp separation in a single stage. The solvent is separated from the stearic and oleic acids by distillation and is returned for reuse.

In commercial operation, the distilled fatty acid mixture is dissolved in methyl alcohol of proper concentration, along with small amounts of a crystal promoter. This solution is chilled in a multi tubular agitated crystallizer, resulting in a slurry containing stearic acid crystals and in suspension. This mixture is separated on a continuous rotary filter with cold alcohol to remove adhering liquid acids. The filter cake, consisting of about 50 percent stearic acid and 50 percent solvent, is melted and transferred to a still where the alcohol is removed and returned to the start of the process. The stearic acid is discharged as a final product ready for finishing and packaging.

The filtered oleic acid solution is pumped through an economizer and then to a still where the solvent is recovered. Oleic acid is discharged into commercial grades suitable for industrial application. If it is desired to produce an extra quality product, the acid may be further treated by distillation, washing and bleaching.

CHEMICAL ENGINEERING

November, 1946

PAGES 168 TO 171



Continuous separation of distilled fatty acids into solid and liquid components is carried out in Cincinnati plants of Emery Industries, Inc., one of which is shown above.


Typical Results From a Standard 30 Tons Per Day Plant


Fatty acid throughput per mo., 1,983,200 lb.

Yield per mo., stearic acid 41.7%, oleic 58.3%


Solvent separation costs per 1,000 lb. exclusive of repairs, depreciation, taxes, insurance, laboratory and general factory expenses were:

Labor	0.76 hr.	Electricity	22.6 k.w.h.
Methanol	7.5 lb.	Water	40 cu.ft.
		Steam	3,500 lb.






Process consists essentially of controlled crystallization of solid fatty acids from polar solvent medium, permitting a sharp separation in a single stage. It is controlled from a central instrument panel by single operator




1 Fatty acid-solvent mixture chilled in a multi-tubular crystallizer which is driven through an ingenious chain arrangement by a single motor




2 Crystallized st... which is installed... percent stearic ac...






mixture chilled in a multi-
which is driven through an
ngement by a single motor




2 Crystallized stearic acid is separated and washed on enclosed vacuum filter
which is installed in an insulated cold room. Filter cake consists of about 50
percent stearic acid and 50 percent solvent



3 Refrigeration
stage ammonia
heat throughou






Refrigeration for operating crystallizer and cold room is obtained with a two-stage ammonia machine driven by a steam turbine. Exhaust is used for process throughout the Emersol plant



4 Solvent is continuously removed from separated stearic and oleic acids in three stills and returned to process for reuse



This is Why the Nash is the Most Simple Compressor



It's the Nash!

There are no mechanical complications in a Nash Compressor. A single moving element, a round rotor, with shrouded blades, forming a series of buckets, revolves freely in an elliptical casing containing any low viscosity liquid. This liquid, carried with the rotor, follows the elliptical contour of the casing.

The moving liquid therefore recedes from the rotor buckets at the wide part of the ellipse, permitting the buckets to fill with gas from the stationary Inlet Ports. As the casing narrows, the liquid is forced back into the rotor buckets, compressing the gas, and delivering it through the fixed Outlet Ports.

Nash Compressors produce 75 lbs. pressure in a single stage, with capacities to 6 million cu. ft. per day in a single structure. Since compression is secured by an entirely different principle, gas pumping problems difficult with ordinary pumps are often handled easily in a Nash.

Nash simplicity means low maintenance cost, with original pump performance constant over long periods. Data on these pumps sent immediately on request.

- No internal wearing parts.
- No valves, pistons, or vanes.
- No internal lubrication.
- Low maintenance cost.
- Saves floor space.
- Desired delivery temperature automatically maintained.
- Slugs of liquid entering pump will do no harm.
- 75 pounds in a single stage.

NASH ENGINEERING COMPANY
325 WILSON, SO. NORWALK, CONN.

One

What a process easy way

By loc you get practices Every pi to erecti

With year lea Crane eq

ONE mos pipe in pro

ONE help avo

OUT suri thro

CRANE Branches

EVER

VALVE PIPE HEATIN

CHEMICA

One Source for Everything in Process Piping Equipment

What a soap plant can do can be done in any process industry to step up piping efficiency the easy way.

By looking to Crane for all piping materials, you get the maximum benefits of standardization practices. Specifying and buying are simplified. Every piping procedure is easier—from design to erection to maintenance work.

With top quality assured by Crane Co.'s 90-year leadership in the field, standardizing on Crane equipment gives you this 3-way advantage:


ONE SOURCE OF SUPPLY offering the world's most complete selection of valves, fittings, pipe, accessories, and fabricated piping—in brass, iron, and steel—for all power, process, and general service applications.

ONE RESPONSIBILITY for piping materials—helping you get the best installation, and avoiding needless delays on jobs.

OUTSTANDING QUALITY in every item—assuring uniform durability and dependability throughout piping systems.

CRANE CO., 836 S. Michigan Ave., Chicago 5, Ill.
Branches and Wholesalers Serving All Industrial Areas

ONE
SOURCE OF SUPPLY
RESPONSIBILITY
STANDARD OF QUALITY



(Right) **BETTER FIT FOR MORE SERVICES**—Crane Iron Body Clamp Gate Valves with improved "U"-bolt bonnet joint. Saves time where valves require frequent cleaning. Easy to open... easy to assemble... always makes up tight. Self-draining bonnet, on inside screw types, insures smooth operation. Sizes to 4-in. Choice of patterns including Quick-Opening. See Crane Catalog, pp. 98-99.

EVERYTHING FROM ...

VALVES • FITTINGS
PIPE • PLUMBING
HEATING • PUMPS

CRANE

FOR EVERY PIPING SYSTEM



Girdler's complete service expedites the answer to your Gas Processing problem

If you need a gas processing plant, your worries are over when you give the job to GIRDLER.

From principle to practice—from laboratory work until the plant is in operation and you know all about how to use it—this qualified, responsible organization handles every step of the job. There are no missing links. The entire job is done right, in the right time, at a fair price.

For example . . . the Girbotol Process for removal and recovery of the acidic gases . . . GIRDLER originated it in principle. And, following through with outstanding engineering achievements in the field, GIRDLER has built more actual plants of this type than any other organization.

GIRDLER's complete follow-through applies to all industrial gas processes.

GIRDLER-planned and GIRDLER-built gas processing plants serve most of the big names in industry.

This includes processes for gas manufacture, purification, separation, and dehydration—processes involving hydrogen sulphide, carbon monoxide, carbon dioxide, inert and controlled atmospheres, natural gas, refinery gases, liquid hydrocarbons, hydrogen, and nitrogen.

**GET GIRDLER ON THE JOB
AND GET IT DONE RIGHT**



The GIRDLER CORPORATION

GAS PROCESSES DIVISION, Louisville 1, Kentucky
District Offices: 150 Broadway, New York 7, N. Y.
2612 Russ Bldg., San Francisco 4, Calif.
311 Tuloma Bldg., Tulsa 3, Okla.

NEW PRODUCTS AND MATERIALS

R. W. PORTER, Assistant Editor

ADHESIVES

Two new adhesives have recently been announced by the E. I. du Pont de Nemours & Co., Wilmington 98, Del. The first of these is an industrial adhesive requiring no catalyst or special preparation and is designated as No. 4665 cement. It is a liquid adhesive which is claimed to be tough and flexible, suitable for bonding metal foils and metal sheets to wood, plastics, vulcanized synthetic and natural rubbers as well as other substances that have widely different coefficients of thermal expansion. It can be applied without thinning, by brushing, roller coating, knife coating, or dipping. It contains 27.5 percent solids. Although insoluble in water, its bond strength is lowered by continued immersion. However, it is claimed that the original bond strength is regained after removal from water. The dried adhesive film is claimed to be resistant to dilute alkalis, acids and corrosive salt solutions. It is also not attacked by petroleum or coal-tar solvents, lubricating oils, alcohols, ethylene glycol, or vegetable oils but it is soluble in ketones or ester solvents. It is also said to be resistant to mildew and fungi. It is suggested that this new material will find application for use with metals, woods, plastics, fabrics, ceramics, vulcanized rubber, paper, natural and artificial leather, plaster and walls or wallboards, concrete and glass.

The second of these two products is a synthetic waterproof adhesive claimed to be more resistant to oxidation than similar natural rubber compounds. This new adhesive cement is recommended for bonding buna-N synthetic rubbers and vinyl films or sheet stocks to rigid surfaces such as steel, aluminum, glass, wood or concrete. It has been given the brand name of No. 5118 Fairprene adhesive cement and has a thermoplastic synthetic elastic composition which does not require vulcanization to obtain maximum adhesive strength. Oils or gasoline will weaken the bond slightly although aromatic hydrocarbons will destroy the bond. It is unaffected by temperatures as low as 40 deg. F. but is weakened at temperatures of 150 deg. F. and higher. It is claimed, however, that full bond strength returns after cooling to normal temperatures. No. 5118 is cold setting and dries to a tacky surface under average conditions in 3 to 10 minutes, and dries completely within two hours.

INSULATING ROOF COATING

SAID to have unusual insulating, waterproofing and fire resistive qualities, a new roof coating called Richlume, is now manufactured by the Richkraft Co., Chicago, Ill. This coating was developed for use

on bituminous roofing materials only. A new plastic vehicle for the aluminum pigment is claimed to produce a close bond with roofing materials without penetrating below the roof surface. It may be applied with brush or spray to tar and gravel tar paper, built up asphalt or composition shingle roofing. It is claimed that the vehicle remains flexible and allows the coating to expand and contract with the roofing under weather conditions, thus preventing cracking, bleeding or checking of the surface. Insulating qualities result from its reflective surfaces which are claimed to reflect up to 80 percent of the sun's rays.

SOLVENT CLEANING AGENT

AN EMULSIFIABLE solvent cleaner designated as Emulsion Cleaner EC-75 has been developed by Enthone, Inc., 442 Elm St., New Haven, Conn. This product is recommended for the removal of oil, buffing compounds and other organic dirt as well as solid dirt from all types of metals including active metals such as zinc, aluminum, brass and nickel silver. One feature of this product is that it will not affect alkali cleaners. It is used undiluted. The material is a penetrating solvent to replace naphtha, kerosene and chlorinated solvents and in addition is claimed to have high detergency and emulsifiability. It is not affected by oil contamination and requires no heating.

JAPANESE PHARMACEUTICAL

ACCORDING to Japanese clinical records, a new drug called Koha appears to be remarkably effective in speeding the healing of severe burns, lesions, ulcers, frostbite, tubercular leprosy, and other diseases. This material is a derivative of neocyanine and was produced by Japanese pharmacologists in an effort to find an agent resembling chlorophyll which would convert sunlight into energy for therapeutic effect. Unable to obtain active chlorophyll, the researchers experimented successfully with neocyanine, a light sensitive agent. The drug is not effective when used as a local dressing, but must be administered intravenously. It is claimed that the drug increases the number of white corpuscles in the blood stream, stimulates regeneration of tissue and increases the survival rate of damaged tissue cells. This new material is more completely described in a report entitled "Pharmacology and Malariology in Japan"; PB-31614; photostat, \$8; microfilm, \$3; 120 pages. It is available from the Office of Technical Services, Department of Commerce, Washington 25, D. C.

CONTENTS

Adhesives	175
Insulating Roof Coating	175
Solvent Cleaning Agent	175
Japanese Pharmaceutical	175
Plastic Stabilizer	175
Aluminum Oxide Abrasive	175
Synthetic Textile Fiber	176
Concrete Floor Paint	176
Stabilized Wood	176
Plasticizer	176
Synthetic Detergent	176
Copper Marine Paint	176
Elastic Fabric	176
Latex	176
Masking Plastic	176
Molding Powder Dyes	176
Photographic Paper	178
Paraffin Hydrocarbon	178
Insecticide Material	178
Liquid Defroster	178
Glass Fiber Diaphragms	178

PLASTIC STABILIZING AGENT

DEVELOPED by the Advance Solvents & Chemical Corp., New York 16, N. Y., a new stabilizing agent, to prevent discoloration and chemical breakdown of vinyl chloride and vinyl chloride acetate copolymers when processed at high temperatures and exposed to sunlight, is now available. Under the brand name of Stabilizer V-1M, this material is said to be compatible and soluble in vinyl resin solutions and can be used in lacquers and coatings based on these materials. Working of vinyl resins at high temperatures without decomposition of the resin may be accomplished by use of this stabilizer to produce clear, transparent films.

ALUMINUM OXIDE ABRASIVE

BY USE of a newly developed process, the Norton Co., Worcester 6, Mass., is now producing a new type of aluminum oxide abrasive. Known as 32 Alundum abrasive, this material is claimed to have a number of advantages over other types of abrasives. It is claimed to cut deeper and faster, cut freer without burning, require fewer dressings, give longer wheel life and reduce grinding time. It is made by a patented process which creates single crystals of high purity in a fluid matrix in an electric furnace. Crystals are separately

formed and have strong solid shapes and many sharply pointed nubs. To retain these many sharp cutting edges the crystals are not crushed but are separated from the matrix by a complicated and continuous chemical process. They are then screened without crushing into the standard grain sizes.

BRITISH SYNTHETIC TEXTILE FIBER

STILL in the preliminary stage of development, a new synthetic textile fiber is now under investigation by the Imperial Chemical Industries, Ltd., 42 Hertford St., London, England. This new fiber produced from a polyester derived essentially from terephthalic acid and methylene glycol has been given the name of Terylene.

The most notable property of Terylene so far observed is its markedly high resistance to light and to heat. Another property is its high initial elastic modulus which should permit it to be readily woven or knitted. Terylene is resistant to microorganisms and bacteria and it is chemically resistant to acids, organic solvents and bleaching agents. It has low moisture absorption and does not swell in water and has good resilience with a high ratio of wet to dry strength. Terylene fabrics can be ironed, laundered and steam-pressed normally. The fiber, however, presents problems in dyeing, and research on this subject is being carried out. Fine filaments can be made as well as heavy coarse filaments giving a wide potential range of texture and types of fabrics.

CONCRETE FLOOR PAINT

MADE from Gilsonite by the Tiz-Nu Corp., 673 Coronado St., Los Angeles, Calif., a concrete floor paint under the trade name of Rubbermastic, is available in color. This floor paint dries tack free in four hours to an enamel-like finish. It is claimed that use of this product will eliminate the necessity of etching or priming and will do away with saponification troubles. It is also claimed to be completely waterproof and will resist acids, alkalis, heat, electrolysis, weather and abrasion. Rubbermastic paint is available in commercial quantities.

DIMENSIONAL STABILIZED WOOD

A CHEMICAL treatment for wood to give it greater dimensional stability was recently announced by the Forest Products Laboratory of the U. S. Department of Agriculture at Madison, Wis. The wood is treated with vapors of a solution of pyridine and acetic anhydride. This swells the wood, reduces by 70 percent its tendency to swell further or shrink, toughens it, improves its resistance to decay and may even improve its strength properties. So far, however, this treated wood has not been evaluated as to the effects of this acetylation process (so-called) on gluing and paintability.

PLASTICIZER FROM PETROLEUM

A PETROLEUM derived plasticizer known as SV Sovaloid C available from Socony Vacuum Oil Co., Paulsboro, N. J., is claimed to possess a number of properties which make it worthwhile for use in plastics, and as a film for fabrics. When used as a film for fabrics, it is applied by roller or knife coating methods in almost any desired thickness on simple coating equipment. It is a less efficient plasticizer than other types used with vinyl resins but its lower cost overcomes this feature. It may be used as a partial or complete replacement for other plasticizers. In both these applications tensile strengths equal to those obtained from other plasticizers are obtained when using larger quantities of SV Sovaloid C. In high concentrations it gives no evidence of exudation of the plasticizer from the finished product. It has a characteristic odor slightly similar to kerosene.

SYNTHETIC DETERGENT

DEVELOPMENT of a synthetic detergent for treating textiles has been announced by the Dexter Chemical Corp., New York, N. Y. Available in two forms under the brand names of Clavodene Concentrate, a 100 percent liquid synthetic detergent, and Clavodene No. 100, an aqueous solution of the concentrate. These products are high molecular weight amine condensation compounds and are recommended for use as detergents in neutral, mild acid, or alkaline solutions. This detergent may be used in the scouring or dyeing of wools or cottons. It is claimed to have good dye-leveling properties and is recommended in both the boiling-off and the dyeing of all types of hosiery. It may be used for wetting out in the rayon processes, as well as cotton. It may also be used in the kier boiling of cotton, and is said to improve the removal of foreign material to enable bleaching with a minimum amount of bleaching agent. Clavodene may be used for rewetting, since it retains its wetting power after drying on the goods.

COPPER MARINE PAINT

A MARINE paint, claimed to be particularly effective against marine life because it contains metallic copper in combination with other ingredients, has several times the service life of ordinary ship hull paint. Developed by research chemists of the Battelle Memorial Institute, this new paint, which can be used over metal and wood, has been subjected to extensive service tests. It is manufactured under license by Amercoat Division, American Pipe & Construction Co., New York, N. Y.

ELASTIC FABRIC

DEVELOPED in the textile laboratories of the United States Rubber Co., Rockefeller Center, N. Y., a new elastic fabric under the brand name of Strex is now available in experimental quantities. The fabric does not contain rubber, and elasticity is achieved by twisting cotton yarn into the

shape of a coil spring. The fabric can be made in various degrees of elongation up to a maximum of 100 percent. It has a lower degree of tension than Lastex and similar materials deriving their elasticity from rubber, but is claimed to withstand repeated laundering or dry cleaning. It has been used for such articles as slip covers, gloves, sweaters and surgical bandages.

LATEX

ANNOUNCEMENT of a new aqueous film-forming material by the Dow Chemical Co., Midland, Mich., should be of interest to the paint, paper and textile industries. Called Dow Latex 512, it will provide an immediate source of supply to those industries that are facing current short supplies of edible vegetable oils such as linseed. Dow Latex 512 is a combination of styrene and butadiene which when air dried is claimed to form a rubbery and tough film with good pigment binding properties and high protective value. Its compatibility with many aqueous emulsions or dispersions of resins, oils, varnishes, starches, waxes, casein, plasticizers and water soluble gums and pigments is another of its important characteristics. The new product is in production and immediately available in 55-gal. non-returnable steel drums and tank cars.

MASKING PLASTIC

MANUFACTURED by the DuBois Co., Cincinnati 3, Ohio, a new masking plastic for paint spray booths is now available. Under the brand name of Filmite, this fluid compound when brushed or sprayed over the walls of dried paint spray booths, forms a tough surface skin over a non-hardening base. This skin resists the impact of paint particles and prevents penetration of the coating and adherence to the wall. Overspray adheres to and accumulates on the skin which, when cleaning is desired, may be peeled from the soft undercoat readily. This compound is supplied in liquid form ready to use. It is water soluble. Filmite is claimed to be non-flammable, non-irritating, non-corrosive and non-toxic.

MOLDING POWDER DYES

EITHER clear or opaque molding powders are readily colored with a new line of dye materials recently announced by the Krieger Color & Chemical Co., 6531 Santa Monica Boulevard, Hollywood 38, Calif. Designated by the manufacturer as "Poly supra concentrate molding powder dyes," this new material gives clear and transparent color effects and can be used with such materials as cellulose acetate, polystyrene, methylmethacrylate and vinyl molding powders. Light shades are produced by adding as little as $\frac{1}{4}$ oz. of this dye material to 26 lb. of molding powder. Medium shades are obtained by adding one ounce to 26 lb. of powder. Application of the dye is easy and simple requiring only that the dye be sprinkled into the molding powder and well mixed prior to being used

Partial list of monsanto intermediates

This product list of Monsanto intermediates is published as a convenient reference—you may find it helpful in your long-range development plans.


Unfortunately, not all of these intermediates are presently available. Some are still in critical supply. Experimental samples on many of them are available, together with prices.

For technical data and other information, contact the nearest Monsanto District Office, or write: MONSANTO CHEMICAL COMPANY, Organic Chemicals Division, 1700 South Second St., St. Louis 4, Missouri. District Offices: New York, Chicago, Boston, Detroit, Cincinnati, Charlotte, Birmingham, Los Angeles, San Francisco, Seattle, Montreal, Toronto.

MONSANTO
CHEMICALS
SERVING INDUSTRY...WHICH SERVES MANKIND

ortho-Aminobicyclohexyl, Refined	ortho-Nitrobiphenyl, Technical
ortho-Aminobiphenyl, Technical	meta-Nitrochlorobenzene
ortho-Anisidine	ortho-Nitrochlorobenzene
para-Anisidine	para-Nitrochlorobenzene
Benzenesulfonic Acid, Technical	para-Nitrophenol
Benzoic Acid, Technical	ortho-Phenetidine
Benzotrichloride	para-Phenetidine
Benzyl Chloride	Phenol, U.S.P.
meta-Chloroaniline	Phenolsulfonic Acid, 65% and 70%
ortho-Chloroaniline	Phosphorus Oxychloride
para-Chloroaniline	Phosphorus Trichloride
ortho-Chlorophenol	Phthaloyl Chloride
para-Chlorophenol	Salicylic Acid, Technical
Cyclohexylamine	Sodium Benzoate, Technical
2,5-Dichloroaniline	Thiourea
2,5-Dichloronitrobenzene	para-Toluenesulfonamide
2,4-Dichlorophenol	Toluenesulfonic Acid, 94%
Dicyclohexylamine	para-Toluenesulfonyl Chloride
2,4-Dinitroaniline	ortho-Vanillin (2-Hydroxy-3-methoxybenzaldehyde, Technical)
2,4-Dinitrochlorobenzene	ortho-Veratraldehyde (2,3-Dimethoxybenzaldehyde, Technical)
ortho-Nitroaniline	

FIRE PAINTS BLACK PICTURES



Listed by
Underwriters
Laboratories, Inc.

WATER BATH PROTECTION SAVES CHEMICAL PLANT

In the picture... fire in one unit of a large butadiene plant was stopped from spreading to other units by a water spray protective system. In just such applications, Blaw-Knox Aquatomic Fog Nozzles are ideal. Simple, reliable, non-clogging, they deliver a cooling, quenching spray under outdoor conditions.

Write for details.



Also—

Blaw-Knox offers Standard Wet and Dry Pipe Systems, as well as Thermostatically Controlled Pre-Action and Deluge Systems.

**Aquatonic
FOG NOZZLES**
by
BLAW-KNOX
SPRINKLER DIVISION

831 Beaver Avenue, N. E.,
Pittsburgh 12, Penna.

in the regular manner. These dyes are available in red, royal blue, blue green, orange, amber, purple, black and yellow. All colors are intermixable which makes it possible to obtain various desired shades of color.

PHOTOGRAPHIC PAPER

HAVING wide latitude and unusual warm-tone characteristics, a new Indiatone portrait projection paper has been announced by the Ansco division of General Aniline & Film Corp., Binghamton, N. Y. This new paper is an enlarging paper intended primarily for portrait use, but it can also be used for contact printing. It is claimed that prints on the new Indiatones do not fog, stain or mottle even with wide variations in developing time. Recommended developing time for optimum print quality is $1\frac{1}{2}$ minutes at 68 deg. F. but good quality prints can be obtained with from $\frac{1}{2}$ to $1\frac{1}{2}$ times the normal exposure by varying the development time between 45 sec. and 4 min. It is available in popular sizes and is packed in $\frac{1}{2}$ gross and 500 unit lots.

PARAFFIN HYDROCARBON

AVAILABILITY in drum or tank car quantities of isoctane of high purity has been announced by the chemical products department of Phillips Petroleum Co., Bartlesville, Okla. Also known as 2,2,4 trimethylpentane, this material is claimed to have a purity of over 99.9 mol percent. It is claimed to be especially useful as a special solvent and as a chemical intermediate.

INSECTICIDE MATERIAL

Now being manufactured on a semi-plant scale, hexaethyl tetraphosphate is available in limited quantities. Having the formula $C_{18}H_{36}O_{10}P_4$, this material is claimed to be useful as an insecticide. It is claimed to be particularly valuable in the control of aphids and spider-mites, in dilutions ranging from 1 to 1,000, or from 1 to 4,000. Hexaethyl tetraphosphate is manufactured by Eaton Chemicals, Inc., 3,100 East 26th St., Los Angeles, Calif.

LIQUID DEFROSTER

A liquid windshield defroster called Merix Frost-Off has been announced by Merrick Chemical Co., Wrigley Bldg., Chicago 11, Ill. This liquid is said to soften grease, ice or frozen rain. According to the manufacturer, it is harmless to auto finishes as it does not contain corrosive chemicals. It is applied with a cloth.

GLASS FIBER DIAPHRAGMS

ASKANIA REGULATOR CO., 1603 South Michigan Ave., Chicago 16, Ill., has developed a substitute for goat's skin for flexible diaphragms that is said to be superior to that material. Previous to the war imported skins of first quality were the only ones suitable. Diaphragms made of glass fiber, which is non-porous, does not sag or stretch, and is resistant to alkalis and acids, were this company's answer to the skin shortage.

Economize WITH POWERS TEMPERATURE REGULATORS

Use a Powers No. 11 Temperature Indicating Regulator when you want the advantages of an easy-to-read dial thermometer combined with a dependable self-operating regulator. The dial thermometer gives a visual check on the performance of the regulator and makes it easy to adjust for the required operating temperature. Various dials and ranges are available.

Is Easy To Install—because both the thermometer and the regulator operate from the same thermal system—only one tapped opening is required.

Write for Circular 2511
THE POWERS REGULATOR CO.
27 Greenview Avenue, Chicago 14, Illinois
231 E. 46th St., New York 17, N. Y.—@Mican
In 47 Cities... See your phone directory. TO

OVER 50 YEARS
OF AUTOMATIC TEMPERATURE AND HUMIDITY CONTROL

CHEMICAL ENGINEERING NEWS

SYMPOSIUM ON COMMERCIAL CHEMICAL DEVELOPMENT

UNDER the joint sponsorship of The Chemical Market Research Association and The Technical Service Association, a symposium on "Organized Commercial Chemical Development" will be held at the Hotel Roosevelt, New York, on December 12. The morning session will open with introductory remarks by Dr. J. M. Boyd, Phillips Petroleum Co. and symposium chairman. Papers will include "The Need for Organized Commercial Chemical Development" by Dr. C. F. Prutton, head of the department of chemistry and chemical engineering at Case School of Applied Science, Cleveland, and "Chemical Market Research" by M. E. Clark, director of market research, Wyandotte Chemicals Corp., Wyandotte, Mich.

S. D. Kirkpatrick, editor of *Chemical Engineering*, will introduce the luncheon speaker, Jan Oostermeyer, president, Shell Chemical Corp., San Francisco, who will speak on "Why Sales Departments Want Organized Commercial Chemical Development."

Dr. John H. Long, manager of sales research, Hercules Powder Co., Wilmington, will open the afternoon session with a paper on "Market and Product Development." He will be followed by W. H. Harding, director of technical service, American Cyanamid Co., Stamford, who will speak on "Application Research and Technical Service" and Dr. Lawrence W. Bass, director of research and development, U. S. Industrial Chemicals, whose topic will be "The Qualifications and Training of Personnel for Organized Commercial Chemical Development."

A social hour will follow the afternoon meeting and the dinner speaker will be Francis J. Curtis, vice president, Monsanto Chemical Co., St. Louis, who will tell "Why Management Wants Organized Commercial Chemical Development." He will be introduced by Walter J. Murphy, editor, *Industrial & Engineering Chemistry*.

KOPPERS PURCHASES KOBUTA STYRENE FACILITIES

NEGOTIATIONS have been completed with the Office of Rubber Reserve whereby the Koppers Co., Inc., will begin private operation of the styrene facilities at the synthetic rubber plant at Kobuta, Pa., built for the government during the war, it was announced last month by Dan M. Rugg, Koppers' vice president and general manager of its Chemical Division.

The styrene plant has been purchased by Koppers from the War Assets Administration. The company also has obtained for a period of 7½ years the use of certain office, laboratory, and shops facilities, steam generating plant, river pumping sta-

tion, tanks and other equipment which the government was unwilling to sell at the time. The consideration for the deal was about \$3,300,000.

Koppers plans to expand its chemical operations at Kobuta and to substantially increase its production of synthetic organic chemicals Mr. Rugg stated. Of the 350 acres included in the complete Kobuta plant, Koppers has purchased 129 acres and obtained the use of 83 additional acres. A condition of the private operation by Koppers of the styrene plant is that a substantial amount of the future production will be reserved for the Office of Rubber Reserve for synthetic rubber. In the first six months, 70 percent of the production will be available to the government and after that 50 percent. Thereby the Office of Rubber Reserve is assured styrene to whatever extent is needed for its synthetic rubber requirements.

BAKELITE TO MAKE VINYLITE PLASTICS IN ILLINOIS

CONSTRUCTION work is now under way on a new plastics plant for the Bakelite Corp. on property recently acquired at Ottawa, Ill. The site of 120 acres was acquired from the Reconstruction Finance Corp. which during the war started to


build there a plant to make truck tires. Bakelite plans call for a manufacturing building to include six bays for the production of Vinylite plastic film and sheeting and one complete pressing unit for the production of plastic rigid sheets.

The primary vinyl resins will be produced by Carbide & Carbon Chemicals Corp., another unit of Union Carbide & Carbon Corp., and shipped to the Ottawa plant for further processing. Key personnel for the new project have been chosen from Bakelite's organization at Bound Brook, N. J., and include A. B. Dickinson, superintendent; J. A. Bruton, assistant superintendent; J. E. C. Valentin, works engineer; W. O. Ackerman, in charge of manufacturing office; and J. H. Haynes, head of works laboratory.

SHELL CHEMICAL TO EXPAND CAPACITY AT HOUSTON

A \$2,500,000 expansion program which is expected to increase Shell Chemical Corp.'s capacity to produce methyl ethyl ketone and secondary butyl alcohol by 150 percent is now well under way, J. Oostermeyer, president of the company, announced last month. The expansion program is to be directed chiefly toward the installation of facilities for the production

New fluid catalytic cracking unit which went on-stream Wednesday, October 9, at the Whiting, Indiana refinery of the Standard Oil Co. (Indiana). With a daily capacity for making 1,050,000 gal. of gasoline, fuel oil and other petroleum products, this is the first of four cat-crackers planned by Standard of Indiana as part of a previously announced \$150,000,000 construction and expansion program. Engineering and construction is being done by The M. W. Kellogg Co., petroleum engineers, of Jersey City and New York under the general supervision of the technical staff of Standard Oil Co.





this is
REX-FLEX

... the *Stainless Steel*
Flexible Metal Tubing

- 18-8 stainless steel!
- Corrugated . . . pressure tight!
- All-metal construction!
- Resists corrosion!
- Strong and lightweight!
- Braided for extra strength!
- Working pressures for over 900 p.s.i.—depending on size!
- Corrects misalignment!
- Serviceable at high and low temperatures!
- Withstands hard usage!
- Long mill lengths!

REX-FLEX is versatile . . . able to handle everything from delicate weigh tank connection jobs . . . to heavy duty work in a variety of industrial applications. REX-FLEX Type RF-51 is available in sizes from $\frac{3}{16}$ " to $1\frac{1}{4}$ " I.D. (REX-FLEX Type RF-41 is available to 6" I.D., incl.) Write today for full information.

Flexible Metal Hose for Every Industrial Use

CHICAGO METAL HOSE CORPORATION
MAYWOOD, ILLINOIS

Plants: Maywood and Elgin, Ill.



of these chemicals at the corporation's Houston, Tex., plant. Contractor for expansion of the Houston facilities is to be C. F. Braun and Co., Los Angeles. Maximum production is scheduled to be attained by third quarter, 1947.

CONSULTING CHEMISTS HOLD ANNUAL DINNER MEETING

THE annual dinner meeting of the Association of Consulting Chemists and Chemical Engineers, Inc., was held at the Hotel Sheraton, New York, on the evening of October 22. Following the dinner a symposium was held on the subject of "Licensing of Chemical Engineers and Chemists" with Albert Parsons Sachs, John M. Weiss and Louis Weisberg as speakers. Numerous speakers participated in the discussion from the floor. At the meeting, the newly elected officers and directors were announced. Officers for the coming year

CONVENTION CALENDAR

American Institute of Chemical Engineers, annual meeting, Atlantic City, December 1-4.

Seventeenth National Exposition of Power and Mechanical Engineering, Grand Central Palace, New York, N. Y., December 2-7.

American Pharmaceutical Mfrs. Association, midyear meeting, Waldorf-Astoria Hotel, New York, N. Y., December 9-11.

Chemical Market Research Association and Technical Service Association, joint symposium, Hotel Roosevelt, New York, N. Y., December 12.

American Association of Textile Chemists and Colorists, annual meeting, Statler Hotel, Boston, Mass., December 12-15.

Synthetic Organic Chemical Mfrs. Association, midyear meeting, Hotel Roosevelt, New York, N. Y., December 17.

Society of Plastics Engineers, convention, Congress Hotel, and plastics exposition, Navy Pier, Chicago, Ill., January 28-February 2.

Seventh International Heating and Ventilating Exposition, Lakeside Hall, Cleveland, Ohio, January 27-31, 1947.


American Society For Testing Materials, spring meeting, Benjamin Franklin Hotel, Philadelphia, Pa., February 24-28.

American Society of Metals, western metal congress and exposition, Civic Auditorium, Oakland, Calif., March 22-27.

National Association of Corrosion Engineers, annual meeting, Palmer House, Chicago, Ill., April 7-10.


American Chemical Society, 111th national meeting, Atlantic City, N. J., April 14-18.

Second National Plastics Exposition, Coliseum, Chicago, Ill., May 5-11.




ALCOHOL

Steel car, 6,000 to 10,000 gallon capacity.




CAUSTIC SODA

Heavily insulated steel car, with or without heater coils, 8,000 or 10,000 gallon capacity. Usually specially lined.



CHLORINE


Insulated, welded car; built to withstand pressure up to 500 pounds; 15 or 30 ton capacity.



COTTONSEED OIL

Clean, steam coiled car of 8,000 gallon capacity.

FOR RENT TANK CARS



Tank car transportation of liquids in bulk, pioneered by General American has proved its versatility, its efficiency, its economy.

The General American fleet comprises more than 37,000 specialized tank cars . . . 207 different types of tank cars . . . designed for the safe and swift hauling of an almost infinite variety of liquids.

General American's strategically located offices, plants, and repair shops keep these tank cars at your service; provide you with precisely the type of tank cars you want, where you want them.


If your problem is the transportation of liquids in bulk, let the nearest General American office help you.

GENERAL AMERICAN TRANSPORTATION CORPORATION

GENERAL OFFICE: 135 South La Salle Street • Chicago 90, Illinois

DISTRICT OFFICES:

New York • St. Louis • Buffalo • Seattle • Los Angeles • Dallas • Houston
Tulsa • New Orleans • Cleveland • Pittsburgh



LARD

Steam coiled car, usually of 8,000 gallon capacity.



WINE

Insulated car with one to six compartments. Interior coated to preserve quality.



MOLASSES

Steam coiled car with heavy capacity trucks; 8,000 gallon capacity.




SULPHURIC ACID

Heavily constructed steel car with heavy truck capacity. Equipped to unload through dome.




FUEL OIL

Steel car, steam coiled, 8,000 to 12,500 gallon capacity.



PROPANE

Heavily constructed car, welded and insulated. Built to withstand internal pressures to 300 pounds. Capacity 10,000 to 11,000 gallons.



CORN SYRUP UNMIXED

Clean, steam coiled with heavy truck capacity. Usually lined with aluminum paint.



LUBRICATING OIL

Steel car, with steam coils, single or multiple compartment; usually 8,000 gallon capacity.



MURIATIC ACID

Car lined with pure or synthetic rubber; 8,000 to 10,000 gallon capacity.



ACETIC ACID

Aluminum Car; 8,000 or 10,000 gallon capacity.



GASOLINE

Clean car, 6,000 to 12,500 gallons; single or multiple compartment.



ASPHALT OR TAR

Heavily steam coiled car; with 2 or more inches of insulation; steam jacketed outlet; 8,000 to 10,000 gallon capacity.


Typical



HIGH PRESSURE NORWALK COMPRESSORS 300 to 15,000 psi.

Example No. 2

Steam-driven,
3-stage compressor,
suitable where
steam power is
available.



Insure Highest Steam Economy, too

In the Norwalk Compressor Book shown below, an application of one of these 3-stage compressors is shown working on Carbon-Dioxide compression for liquifaction service.

Modern piston-valve steam cylinders are directly connected in tandem to the compressor. Notice how the piston-rods may be disconnected and the gas pistons removed without interference with the steam power unit.

Norwalk — established in 1865 — continues to pioneer in high-pressure compressors. We design compressor equipment to meet the specific requirements of your industry. Or, we will advise you when one of our compressors, already developed, will meet your conditions.

Many different types, for all forms of power-drive, in single and multiple stages (up to 5 stages) are illustrated and described in the Norwalk Book, shown opposite. Write for your copy.



NORWALK COMPANY, INC.

10 NORTH WATER ST., SOUTH NORWALK, CONN.
SALES OFFICES IN PRINCIPAL CITIES

PIONEERS OF THE INDUSTRY FOR 81 YEARS

are Nicholas M. Molnar, Molnar Laboratories, New York, president; Prof. A. Taub, College of Pharmacy, New York, vice president; M. F. Lauro, Bureau of Chemistry, New York Produce Exchange, secretary; and P. F. Wehmer, Electrical Testing Laboratories, New York, treasurer. New directors are C. A. Blair, The Blair Laboratory, New York; Gustavus J. Esselen, Gustavus J. Esselen, Inc., Boston; and Earl D. Stewart, Schwartz Laboratories, New York. Albert Parsons Sachs, past president and consulting engineer of New York is a hold-over director.

GAS ASSOCIATION MEETS WITH LARGE "SHOW"

AMERICAN GAS ASSOCIATION held its first full-scale convention at Atlantic City from October 7 to 11 with the support of a large appliance exposition held under the auspices of Gas Appliance Manufacturers Association. Both the convention and the exposition had near record support in attendance and interest.

AGA will be led during the coming year by newly selected officers: president, R. H. Hargrove, United Gas Pipe Line Co., Shreveport, La., and vice presidents, Hudson W. Reed, The Philadelphia Gas Works Co., and Robert W. Hendee, Colorado Interstate Gas Co., Colorado Springs, Colo. The technical section officers for the coming year are: chairman, C. S. Goldsmith, The Brooklyn Union Gas Co., and vice chairman, A. C. Cherry, Cincinnati Gas & Electric Co.

The next convention of AGA will be held in San Francisco during October of 1947. Meantime various sections and regional groups will hold their customary "Conferences." Most important of these special meetings will be the Production and Chemical Conference, tentatively scheduled to be held in New York during May.

POWER SHOW WILL FEATURE ENGINEERING ADVANCES


TECHNICAL advances, widely influencing the entire outlook for the production and use of industrial power, will be featured at the 17th National Exposition of Power and Mechanical Engineering. Returning once more to its traditional site in Grand Central Palace, New York, December 2-7, the exposition will be held coincident with the annual meeting of the American Society of Mechanical Engineers.

Progress in methods, practice and equipment design, as revealed by the exhibits promise a considerably greater advance all along the line than has often been noted at these biennial displays because of the dual influence of innovations in war production and also the partial suspense of commercial animation during the past decade. Many products at the Power Show will be entirely new, others revised to incorporate an improved selection of materials; new methods of manufacture have also encouraged design changes from the motive of economy in a good many instances.

The exposition, as in past years, is primarily a forum for the manufacturers and users of power plant equipment—fuel

BAKER PERKINS DISPERSION MIXERS

INSURE HOMOGENEOUS
MIXTURE OF ALL INGREDIENTS




To give your paints and enamels the uniform quality that paves the way to customer preference, you must thoroughly disperse pigments throughout every batch. You can easily and quickly accomplish such consistent mixing day after day with Baker Perkins Dispersion Mixers.

These husky mixers utilize scientifically designed blades to disperse all elements with speed and thoroughness that cannot be duplicated by ball mills, grinding mills, or roll mills. Illustrated in discharge position is just one type in the complete Baker Perkins line—the Size 15 Type VUMM Dispersion Mixer, with 2 speed, 100 HP motor. For homogeneous dispersion of pigments, it will pay you to use a B-P Dispersion Mixer . . . preferred by many paint and enamel manufacturers whose products have a reputation for unvarying quality. For the best answer to all your mixing problems, consult the Baker Perkins Sales Engineer in your area or write direct to Baker Perkins Inc., Chemical Machinery Division, Saginaw, Mich.

Baker Perkins Inc.

SAGINAW • MICHIGAN



Whether it be these gigantic magnetic separators for difficult ore concentration problems or a diminutive 3" magnetic clutch for machinery control, Stearns Magnetic engineers are prepared to serve you with many years of practical and profitable application experiences.

If you need protection for your product, machinery or employees against the hazards of tramp iron—concentration of ores and minerals or reclamation of metals, for improved values—purification—moving material fast and economically with magnets—controlling machinery with clutches and brakes—Stearns Magnetic equipment will speed production, lower costs.

Consult us for reliable magnetic engineering service.



handling, combustion, the distribution, economizing and utilization of heat, auxiliaries, measuring and recording instruments, controls and even applications of power in a number of classes of machinery, especially that intended for the construction, upkeep and overhauling of power plants.

With approximately 400 exhibits, filling all available space on four floors of the Palace, the exposition will be one of the largest and most diversified ever held. Much of novelty and technical interest is being held back by exhibitors for disclosure after the opening date. A review of information on the displays made available by exhibitors in advance, however, indicates a well rounded program of new information.

NEW SULPHURIC ACID PLANT BUILT AT CHARLESTON

A new sulphuric acid plant has been under construction at Charleston, S. C., according to an announcement by officials of the H. K. Ferguson Co. The plant was erected for A. F. Pringle & Co., Inc. and is to replace a box chamber acid plant destroyed by fire early last February. The new plant consists of six Mills-Packard chambers.

GERMAN PLANTS APPROVED FOR INDUSTRIAL REPARATIONS

REPORTS from the Allied Control Council at Berlin indicate that some progress is being made in forwarding the Potsdam program for industrial reparations from Germany. Up to September 15 about 500 German plants in the three western occupation zones had been officially listed as available for reparations. However, neither regulations nor official policy have been developed to govern eventual transfer of German reparations, acquired by the United States, to private concerns except a decision giving jurisdiction over this prospective job to the office of Foreign Liquidation in the State Department.

Originally the United States was awarded 28 percent of the plants and facilities taken from Germany as reparations but it voluntarily pared down its share to 11.8 percent in order that more of these plants and facilities might be made available to the smaller European nations. So far only one American claim has been officially filed. This is for the Hensoldt & Sons optical instruments factory at Herborn, in Hesse-Nassau. The plant has 240 undamaged machine tools which a pool of 11 American optical and engineering firms would like to have for domestic use. An American claim probably will be filed for that part of the Aschau armaments plant at Muelldorf, Bavaria, which makes briquettes. An American firm wants to acquire this plant for operation in Salonika, Greece, where the company is under contract to install a hydroelectric project.

For a time, plants were allocated and removal from the western zones actually started, on the theory that such removals, before a final settlement was reached, could not exceed the amount any nation would be allotted in the peace terms and also on the theory that the plants should be put into operation outside Germany as soon as



IF YOUR research laboratory does not have equipment for X-ray diffraction analysis it is not complete. The unvarying patterns in the atomic structure of many materials can be determined most rapidly by X-rays.

Now is the time to consider the reasons why the Norelco X-ray Spectrometer and Norelco X-ray Diffraction Equipment are of prime importance to your laboratory.

Norelco X-ray Spectrometric and Diffraction Apparatus can serve you in material analysis, product control, competitive comparison and research. These modern units of analysis are essential to the maintenance of a sound competitive position or even leadership in industry.

Eliminate the "blind spot" in your laboratory by installing Norelco X-ray equipment. Full details are yours for the asking.

Norelco
Reg. U. S. Pat. Off.




ELECTRONIC PRODUCTS

NORTH AMERICAN PHILIPS COMPANY, INC.

The range of applications for X-ray Diffraction cover many industrial processes. It provides patterns of substances which can be used for analytical procedures. For comparison, it provides an accurate method of differentiation, inasmuch as no two substances produce identical patterns. For control, patterns derived from materials having demonstrated acceptable characteristics may be employed as standards.

DEPT. J-11, 100 EAST 42ND STREET
NEW YORK 17, N. Y.



*Reilly
Ethyl
Phenols*

● Made commercially available within the past year, Reilly Ethyl Phenols have proved interesting and helpful products in many different industries, including plastics, insecticides, disinfectants, pharmaceuticals, rubber chemicals, plasticizers, photographic compounds, dyestuffs, wetting agents; also in various organic syntheses.

Reilly Ethyl Phenols are available in a 95% pure grade, and prompt delivery can be made.

Other refined Reilly phenols include: phenol, ortho cresol, meta cresol, para cresol, 1, 2, 4-xyleneol, 1, 3, 4-xyleneol, 1, 3, 5-xyleneol and 1, 4, 2-xyleneol.

This 56-page booklet and supplement, describing the complete line of Reilly coal tar chemicals, acids, oils, bases and intermediates, will be sent on request.



REILLY TAR & CHEMICAL CORPORATION

Merchants Bank Bldg., Indianapolis 4, Indiana

500 Fifth Avenue, New York 18, N. Y. • 2513 S. Damen Avenue, Chicago 8, Ill.

Reilly Coal Tar Chemicals For Industry

possible. Owing to political developments this procedure was halted and a freeze order now is effective in the western zones.

German Plants for Reparations

Approved up to September 15, 1946

Plant	Location
Optical Instruments	
Hensoldt & Soehne	Herborn
Explosives and Propellants	
Fabrik How Lichtenau	Furstenhagen
Fabrik Kaufbeuren	Kaufbeuren
Fabrik Aschaff	Muhldorf
Fabrik Ebenhausen	Ingoelstadt
Warren Commission AG	Denenberg/Elbe
Dynamit AG	Dunenberg
Clausthal I	Krummel
Fabrik Allendorf	Clausthal, Selterfeld
Fabrik Bobingen	Allendorf, Greater Hesse
Fabrik Kaufering	Bobingen, Bavaria
Pulverfabrik Hasloch	Kaufering, Bavaria
Werk Kraiburg	Hasloch, Bavaria
Wolf & Co. Factory A	Kraiburg, Bavaria
Wolf & Co. Factory B	Bornitz
Wolf & Co. Factory C	Duernden
	Lebenau
Soda Plant	
Mathes & Weher	Duisburg
Activated Carbon	
Chemische Werke	Harzwasser, Langeisheim
Vinyl Chloride	
I. G. Farbenindustrie AG	Rheinfelden
Acetone	
Degussa	Mainz, Mombach
Solvents and Pharmaceuticals	
Anorgana GmbH (except ethylene-glycol unit)	Gendorf, Bavaria
Oxygen and Industrial Gases	
Kamellwerke	Kamell-Bettenhausen
Soarstoffwerke	Griesheim
Organic Chemicals and Dyes	
C. F. Hahnberg GmbH	Lesse, Hannover
Lonalwerk GmbH	Lesse, Hannover
I. G. Farbenindustrie	Ludwigshafen
Griesheim Werke	Griesheim, Greater Hesse
Offenbach Werke	Offenbach
Pentaerythritol	
Werke Schrobenhausen	Schrobenhausen, Bavaria
Werke Lippoldsborg	Lippoldsborg, Bavaria
Werke Weiden	Weiden, Bavaria
Synthetic Rubber	
Chemische Werke Huels part only	Muenster
I. G. Leverkusen (part only)	Leverkusen/Koeln
Pyrotechnics	
Hans Meag	Wuppertal, Rosendorf
Burmester Trittau	Hamburg
Fabrik Frita Sauer	Gershofen, Bavaria
Carl Fleming	Neugraben/Hannover
Carl Fleming	Neugraben/Hannover
Synthetic Gasoline	
Chemische Werke Essener	Bergkamen
Steinkohle AG	Dortmund
Dortmunder Paraffin Werke	Gelsenkirchen
Gelsenberg Bensen AG	Gelsenkirchen
Gewerkschaft Victor Castrop	
Rauzel Hydrierwerk	
Scholver AG	Gelsenkirchen-Buer
Krupp Treibstoffwerk	Wanne-Eickel
Hulrichs AG	Oberhausen-Holten
Hulrichs GmbH	Bottrop-Bay
Steinkohlenbergwerk	
Rheinpreussen Chemische Werke	Meerbeck-Moers
Union Rheinische Braunkohlen Kraftstoff AG	Wesseling

GENERAL MILLS TO EXPAND IN CHEMICAL FIELD

THAT General Mills is contemplating a larger participation in the manufacture of chemicals is indicated by an announcement that the Chemical Division of the company is planning the construction of a plant at Kankakee, Ill., which will be used for the production of organic chemicals. The Division now operates a polyamide resin plant in Minneapolis. The Chemical Division also is in charge of the

PUMPING STATION IN THE WELL

BJ

The only basic improvement in deepwell turbine design...since Byron Jackson introduced the first deepwell turbine pump in 1901.

SUBMERSIBLE PUMP

THE SUBMERSIBLE is a close-coupled deepwell turbine pump and electric motor—a complete pumping station. This motor-pump unit is suspended in the well by the discharge pipe...and operates *entirely submerged in water at any well-depth*. Thus the shaft alignment and bearing protection problems of shaft-type installations are entirely eliminated.

1000 FOOT SETTINGS are quite practical for the Submersible. This unique motor-pump unit operates equally well 50 feet down or 2000 feet down...because there are no shaft alignment or bearing protection problems. Many Submersibles are operating at depths from 900 to 1000 feet with amazing efficiency and unvarying dependability. *Motor sizes: 10 to 350 h. p. Capacities: 50 to 20,000 gpm.*

Byron Jackson Co.

LOS ANGELES 54, CALIFORNIA

Offices in Principal Cities

SUBMERSIBLE ADVANTAGES

Shaft-type Installations Cannot Equal These

NO ADJUSTMENTS AFTER
INSTALLATION

YEARS OF AUTOMATIC,
TROUBLE-FREE OPERATION

NO WELL TOO DEEP
ADAPTABLE TO CROOKED
WELLS

MAXIMUM EFFICIENCY

NO PUMP HOUSE REQUIRED

NO WATER
CONTAMINATION
SILENT OPERATION

UNAFECTED BY FLOODS
OR ATMOSPHERIC
CONDITIONS

SAFE AGAINST VANDALISM



1000 FEET
OR MORE
BELOW THE
SURFACE

Looking for Bigger Markets?



*35 of America's 100 largest cities
are within 500 miles of the center
of Southern New England.*

Within this same 500 mile radius live 58,317,815 people with the highest potential buying power in the world. One indication of the sales opportunities which exist here is the fact that the U. S. portion of this fertile market paid 50% of all income taxes received by our Federal Government.

Easy access to millions of people with money to spend is one of many factors

in your favor when you locate your industry in Southern New England.

For a complete, factual resume of all advantages, write for the new 32-page booklet, "SOUTHERN NEW ENGLAND FOR TOMORROW'S INDUSTRY." Address: P. E. Benjamin, Mgr., Industrial Development, New Haven R. R., Room 201G, 80 Federal Street, Boston 10, Mass.

THE **NEW HAVEN** R. R.

SERVING NEW YORK AND THE GREAT INDUSTRIAL STATES OF
MASSACHUSETTS, RHODE ISLAND AND CONNECTICUT

soybean oil refining unit which went into operation last September at Belmond, Iowa. At this refinery, lecithin is removed from crude soybean oil by a degumming process. Three other oil refining units are about ready to be placed in operation.

FIRST NATIONAL MATERIALS HANDLING EXPOSITION

THE first exposition to deal entirely with material handling problems of industry will be held at the Public Auditorium, Cleveland, January 14-17. The problems of the chemical field will receive special attention in a separate program of prepared papers and panel discussions. Chemical executives will have an opportunity to see and compare under one roof competing systems and machinery for materials handling. Production line handling as well as handling for receiving, stacking, shipping, loading, and warehousing will be considered by the panels.

Earl J. Burke, manager of shipping, Republic Steel Co., heads the policy committee of the exposition which is under the management of Clapp & Poliak, Inc. of New York.


DUPONT ANNOUNCES PLANS FOR PLANT EXPANSIONS

PLANS for construction of a new unit on its electrochemicals plant site at Niagara Falls have been announced by E. I. du Pont de Nemours & Co. The new unit will be used for the manufacture of adiponitrile which will be shipped to other plants for further processing. It will consist of four main buildings including a general office, and laboratory building, a power plant, water-pumping station, electric substations, and miscellaneous structures. R. L. Hardy, manager of the Niagara Falls plant says the project is estimated to cost about \$1,000,000 and construction would require about 15 months.

The company also reports that the Civilian Production Administration has approved approximately \$600,000 of new construction which will be used to enlarge its facilities for producing synthetic detergents at Deepwater, N. J.

GENERAL ANILINE & FILM RECORD OF RESEARCH

MORE than 300 inventions and improvements in the chemical, dyestuffs, plastics, and photographic fields have resulted from the work of the Central Research Laboratory of General Aniline & Film Corp. since its establishment at Easton, Pa., in 1942. George W. Burpee, president, disclosed last month in announcing the appointment of Dr. Arthur L. Fox as director of the laboratory. Mr. Burpee said that company research had made it possible to duplicate virtually every dyestuff formerly imported from Germany. He classed as outstanding among the company's research accomplishments, the development of a new line of chemicals from acetylene. The company is now constructing at Grasselli, N. J., a semi-works and pilot plant where chemicals from acetylene will be made by



Greater Production from Every Machine

NO MATTER what you make, where you are located, or the size of your plant, Texaco Lubricants and specialized Lubrication Engineering Service will help you get greater production—with fewer rejects and lower unit costs. For instance—

Machining operations of every type are vastly improved through the use of *Texaco Cutting and Soluble Oils*. They increase tool life—often double or triple it—improve both quantity and quality of output.

Hydraulic mechanisms operate more dependably with *Texaco Regal Oils (R & O)*

... hydraulic oils that *prevent rust and sludge* ... used and recommended by leading hydraulic equipment manufacturers.

High-speed ball and roller bearings last longer, cost less to maintain, lubricated with *Texaco Regal Starfak*. It exceeds every test requirement for an ideal anti-friction bearing lubricant.

Enjoy Texaco benefits in your plant. Call the nearest of the more than 2300 Texaco distributing plants in the 48 States, or write The Texas Company, 135 East 42nd Street, New York 17, N. Y.



TEXACO Lubricants, Fuels and Lubrication Engineering Service

Tune in ... TEXACO STAR THEATRE presents the NEW EDDIE BRACKEN SHOW every Sunday night. See newspapers for time and station.

CHEMICAL ENGINEERING • NOVEMBER 1946 •

**INDUSTRIAL PLANTS
CHEMICAL PLANTS
FOOD PLANTS
..Your PLANT!**

**THERE IS NO OTHER
Filter
LIKE THIS**



Illustrated are the radically different Klein Ideal Filter Leafs with discharge tubes that practically eliminate the danger of clogging.

**The Stainless Steel
KLEIN
IDEAL DIATOMACEOUS
EARTH FILTERS AND
SLURRY FEEDERS**

Many important and exclusive improvements and radical innovations have been incorporated in the precision-built Klein Ideal Diatomaceous Earth Filters and Feeders. Constructed of stainless-steel they utilize a new exclusive filter principle that will bring you a new high in maximum efficiency, minimum maintenance and product uniformity.


WRITE TODAY for full information and the latest Klein Bulletin.

Established 1909

KLEIN

FILTER & MANUFACTURING COMPANY
1225-29 School Street • Chicago 13, Ill.

***A Complete Laboratory*
FOR THE RESEARCH CHEMIST...**



Here is a complete laboratory for the research chemist... five steel units, plus an acid-resistant stone fume hood equipped with fluorescent lighting, built into one compact twelve-foot assembly.

This is only one example of how Hamilton standard steel units provide greater efficiency and better working conditions in your laboratory at lower cost.

Let our experienced engineers show you how Hamilton standard units solve all your equipment problems. Write Department 295-C&M for details.

HAMILTON MANUFACTURING COMPANY • TWO RIVERS WISCONSIN

techniques developed by the company. Dyestuffs and various textile auxiliaries also will be produced there.

**R. LINDLEY MURRAY TALKS ON
ALKALI AND CHLORINE**

MEMBERS of the Philadelphia-Wilmington Section of the American Institute of Chemical Engineers heard a talk by R. Lindley Murray, of Niagara Falls, N. Y., vice-president in charge of research and development of the Hooker Electrochemical Co., at their meeting on October 10 in the Hotel DuPont, Wilmington, Del.

Mr. Murray spoke on "The Growth of the Electrolytic Alkali and Chlorine Industry." Raymond P. Genereaux, chairman of the section, announced the appointment of the following nominating committee which will present its report at the next meeting to be held in Philadelphia December 10: David Shaw, H. S. Lukens, R. M. Lawrence and James Lawrence.

**ENGINEERING FOUNDATION
ELECTS OFFICERS**

HOLDING its annual meeting on October 17 in the Engineering Societies Bldg., New York, the board of directors of The Engineering Foundation re-elected Dr. A. B. Kinzel as chairman for the coming year. Dr. Kinzel is vice president of Union Carbide & Carbon Research Laboratories, Inc., and of the Electro Metallurgical Co. Other officers elected were Dr. L. W. Chubb, director of the Westinghouse Research Laboratories, vice chairman; Dr. Edwin H. Colpitts, formerly vice president of Bell Telephone Laboratories, re-elected director; and John H. R. Arms, re-elected secretary. Dr. Kinzel will represent the Foundation on the executive board of the National Research Council.

**PACKAGING FORUM WILL BE
HELD IN CHICAGO**

INDIVIDUAL packaging conferences by industry groups rather than general discussions of suppliers, manufacturers, and machinery makers, will feature the eighth annual two-day Forum of the Packaging Institute which will be held at the Hotel Stevens, Chicago, on November 25-26. Walton Lynch is president of the Institute and Mason Rogers, Dewey and Almy Chemical Co., is chairman of the program committee.

**WOOD DISTILLATION WILL
BE DISCUSSED IN BOSTON**

THE Northeastern Wood Utilization Council will discuss wood distillation during its next invitation meeting to be held in the Parker House, Boston, Mass., on December 12.

The last 25 years have marked the steady decline of the hardwood distillation industry due to inroads caused by synthetic methanol and acetic acid. Yet charcoal cannot be duplicated by any synthetic process and is a vital product by itself or as activated charcoal. Work will be reported on both an improved design of a charcoal kiln to make that

EXTREME LIGHT WEIGHT

(ONLY 13½ LBS.)

→
**WITH COMPLETE RESPIRATORY
PROTECTION**



MAKES ITS OWN OXYGEN

M·S·A

CHEMOX
SELF-GENERATING

OXYGEN BREATHING APPARATUS

**Major
Industrial
Applications**

- Steel Mills
- Chemical Plants
- Public Utilities
- Refineries
- Tunnelling
- Sewage Works
- Fire Departments
- Steamships, etc., etc.



**A SINGLE
REPLACEABLE CANISTER
GIVES 1 FULL HOUR'S
RESPIRATORY PROTECTION
IN UNBREATHABLE AIR**

*—under hard
physical work!*

*Note these extraordinary
CHEMOX features*

- Fog-free lenses ...
- Generates its own oxygen in a replaceable chemical canister—in the amount you need, as you need it, by merely breathing into it ...
- No cylinders, high pressure valves or fittings ...
- Minimum maintenance required...
- Comfortable harness ...
- Simple to use ...
- Proved by years of Navy battle service!

SEE CHEMOX
Write for a Demonstration!


MINE SAFETY APPLIANCES COMPANY

BRADDOCK, THOMAS AND MEADE STREETS • PITTSBURGH 8, PA.

District Representatives in Principal Cities

In Canada: MINE SAFETY APPLIANCES COMPANY OF CANADA, LIMITED


TORONTO . . . MONTREAL . . . CALGARY . . . WINNIPEG . . . VANCOUVER . . . NEW GLASGOW, N. S.



HELICOID CARTRIDGE SNUBBER

...THE SIMPLEST OF ALL PRESSURE GAGE SNUBBERS

... for use where pulsations of gage pointer make accurate reading difficult or impossible. Damping action assured by porous cartridge of compressed, powdered bronze, threaded into gage socket or into snubber body. No adjustments ever needed. Specific porosity of cartridge makes it effective for required service - air, gas, water, steam or oil. Available for all pressures up to 10,000 pounds. May be supplied with Helicoid Gages or bought separately for use with other gages.



HELICOID —

A DIFFERENT KIND OF PRESSURE GAGE

The unique design of the Helicoid movement - with cam and helical roller instead of gears - obsoletes conventional type pressure gages. A Helicoid Gage will maintain its guaranteed accuracy longer - a fact proved in thousands of installations. For complete information, write for our Catalog DH-818.

ACCO



**HELICOID GAGE DIVISION
AMERICAN CHAIN & CABLE**

Bridgeport 2, Connecticut

product alone and the latest techniques of wood distillation. The continuous processes giving rise to 60 percent higher yields of charcoal, acetic acid, and wood alcohol, will be reported and evaluated.

AMERICAN ENKA TO BUILD RAYON TIRE YARN PLANT

THE American Enka Corp., manufacturers of rayon yarns, has awarded contracts for engineering and construction of a new rayon tire yarn plant, to be located at Lowland, Tenn., to The H. K. Ferguson Co. The plant will consist of a complete new production unit, and the contract covering its design and construction is one of the largest industrial building contracts awarded in recent months.

Approval for the project has been granted by the Civilian Production Administration and construction at the plant site is expected to start immediately. Design work is now in progress in the Cleveland offices of The Ferguson company.

LILIENTHAL HEADS ATOMIC ENERGY COMMISSION

TO THE Atomic Energy Commission, appointed by President Truman in the latter part of October, goes the responsibility of converting the atom industry from its status of a weapon of war to that of peacetime application. The Commission succeeds Manhattan District as operator of the vast atomic plants at Oak Ridge, Hanford, and Los Alamos, as well as the research institutions such as Argonne Laboratory at Chicago. It will expand Manhattan District's vast peacetime programs. It has a monopoly of production of U-235 and plutonium and will license all industrial and academic work in the field. It assumes jurisdiction over dissemination of all information relating to basic knowledge and discoveries in nuclear physics. These powers are conferred under the terms of the Atomic Energy Act of 1946.

David E. Lilienthal, head of Tennessee Valley Authority, is chairman of the Commission. Named to serve with him are Robert F. Bacher, professor of physics and director of the Laboratory of Nuclear Studies, Cornell University; William W. Waymack, vice president and editor, *Des Moines Register and Tribune*; Lewis L. Strauss, partner, Kuhn, Loeb & Co.; and Sumner T. Pike, former member of the Securities and Exchange Commission.

HOOVER ENDOWMENT FUND TO UNIVERSITY OF ROCHESTER

An announcement from Alan Valentine, president of the University of Rochester says that a \$50,000 endowment fund for the Department of Chemistry has been established by Harry M. Hoover. The fund will be paid to the university in increments of \$5,000 a year for 10 years and is to be used for general purposes of the department of chemistry under the direction of Dr. W. Albert Noyes, Jr., chairman of the department and director of the research laboratory. Dr. Noyes is president-elect of the American Chemical Society.


Mr. Hoover was graduated from the

New!

A Handbook on Welding Aluminum

Are you welding aluminum now? Do you plan to weld aluminum in the future?

If so, this book is for you!



HERE'S a new up-to-the-minute book, "Welding Aluminum," that presents a concise, authoritative discussion of problems dealing with welding aluminum and aluminum alloys. Many new war-developed applications are described. Under a single cover, in handy usable form, you will find detailed information on 11 aluminum welding processes, from edge preparation to finishing, a comprehensive discussion of aluminum alloys and tempers, and helpful tables on properties, gauges, sizes, and strengths.

"Welding Aluminum" is clearly illustrated with 44 interesting photographs and graphs of welding operations. If you work with aluminum, you'll find "Welding Aluminum", prepared by the technical staff of the Reynolds Metals Company, an invaluable reference book.

How do you get your copy? Simply fill out the coupon on this page and mail with your check or money order for one dollar, to cover the cost of printing and mailing, to Reynolds Metals Company, 2500 South Third Street, Louisville 1, Kentucky.

83 PAGES packed with accurate up-to-the-minute facts, figures, and photographs—about

GAS WELDING

Edge Preparation
Cleaning and Preheating
Welding Flame
Welding Rods
Welding Fluxes
Heat-Treatable Alloys
Aluminum Castings

ARC WELDING

Metal-Arc Welding

Carbon-Arc Welding
Atomic-Hydrogen Arc Welding
Inert-Gas-Shielded Welding


RESISTANCE WELDING

Spot Welding
Seam Welding
Flash Welding

BRAZING ALUMINUM

Furnace
Torch

SOLDERING ALUMINUM



ALLOY SELECTOR

Just two settings to place at your fingertips the mechanical properties, chemical composition, physical constants, thermal treatments, and specification numbers of 18 aluminum alloys. Price \$1.00. (Check space in coupon.)



METALS WEIGHT CALCULATOR

One of the handiest calculating devices ever developed... simple... accurate... fast. Calculates weights of aluminum, magnesium, steel, brass, copper, and nickel. Only \$.50. (Check space in coupon.)

Reynolds Metals Company
2534 South Third Street
Louisville 1, Kentucky

1066-A1-8B



Please send me "Welding Aluminum." I enclose \$1.00 (check or money order) to cover the cost of printing and mailing.


NAME _____
TITLE _____
COMPANY _____
ADDRESS _____
CITY _____ ZONE _____ STATE _____

() Please send me a Reynolds Aluminum Alloy Selector. I enclose \$1.00.
() Please send me a Reynolds Weight Calculator. I enclose 50 cents.

PLEASE PRINT OR TYPE CAREFULLY

ANSUL SO₂ IN INDUSTRY

The versatility of Ansul Liquid Sulfur Dioxide in industrial practices is illustrated by the following examples:



In addition Ansul Liquid Sulfur Dioxide is being currently used as a bleaching agent • purifier • preservative • solvent • fumigant • protective atmosphere in magnesium fabrication • refrigerant and in polymerization, etc.



Consult Ansul Technical Staff relative to the development of these and other applications for SO₂ in your processes. Write for treatise on Liquid Sulfur Dioxide and request bulletins describing specific Sulfur Dioxide applications.

PHYSICAL PROPERTIES	
Chemical formula.....	SO ₂
Molecular weight.....	64.06
Color (gas and liquid).....	Colorless
Odor.....	Characteristic, pungent
Melting point.....	-103.9° F. (-75.5° C.)
Boiling point.....	14.0° F. (-10.0° C.)
Density of liquid at 80° F.....	(85.03 lbs. per cu. ft.)
Specific gravity at 80° F.....	1.363
Density of gas at 0° C. and 760 mm.....	2.9267 grams per liter (3.1827 lb. per cu. ft.)
Critical temperature.....	314.82° F. (157.12° C.)
Critical pressure.....	1141.5 lbs. per sq. in. abs.
Solubility.....	Soluble in water
Purity.....	99.9+ % (by wt.) SO ₂ (H ₂ O less than 0.01%)

*REG. U.S. PAT. OFF.

Ansul Also Manufactures Methyl Chloride

ANSUL CHEMICAL COMPANY
 INDUSTRIAL CHEMICALS DIVISION, MARINETTE, WIS.
 Eastern Office: 60 E. 42nd St., New York City

University of Rochester in 1894. He was elected vice president and sales manager of the Hooker Electrochemical Co. in 1922 and later became president. At present he is chairman of the board of the company.

WAA MOVES NEW YORK UNIT

NOTICE has been issued by the Office of Information calling attention to the fact that the New York unit of War Assets Administration sales information division and display room has been moved from 70 Pine St. to the ground floor of 37 Broadway.

READERS' VIEWS and COMMENTS

CORRECTION AND COMMENT

To the Editor of Chemical Engineering:

Sir:—With reference to the article "Gauss's Formula" by A. E. Kroll, p. 102, September 1946, I suppose a number of letters have been received pointing out the errors in Table I, page 103.*

U₁ for n = 6 should be 0.0338

K_a and K_s for n = 4 are reversed

The use of this method of numerical integration will save considerable time over graphical methods in certain cases. Like so many articles of this type, the advantages of the method are expounded, but the equally important restrictions of its use are not clarified. Where the data fit a curve of the nature shown in Fig. 1, the method is good, but where you have several peaks and lows, the method is not applicable with accuracy. This point was not brought out.

FREDERICK BELLINGER

Associate Professor
 Department of Chemical Engineering
 Georgia School of Technology
 Atlanta, Ga.

* Yes, several.—Editor.

REBUTTAL

To the Editor of Chemical Engineering:

Sir:—I would like to thank Prof. Bellinger for calling attention to the errors in Table I of the article on Gauss's formula.

Fortunately the functions encountered in most engineering work are relatively simple. In the calculations suggested in the article, curves having several peaks and lows (maxima and minima) very seldom occur. The article was written with this in mind and four points will, in most cases, give desirable accuracy.


Where a function varies rapidly, or in a peculiar manner, or has several maxima and minima, the use of an adequate number of points will give results with accuracy suitable for most practical purposes.

I believe that Gauss's method of integration will save considerable time over graphical methods in most cases, while in certain other cases, where many points are necessary to give the desired accuracy, the graphical method may have the advantage.

A. EDGAR KROLL

Bethlehem, Pa.

Timken 5% Nickel Alloy Tubes SERVE LONGER in Black Liquor Evaporators . . .



From laboratory studies, and investigations and testing under actual plant conditions, in many northern and southern mills during the last 8 years, Timken has developed 5% Nickel tubes which meet specific black liquor corrosive problems for greatly improved life-over-cost.

No other steel producer has devoted so much research to physical requirements necessary to expedite installation and assure maximum service. Studies have included causes of general corrosive attack and pitting in actual service where black liquor concentrations run over 40% solids, where liquor temperatures exceed 220 degrees F., where sulphidity of cooking liquors exceeds 25%, and where forced circulation evaporators have had thru-put increased by larger pump installations.

Timken 5% Nickel alloy tubes have uniformity of structure and are given flaring and hydrostatic tests at 1,000 lbs. per square inch.

A Timken specialist will bring you recommendations. Write Steel and Tube Division, The Timken Roller Bearing Company, Canton 6, Ohio.

TIMKEN
Fine Alloy
STEEL AND
SEAMLESS TUBES

★ YEARS AHEAD — THROUGH EXPERIENCE AND RESEARCH

SPECIALISTS in hot rolled and cold finished Alloy Steel Bars for forging and machining applications, as well as a complete range of Stainless, Graphitic and Standard Tool Steel analyses. Also Alloy and Stainless Seamless Steel Tubing for mechanical and pressure tube applications.

PACIFIC PROCESS INDUSTRIES

TRENDS • EVENTS • DEVELOPMENTS

JOHN R. CALLAHAM, Pacific Coast Editor, San Francisco, Calif.

COSGRAVE BECOMES WESTERN EDITORIAL ASSISTANT

To assist in the expanding editorial activities of *Chemical Engineering* in the West, Mr. James F. Cosgrave recently joined the publication's San Francisco staff. Mr. Cosgrave will assist the Pacific Coast editor in covering the expanding chemical, chemical process and chemical equipment industries of the 11 Western States and in the launching of this magazine's *Pacific Process Industries* western supplement in January. This section, initiated in July 1945, will thus be able to expand in line with the progress and activities of the chemical process industries of the region.

A native Californian with a family history rich in Mother Lode traditions, Mr. Cosgrave attended Fresno State College and became active in science clubs and school journalism as well as serving as an instructor in chemistry laboratory classes. After obtaining his degree in 1945, Mr. Cosgrave immediately joined the engineer-



James F. Cosgrave

ing staff of Shell Development Co. in Los Angeles where he was engaged in research and pilot plant development work until he joined *Chemical Engineering* in October.

WOOD-TREATING LABORATORY OPENED IN OREGON

A LABORATORY to place chemical research in close contact with treatment of Douglas fir and other western species was opened November 1 at the Wauna, Ore., treating plant of American Lumber & Treating Co., according to F. W. Gottschalk, technical director in Chicago. The new research unit will be in charge of William A. McFarland, chemical research engineer, who has been with the firm since 1941.

Besides the plant operation itself, facilities at the Wauna laboratory will include a pilot plant to handle pressure treatment of full-length lumber items, resin impregnation equipment, and facilities for gluing pressure-treated wood into large structural members. Plans include enlargement of facilities, for strength testing and for evaluating electrical resistivity of wood.

UTAH SILICA BRICK PLANT SOLD BY WAA

SALE of a silica brick plant at Lehi, Utah, to General Refractories Co. for \$375,000 has recently been announced by WAA, who stated that the price was 124 percent of the fair value. High bidder on the plant, which was operated during the war by Gladding-McBean & Co., the firm plans to continue manufacturing silica brick to be used in the lining of steel furnaces and similar purposes. The plant is located on 14.7 acres, has six kilns, and a rated capacity of 4,000,000 silica bricks yearly. According to WAA, the plant is not adaptable to the manufacture of standard brick.

WYANDOTTE EXPANDS WESTERN SODA PLANT OPERATIONS

AN EXPANSION program in western operations by Wyandotte Chemicals Corp. is now under way, according to Charles O. Chestnut, manager of the firm's Pacific Division, San Francisco. The program involves three moves: A long-term expansion in soda ash capacity at the Keeler, Calif., plant of Natural Soda Products Co., a subsidiary since about 1934; production of

sodium sesquicarbonate, a new product, at the same plant and expansion of facilities for producing this chemical; and future erection of a new West Coast plant, probably to be located in the Los Angeles area, for compounding detergent and related products.

Using brines from Owens Lake in Inyo County, the Keeler plant of Natural Soda Products Co. has been expanding its output of soda ash from trona for the past three years, and an additional general expansion is now being considered. Output of soda ash for 1946 is expected to be about 50 percent greater than for 1945, according to Mr. Chestnut.

An intermediate in the Keeler operations is sodium sesquicarbonate, which the firm has recently purified, dried and placed on the market as a new product under the name Sesqui-Sec. First commercial production from these new facilities, for which a further expansion is already planned, was during October. In the form of granular crystals and analyzing 40 percent Na_2O , this product goes primarily into detergent compositions; the market is entirely in the West. Compounding operations, new to Wyandotte on the West Coast, will begin at Keeler within a few months; within a year or so the firm expects to erect a large compounding plant in the Los Angeles area. This unit would specialize in laundry, food, beverage and general detergent products and would become a substantial user of western materials such as soda ash, caustic soda, bentonite and volcanic ash.

SPECIALTY PAPER MILL EXPANSION COMPLETED

EXPANSION program of the Westminster Paper Co. at New Westminster, B. C., has been completed and the plant is ready for operations that will double its previous output of 9,000 tons annually of paper towels, tissue, fruit wrappings and waxed papers. Cost of the expansion has been placed at \$1,500,000. Increased produc-

Pacific Chemical Exposition Scheduled for 1947

Reflecting the rapid growth in the chemical, equipment and process industries of the West, the first regularly scheduled Pacific Chemical Exposition for the western states and the Pacific area will be presented in the Civic Auditorium, San Francisco, Oct. 21-25, 1947. The Exposition, sponsored by the California Section of the American Chemical Society, will feature an Industrial Chemical Conference and Display and will be under the chairmanship of Paul H. Williams of Shell Development Co. Manager will be Marcus W. Hinson, who has handled the National Chemical Exposition in Chicago since 1940.

Advisory board for the Exposition consists of H. K. Benson, head, Department of Chemistry & Chemical Engineering, University of Washington; Willard H. Dow, president, Dow Chemical Co.; Gustav Egloff, director of research, Universal Oil Products Co.; R. G. Follis, president, Standard Oil Co. of California; A. H. Hooker, western sales manager, Hooker Electrochemical Co.; Louis B. Howard, chief, Bureau of Agricultural & Industrial Chemistry, U. S. Dept. of Agriculture; Sidney D. Kirkpatrick, editor, *Chemical Engineering*; Ernest O. Lawrence, director, Radiation Laboratory, University of California; Paul D. V. Manning, vice president, International Minerals & Chemical Corp.; Walter J. Murphy, editor, *Industrial & Engineering Chemistry*; W. Alfred Noyes, Jr., president-elect, American Chemical Society; J. Oostermeier, president, Shell Chemical Corp.

Also on the advisory board will be Linus Pauling, director, Gates & Crellin Laboratories of Chemistry, California Institute of Technology; Ralph Sanborn, director of plant coordination, California Packing Corp.; Walter A. Schmidt, president, Western Precipitation Corp.; Robert C. Sproul, president, University of California; Robert L. Taylor, editor, *Chemical Industries*; Donald B. Tresidder, president, Stanford University; James G. Vail, vice president, Philadelphia Quartz Co.; Brayton Wilbur, president, San Francisco Chamber of Commerce.

BOOST PRODUCTION

Eliminate Maintenance Cost
with Tanks and Floors by ATLAS
designed especially to meet
YOUR Service Conditions!

TANKS with linings of Atlas rubber, resin or triple membranes protected with Atlas brick and acid-proof cements. . . .

FLOORS of Atlas brick and acid- and alkali-proof cements. . . .

Here are four interesting Atlas installations. Pictures 1, 2 and 3 were taken in one chemical plant; No. 4 in another.



(No. 2)

Acid- and Alkali-proof floor being laid in process building. Construction is of acid-proof brick joined with Atlas ALKOR (5). This floor is tight, strong and leak-proof.

● Our Engineering Department will gladly furnish recommendations and estimates. In writing, please mention service conditions. An Atlas field representative may be reached at the nearest listed branch office. Address us here at Mertztown for Technical Bulletin No. TV-12-C.

- 1—Carbo-KOREZ consists of liquid synthetic resin binder and acid-proof powder, mixed on the job to form the acid-proof mortar. Carbo-KOREZ withstands temperatures to 360° F.
- 2—Tegul-VITROBOND is a sulphur base cement, plasticized with olefine polysulphide to withstand mechanical and thermal shock. Takes temperatures up to 200° F.
- 3—Atlatisel Triple Membrane consists of alternate layers of Atlastic #31 asphaltic cement and Tegul-VITROBOND #440, yellow plasticized sulphur cement.
- 4—Atlatic #31, asphalt cement, is used as the impervious layer in acid-proof brick floors and for lining concrete sump pits when acid service is not severe enough to call for more expensive Atlatisel.
- 5—ALKOR is the **original** acid- and alkali-proof cement, developed by Atlas more than seven years ago. (**ALL OTHERS ARE IMITATIONS.**) ALKOR withstands temperatures to 360° F.

Carbo-KOREZ, Tegul-VITROBOND and ALKOR are inert, each to a given group of acids, alkalis, corrosives and organic compounds.




(No. 1)

Two 3000 gallon concrete tanks for storing hydrochloric acid, contaminated with organic acids and solvents. These tanks are of Atlas Dual Construction,* Carbo-KOREZ (1) and Tegul-VITROBOND (2) and are lined with Atlatisel (3). Exteriors are


protected with Atlatic #31 (4). Tank tops are of reinforced concrete faced on inside with liner plates joined with Carbo-KOREZ (1). Small openings in tops fitted with Saran piping.

*Fully protected by U. S. Patents.



(No. 3)

Brick and ALKOR (5) lined pit for collecting acid and alkali wastes. Six of these pits are connected in series. Wastes from floor (picture #2) and from chemical process equipment feeds into these sumps. As wastes travel from pit to pit, sludge and solids settle out and wastes finally pass off into sewers.



(No. 4)

Pipe trench laid with white acid-proof brick joined with ALKOR (5). This trench protects building foundation from possible damage due to leaking valves or pipe joints. Trench serves also as supplementary drain when floors are washed down.

THE

Atlas Mineral

PRODUCTS COMPANY OF PENNA.

MERTZTOWN

*ATLANTA 3, Ga., 432 Spring St., N. W.
*CHICAGO 1, Ill., 333 No. Michigan Ave.
*DETROIT 2, Mich., 2970 W. Grand Blvd.
*NEW YORK 16, N. Y., 280 Madison Ave.

PENNSYLVANIA

PITTSBURGH 10, Pa., 4656 Old Boston Rd.
PHILADELPHIA, Pa., 355 Fairview Rd.
Springfield, Pa.
ST. LOUIS 8, Mo., 4485 Olive St.

THE ATLAS MINERAL PRODUCTS CO. OF TEXAS, INC. Box 252, Houston 1, Texas

DALLAS 5, Tex., 3921 Purdue St.
*DENVER 2, Colo., 1921 Blake St.
*HONOLULU 2, Hawaii, U. S. A., Lewers & Cooke, Ltd., P. O. Box 2930

*KANSAS CITY 2, Kan., 1913 Tauramee Ave.
*LOS ANGELES 12, Cal., 172 S. Central Ave.
*SAN FRANCISCO 3, Calif., 244 Ninth St.
*SEATTLE 4, Wash., 1252 First Avenue, S.

*Stock carried at these points

IN CANADA: Atlas Products are manufactured by
H. L. BLACHFORD, Limited, 977 Aqueduct Street, Montreal, P. Q.



Money to be Made in Missouri

A parent plant or branch office in Missouri is a bid for better business. There's money to be made in Missouri . . . and here's why:

The new state constitution is modern, favorable to industry. Low taxes. Water supply unlimited. Low cost power and natural resources in abundance. Excellent transportation facilities. Wealth of diversified markets. Skilled and semi-skilled native labor available in 350 alert, cooperative communities.

During first nine months of 1946, 2,251 new businesses were incorporated in Missouri.

Specialized, confidential service to industrialists. Write direct: Missouri State Division of Resources and Development, Dept. M55, Jefferson City, Mo.

**THE STATE
OF MISSOURI**

In The Heart of America

tion centers largely around a new Beloit machine capable of turning out 34 tons daily of facial tissues, waxing stock and cellulose wadding. Beater room and finishing room production has also been increased. Unbleached sulphite and groundwood pulp supplies come from Powell River Co., while bleached sulphite is supplied by British Columbia Pulp & Paper Co.

LARGE REFINERY TO BE BUILT IN MONTANA

PLANS for construction of a new \$8,000,000 refinery at Billings, Mont., by Carter Oil Co. were announced recently by O. C. Schorp, president of the western operating subsidiary of Standard Oil of N. J. The new plant will have a capacity of 18,000 bbl. per day of crude throughput and will include a catalytic cracking unit. Since some delay in delivery of equipment is anticipated, the plant probably will not be able to operate before 1948. It will be the largest of its type in the state of Montana as well as in the entire Rocky Mountain territory.

Carter Oil Co. now operates four refineries, with daily crude capacities as follows: Billings, Mont., 10,000 bbl.; Cut Bank, Mont., 4,000 bbl.; Lowell, Wyo., 3,000 bbl.; Newcastle, Wyo., 1,600 bbl.

STARCH-GLUCOSE PLANT GOING UP IN CALIFORNIA

GROUND was broken in late August for a \$200,000 starch and glucose plant to be built by the Northwest Chemurgy Corp. of Wenatchee, Wash., (*Chem. & Met.*, June 1946, p. 175) near Hatfield, Modoc County, Calif. The new plant will use cull potatoes for making glucose and starch; daily capacity will be 30,000 lb. of products from 200 tons of potatoes processed during a 3-shift day. The unit, to employ 60 persons, is expected to operate ten months of each year. The making of glucose and starch from potatoes is a comparatively new process in the United States, being introduced in the State of Washington about six years ago. In addition to using culls, the plant can absorb number 2 grade potatoes when marketing elsewhere is unprofitable. Clarence Rice is superintendent. The Klamath Potato Products Co. of Caldwell, Idaho, also has a plant under construction at Merrill, Ore. Both plants expect to be ready to operate by harvest time.

PLYWOOD GLUE CONSUMPTION CENTERS IN NORTHWEST

CLOSE to 99 percent of the nation's output of softwood plywood comes from 35 mills located in the Pacific Northwest, according to a recent release of the U. S. Bureau of the Census. One new mill began operations during the first quarter of the year. At least 97 percent of all softwood plywood is made from Douglas fir, the remaining 3 percent mainly being Ponderosa pine. Very small quantities of Western hemlock are used. Although production of softwood plywood has decreased since 1942, this has largely been a result of labor shortages and strikes.

Since 1942, moisture resistant types (bonded principally with soybean and casein glues) have fallen from 85 percent

CASE HISTORY No. 10

One in a series of factual experiences of a group of American manufacturers with Multi-wall Paper Bags.

COST COMPARISON (Per Ton)

	Burlap Bags	Paper Bags
Container cost . . .	\$2.18	\$1.70
Labor cost55 1/2	.30 1/2
Total bag and labor cost	\$2.73 1/2	\$2.00 1/2
Saving, paper over fabric . . .		73¢

CLASS OF PRODUCT PACKED

CEMENT	FERTILIZER ✓
CHEMICALS	FOOD
FEEDSTUFFS	MISCELLANEOUS

PRODUCT CHARACTERISTICS

ABRASIVE	GRANULAR ✓
CORROSIVE	HEAVY
DELIQUESCENT	HYGROSCOPIC ✓
FLUFFY	LIGHT
FREE-FLOWING	VISCOUS

ST. REGIS BAG PACKAGING SYSTEMS are made in a variety of capacities, speeds, and manpower requirements to suit specific products and plant layouts. Machines are available in types to meet the special characteristics of a wide range of products, with filling speeds as high as twenty-four 100-lb. bags per minute — with one operator.

BIRDS EYE VIEW

OF PACKAGING EFFICIENCY


Up to 1940, I. P. Thomas and Sons Co., of Camden, N. J., packed its mixed fertilizers in 167-lb. open mouth burlap bags.

At each of the three packing units in its Paulsboro, N. J., plant, eleven men were required to fill, check-weigh, and then sew the bags closed. The packaging output per unit averaged 18 tons an hour.

Realizing in 1941 that burlap might become scarce, the company installed three 160-FB St. Regis Packers and changed over to Multiwall paper valve bags. With this

equipment as a basis, the company put into operation the highly efficient St. Regis Packaging System shown in the illustration.

HERE'S HOW IT WORKS—One man operates the St. Regis Packer, shown at left, which simultaneously weighs and fills the bags. A conveyor carries the factory-closed paper bags to a scale where they are check-weighed and then stacked on pallets. Fork lift trucks take the pallets to storage, to freight cars, or to waiting trucks. The entire operation is simple, compact, and efficient.



Here are the results—

PRODUCTION INCREASED 38%

—Packaging output per unit jumped from 18 tons an hour under the old system to 25 tons an hour with the St. Regis Packaging System.

LABOR COSTS PER TON CUT 45%

—Only eight men (four of whom are shown in photo)

are required for each packing unit, instead of eleven under the old packaging system.

CONTAINER COSTS REDUCED 22%

—Multiwall paper bags cost \$1.70 for each ton packed . . . 167-lb. burlap bags cost \$2.18 per ton.

CUSTOMER ACCEPTANCE—Paper bags protect against caking of contents—a problem often experienced with the use of burlap bags. And customers find 100-lb. Multiwalls easier to handle than bulky 167-lb. burlap bags.



ST. REGIS SALES CORPORATION

(Sales Subsidiary of St. Regis Paper Company)

NEW YORK 17: 230 Park Ave.

CHICAGO 1: 230 No. Michigan Ave.

BALTIMORE 2: 2601 O'Sullivan Bldg.

SAN FRANCISCO 4: 1 Montgomery St.

Without obligation, please send me full details regarding "Case History" No. 10, outlined above.

NAME _____


COMPANY _____

ADDRESS _____

Mail this coupon for the complete story

Allentown Birmingham Boston Cleveland Dallas Denver
Detroit Franklin, Va. Los Angeles Nazareth, Pa. New Orleans
No. Kansas City, Mo. Ocala, Fla. Oswego, N. Y. Seattle Toledo

IN CANADA: St. Regis Paper Co. (Can.) Ltd., Montreal, Vancouver.



HOT STUFF - Under Control

Want a hot, even temperature for your processes? And are you afraid of high pressures? MERRILL PROCESS can give you temperatures up to 600° F. with scarcely any pressure. Heat input may be regulated, graded, and controlled to a nicety.


In many a Chemical Plant, these MERRILL PROCESS advantages have improved product—and lowered operating costs. Large and small operating units available, designed by engineers with a lifetime of experience.

Investigate the Merrill Process System, built in standard size units for small or large applications. Send for your copy of our new 64-page booklet.

Parks-Cramer Company
ENGINEERS AND CONTRACTORS
1104 Old South Building, Boston, Massachusetts



of total production to 70 percent in 1945. Exterior-type plywood is bonded with phenolic resin glue. During the past four years, there has been a decrease in "glue spread" (plywood produced per pound of glue used) from 35.3 to 30.8 sq.ft. for



moisture-resistant types and an increase from 15.7 to 18.8 sq.ft. for exterior types. The accompanying map shows location of the industry in the United States, while the table gives consumption of glues by types.

Glue Consumption in Northwest Plywood Mills¹

	Thousands of Pounds			
	Casein	Soy-bean	Phenolic ²	Total ³
1942.....	3,595	37,380	17,262	61,736
1943.....	3,936	26,088	19,764	53,151
1944.....	1,935	27,879	23,067	55,941
1945.....	3,287	22,473	19,393	47,302
1946 (8 mo.)	3,448	14,567	15,921	35,062


¹ Softwood plywood. From Bureau of the Census. ² Usually reported on a "wet" basis; all other types usually reported on a "dry" basis. ³ Difference between total and sum of three types represented by other types of glue.

HUGE CEMENT EXPANSION NOW UNDER WAY

PLANS for a huge expansion program at Portland, Colo., and Devil's Slide, Utah, were recently announced by Ideal Cement Co., Denver. The program, already under way, is estimated to exceed \$5,000,000. It is hoped that the new plants will be in production for the 1947 season.

At the Portland plant, a contract has been awarded Stearns-Roger Mfg. Co. for engineering and construction of a new crushing unit, cost of which will exceed \$300,000. The new plant will be a complete unit with two wet process kilns 9.5 x 375 ft., each with a capacity of 2,000 bbl. daily. The present plant will be kept in full operation throughout the construction period and afterwards as long as the demand for cement requires. The new unit's capacity of 4,000 bbl. daily will more than double the present plant's output.

At Devil's Slide, detailed plans are



FOR FAST SERVICE ON STAINLESS TUBING ORDERS ... Call Your Carpenter Distributor!

- **ALBANY, NEW YORK**
Anti-Corrosive Metal Products Co., Inc.—
Castleton 2511
- **ATLANTA, GEORGIA**
J. M. Tull Metal & Supply Co.—Walnut 3525
- **BALTIMORE, MARYLAND**
Horace T. Potts Co.—Mulberry 8260
- **BEAUMONT, TEXAS**
Standard Brass & Mfg. Co.—Beaumont 1129
- **BERKELEY, CALIFORNIA**
American Rolling Mill Co. of Calif.—
Ashberry 5600
- **BUFFALO, NEW YORK**
Service Steel Company—Delaware 8900
- **CAMBRIDGE, MASS.**
Industrial Steels, Inc.—Trowbridge 7000
- x **CHICAGO, ILLINOIS**
Cherry-Burrell Corp.—Dearborn 7900
(Sanitary Tubing)
C. A. Roberts Co.—Haymarket 6330
Branch Office of
The Carpenter Steel Company
Welded Alloy Tube Division—
Central 3506
- **CINCINNATI, OHIO**
Service Steel Co.—Wabash 2750
- **CLEVELAND, OHIO**
Cleveland Tool & Supply Co.—Cherry 2510
- **DETROIT, MICHIGAN**
Service Steel Company—Randolph 9350
- **ELIZABETH, NEW JERSEY**
Schnitzer Alloy Products Co.—Eliz. 2-2090
- **EUGENE, OREGON**
Electric Steel Foundry Co.—5012
- **HOUSTON, TEXAS**
Standard Brass & Mfg. Co.—Preston 1123
A. P. Wright—Fairfax 0268
- **INDIANAPOLIS, INDIANA**
C. A. Roberts Co.—Market 8455
- x **KENILWORTH, NEW JERSEY**
The Carpenter Steel Company
Welded Alloy Tube Division—
Elizabeth 3-2100
- **KINGSPORT, TENNESSEE**
Slip-Not Belting Co.—Kingsport 5128
- **KNOXVILLE, TENNESSEE**
Slip-Not Belting Co.—Knoxville 3-3811
- **LOS ANGELES, CALIFORNIA**
American Rolling Mill Co. of Calif.—
Prospect 8365
Electric Steel Foundry Co.—Lucas 7251
- **NEW YORK, NEW YORK**
Peter A. Frasse & Co., Inc.—Walker 5-2200
- **PHILADELPHIA, PENNA.**
Horace T. Potts Co.—Nebraska 4-8870
- **PITTSBURGH, PENNA.**
Chandler-Boyd Co.—Hemlock 1860
- **PORT ARTHUR, TEXAS**
Standard Brass & Mfg. Co.—
Port Arthur 9377
- **PORTLAND, OREGON**
Electric Steel Foundry Co.—Atwater 2141
- x **ST. LOUIS, MISSOURI**
C. A. Roberts Co.—Chestnut 7070
Branch Office of
The Carpenter Steel Company
Welded Alloy Tube Division—
Franklin 0905
- **SAN FRANCISCO, CALIF.**
Electric Steel Foundry Co.—Douglas 8346
- **SEATTLE, WASHINGTON**
Electric Steel Foundry Co.—Elliott 4161

THE CARPENTER STEEL COMPANY • Welded Alloy Tube Division • Kenilworth, N. J.

CARPENTER STAINLESS TUBING for

- Strength and Rigidity
- Weight Savings
- Corrosion Resistance
- Heat Resistance
- Accuracy
- Fabricating Savings
- Longer Service Life
- Sales Appeal




Carpenter

WELDED

STAINLESS TUBING

Start and stop material flow

with non-clogging **Beaumont Rotary Gates**



These gates are always easy to open and close because material in the gate body is simply rotated with the machined rotor to cut off flow. The rotor opening is the same diameter as the pipe; in the open position there is no restriction to flow.

Beaumont Rotary Gates are quick acting, dust-tight and can be used at any angle . . . for alum, bauxite, fluorspar, sulphur and similar materials.


Investigate the complete line of Beaumont Gates. Send us your gate problem for engineering recommendations.

BEAUMONT BIRCH CO.

1510 Race Street • Philadelphia 2, Pa.

HIGH SPEED . . .

MOTOR DRIVEN SUSPENDED



• **LARGEST CAPACITY**

in proportion to
basket diameter . . .

• **HIGHEST SPEED**

in acceleration, running,
braking, unloading . . .

• **LABOR SAVING**

bottom discharge for solids . . .

• **SELF BALANCING**

to handle unbalanced
loads without difficulty

FLETCHER

CENTRIFUGALS

Engineering consultation available—send for catalog.

FLETCHER WORKS, 235 GLENWOOD AVE., PHILADELPHIA 40, PA.

under way which involve practically a duplication in size of the new plant at Portland. The \$2,500,000 Utah plant will be operated in conjunction with the present plant as long as the demand requires, thus increasing capacity about 3-fold. A new battery of storage silos and new packhouse will provide a capacity for 250,000 bbl. and permit simultaneous packing of as many as five types of product. Unprecedented demands for cement in the Rocky Mountain area, reflecting the rapid industrial growth of the region, prompted the firm's expansion moves.

WEST'S BENTONITE OUTPUT REACHES NEW HIGH

ALMOST 80 percent of the increased national output of bentonite in 1945 came from Wyoming, South Dakota and California, with the Wyoming-South Dakota area producing nearly 66 percent of the total. According to the U. S. Bureau of Mines, the national output in 1945 exceeded the 1944 tonnage by 5 percent and tripled that of 1938, marking the seventh consecutive, record-breaking year. Sales for use as a foundry-sand bond, down 11 percent from 1944, accounted for approximately 28 percent of the total; oil well drilling muds, up 34 percent, took a similar amount. A little over 25 percent was used in oil filtering and decolorizing.

Output of Bentonite, Short Tons*



Year	Calif.	Wyo.	S. D.
1939	11,699	76,133	31,528
1940	7,867	91,714	40,481
1941	6,981	145,574	57,139
1942	4,745	139,410	88,149
1943	7,104	159,252	124,528
1944	6,649	196,138	169,893
1945	16,187	199,293	178,347

* U. S. Bureau of Mines. Does not include output of Arizona, Colorado, Montana and Utah, for which data were not given.

CLOROBEN SEWAGE TREATMENT PREFERRED TO CHLORINE

By COURT order, the city of Los Angeles and contributing communities are required to sterilize sewage before discharge into the ocean and to proceed at once with construction of a sewage treatment plant, estimated to cost \$21,000,000. Since it will be at least two years before this plant can operate, the city has experimented to find a better and cheaper method than chlorination and to permit reopening of nearby beaches from the quarantine against surf bathing. According to the Los Angeles Bureau of Sanitation, the experimental use of Cloroben instead of chlorine probably saved the city about \$180,000 during the past five summer months in which the court order was effective. This chemical, manufactured by the Cloroben Corp. of Jersey City, N. J., is a chlorinated benzene with two chlorine molecules in the ortho position and with added emulsifiers. It has a phenol coefficient of 13. However, due to its effectiveness in eliminating H₂S and slimes, the city has just decided to continue use of Cloroben during the winter months and throughout next summer.

Upon the performance of 50 dosing stations operating in June, it was shown that bacterial population of sewage was reduced 50-90 percent by use of 1 ppm.



**LOADS
CARRIES
DUMPS**



Model H-A Payloader, 10½ cu. ft. bucket, gasoline powered — 2 speeds forward — 2 reverse speeds. 1 yd. bucket available for light materials.



Model H-L Payloader, for greater capacity and heavier duty service. 1 yd. bucket — gasoline or Diesel power. 8 forward speeds — 2 reverse.

HOUGH *Payloader* cuts chemical handling costs

Here's one sure way to cut corners on handling costs — speed up production — save labor. The Hough Payloader pays its way every day — loading or unloading freight cars, charging bins or conveyors, unloading ship's holds; digging, loading, carrying, spreading or dumping any type of bulk material.

The HA Payloader will do the work of 8 to 10 men — handles 25 to 35 tons of chemicals per hour. One plant saved 28 man hours per car of chemical in labor costs alone — plus \$75 per car through bulk shipment.

Over a quarter of a century of material handling experience has been built into the Payloader — more than 5,000 Hough units are serving industry throughout the world — cutting handling costs — saving labor — stepping up production. Let the Payloader take over your chemical handling problems — now, when production is vital, when labor is critical, when rising production costs are pinching profits. There is a Hough dealer near you to help in the solution of your material handling problems.

GET COMPLETE DETAILS Two new catalogs now available — complete with mechanical details and specifications, action pictures, performance data. Ask for No. 162 on the HA, or No. 163 on the HL.



THE FRANK G. HOUGH CO.
MATERIAL HANDLING EQUIPMENT SINCE 1920
2000 SUNNYSIDE AVE., LIBERTYVILLE, ILLINOIS



Butadiene Storage..



PROTECTION

Certain manufacturing processes created through wartime exigency present countless problems from the standpoint of safety during the peacetime years ahead.

One such process is the manufacture of synthetic rubber as is produced at the Goodyear operated Rubber Reserve Plant at Akron, Ohio. Farsighted company engineers realized the need of absolute security against fire damage for their butadiene storage and handling facilities, and they got it. "Automatic" FIRE-FOG was the answer, for these test proved systems were designed and developed particularly for the control of fires originating in highly flammable liquids and solids. The protection of each operation at this plant was of necessity engineered in a most exacting manner thus assuring the utmost in safety at a minimum of cost.

Isn't now the time to determine whether your fire hazard protection is adequate? An "Automatic" Sprinkler engineer will cheerfully furnish complete information about an "Automatic" FIRE-FOG installation—where it should be used, why it protects, how it operates. Write today.

"Automatic" Sprinkler

"AUTOMATIC" SPRINKLER CORPORATION OF AMERICA

YOUNGSTOWN, OHIO OFFICES IN 37 CITIES

"Automatic" Sprinkler designs, manufactures and installs a complete line of fire protection devices and systems for all types of fire hazards. Listed by Underwriters' Laboratories, Inc., and approved by Factory Mutual Laboratories

Cloroben, 90 percent by 1.5 ppm., and 99 percent by 1 ppm. Cloroben plus 20 percent of the Cl_2 demand. Meanwhile, H_2S was reduced from 5-25 ppm. to 0.1 ppm. or less and grease, slime and bacterial growths adhering to sewer pipes were removed. Mosquitoes, flies and other obnoxious insects are also controlled by the chemical. Cloroben-treated sewage diluted with 100 parts of sea water in contact for 3-5 hr. increased bacterial reduction from 30 to 70 percent. At the last report, extreme ends of the bathing beaches were free from dangerous bacterial contamination.

Largely as a result of the promising work in Los Angeles, Salt Lake City began experiments with Cloroben during September. If the experimental treatment is successful, it will probably become a permanent procedure and may thus eliminate need for a \$2,000,000 sewage disposal system in that city. Cost to Salt Lake City, it is estimated, may not exceed \$50,000 yearly, including \$36,000 for the sewer system and \$14,000 for mosquito control.

FIRST WESTERN LATEX PLANT READY TO OPERATE

WHAT will be the first latex manufacturing and processing plant west of the Rockies is now ready to be operated by American Anode, Inc., a subsidiary of B. F. Goodrich Co., in Los Angeles. The plant will produce liquid rubber and plastic latex material for sale to finished products users throughout the West, according to R. V. Yohe, president of American Anode. It will have an annual design capacity of 4,000,000 lb. of dry base in the form of liquid latex, which may contain up to 60 percent solids for synthetic and natural rubbers and 40 percent for plastics materials. Storage facilities will be available for 30,000 gal. of latex.

The unit, located near the B. F. Goodrich Co. synthetic rubber plant in Los Angeles, will have Robert A. Lees as manager. It will produce liquid latex for use in coating metals and wire, for impregnating paper, fabrics and textiles, and for the manufacture of various rubber goods.

NEW PLUTONIUM PROCESS STUDIED AT HANFORD

A NEW era of large-scale construction may possibly be in prospect for the atomic energy plant of Hanford Engineer Works at Richland, Wash., according to a recent release announcing the appointment of Dr. W. D. Coolidge as head of the General Electric Co. new atomic energy laboratory division. General Electric Co. took over operations of the plutonium plant on September 1. Evidently being considered is a radically new plutonium separation process. Improvements in the chemical separation process have already increased the yield of plutonium and decreased consumption of process reagents.

Separation of radioactive isotopes on a plant scale has been started, it was reported. Small quantities of radio-iodine have been separated; larger quantities can be made available with minor changes in equipment. Neptunium, a transitional element in the conversion of uranium to plutonium, has

PATTERSON-KELLEY
Heat Exchangers
AND
Process Equipment

PATTERSON-KELLEY HEAT EXCHANGERS WITH DOUBLE CORROSION RESISTANCE

...THEY'RE FURNISHED WITH DUPLEX TUBING



Duplex Tubing in Patterson-Kelley Heat Exchangers provides maximum corrosion resistance for both inner and outer contacts. From a wide range of metals for inner and outer components of the tubing the best combination may be selected for resisting the two liquids or gases encountered. In contrast with monometal tubing, the corrosion resistance of neither inner nor outer surface need be sacrificed.

Here are a few of the Patterson-Kelley Heat Exchanger applications with Duplex Tubing and the products handled:

Application	Tube Components	Products in Contact
Ammonia Liquor	outer—steel inner—copper	ammonia—liquor treated river water
Formaldehyde	outer—aluminum inner—copper	formaldehyde water
Acetic Acid	outer—aluminum inner—copper	acetic acid water
Hydrocarbon Vapor	outer—arsenical admiralty inner—steel	water hydrocarbon vapor
Plastics	outer—arsenical admiralty inner—aluminum ^o	water raw plastics
Amino Compound	outer—copper inner—steel	water nitrogen compounds
Soap Solution	outer—steel ^o inner—arsenical admiralty	soap solution water
Beer Cooler	outer—copper inner—steel	beer water
Edible Oils	outer—aluminum inner—arsenical admiralty	food products water
Carbonated Liquid	outer—aluminum inner—copper	carbonated liquid water

^oto avoid color contamination

In Duplex Tubing there are no fixed combinations of outer and inner tube components. Practically any combination of corrosion resisting metals can be furnished. That's why these Patterson-Kelley Heat Exchangers give maximum resistance to corrosion for both contact surfaces.

Our engineers will be glad to discuss the application of Duplex Tubing construction for the heat exchangers you need.



THE PATTERSON-KELLEY

Company, Inc.

109 WARREN STREET, EAST STROUDSBURG, PA.

NEW YORK 17—101 Park Avenue
CHICAGO 4—Railway Exchange Bldg.

PHILADELPHIA 3—1700 Walnut Street
BOSTON 15—96-A Huntington Avenue

Representatives in Principal Cities

CHASE LINERS

** Stop Liner Breakage!
* Stretch in All
Directions!*



Chase Liners are better, more resilient, more flexible! Here's why: they're crinkled for vertical elasticity and pleated for horizontal elasticity! Result: no more broken liners nor costly damage to contents due to liner failure or breakage.

Check on Chase Liners today. They're the crinkled and pleated liners that assure savings... that actually cost no more!



CHASE BAG CO.

GENERAL SALES OFFICES
309 WEST JACKSON BLVD., CHICAGO 6, ILL.

BOISE • DALLAS • TOLEDO • DENVER • DETROIT • MINNEAPOLIS
ST. LOUIS • NEW YORK • CLEVELAND • MILWAUKEE • PITTSBURGH
BUFFALO • KANSAS CITY • MEMPHIS • GOSHEN, IND. • PHILADELPHIA
NEW ORLEANS • ORLANDO, FLA. • SALT LAKE CITY • OKLAHOMA
CITY • PORTLAND, ORE. • REIDSVILLE, N. C. • HARLINGEN, TEXAS
CHAGRIN FALLS, O. • HUTCHINSON, KAN. • WINTER HAVEN, FLA.

been separated and made available for scientific study in quantities never before achieved.

BARIUM INDUSTRY SHOWS INCREASED ACTIVITY

WESTERN producers of barite were active in seeking new deposits, and output of this mineral during 1945 increased in California and Nevada, according to the U. S. Bureau of Mines. Output in the latter state increased from 22,390 short tons in 1944 to 28,919 tons in 1945.

California-Nevada Barytes Mines division of Glidden Co., Oakland, reopened a mine at Tonapah, Nev., and the Chemical & Pigment division of the firm continued grinding activities and production of lithopone at its Oakland, Calif., plant. Barium Products, Ltd., of Modesto, Calif., a division of Westvaco Chlorine Products Corp., continued production of barite from Battle Mountain, Nev., and began operations at a mine near Greenville, Plumas County, Calif. This firm manufactures barium hydroxide, peroxide and other

barium chemicals at its Modesto plant. Vernon Barium Products Co. of Los Angeles has evidently ceased manufacturing specialty barium chemicals.

The Industrial Minerals & Chemical Co., Berkeley, operated the Nelson mine near Carlin, Nev., in 1945. Baroid Sales Division of National Lead Co., Los Angeles, acquired the barite property of Industrial Minerals & Chemical Co. at Washington, Calif., and opened a new mine at Auburn, Placer County. This firm, which markets barite extensively for use in heavy-gravity oil well drilling muds, leased a deposit in Tulare County, Calif., and continued operation of the El Portal mine, Mariposa country. This deposit, first worked in 1920, has given the largest commercial production to date in California. The mineral is in part witherite. There is also a small and intermittent output of barite reported from deposits near Hailey and Troy, Idaho.


Largest newcomer to the western barite field is Arizona Barite Co., a subsidiary of Houston Oil Field Material Co., which has begun mining a property on the Salt River above the Granite Reef Dam. Also with

Western Producers and Processors of Barium Minerals¹

Producing Firm	Location	Products or Activity
Arizona Barite Co. ²	Mesa, Ariz.	Barite; grinding
Baroid Sales Div., National Lead Co.	Washington, Auburn, Calif.	Barite
	El Portal, Calif.	Barite, grinding
Barium Products, Ltd. ³	Greenville, Calif.	Barite
	Battle Mt., Nev.	Barite
	Modesto, Calif.	Grinding; chemicals
California-Nevada Barytes Mines ⁴	Tonapah, Nev.	Barite
Chemical & Pigment Div., Glidden Co.	Oakland, Calif.	Grinding; lithopone
Industrial Minerals & Chemical Co.	Carlin, Nev.	Barite
	Berkeley, Calif.	Grinding

¹ For the year 1945, as reported by the U. S. Bureau of Mines and private sources. ² A subsidiary of Houston Oil Field Materials Co. ³ A subsidiary of Westvaco Chlorine Products Corp. ⁴ A subsidiary of the Glidden Co.

INCONEL CONDENSER



LEADER BUILDS
TANKS — KETTLES — FRACTIONATING COLUMNS
HEAT EXCHANGERS and SPECIAL EQUIPMENT
OF
STEEL—STAINLESS STEEL—NICKEL—MONEL
INCONEL—COPPER—EVERDUR—HERCULOY
HASTELLOY — ALUMINUM and CLAD STEELS

LEADER IRON WORKS, INC.
2200 N. JASPER DECATUR, ILLINOIS



FOR CERTAINTY IN CHEMICAL CONTROL

... Rely on B&A Reagents

Chemical control has become indispensable to modern process industries all the way from acceptance of raw materials on through to certification of finished products. In industrial laboratories America over, the control chemist, working with the precision tools of his profession, safeguards product quality and uniformity . . . helps obtain production economies and efficiency.

For certainty in such responsible work, depend on B&A Reagents.

These high purity products of General Chemical Company's Baker & Adamson Division are chemi-

cal micrometers for your most exacting analyses. They are made to the decimal-point accuracy of A.C.S. standards . . . and are backed by all the specialized skills and science B&A has developed in 64 years of "setting the pace in chemical purity." Extensive stocks of B&A Reagents are carried at the Company's own chain of regional warehouses from coast to coast.* Use the one nearest you to fill your reagent needs. By telling the B&A Technical Serviceman your month-to-month requirements he can plan with you in building these local stocks to supply you quickly . . . conveniently . . . whenever you call.



Do you have this 200-page catalog?

If you buy or specify industrial laboratory reagents, you will find the 200-page book of B&A products an invaluable guide to 1,000 quality chemicals. For free copy, make request on business letterhead to nearest B&A office below.



GENERAL CHEMICAL COMPANY BAKER & ADAMSON DIVISION

40 RECTOR STREET, NEW YORK 6, N. Y.


Sales and Technical Service Offices: Albany* • Atlanta • Baltimore • Birmingham* • Boston • Bridgeport
Buffalo* • Charlotte* • Chicago* • Cleveland* • Denver • Detroit* • Houston • Kansas City
Los Angeles* • Minneapolis • New York* • Philadelphia* • Pittsburgh* • Providence • St. Louis*
San Francisco* • Seattle • Wenatchee (Wash.) • Yakima (Wash.)

In Wisconsin: General Chemical Wisconsin Corporation, Milwaukee, Wis.

In Canada: The Nichols Chemical Company, Limited • Montreal* • Toronto* • Vancouver*

SETTING THE PACE IN CHEMICAL PURITY SINCE 1882

* Complete stocks carried here.



**A BUSHEL OF OATS
EVERY 2 SECONDS**

by Air

Moving 45,000 bushels of oats every 24 hours, on a 7-block underground trip by air, calls for plenty of stability in the blower. That's an outstanding characteristic of all Roots-Connorsville equipment.

But there's accuracy built into these blowers, too—accuracy that you can depend on to deliver precisely any large or small amount of air or gas for chemical processes. Whether your specific work can be done best by Rotary Positive or Centrifugal units—we design and supply whichever will give the most satisfactory results. That's R-C *dual-ability*, which we apply without prejudice.

This *dual-ability* is at your service on any problem of moving air or gas, and for many liquid-moving applications.

ROOTS-CONNERSVILLE BLOWER CORPORATION

One of the Dresser Industries

611 Illinois Avenue, Connorsville, Indiana



BLOWERS FOR EVERY NEED

ROTARY POSITIVE AND CENTRIFUGAL BLOWERS • EXHAUSTERS • BOOSTERS
LIQUID AND VACUUM PUMPS • METERS • INERT GAS GENERATORS



grinding facilities, this firm is now in operation with a capacity of 100 tons of finished product daily. A considerable part of the material is marketed in California.

Although drilling muds constitute the largest outlet for barite in California, as much as 35 percent of the state's output has gone into manufacture of lithopone and barium chemicals, according to one source. The attached table summarizes activities of western producers and processors of barite during 1945.

GLUTAMATE PLANT TO OPERATE SOON

CONSTRUCTION work is now progressing on the new monosodium glutamate plant of International Minerals & Chemical Corp. at San Jose, Calif., and it is expected that the unit may begin operations late this year. The entire project should be completed early in 1947. The plant will produce monosodium glutamate and related amino compounds from concentrated Steffens waste from beet sugar factories in California and Oregon. The San Jose plant, including pilot plant facilities and Steffens waste concentrating units at the sugar factories, will represent an investment of about \$3,500,000. Sufficient storage is being provided to permit year-round operation of the amino products plant.

The San Jose plant will be the first of its kind in this country; the firm's other glutamate plant at Toledo, which increased production some 80 percent last year, operates on grain proteins. Monosodium glutamate is widely used to impart a "meaty" flavor to certain foods. Before the war, world production was largely controlled by the Japanese.


THIRD ATOM-SMASHER BEING BUILT IN BERKELEY

Now under construction is the third of the atom-smashing machines at the University of California at Berkeley. Known as a linear accelerator, the 40-ft. experimental model will be used to bombard atomic nuclei with protons accelerated along the linear course of the machine's tube by scores of radar transmitters. Although the basic concept of the apparatus is not new, it will be novel in its source of power. Idea of using radar sets as a power source originated with Dr. Luis W. Alvarez, nuclear physicist at the University, who has charge of research and construction on the project. Funds were provided by the Manhattan District, while the Army Signal Corps provided several hundred surplus radar sets. Other atom-smashers at the University are the 184-in. cyclotron with its 4,000-ton magnet, which is nearing completion, and the McMillan synchrotron (*Chem & Met.*, June 1946, p. 170), still under construction.

The linear accelerator consists essentially of two concentric tubes, the inner of which is approximately 1.5 in. diameter and cut into sections of different lengths separated by gaps. A Van de Graaff generator fires the proton bullets into the breach of the apparatus, at which time they also receive their first electrical kick from the radar power source. Within the tube, the bullets are protected while the electrical field alter-

CONSIDER DOWTHERM


for HIGH TEMPERATURE (700°) HEATING AT LOW PRESSURE



When high and closely controlled temperatures are necessary, Foster Wheeler Dowtherm heating systems offer many advantages — uniform temperatures, high rate of heat transfer, flexible design to permit heating and cooling in the same cycle. Further, Dowtherm systems do not require expensive pressure parts — pressure remains low even at 700°F, upper recommended working temperature.

If you are looking for a solution to some problem of high temperature processing, write for more detailed information to


FOSTER WHEELER CORPORATION • 165 BROADWAY, NEW YORK 6, N. Y.



FOSTER WHEELER

WILLIAMS

**HEAVY DUTY HAMMERMILLS
FOR INDUSTRIAL USE . . . Grind Chemicals
. . . Crush 4 feet Cubes of Rock . . . Shred
Steel Turnings**



Sectional view of Williams over-running hammermill with heavy liners and grinding plate for limestone and other hard material. Particular attention is directed to the grinding plate adjustment which assures uniform close contact of hammers and grinding plate at all times. Also note the metal trap which provides an outlet for the escape of tramp iron.

Williams Hammer Grinder direct connected to motor, all mounted on heavy cast base. This type of drive is economical to operate and easy to install.

Reduces

**A N I M A L . . . MINERAL
VEGETABLE MATTER**

Capacity from 50 pounds to 300 tons per hour

• Williams is the world's largest organization of crushing, grinding and shredding specialists and have developed standard machines for the reduction of practically every material whether animal, mineral or vegetable. Capacities range from 50 pounds to 300 tons per hour permitting selection of exactly the proper size for your work. Whether you wish to grind chemicals to 400 mesh, crush 4 feet cubes of rock or shred steel turnings, you can profit by Williams' experience.

THE WILLIAMS PATENT CRUSHER & PULVERIZER CO.
2706 North Ninth St. St. Louis, Mo.

Sales Agencies Include

Chicago
37 W. Van Buren St.

New York
15 Park Row

Oakland, Calif.
1629 Telegraph Ave.



Williams

PATENT CRUSHERS GRINDERS SHREDDERS

nates. As they emerge from this section and cross the gap they are accelerated again and enter the next section, longer to provide necessary protection from the electrical field. The bullets finally crash the atomic nuclei target. If the 40-ft. model is successful, a 280 ft. tube may be built capable of accelerating particles to 280 million electron volts, which is the power range of the cyclotron and synchrotron now building.

Scientists soon will have atom smashers powerful enough to duplicate the explosions carried on in nature by cosmic rays and hence may produce at will the mesotrons now found only in cosmic ray explosions, according to Dr. J. R. Oppenheimer. This would lead to a new era in atomic physics. According to Dr. Oppenheimer, the particles now known to be parts of the atom are the electron, proton, neutron, positron, mesotron, gamma ray and a hypothetical particle called the neutrino.

SULPHITE LIQUOR ALCOHOL OUTPUT INCREASED

PRODUCTION of industrial alcohol from sulphite pulp liquors by Puget Sound Pulp & Timber Co., Bellingham, Wash., increased from 547,272 gal. for the first six months of 1945 to 748,055 gal. for the comparable period this year, according to a statement by the firm. The alcohol unit, only one of its kind in this country, began operations in March 1945. The plant has operated at a capacity of 6,500 gal. alcohol daily; with resumption of normal log production, it is probable that this rate will be increased.

In the second quarter of 1946, pulp production rose to 19,800 tons from 15,400 tons for the first three months, reflecting June production at 78 percent of capacity compared to an average of 52 percent in the first five months of 1946. A new hydraulic barker, installed in June, resulted in a 17 percent savings in log consumption in its first month's performance.

A new \$460,000 paperboard mill, to be known as Bellingham Paper Products Co., will be constructed on Puget Sound Pulp & Timber Co. property and will be 75 percent owned by this firm. The new plant will consume an estimated 12 percent of the capacity output of the parent firm's pulp mill and will be capable of producing 45 tons of paperboard daily.

KAISER BEGINS PHOSPHATE FERTILIZER OPERATIONS

IN RESPONSE to the greatest demand ever experienced on the Pacific Coast for fertilizer materials, the Kaiser subsidiary Permanente Metals Corp. has just begun commercial production of phosphate fertilizer at Permanente, Calif., under the name Thermo-Phos. The material is a new type of product made by electric furnace fusion of serpentine and phosphate rock. Two furnaces formerly used to turn out ferrosilicon for the Manteca, Calif., magnesium plant have been reconverted to produce the fertilizer.

Permanente is now producing 150 tons of Thermo-Phos daily and plans to increase output to over 200 tons daily as soon as sufficient labor can be obtained, stated

If you don't make a business of *Drying-*



we can tell you who does



No need to bother yourself with unfamiliar DRYing tasks. There are companies whose specialty is drying air, gases and organic liquids to very low dew points. They make machines for doing this work automatically.

For years, our engineers have been assisting

these manufacturers in solving DRYing problems. "What makes a consistently efficient drying agent? (Alorco Activated Aluminas answer that one) ... What materials will it dry? ...

How to speed up this work? ... What volumes can it handle? ... How to lower the dew point?

We'll tell you the answers to these DRYing questions, and give you the names of DRYing specialists. Call the nearby Alcoa office, or write ALUMINUM ORE COMPANY, 1910 Gulf Building, Pittsburgh 19, Pennsylvania.

ALUMINUM ORE COMPANY



Aluminas and Fluorides

SUBSIDIARY OF ALUMINUM COMPANY OF AMERICA

LIQUIDOMETER

Tank Gauges

**ALWAYS
DEPENDABLE**



"LIQUIDS WORTH STORING ARE WORTH MEASURING"

THE **LIQUIDOMETER** CORP.
36-29 SKILLMAN AVE., LONG ISLAND CITY, N.Y.



Consult NORBLO Whatever Your Need for Dust or Fume Control...

Modern dust and fume collection performs several functions. It can be a production process (especially in smelting), a means of salvaging valuable dusts, a safeguard against explosions and adequate plant maintenance.

Whatever your particular situation or need for dust control, Norblo designs and makes suitable equip-

ment, of advanced design, for continuous heavy duty or for intermittent service. You get highly efficient, low-cost, long-lived equipment backed by 30 years specialized experience in building dust control systems, exhaust fans and related products.

Without obligation, write us stating your problem, get preliminary suggestions and literature.

Norblo

THE NORTHERN BLOWER COMPANY
6411 BARBERTON AVENUE CLEVELAND 2, OHIO

D. A. Rhoades, vice president and general manager of the corporation, who added that his firm entered the phosphate fertilizer field because of the local shortage and the fact that two-thirds of California's needs now have to be shipped from the eastern states and British Columbia. Immediate plans call for the marketing of Thermo-Phos in California only because local demands exceed Permanente's present capacity.

In describing the use of Thermo-Phos, Dr. A. C. Byrns, director of research of Permanente Metals Corp., explained that it can be applied directly to the soil, but that the major proportion is employed in mixed fertilizers. Unlike superphosphate, the new product contains an appreciable amount of magnesium. Raw materials are phosphate rock from Idaho and serpentine obtained locally.

LURGI PROCESS FUEL PLANT SCHEDULED FOR UTAH

PLANS for construction of a plant in Salt Lake City to manufacture smokeless fuel from Utah coals were announced recently by Walter M. Russell, president of Utah Chemical & Carbon Co. Several types of smokeless fuels will be produced by the Lurgi process, and the firm expects to produce a large quantity of oils of importance in chemical markets. Harry W. Monahan, chief engineer and operating executive of the new company, stated that Utah coals are ideal for the Lurgi system and predicted that the firm's smokeless fuel will equal the best grades of Pennsylvania anthracite. More than 1.3 ton of coal would be required for each ton of briquets or char. J. L. Pritchard & Co. of Kansas City will have the contract for building the plant, but the site has not yet been selected. The company was incorporated by Grant MacFarlane, Salt Lake attorney and former president of the state senate.

CALIFORNIA SETS UP CHEMICAL ENGINEERING CURRICULUM

UNDER the direction of Dr. Wendell Latimer, dean of the College of Chemistry, the University of California at Berkeley is setting up a chemical engineering curriculum to meet the increasing needs of western industry for chemical engineers. The curriculum, being established in collaboration with the College of Engineering, is under the direction of Dr. Philip W. Schutz, formerly with Columbia University and the Manhattan District, as professor of chemical engineering. Dr. Schutz will be assisted by Dr. C. R. Wilke from Washington State College and by Mr. LeRoy Bromley, formerly with the Manhattan District. Further staff additions are anticipated as the curriculum is expanded and becomes more established.

At present, a four-year bachelor's curriculum and the master's degree are being offered in chemical engineering. The undergraduate course, in which unit operations are now receiving most emphasis, will use laboratory and equipment facilities of the College of Chemistry and the College of Engineering, but the degree will be given by the former. Graduate work, now limited to the master's degree, will be administered jointly by the two colleges.

"Pittsburgh"

SPECIALISTS IN CHEMICALS DERIVED FROM COAL, TAR AND BY-PRODUCT GAS

Unlocking the chemical treasure house of coal, and extracting and recovering its multifold components for the uses of science, industry and commerce, is the business of Pittsburgh Coke & Chemical Company.

Here modern plant facilities, earnest and foresighted research, favorable shipping location and advantageous sources of supply combine to assure you of dependable, uniform, quality chemicals.


Expanding volume and range of products and increasing capacities make *Pittsburgh* better able to serve you than ever. Our technicians will welcome an opportunity to discuss your needs.

"PITTSBURGH" Coke and Chemical Products

AROMATIC HYDROCARBONS:
BENZOL, TOLUOL, XYLOL, NAPHTHALENE
TAR ACIDS: PHENOL, CRESOLS
SULPHURIC ACID: ALL GRADES
TAR, PITCH and CREOSOTE
SULPHATE OF AMMONIA
TAR BASES: PYRIDINE, PICOLINES
SODIUM CYANIDE • SODIUM THIOCYANATE
ACTIVATED CARBONS

OTHER PRODUCTS:
NEVILLE COKE—EMERALD COAL—PIG IRON—
GREEN BAG CEMENTS—CONCRETE PIPE—LIME-
STONE PRODUCTS—IRON ORE

INQUIRIES INVITED



CHEMICAL SALES DIVISION

Pittsburgh Coke & Chemical Company

Grant Building • Pittsburgh 19, Pennsylvania

5 GAL. LUG
COVER PAIL.
OTHER STEEL
CONTAINERS,
3 GAL. TO 55 GAL.



INLAND STEEL CONTAINERS

**... experience and resources
insure container satisfaction**

Experience, skill, extensive resources,
and unexcelled manufacturing facilities,
combine to insure *quality* steel
containers, ideally suited to your particular
needs.



INLAND STEEL CONTAINER CO.

Container Specialists

4532 S. MEHARD AVE., CHICAGO 38, ILL.

PLANTS AT: CHICAGO • JERSEY CITY • NEW ORLEANS

and will be primarily a research degree. Special courses such as in petroleum and metallurgical engineering will be given by the respective engineering departments. The chemical engineering curriculum now has about 45 junior and senior students and about 25 candidates for the master's degree.

CHEMICAL ENGINEERING EDUCATION — CORRECTION

IN THE September columns of this department the statement was made that the University of Washington and California Institute of Technology were the only schools in the West having chemical engineering departments accredited by the American Institute of Chemical Engineers. This was obviously an error. The chemical engineering department of Oregon State College, Corvallis, has been accredited by the AIChE since October 1942. Under the guidance of G. W. Gleeson, dean of the School of Engineering & Industrial Arts and head of the department of chemical engineering, the staff of Oregon State College has made notable contributions in chemical engineering, both educationally and in the field of applied research.

RECENT PROCESS INDUSTRY PLANT EXPANSIONS

Salt—Construction of a \$500,000 addition to the plant of Leslie Salt Co., Newark, Calif., got under way recently to replace equipment of the Arden plant. The new unit will have an annual output of 100,000 tons; completion will require about six months.

Wood Flour—Specialty Wood Products Co. has begun operations of a new plant at Yardley, Wash., which has a capacity of 50 tons of wood flour daily. The product is used largely as a filler by eastern producers of plastic materials and asphalt roofing.

Process Equipment—Blaw-Knox Corp. of Pittsburgh, Pa., has purchased a 26-acre site north of Santa Clara, Calif., and intends to erect a \$1,000,000 plant to manufacture processing and road building equipment.

Insecticides—San Francisco Sulphur Co., Berkeley, Calif., a subsidiary of Stauffer Chemical Co., has been granted CPA permit to erect a \$57,000 new plant adjoining present facilities in Berkeley for increasing production of insecticidal sulphurs.

Wood Pulp—Construction to house an eighth digester and provide additional chip storage is under way at Rayonier's Port Angeles, Wash., pulp mill as part of the company's \$4,000,000 plant improvement program. The firm produces a high-grade cellulose pulp.

Refinery—Articles of incorporation of the Phoenix Refining Co., Phoenix, Ariz., have been filed and plans to build and operate an oil refinery announced. The proposed refinery will have a capacity of 5,000 bbl. of gasoline and 1,500 bbl. of asphalt daily. Crude oil will be piped from west Texas by Arizona Pipeline Co.

Precious Metals—Handy & Harman, New York, refiners and processors of precious metals, has announced that a new plant is being built in Los Angeles to serve the Pacific Coast. The new unit is expected to start operations within a month or so.

Superphosphate—Stauffer Chemical Co. has announced a \$145,000 expansion program at the Richmond, Calif., plant which will essentially double capacity of the unit to produce superphosphate. Construction is now getting under way. Stauffer, only producer of superphosphate on the West Coast, has a similar plant near Los Angeles.



If you have a problem in metal cleaning, electroplating, enameling, corrosion, acid-proof construction.....get in touch with the Pennsylvania Salt Manufacturing Company, *Chemicals*, 1000 Widener Building, Philadelphia 7, Pa. • New York • Chicago • St. Louis • Pittsburgh • Cincinnati • Minneapolis • Wyandotte • Tacoma

Since 1925

HILCO EQUIPMENT

has been purifying a wide variety of lubricating, fuel, and industrial oils

EQUIPMENT SERVICED BY HILCO in the Chemical Industry includes:

★ **VACUUM PUMPS**—lubricating and sealing oil maintained free from grit, sludge, acid, moisture and dissolved gases.

★ **COMPRESSORS**—kept free from carbon and varnish deposits.

★ **DIESEL ENGINES**—lube oil constantly kept in condition of new oil, greatly extending engine life; fuel oil filtered, promoting combustion efficiency.

★ **TRANSFORMERS**—insulating oil fully desludged, neutralized, dehydrated and deaerated without taking transformers out of service.

TYPICAL HILCO CONTINUOUS VACUUM PUMP OIL PURIFYING SYSTEM



Oil is purified after each pass through pump.



★ **THE HILCO OIL RECLAIMER** is a miniature refinery which by continuous operation removes oil contaminants from a lube system as fast as they are formed or introduced, thus maintaining the oil at new oil specifications.

★ **PROTECT YOUR INVESTMENT** in process equipment by keeping the lubricating systems clean. HILCO equipment is available to take care of all types of oil purifying problems.

THE HILLIARD CORPORATION

131 W. Fourth St., ELMIRA, N. Y.



WRITE TO-DAY!
FOR
FREE INFORMATION

THE HILLIARD
Corporation
ELMIRA, N. Y.
PLEASE SEND YOUR
BULLETIN NO. 98

NAME _____
COMPANY _____
STREET _____
CITY _____ STATE _____

NEWS FROM ABROAD

CHEMICAL EXPANSION PROGRAMS IN GREAT BRITAIN FACE LABOR AND PLANT SITE PROBLEMS

Special Correspondence

IN THE PAST twelve months most of the leading chemical companies in the British Isles have announced far-reaching extension and modernization programs. Imperial Chemical Industries, Ltd. has a provisional program of capital expenditure for the next eight years involving investments of over £40,000,000. Plans of companies with less extensive activities are proportionately smaller but not less ambitious. Courtaulds and Celanese are expanding their rayon and plastics production, Imperial Smelting and Fisons, pigments and fertilizers, Pinchin Johnson and Goodlass Wall, paint manufacture.

In the pharmaceutical and plastics trades many new ventures are under way; on penicillin plant alone more than £3,000,000 has been spent so far. Outside firms, like Distillers Co., the leading British alcohol producer, are entering the chemical field as producers. Specialty oil refiners and coal distillers are developing their chemical business. A new firm, Petrocarbon Ltd., intends to spend nearly £2,000,000 on a plant for extracting aromatic hydrocarbons from oil products in the next two years. Though precise figures are lacking, it seems likely that on the most prominent of these new chemi-

cal works a total sum exceeding £10,000,000 will be spent each year, possibly for a decade or longer.

These new plants are likely to revolutionize Britain's chemical industry. Some 10,000 additional workers will be needed annually merely to staff new factories, to say nothing of those needed to make up for natural loss of labor. The capital outlay of about £1,000 per worker envisaged in some typical new plants is substantially higher than what was usual before the war; as evidence of progressing mechanization of producing processes especially in the heavy sectors of the chemical industry it raises important problems of finance and labor policy. 'Cheap money' and mounting wages place a premium on labor-saving by costlier plant, especially if full-capacity production is assured but high depreciation rates due to the swiftness of technical advance largely offset this advantage. Nevertheless British chemical manufacturers favor mechanical methods; for the shortage of labor is expected to last for some time, chemical factories are not generally popular with women workers, and wages are unlikely to recede from their present high level. Shortage of labor also makes for

If

you use
or Distribute

PRESSURE REDUCING VALVES

for

- AIR LINES
- PAINT SPRAY EQUIPMENT
- AUTOMATIC OILERS
- DRINKING FOUNTAINS etc.

Consider CASH-ACME's continued acceptance by the nation's largest manufacturers and jobbers during the past twenty-five years, as indicative of their satisfactory performance.

See your Mill Supply dealer—ask for CASH-ACME Automatic Valves.


Bulletin No. 144
available on request.

CASH-ACME

A.W. CASH VALVE MFG. CORP.

6614 EAST WABASH AVE.
DECATUR ILLINOIS

EFFICIENT *Low Cost* DRYING



The General American Louisville Counter-Current Direct Heat Dryer (for operation at either high or low temperatures) offers chemical process plants a continuous, efficient, low cost means of drying many materials, such as:

Barytes
Ferrous Sulphate
Resins

Salt
Bone Black
Ammonium Sulphate

Sodium Sulphate
Di-Sodium Phosphate
Magnesium Sulphate
Bauxite

The Louisville Counter-Current Rotary Dryer is a rotating cylinder with lifting flights designed to shower the material efficiently across the whole cross section of the dryer cylinder. When suitable for the material to be dried, it has the advantages of low first cost and of attaining minimum residual moisture in the dried product.

General American builds other Louisville Rotary Dryers including: Steam Tube, Indirect Steam, Type "L" (semi-indirect heat), Parallel-Current and Indirect Direct Heat.

Write for bulletin No. 54 or ask one of our drying engineers to analyze your problem.

Other General American Equipment

FILTERS
EVAPORATORS
THICKENERS
CALCINERS
KILNS
TURBO-MIXERS
DEWATERERS
TANKS
TOWERS
BINS

General American

TRANSPORTATION CORPORATION
process equipment • steel and alloy plate fabrication

SALES OFFICE: 10 East 49th St.
Dept. 800 New York 17, New York

WORKS: Sharon, Pa., East Chicago, Ind.




OFFICES: Chicago, Louisville, Cleveland,
Sharon, Orlando, St. Louis, Salt Lake City,
Pittsburgh, Washington, D. C.

HYDROFLUORIC ALKYLATION For Aviation Gasoline

Florite^{*}

DEHYDRATION UNIT



Industrial Advances call for More Efficient Drying Agents

Equal or superior to other granular desiccants in drying efficiency and general performance, more economical in use because of longer life under the conditions of service involved, and lower in initial cost than most alternative materials, Florite^{*} has rapidly found its way into exacting processes where drying agents are employed. Hydrofluoric Acid Alkylation of light petroleum fractions, represented by the chart above, is a noteworthy example. Propane, butane, air, nitrogen, carbon dioxide, refrigeration compounds, and various other fluids are successfully dehydrated with Florite. The desiccant is capable of regeneration again and again by heating to 350°F.

Made from bauxite by special processes of activation and mechanical adaptation, Florite uses no highly critical wartime materials and is therefore fully available for any users' requirements. Correspondence is invited.

^{*}Trade Mark Registered.

FLORIDIN COMPANY, INC.

ADSORBENTS

Room 52

220 Liberty St., Warren, Pa.

dispersal of new plant, as firms hitherto concentrating on one locality have experienced difficulties in obtaining female labor and skilled men.

The tendency towards dispersal which is a feature of new plant construction at the consuming end of the chemical industry, in the pharmaceutical and cos-metical trades, but also in paint and fertilizer production, however is primarily due to increased costs of transport. Rail-way charges in particular have gone up substantially. Many firms can make use of alternative accommodation secured dur-ing the war. Besides, it has been found that dispersal helps to keep down stocks required to assure regular distribution. Preference for previously neglected areas is also partly due to availability of idle war factories which can be leased on favorable terms and to official advice con-cerning plant location; in these areas con-struction materials and building labor are usually not quite so short as in more active population centers. Building licenses for new factories are easier to obtain, and the local authorities on whom so much depends nowadays are more likely to be helpful.

SHORTAGE OF COAL

More crucial than labor shortages, trans- portation costs and construction licenses is the problem of assuring adequate coal supplies. It is widely believed that owing to larger calls from industry, reduced mine-head and trade stocks and lower out- puts, all factories will not be able to cover full requirements this winter. Some chemical works have followed the govern- ment advice and switched over to oil where coal is not indispensable, but the capital outlay for oil burners is about double that for coal burners. Other fac- tors also mitigated against change-over in boiler and power plant at short notice. It is already reported that some makers of heavy chemicals have had to cut produc- tion owing to lack of coal, and the Minis- ter of Fuel has appealed for a voluntary cut in industrial and domestic fuel and power consumption by 10 percent this winter.

If the winter is normally cold, output cuts will hardly be avoidable, and it is generally agreed that recruitment of out- side labor for the mines and other drastic expedients will not yield any early results. When the National Coal Board takes over the nationalized colliery industry at the beginning of next year, it will be faced with difficulties which must be tackled at once, and it is by no means certain whether the long-term problem of supply- ing coal in good quantity, in proper qual- ity and at reasonable prices will be solved to general satisfaction. The biggest chem- ical producer in the country is now pay- ing £3,500,000 more for its coal and coke than before the war. It needs little imagination to visualize the consequences of insufficient coal supplies and excessive coal prices for the chemical industry.

Although the need for economy in use of coal and the widest possible develop- ment of coal processing to save fuel is obvious, little progress has been made in modernization and extension of the coal distilling industry. Little has been heard of projects for the erection of new coke-



CORROSIVE CHEMICALS GET NO GRIP ON **DU PONT** POLYTHENE

For containers of all kinds, gaskets, cap liners, and tubing . . . the outstanding chemical inertness of Du Pont polythene is one of its chief advantages. Men who handle corrosive chemicals are constantly finding new uses for this versatile Du Pont plastic. But chemical inertness is not the whole story . . . far from it.

Polythene absorbs practically no water (0.005%). It is light in weight (specific gravity 0.92). Extremely tough and flexible at low temperatures. Tasteless . . . odorless . . . non-toxic, it contains no plasticizer. Can be injection- or compression-molded, extruded, calendered or heat sealed. Sure you have complete data on this unique thermoplastic? If not, write E. I. du Pont de Nemours & Co. (Inc.), Plastics Dept., Room 1011, Arlington, N. J.

**AT ROOM TEMPERATURES
THERE IS NO KNOWN SOLVENT
FOR DU PONT POLYTHENE**




Du Pont manufactures polythene molding powder.
Commercial extruders convert polythene into the form of:



DETECT FUEL WASTE IN 40 SECONDS

with the....

FYRITE CO₂ INDICATOR



The FYRITE makes accurate CO₂ analysis of the flue gases easy—and CO₂ percentage is the direct index of fuel wasted up the stack due to needless excess air being drawn into the furnace. There is nothing tricky or complicated about a CO₂ test with the FYRITE—requires no skill or special training—there are no valves, clamps, or leveling bottle to manipulate—one test takes less than a minute. More than 13,000 in successful use.

Write for Bulletin 703.

\$24.00

Complete with rubber aspirator bulb, industrial type flue filter, and carrying case.

BACHARACH INDUSTRIAL INSTRUMENT CO.
7008 BENNETT STREET • PITTSBURGH 8, PA.

**Also Available!
OXYGEN INDICATOR**
for DIRECT Oxygen Analysis
Employs FYRITE principle...
accuracy not affected by tem-
perature and atmospheric condi-
tions, or by presence of other
gas in sample.
Ask for Leaflet 700

VIKING PUMPS

WIDE OPEN

For YOUR Inspection

Know VIKING PUMPS and you know why they are rugged... simple... dependable. There are no blades, springs, gadgets, timing gears or a mass of other devices required to make them work or help improve and retain efficiency.


The VIKING is simple... just 2-moving "gear within a gear" parts make up the pumping principle. That is why they work so well for pumping any clean liquid regardless of viscosity. They are self priming without pulsation... deliver against discharge pressures up to 50-100-200- or 500 psi, depending upon construction and applications.

Know VIKING and what they can do for you. Send for free bulletin 463C today.



See Our
Catalog In
SWEETS

VIKING PUMP COMPANY
CEDAR FALLS, IOWA



oven plant since the end of the war, and the very progressive low-temperature carbonization enterprise has not formulated any new plans this year. On the other hand, new designs promising great economies in coal are in the blue-print stage. Private managements are unwilling to risk large new investments while nationalization is pending and its repercussions on carbonization works scheduled to remain outside the Coal Board's sphere of control are uncertain.

In these circumstances it is worthy of special note that the largest single new enterprise yet announced is the ICI £10,000,000 heavy organic chemicals plant for which a site is now being prepared at Wilton near Middlesbrough; it thus appears that the long-term outlook as regards coal supplies in this important field is viewed with confidence. Even those whose aim it is to build up an organic chemical industry on imported petroleum admit that the coke-oven industry is likely to remain the chief raw material support of this branch of production. The big plant which Petrocarbon Ltd. intends to erect at Partington near Manchester for a throughput of 50,000 tons (later possibly to be doubled) of naphtha or gas oil and perhaps shale oil and low-temperature carbonization products is not expected to do more than make a small contribution to Britain's supply of aromatic organic chemicals, which however will be doubly welcome because the output of different products can be varied to meet changes in market requirements and the residual gas mixture contains a high proportion of olefines for further treatment.

WAR PLANT CONVERSION

As construction of new factories meets with considerable difficulties owing to the building industry's preoccupation with dwelling houses, there has been comparatively more news concerning conversion of war factories to peacetime use than there is regarding entirely new works. A big plant just opened by Dunlop at Speke, Liverpool, is perhaps typical of larger factories of this type. In a relatively short time Dunlop adapted this huge factory to its own needs. Even so the capital outlay was several million pounds sterling for a plant which now employs 4,000 workers and will eventually give work to 6,000-7,000. Straight flow production has been assured by maximum use of mechanical devices (all mixing operations and the weighing of carbon and lamp black, etc., are carried out by machine), but difficulties are still being experienced through shortage of raw materials, even though rubber itself is not in short supply. The plant is capable of processing and manufacturing operations permitting continuous production from the crude rubber to finished tires and footwear.

Liverpool is also the location of other new chemical works, including the first deep-fermentation penicillin plant which is operated by Distillers Co. Port towns have been chosen for many new chemical factories, especially in the heavy section where access for ocean-going vessels is of great advantage. Lancashire in the northwest and the Newcastle and Dur-



Stearns-Roger
Agitators

**FOR THE CHEMICAL AND
METALLURGICAL INDUSTRIES**

*Simplicity in
Digestion and
Precipitation*

Stearns-Roger
THE STEARNS-ROGER MFG. CO. DENVER, COLORADO

**EVERYWHERE
IN
VACUUM PROCESSING**



KINNEY

HIGH VACUUM PUMPS

FOR HIGH PUMPING SPEED AND LOW ABSOLUTE PRESSURE

In the new vacuum coating units now being developed by Distillation Products, Inc., Rochester, N. Y., two 110 cubic foot Kinney pumps are used for rapid pump down and backing the Distillation Products, Inc., diffusion pumps. The illustration also shows four Kinney Vacuum Tight Valves which are used on all types of systems where "no leakage" is of utmost importance. Everywhere . . . in this country and abroad . . . Kinney High Vacuum Pumps meet the heavy demands of large scale process operations — exhausting lamps and tubes, sintering metals, producing penicillin, and performing countless other operations in modern vacuum processing. Kinney Single Stage Vacuum Pumps produce and maintain low absolute pressures to 10 microns; Compound Vacuum Pumps to 0.5 micron.

Send for Bulletin V 45.

KINNEY MANUFACTURING CO.

3551 WASHINGTON ST., BOSTON 30, MASS.

NEW YORK • CHICAGO • PHILADELPHIA • LOS ANGELES • SAN FRANCISCO

FOREIGN REPRESENTATIVES

General Engineering Co. (Radcliffe) Ltd., Station Works, Bury Road, Radcliffe, Lancashire, England

Horrocks, Roxburgh Pty., Ltd., Melbourne, C. I. Australia

W. S. Thomas & Taylor Pty. Ltd., Johannesburg, Union of South Africa

We also manufacture Liquid Pumps, Clutches and Bituminous Distributors

ham areas in the northeast are favorite regions for new chemical works also because of the availability of coal and labor, while firms with principal factories in southern towns, at Nottingham, Coventry and London, tend to spread their manufacturing activities.

One interesting aspect of the location of new chemical factories is the provision for later extensions and for customers who may wish to erect plants near their raw materials source. Availability of both coal and salt near densely populated areas close to the sea gives a natural advantage to some English counties, but in other cases importers of foreign commodities, such as mineral oils, pyrites and zinc concentrates, and oilseeds, have been able to attract manufacturing industries because of cheap byproducts they are able to offer for other chemical manufactures. In some instances government support has caused chemical manufacturers to build plant in otherwise neglected areas, thus providing an outlet for local raw materials and labor; the young Scottish seaweed industry is an example of the possibilities opening up, but also of the unexpected difficulties encountered, when official encouragement is given to the development of indigenous raw material resources.

It is probably true that at no time between the two wars was there so much initiative and long-term planning in Britain's chemical industry as there is now. Whether all these new factories will be able to withstand the severe climate of international competition when the present sellers' market comes to an end remains to be seen. It is to be noted that none of the factories are meant to work exclusively or predominantly for exports. Their basis will be the home market, but their geographical position and production conditions will enable them to avail themselves of opportunities in foreign markets.

Some British chemical manufacturers hope to take over a substantial part of the export business of German prewar manufacturers, and the export returns so far seem to justify their confidence. It may be said that compared with other British industries the export business of the chemical trades rests on sound foundations. More recently, however, increases in cost elements have forced many makers to revise their calculations, and this may have adverse repercussions. For the time being the outlook remains good.


BRITISH PLANT WILL USE CATAROLE PROCESS

AN ESTATE of 700 acres at Partington, adjoining the Manchester Ship Canal, has been purchased by Petro Chemicals, Ltd. a new company formed to produce chemical materials from petroleum. The venture is financed by \$7,200,000, of which one half has been subscribed by the Finance Corporation for Industry and the other half by a group of private financial institutions. The plant, which will produce from oil a wide range of liquids and gases used in making of paints, dyestuffs, plastics, and other products, is intended to form the nucleus of a large industrial estate composed mainly of plants using some of its products. The new plant will be based on the "Catarole" process.

WeldELLS

for example:

Permanent identification markings on every fitting



JUST one of a number of reasons why so many piping people prefer WeldELLS is that every fitting has its size and thickness marked on it in such a way that it will stay there.

The expense we go to in providing legible and permanent marking pays dividends to users in handling and storing WeldELLS in the shop and on the job. It eliminates "wrong size" errors; saves time and trouble.

Yes, it's another example of extra steps we take that mean extra value to you in WeldELLS. Add it to the features listed opposite and you see why WeldELLS "have everything" . . . why they give you the means of doing the job as well as it can be done, as fast as it can be done, and, therefore, as economically as it can be done.

WeldELLS alone combine these features:

- Seamless—greater strength and uniformity.
- Tangents—keep weld away from zone of highest stress—simplify lining up.
- Precision quarter-marked ends—simplify layout and help insure accuracy.
- Selective reinforcement—provides uniform strength.
- Permanent and complete identification marking—saves time and eliminates errors in shop and field.
- Wall thickness never less than specification minimum—assures full strength and long life.
- Machine tool beveled ends—provides best welding surface and accurate bevel and land.
- The most complete line of Welding Fittings and Forged Steel Flanges in the World—insures complete service and undivided responsibility.

TAYLOR FORGE & PIPE WORKS

General Offices & Works: P.O. Box 485, Chicago
 New York Office: 50 Church Street
 Philadelphia Office: Broad Street Station Bldg.
 Los Angeles Office: Subway Terminal Bldg.

have everything

What's new at



De-ionized Water!...

(the modern low-cost equivalent of distilled water)



TO OBTAIN PURE WATER for certain of its processes, the New York Quinine and Chemical Works, Inc. (NYQ) operates this ILLCO-WAY De-ionizer (600 gph) in its Brooklyn plant... another example of how leading concerns rely on De-ionized Water for quality manufacture.

In hundreds of efficient plants today, modern compact ILLCO-WAY equipment is producing pure water—the equivalent of distilled water, but costing 90% to 99% less than heat-distilled water!

That's the remarkable saving you make with ILLCO-WAY De-ionizing equipment. Water produced is *uniform* at all times... is daily meeting exacting standards in pharmaceutical, chemical, cosmetic and industrial plants.

Units are designed to meet your needs; flow rates from 12 gph (portable unit) up to 500,000 gph or more... Investigate this process today—write for latest literature.

ILLINOIS WATER TREATMENT CO.

844-11 Cedar St., Rockford, Illinois
7310-811 Empire State Bldg., New York City

WATER TREATMENT ENGINEERING



SCARCITY OF RAW MATERIALS RESTRICTS ACTIVITIES IN CHEMICAL INDUSTRIES OF SOUTH AFRICA

Special Correspondence

WORK HAS started on extensions, estimated to cost nearly £1,000,000, to the African Explosives and Industries fertilizer factory at Umbogintwini in Natal. It will be one of the biggest in the world when completed at the end of next year. Output will be increased to 320,000 tons of superphosphate—more than four times the 1938 output, and it is expected that South Africa will have 500,000 tons of fertilizer available by the end of next year. The balance of 180,000 tons will be produced by the company's factory at Somerset West, near Cape Town. When the war curtailed imports of fertilizer, South African factories reached a production peak of 300,000 tons, which cannot supply current needs.


A recent private investigation into the possibilities of extracting oil from South African shale deposits by the electrothermic process developed by the Swedish engineer, Dr. F. Ljungstrom, revealed that in certain circumstances the process could be used economically in the Union. A statement issued by the Swedish Consulate in Pretoria says it appeared that seams of oil-shale in the Transvaal were covered by a very thick layer of sandstone. A depth of about 55 yards had to be penetrated before borings reached the oil-bearing shale, which was at the most about 12 yards thick. Dr. Ljungstrom did not consider this exceptionally favorable for the process he had

developed. The covering layer should not be more than 12 to 18 yards thick, and a heavier seam of shale of from 18 to 23 yards would be desirable. But the average percentage of oil in the Transvaal shale was estimated at 10 to 15 percent, against only 5 percent in Sweden, and he therefore considered it possible to start economic production based on 12 yards of shale covered by about 23 yards of sandstone.

If the oil shale in the Transvaal yielded, when gasified, equal calorific values of gas and oil, it should be possible to produce all the electric energy needed for Dr. Ljungstrom's process of heating the shale by using the gas in a power station. The report states: "Dr. Ljungstrom considers that to form a definite opinion of the economic possibilities of oil production from the shales of the Transvaal it would be highly desirable for a closer geological investigation to be carried out."

The possibility of establishing an organic chemical industry in the Union was discussed in a paper by Dr. S. R. Haas, chemical engineer, read at the conference of "Science in the Service of South Africa" at the University of the Witwatersrand. He said at the moment South Africa had only two branches of the organic chemical industry which were well developed. These were the manufacture of explosives and of chemicals based on alcohol and by-

INCREASE YOUR BULK BAGGING PRODUCTION with the CONSOLIDATED Model 84 Super-Bagger




USERS REPORT INCREASES UP TO 50%


Write for information

CONSOLIDATED PACKAGING MACHINERY CORP.
BUFFALO 13, N. Y.


PICTURE OF A CASTING FAILURE



-that will never happen!





• There's a deeply hidden flaw here
—an imperfection that might cause
trouble later if it went undetected now.

A Sivyer radiographic picture caught
it. Now it can never wear the
Sivyer diamond  —for this is the
mark of sound castings.

In other ways, too, Sivyer steel castings must pass
the test. They must possess close dimensional accuracy
... be true to pattern contour and shape ... have an
extra degree of finishing for less processing on your part.

These are the reasons critical buyers specify Sivyer
castings for more satisfactory, more lasting service.

SIVYER STEEL
CASTING COMPANY
MILWAUKEE  CHICAGO 

For Better Filtration

**SHRIVER
FILTER
PRESSES**

under any conditions of



**CORROSION
TEMPERATURE
PRESSURE
DELIVERY**

No filtration equipment matches the Shriver Filter Press for versatility of application, for solids recovery, clarification, extraction, thickening, washing or drying of cake. None meets its breadth of design for size, capacity, ability to meet the chemical and physical requirements of the material to be processed or the conditions of operation.

Shriver Filter Presses may be built of any metal, rubber-covered metal, rubber, wood or plastics; for hot or cold filtration, at any pressure to 1000 p.s.i., of any normal, heavy, thick or viscous material at any desired rate.

Shriver steam-heated, corner (eyed) feed, closed-delivery, washing, leak-proof filter press with aluminum hollow (jacketed) plates and frames.

Shriver corner (eyed) feed, close delivery, washing filter press with stainless steel plates and frames.



**This New Free Book
Revised-Up-to-Date
Better than Ever. Write**

T. SHRIVER & COMPANY, Inc.

802 Hamilton St. • Harrison, N. J.



products. The remainder of the organic chemical industry was actually only a "mixing" industry which depended on materials from overseas. There seemed to be a reluctance to discuss the idea of an industry based on indigenous raw materials. Objections were that the country had a limited consuming power for such products and that coking coal deposits were small. The answer lay in creating a demand for the products, and using the large deposits of low-grade coal. The Fischer process had proved that low grade coal could produce a full range of organic compounds—even including, before the war, the production of petrol at 6d. a gallon.


Owing to the action of the Soviet Union in buying all Argentina's supplies of linseed oil, and the trade ban with India, South Africa faces a serious shortage of paint in the next few months. Supplies of linseed oil are low and the price rose by 2s. 6d. a gallon recently. It is said that the Russians sent two tankers to the Argentine and bought up 20,000 tons of linseed oil. Uruguay manufactures linseed oil, but South Africa cannot obtain those supplies because Uruguay is in a United Kingdom purchasing area.

SOAP PRODUCTION CUT

South Africa's largest soap makers, who have their main factory in Durban, have had to cut production by nearly 50 per cent owing to the shortage of oils and fats. This information was given by the chairman of the company in Durban. South Africa used to get most of its oils and fats from India and the Belgian Congo, he said. Now India, owing to its own shortage, had stopped exporting groundnuts. The Belgian Congo supplies go into a central pool and are allocated by the Combined Food Board in Washington. South Africa's allocation has been cut sharply. Raw materials for soap and foodstuffs were largely interchangeable. A large proportion intended for soap-making had been diverted and after being refined and treated were used for edible fats. The company is operating its own rationing scheme. All customers have had their orders cut down in proportion to the amount the factory is able to produce.

A new promotion is the National Match Co. Ltd., with an authorized capital of £250,000 in 1,000,000 5s. shares, of which 600,000 have been issued and 160,000 are being offered for public subscription at 8s. 6d. Apart from its interest in the manufacture of matches the company will have an interest in another company formed to manufacture cardboards and insulating boards.

All stocks of poison gas in the Union have been destroyed. With the destruction by burning in blast furnaces of the remaining gas bulk stocks and the dismantling of gas equipment at the two factories, the only mustard gas now anywhere near the Union is the consignment dumped off the Port Elizabeth coast. Chemical warfare plants in the Union were constructed during the war for the British Ministry of Supply for the purpose of manufacturing poison gas. It took 14 months to destroy the mustard gas stocks, a hazardous operation carried out without any casualties.



Century Splash Proof
Squirrel Cage Motor



Century Splash Proof
Slip Ring Motor



Century Splash Proof Direct
Current Motor

Century Splash Proof Motors

**PROTECTED—
FROM A TRICKLE OF
LIQUID TO THE FULL
FORCE OF A HOSE
DURING PLANT WASHDOWN**

From a trickle of dripping liquid to the full force of a hose during a plant washdown, Century Splash Proof motors will keep the vital parts of the motor dry — keep them in service longer. They eliminate unnecessary production losses due to dripping or splashing liquid or falling solids which might otherwise damage the vital parts of the motor.

Century Splash Proof motor windings are insulated to resist the damp atmospheres found where splash proof design is recommended. Special insulations are often provided

for unusual concentrations of acids and alkali. This gives you additional protection against costly work stoppages.


These motors are ideal for installations on such equipment as pumps, conveyors, agitators, washers, dryers, and many others often encountered in food, chemical, and textile processing. In addition to splash proof designs Century offers a wide range of types and sizes from 1/20 to 600 horsepower.

Specify Century motors on all your electrically powered equipment. They are engineered to the functional characteristics of the machine they drive to assure top performance.



CENTURY ELECTRIC CO. 1806 Pine St., St. Louis 3, Mo.

Offices and Stock Points in Principal Cities



Pennsylvania Power & Light Company
Hauto Steam Electric Station

The new addition to the Hauto Station pictured here is another noteworthy installation made by the Daugherty Company — long experienced in the fabrication and erection of power and process piping. In this new addition, two boilers operate at 1325 p.s.i. and 930° F. to serve a turbo-generator of 31,250 KW capacity.

Daugherty Company offers these facilities for power and process piping work: FABRICATION of high-pressure, high-temperature piping including alloy tubing. EQUIPMENT for field stress-relieving and radiographic inspection. WELDERS qualified for all classes of work. SUPERVISION by an unexcelled metallurgical, engineering and construction staff.

Daugherty Company, Inc.

502 Union National Bank Building, Youngstown 3, Ohio

PIPING CONTRACTORS for the POWER and PROCESS INDUSTRIES

Large-scale experiments initiated by the Minister of Health are taking place at commercial mills on technical problems involved in fortifying maize-meal with food yeast. If success is achieved steps will be taken to produce sufficient food yeast to fortify maize-meal on a large scale. The secretary for public health says these experiments and the requirements of hospitals and allied institutions, which are also experimenting on the best methods of its utilization, will absorb all the food-yeast surplus for some time to come.

The fertilizer shortage is still serious with little hope of immediate relief, said the Controller of Fertilizers. There is a possibility of increased allocations of phosphates next year for those who apply, he said. No nitrates had reached the Union since July. The potash shortage also was serious. The shortage of fertilizers was aggravated by the shortage of bags.

SEAL OIL REFINERY

As a result of investigations carried out at the Cold Storage and Dehydration Laboratories in Cape Town, a pilot plant is being installed in the new sealing vessel Gamtoos to extract refined oil from the blubber of seals. It is intended to solve equipment that will enable a high-grade seal oil to be refined on board the ship. This oil would be suitable for the manufacture of margarine as well as for cooking purposes. It is also hoped that a process will be found for reducing the seal carcasses to cattle feed or fertilizer. New products to emerge recently from the government dehydration headquarters in Cape Town are dehydrated soup pulps and puffed dehydrated potatoes.

Addressing members of the Cape Industrialists' Association recently, an official of the South African Bureau of Standards said a national committee was being set up to investigate standardization of containers. He said the bureau's laboratories had been established, the meteorology laboratory was in use, and part of the chemical laboratory was expected to be in operation in the near future. It also was planned to set up laboratories for testing electrical meters, automobile batteries and electric lamps.

Increasing emphasis on prefabrication as the only practical solution to the housing program has stimulated interest in the potentialities of vermiculite, one of the most promising materials found in commercial quantities in South Africa. The manufacture of vermiculite products was started at Industria, Johannesburg, by South African Vermiculite and General Industries, registered in May, 1944, with a capital of £50,000.

It was considered that vermiculite, which is sound-proof, heat-proof, rot-proof and vermin-proof, had an important role in the rising demand for lightweight concretes, prefabricated materials and plastics of all kinds. Production was concentrated initially on flooring, refrigeration and other insulation products, and refractories, while attention also was devoted to the large-scale production of pre-cast, lightweight concrete slabs. Vermiculite is the basis of a prefabricated housing project undertaken by Kimlite Industries, also of Johannesburg. After a large amount of experimental

For pointers on Heat-Treating Stainless

consult **EASTERN!**

Softening 18-8? How long should 10-gage E-S 18-8 (Type 302) sheet be held at heat to soften it between deep-draws? Can it be heated in a salt bath?

Oil-Quenching? Will oil-quenching make E-S 18-12 Mo stainless (Type 316) plate pick up carbon and lose corrosion-resistance?

25-20 Hardenable? To what Brinell can we harden E-S 25-20 chrome-nickel steel (Type 310) blades by heat-treatment? Can they be case-hardened?

Stress-Relieving? What heat-treatment do you recommend for stress-relieving titanium-stabilized stainless (Type 321) sheet after welding?

Burn Off Oils? Will the soluble oils used in drilling E-S 18-8 (Type 304) plate burn off without affecting it when the plate is heated to anneal the hard spots?

Minimizing Scale? How can we reduce scale formation when annealing light E-S 17-7 stainless (Type 301) sheet? We now hold it at 2,000° F. for 15 minutes

When questions like these come up in heat-treating stainless sheet or plate, take advantage of Eastern Stainless technical service. Stainless isn't temperamental, but procedures must be correct for it to give its best service. Send us your question—no matter how simple or complex—and you'll soon find that Eastern has the right answers where stainless steel is involved. And you can get those answers fast—by phone, telegram, or return mail, as you wish.

Many of the answers are already at your fingertips when you have a copy of our catalog, "Eastern Stainless Steel Sheets." Write for one today.

EASTERN STAINLESS STEEL CORPORATION

BALTIMORE 3, MARYLAND

JM Leo E-1.1

**Ask
Eastern
for the
Answer
when
Stainless
is the
Question**



EASTERN STAINLESS

VISIT EASTERN STAINLESS STEEL CORPORATION AT BOOTH NO. B-185, NATIONAL METAL CONGRESS, ATLANTIC CITY

SHORTEST TIME FROM IDEA TO PRODUCTION

of synthetic-organic chemicals, pharmaceuticals, fermentation products, foods, may well lie in calling upon Hicks resources. We have a wealth of information and performance data on such production, available to clients, which, with the flexible Hicks organization for engineering, design, fabrication, procurement and construction, adds up to minimum time in realizing a product idea.

Your project may call for test tube to commercial production service or require only a changeover or addition to existing plant and equipment—either will receive the same specialized thought and effort from the Hicks organization. And, in either case you can be sure that Hicks work will be authoritative and complete down to the last detail.

If you have a product idea call for Hicks. A preliminary interview—no charge—may point the way to its profitable development. Telephone or write S. D. Hicks & Son Co., 1671 Hyde Park Ave., Boston 36, Mass.

Hicks
CHEMICAL & PROCESS
ENGINEERING

SEALED *Against* FUMES

No. 5421

For handling concentrated Sulphuric and other acids, difficult to seal by stuffing box packing...TABER Vertical Pumps is a logical answer.

Since liquid is not in contact with the Taber stuffing box there is no leakage.

Taber Vertical Pumps are sturdily constructed for mounting in processing or storage tank, and to operate in a vessel sealed against fumes or gases.

PLEASE WRITE ON YOUR
LETTERHEAD FOR CONCISE TABER
Bulletin V-837

TABER PUMP CO. ESTABLISHED 1859
294 ELM STREET BUFFALO 3, N. Y.

TABER PUMPS for Higher Practical Performance



work, Kimlite Industries has developed and patented suitable binding materials which, mixed with vermiculite, give a block or slab with high crushing strength, high heat insulating value, and when suitably surfaced, weather resistance combined with attractive appearance.

A big new abattoir planned for Johannesburg, as a result of recommendations made by the commission which investigated slaughter houses and cold storages throughout the Union in 1944 and 1945, is likely to engage experts from overseas to advise on the making of valuable drugs and medicines from the various glands recovered from slaughtered stock.

Fears that diminishing coking-coal resources might necessitate a retardation in local iron production have been proved groundless. Investigations into methods in use in Sweden since 1926 for the production of iron direct from its ores, without the use of coke, indicate that South Africa need have no qualms about producing to the limit of her capacity, for the improved direct reduction methods make use of ordinary coal, colliery slack, or anthracite, none of which need be converted to coke before use. The supplies of coking coal in the Union are very limited, and consequently increasing interest is being shown in these iron and steel developments.

The possibility of khaki bush, regarded as a noxious weed, being cultivated in South Africa, is envisaged by a Pretoria research chemist, who has perfected a method of recovering oils from the weed. He stated that he had heard that some farmer made a very effective dip from khaki bush by boiling green weed in water and using the infusion in the cattle dipping tank. Following up this clue, he found the plant contains an oil which insect pests, such as ticks and fleas, will avoid. He found that by a treatment with benzene, followed by distillation, the oil can be recovered, and that it formed a powerful insecticide. Further experiments revealed this oil as possessing remarkable frothing properties.

SWISS INSTITUTE TO TEACH CHEMICAL ENGINEERING

Last spring the pharmaceutical concern, F. Hoffman-La Roche & Co., Basle, Switzerland, celebrated its fiftieth anniversary. This coincided with the half century jubilee with the company of Dr. Emil C. Barell, its president and chairman of the board of directors. The firm was established by Fritz Hoffman-La Roche who was its president until his death in 1920. Then Dr. Barell assumed the presidency and under his guidance the firm grew to be not only the oldest but also the largest concern in its field in Switzerland with affiliates in most countries throughout the globe.

Dr. Barell, who for the past five years has been connected with company's plant in Nutley, N. J., returned to Switzerland for the double celebration and made the occasion memorable by setting up two funds, one with a capitalization of one-half million dollars to offer financial aid to scientists at Swiss universities for group research on special problems in pharma-




Old Reliable Red Band says—


*Grain goes to bed
on an endless chain!""**



1 Early American settlements had community granaries like those of Biblical times for winter storing of grain. In 1834, the first modern grain elevator was built in Buffalo. By 1866, bulk handling of grain was an established industry.



2 Chains of buckets were run, by cumbersome ropes and countershafts, from one central power source on the ground floor. In 1896 came the biggest improvement to date—individual motors were developed to drive each conveyor unit separately.



3 Today, with electrical horsepower, a Buffalo grain elevator can unload grain from lake carriers at the rate of 85,000 bushels an hour. Howell has been building specialized motors for grain elevators and other industries since 1915.

Have you a hard job for Horsepower?

Perhaps you have a process where extremely high or low temperatures exist—excessive moisture—high starting torque—or just a real tough job for a motor. Then get a protected industrial type motor that's built to "take it."


Here's why industrial type Howell Motors stand up:

- (1) Precision-built of finest materials, with copper or bronze rotors, and completely insulated.

- (2) Smooth-operating because statically and dynamically balanced.

- (3) Designed for the toughest tasks in industry—consequently better-performing on *all* jobs.

See your nearest Howell Representative for your needs in specialized or standard motors up to 150 h.p. Remember, you pay no more for industrial type Howell Motors—and you always get top quality for your money.



Howell Enclosed, Fan-Cooled Motor—Type K, available through 125 h.p. Also a wide range of other Howell industrial type motors up to 150 h.p.

HOWELL MOTORS

HOWELL ELECTRIC MOTORS CO., HOWELL, MICH.

Manufacturers of Quality Industrial Type Motors Since 1915



Be Sure it's *Tannate*



Tannate flat belt short center drives assure correct belt tension at all times—regardless of load, centers or unusual conditions; proper tension is automatically maintained. This means longer service life for your equipment as it is relaxed between peak load.

The Tannate leather belt has not only a very high coefficient of friction but also a great pliability that helps keep machines running at top speeds.


Tannate leather belting is treated to resist moistures, oil and weak acids. It has unusually high tensile strength which contributes toward increased service life and reduced maintenance expense . . . and lower end cost for your belting.

With Tannate flat belt short center drives, center distance adjustments can be made while the drive is running; production goes on smoothly without interruption.

J. E. RHOADS & SONS

35 N. SIXTH ST., PHILADELPHIA 6, PA.

NEW YORK • CHICAGO • ATLANTA



RHOADS

Tannate-Rockwood
SHORT CENTER DRIVE

chemical research; the other, amounting to one-quarter million dollars, for "The Emil Barell Fund for the Training of Chemical Engineers" Money from the latter fund will be used to establish a course in chemical engineering at the Swiss Institute of Technology in Zurich, the course to be based upon the American pattern.

DUTCH CHEMICAL INDUSTRY GIVEN FINANCIAL AID

UP TO THE end of September, the Netherlands Bank for Reconstruction had granted credits in the amount of \$1,935,000 to the Dutch chemical industry. The Bank, similar to the RFC in the United States is aiding in the rehabilitation of Dutch industry. But aid is being provided by participation with private firms, rather than by the nationalization of the country's industries as in some other European states.

The Reconstruction Bank (Finance Corporation for Netherlands Economic Reconstruction, Limited) was established in the Hague on October 31, 1945, with resources provided by the Royal Netherlands Treasury, the Netherlands Bank (since nationalized), the big joint-stock and private bank, the two central agricultural banks, and by a large number of insurance companies, investment trusts, savings banks, and pension funds.

Primary purpose is to provide funds for rebuilding war-shattered industries, for normal re-equipment, expansion and development, and for new enterprise. Additionally, the bank acts on behalf of the Treasury in making government war damage payments. Its field of activity extends to all aspects of trade, commerce, and industry both in the metropolitan and overseas territories, but in practice it confines itself largely to manufacturing and the primary industries.


Total credits granted amounted to \$17,600,000 in September. A total of \$26,400,000 had been distributed by the same date on account of war damage claims payable to the government. The credits on which agreement is about to be reached, plus financial aid requested recently, amount together to \$43,000,000, which suggests that within several months the total transactions of the Reconstruction Bank may top \$85,000,000.

One of the bank's chief contributions is in stimulating industries designed to supply home and export markets which were formerly dominated by German goods. Textiles and dyestuffs have received particular attention.

American interests have also been active in the expansion of Dutch industry. B. F. Goodrich Co. has completed arrangements for a factory with an annual output of 100,000 tires, while U. S. money is reportedly involved in the recent establishment of the Netherlands' first plastic industry.


ADVISER TO CZECHOSLOVAKIA CHEMICAL INDUSTRIES

ANNOUNCEMENT is made by the London office of McGraw-Hill World News to the effect that Dr. George Lewi, A.F.C.D.I., industrial consultant, London, has been appointed chemical advisor for



Properties of ether and nitrile—combined

Isopropoxypropionitrile



Isopropoxypropionitrile is a comparatively colorless liquid with a boiling point of 82-86°C. at 2.5mm. Hg. It is readily soluble in alcohols, benzene and ether, but only slightly soluble in water. It combines the chemical and physical properties of ethers and nitriles and is potentially valuable as an intermediate in the preparation of numerous compounds.

The usual reactions of nitriles can be carried out which lead

to the formation of the amide, acid, ester, imino-ether, imido-halide, and amidines. The amine can be prepared by hydrogenation. The combination of ether linkage and cyano group suggests the use of this compound as a solvent for certain applications.

Isopropoxypropionitrile is currently available in research quantities from our pilot plant. Should your problem indicate the use of other alkoxypropio-

nitriles, we shall be pleased to discuss their availability with you.

For samples and complete technical information write Section ND, Synthetic Organic Chemicals Department, American Cyanamid Company, 30 Rockefeller Plaza, New York 20, N. Y.

Other Cyanamid Nitriles

Glycolonitrile	HO-CH ₂ -CN
Lactonitrile	CH ₃ -CHOH-CN
Ethylene Cyanohydrin	HO-CH ₂ -CH ₂ -CN
Acrylonitrile	CH ₂ =CH-CN

SAMPLES AND TECHNICAL DATA

AMERICAN
Cyanamid
COMPANY
Industrial Chemicals Division



American Cyanamid Company
Section ND, Synthetic Organic Chemicals Dept.
30 Rockefeller Plaza, New York 20, N. Y.

Gentlemen:

☐ Send me sample of Isopropoxypropionitrile ☐ Send technical data sheet

Name _____

Position _____

Company _____

Address _____

THE SUPERIOR CATALYST

for EDIBLE OIL and FAT HYDROGENATION

SELECTOL A

SELECTOL A is a highly active and selective catalyst for the hydrogenation of refined edible oils and fats. Tests have shown that it has about 50% greater activity than other catalysts (activity determined by hydrogenating oils with equal amounts of the catalyst and measuring the iodine value change in a fixed period of time).

SELECTOL A is especially effective for low temperature hydrogenation of fats and oils where the highest degree of selective hydrogenation is desired.

For your conclusive confirmation of the superiority of **SELECTOL A** catalyst, we shall be pleased to send you—at no cost—a generous sample for testing in your laboratory.

Drew consultants are available at any time to discuss your particular catalyst problem—and see that you are supplied with the catalyst best suited for your individual needs. Just fill out the handy coupon—our representative will call promptly.

SELECTOL A is packed in removable-top metal drums—500 lbs. net weight—and contains 17 to 19% active metal content suspended in semi-liquid edible oil.

E. F. DREW & CO., Inc.

(Catalytic Chemicals Division)

Main Office: 15 E. 26th Street, New York 10, N. Y.

Factory and Laboratories—Boonton, New Jersey

SELECTOL A
is now being used by some of the largest oil processors in America.

RESISTOL A

—a companion product of **SELECTOL A**—is used in the hydrogenation of inedible oils.

E. F. DREW & CO., Inc.
15 E. 26th Street, New York 10, N. Y.

Please send sample of **SELECTOL A** ☐

Please send sample of **RESISTOL A** ☐

Have your representative call ☐

NAME _____

COMPANY _____

ADDRESS _____

the United States and the British Empire to the directorate of the nationalized chemical industries of Czechoslovakia. David Lee, A.B.I.C., formerly personal assistant to the controller of chemical defense development at the Ministry of Supply, is now associated with Dr. Lewi.

LARGE AMMONIUM SULPHATE PROJECT IN INDIA

CONSTRUCTION is about to get under way on the huge \$30,000,000 ammonium sulphate fertilizer factory sponsored by the Indian Government at Sindhri in the Province of Bihar in Eastern India.

The government has announced that approximately \$10,000,000 worth of plant equipment in the form of boilers, gas compressors, gas plant and turbo-alternators already has been ordered from abroad, mostly in Great Britain, and that certain other heavy equipment will be imported later.

To encourage Indian manufacturers a wide range of equipment and machinery will be purchased from within the country, however, and the government is seeking bids from domestic firms for such needs as structural steel, water mains, piping, and certain types of electrical equipment.

The Central Government Public Works Department is about to start work on the construction of factory foundations, roads and drainage systems as well as the erection of a special village to house the staff of the factory. Meanwhile the Bihar Public Works Department has been assigned the development of the water supply scheme.

NEW PLANT IN SOUTH WALES FOR MONSANTO LIMITED

CONSTRUCTION of a new organic chemicals producing plant in Newport, Monmouthshire, South Wales, is planned by Monsanto Chemicals Limited. A 125-acre site has been acquired for the new plant, and full-scale production is planned for early 1948. More than half of the new plant's production will go into exports. The Newport works, to employ between 500-600, is only part of a \$10,000,000 expansion program which Monsanto has under way, which also involves plant extensions and a spacious research and development laboratory at the principal plant at Ruabon in North Wales.

NETHERLANDS EAST INDIES CLOSED TO BUSINESSMEN

THE American Consulate General at Batavia, Java, reports that American businessmen have not been granted permission to visit the Netherlands East Indies in appreciable numbers. Those admitted are, for the most part, representatives of American firms which were established there before the war. At present all foreign trade has been taken over and is operated by the government through the NIGIEO (Netherlands Indies Government Import and Export Organization). All exports are sent to the Netherlands Purchasing Commission in New York and conversely imports are shipped by

SPACE SAVER

THAT PROVIDES LOW-COST COMPRESSED AIR

SERIES WN-112


for capacities of 378

to 1828 cfm, pressures

up to 125 psi

If space is precious in your plant, that's one more reason why you'll want to specify the Sullivan WN-112 Compressor. It's more compact than other compressors of equivalent capacity because of its advanced design and use of alloy metals—and it operates more economically . . . gives longer heavy duty service. Installation is simple, and maintenance low.

For full details write for bulletin A-52



Sullivan Air Compressors

PORTABLE AND STATIONARY — ¼ HP TO 600 HP

ALWAYS DEPENDABLE!

W&D 1512




*Consult a
Joy Engineer*

SULLIVAN DIVISION

JOY MANUFACTURING CO.

GENERAL OFFICES: HENRY W. OLIVER BLDG., PITTSBURGH, PA.

GASES? VAPORS? FUMES? CORROSIVE



Users get more economical service from TRANSITE INDUSTRIAL VENT PIPE

MANY users have found, in Transite Industrial Vent Pipe, a way to cut venting costs. These sturdy ducts resist many of the corrosive vapors, fumes, dusts and gases encountered in industrial operations.

Made of asbestos and cement, Transite Industrial Vent Pipe is rustproof . . . provides effective and economical venting service in a wide variety of industries.

Of course, you can use Transite Industrial Vent Pipe outdoors, as well as indoors. It is strong, durable and highly weather-resistant. It needs no painting.

Light in weight . . . easy to assemble . . . Transite Industrial Vent Pipe comes in 19 sizes—from 2" to 36" diameters—with a complete assortment of fittings for each size.

For more information, write for Data Sheets DS Series 335.
Address Johns-Manville, Box 290, New York 16, N. Y.



Typical industries in which Transite Industrial Vent Pipe is used

Aircraft	Dairy	Gas	Paint	Shipbuilding
Automobile	Drug	Glass	Petroleum	Shoe
Baking	Electrical	Laboratory	Potash	Smelting
Bleaching	Explosive	Laundry	Pulp & Paper	Soap
Boiler Works	Farm Machinery	Leather	Quarrying	Soft Drink
Brewing	Food	Match	Railroad	Sugar Refining
Canning	Foundry	Meat Packing	Rayon	Textile
Ceramic	Furnace	Metal	Refrigeration	Tool
Chemical	Furniture	Mining	Rubber	Water & Sewage

Johns-Manville
TRANSITE Industrial Vent **PIPE**

the Commission on orders from NIGEO. This situation is expected to continue until the end of the year. Batavia is crowded and accommodations can be obtained only for a limited number while it is practically impossible to visit points outside Batavia as connections with other cities are entirely by air and priorities are granted only in cases of urgent necessity.

NEW COMPANY TO MAKE HEAVY CHEMICALS IN INDIA

Writing from Calcutta, McGraw-Hill World News reports that the latest entrant into India's budding heavy chemicals industry is Ispahani Chemicals Ltd., with an authorized capitalization of approximately \$3,000,000, which now is offering shares to the public.

The new firm proposes to produce sulphuric acid and caustic soda at a plant to be built in the outskirts of this city. Purchase of a sulphuric acid plant complete with all incidental machinery and apparatus manufactured by the Monsanto Chemical Co., St. Louis, already has been arranged. The plant has a 10-ton daily capacity. Negotiations now are underway for the acquisition of a caustic soda plant of the electrolytic type with a daily capacity of 5½ tons of caustic soda and 5 tons of chlorine.

Ispahani also plans to develop the production of byproducts and subsidiary chemicals. Its management is in the hands of a group of well-known Calcutta industrialists.

SULPHUR WELLS DRILLED IN VERA CRUZ, MEXICO


MEXICAN GULF SULPHUR Co. and the American Sulphur Co. S. A. (a Mexican corporation), have completed the drilling of four important sulphur wells in the Province of Vera Cruz, Mexico, according to an announcement by Eugene L. Norton, president of Mexican Gulf Sulphur. The wells have proved up what is apparently a very large new deposit of salt dome sulphur, he added, similar in nature to the large deposits now being mined on the Gulf Coast of Texas and Louisiana.

INDUSTRIAL LABORATORIES TO BE BUILT IN MEXICO

The Mexican Minister of National Economy, engineer Gustavo P. Serrano, just made public that the President of the Republic signed a decree approving the setting up of two buildings in Sotelo Heights, near Mexico City, destined to house laboratories for industrial testing and experimenting. The two buildings will cost \$60,000. This sum has been collected from industrialists.

The Federal Government will donate the grounds, water and electric supply for the works. One of the laboratories will serve for the testing of and experimenting with products manufactured out of Mexican hard fibers such as henequen (sisal), palm fiber, etc. In the other, experiments and tests with oils, soaps and candelilla wax will take place.


FLOW-MASTER



THE FINEST

Precision Stainless Pump

**FOR THE
PROCESSING
INDUSTRIES**



•FLOW-MASTER "Commander" 500-4000 G. P. H. Against Head Pressures Up To 1,000 psi. Automatic Wear Control Device Compensates For Normal Lateral Wear. Side Manual Adjustment Compensates For Normal Peripheral Wear.

Catalog 25-A Contains Specifications, Engineering Data, Prices.



**FLOW-MASTER Pumps—Homogenizers
Kom-Bi-Nators
Equipment For The Process Industries**

MARCO COMPANY Inc. Wilmington 50, Del.



PLATE AND SHEET STEEL PRODUCTS

If it's a tank, guard, base or special metal part for a new machine or to replace a worn out unit, Littleford is equipped to make the most intricate of fabricated steel products. Whether it's to be made from plain steel or alloy metals it can be formed and welded to the exact detail. It's no problem to get special fabricated metal parts, let Littleford be your source of supply, even if it's for one unit or many—send blueprints for estimate of cost.



LITTLEFORD

LITTLEFORD BROS., INC.
423 E. Pearl St., Cincinnati 2, Ohio.

GERMAN CHEMICAL INDUSTRIES

To obtain reports abstracted here: Order by PB Report number, author and title from the Department of Commerce, Office of Technical Services, Washington, D. C. Make check or money orders payable to the Treasurer of the United States. (Title, author and PB Report number as well as date, number of pages, price for microfilm copies and price for photostat copies accompany each of the abstracts published below.) Do not send orders to Chemical Engineering.

Miscellaneous Secret Correspondence Concerning Work in Progress—This important secret file contains among other chemical and metallurgical projects which were in process for the German High Command (OKW) the following reports: (1) Kaiser Wilhelm Institut für Physikalische Chemie und Elektro-Chemie, Berlin-Dahlem, Faraday Way 4-6, reports on a complete card index compiled by Dr. Trude Langer on material for chemical warfare from 1897 to date of report—July 26, 1943. (2) School for Technology, Stuttgart, Schellingstrasse 26; reports by Prof. Dr. R. Fricke, July 1943 on "Hopcalithen" a chemical against carbon monoxide, developed to perfection by the Russians, and on a fire starting substance which cannot be extinguished by water or sand. (3) University of Graz, Austria, a report by Prof. G. Tantsch, Sept. 1944 on the dialysis of thorium and other metallurgical and chemical problems. (4) University of Leipzig, a report by Prof. Wo. Oswald, July 1943 on how to prevent lubricating oil from foaming in air-plastic motors. (Germany. Reichsforschungsrat, PB 20484; 1938-1944; 125 p.; M. \$1.50; P. \$9.)

A German Thermometer for Use in the Range 400-1,200 Deg. C.—The thermometer, calibrated from 400 deg. C., proved to be constructed in silica, filled with gallium, and provided with a hydrogen atmosphere above the

gallium. The maximum error was -23 deg. (at 500 deg. C.), but in the range for which it was being used at the V. A. W. Lippewerk, 950 deg. to 1,000 deg. C., the error was uniformly $+50$ deg. C. Diagrams of the thermometer and a bibliography are included. (C. J. Smithells, BP 25550; Feb. 1946; 12 p.; M. \$1; P. \$1.)

Synthetic Tanning Agents and Leather Auxiliary Products of the I. G. Farbenindustrie—This report describes the results of an investigation of the I. G. Farbenindustrie regarding the manufacture of synthetic tanning agents at Hocht, Ludwigshafen and Leverkusen. The investigation disclosed that I. G. Farben manufactured large quantities of synthetic tanning assistants and tanning agents both before and during the war. These products were for the most part exceedingly complex in chemical composition but were mainly sulfonated derivatives of phenol and/or aromatic hydrocarbon-formaldehyde condensates, sometimes with the addition of sulphite cellulose liquor to the reactants. Process data is provided for the more complex and important syntans, together with an outline of the composition of simpler or less important products, including products with the names "Tannigan", "Gerbstoff" and "Ferrigan." Some information on the properties of these products is also given. Fat substitutes for the leather industry and agents for

Immersion Heating with VITREOSIL (Vitreous Silica) HEATERS



When other methods are unsatisfactory, acid solutions in tanks of any material can safely be heated by Vitreosil electric immersion heaters.

Send for Bulletin #2




The THERMAL SYNDICATE Ltd.

12 East 46th St.

New York 17, N. Y.

3 WAYS to CONTROL TEMPERATURE

WITH BAILEY PYROTRON ELECTRONIC RESISTANCE THERMOMETERS



1. FOR AIR-OPERATED SYSTEMS



A free floating air pilot valve actuated by the Pyrotron slidewire unit establishes an air loading pressure for the control of valves and drives. Adjustments and relays provide flexibility of range, sensitivity, and speed of response, as well as reset action, easy coordination with other factors, and remote manual control.

2. FOR ON-OFF ELECTRICAL SYSTEMS



By Electronic Relay—Two slidewires, one set manually to the desired temperature standard by a convenient knob and scale, and the other automatically positioned by the Pyrotron slidewire unit, form a control bridge which operates an electronic relay.



By Electric Contacts—Adjustable cam on Pyrotron slidewire unit operates a totally enclosed snap switch.

3. FOR MODULATED ELECTRONIC SYSTEMS



A control bridge formed by two slidewires establishes a small signal voltage which changes in phase and intensity to operate a standard electronic control unit. The d-c output of this unit is accurately regulated according to the signal and applied to a saturable core reactor to vary voltage on the a-c heating circuit.

UNUSUAL FEATURES OF THE BAILEY PYROTRON ELECTRONIC RESISTANCE THERMOMETER

1. Resists vibration and shock.
2. Needs no careful leveling.
3. Motor drive provides abundant power for operation of recording pen, controller, alarms and signals.
4. Simple a-c measuring bridge needs no battery.
5. Sturdy electronic units keep the bridge in continuous balance and replace the usual galvanometer and its attendant mechanism for step by step balancing.
6. Interchangeability of packaged units simplifies replacement.

For details on this unusual Electronic Resistance Thermometer, which indicates, records and controls temperatures between -100°F . and 1200°F . ask for Bulletin 230-A. R-10

BAILEY METER COMPANY

1054 IVANHOE ROAD

CLEVELAND 10, OHIO

Controls for Processing

TEMPERATURE
PRESSURE
% OXYGEN
% COMBUSTIBLES
FLOW
LEVEL
DENSITY
RATIO



for K & M's
Revolutionary
**KONTROL
MOTOR
DIAPHRAGM
VALVE**

Just two simple quick-acting clamp screws to loosen, and your diaphragm casing is off. Tight-sealing clamp ring eliminates multiple bolts completely. Duo-seal molded diaphragm lips are automatically self-sealing.

67 years of control engineering "know how" produced this revolutionary new KONTROL MOTOR... featuring these design innovations:

- Pressed Steel Diaphragm Casing... lighter... tougher, more durable.
- Rigid Welded Steel Tubular Yoke.
- Long calibrated Steel spring... fully enclosed.
- Enclosed ball bearing Spring Adjusting Screw.
- Streamlined Flow Valve Body with high capacity... unrestricted flow areas.
- Super-finished Disc Guides, honed guide bushings, top and bottom... for minimum friction; increased life.

Used with air operated instruments or auxiliary pilot units, the K & M KONTROL MOTOR regulates the flow of steam, liquids or gases — efficiently and sensitively. Send us your control problems. We'll show you how the KONTROL MOTOR valves will solve them. Write for new KONTROL MOTOR bulletin.

KONTROL
KIELEY & MUELLER
MOTOR

KIELEY & MUELLER, INC., North Bergen, New Jersey

impregnating and waterproofing leather were also made by the I. G. and the composition and manufacture of these are described, including the series "Derminol." Also mentioned are the impregnating and waterproofing series of "Densodrin." Production figures for many of these products are provided. The appendix includes diagram and description of the handling of sulphite-cellulose liquor. (W. Baird, PB 25646; n.d.; 36 p.; M. \$1; P. \$3.)

Acrylic Esters, Synthesis from Acetylene and Nickel Carbonyl—This report, together with its appendix and flowsheets, covers the synthesis of ethyl acrylate from acetylene and nickel carbonyl and the regeneration of the nickel carbonyl. (J. F. C. Gartshore and J. D. Rose, PB 25648; n.d.; 10 p.; M. \$1; P. \$1.)

Method to Produce Hydrogen Peroxide (H_2O_2)—This is a translation of a discussion by Dr. Harant on the production of H_2O_2 . The discussion covers many of the methods and possible methods in Germany and each process is covered in some detail. The methods discussed are: (1) Barium peroxide and acid; (2) autoxidation of organic compounds; (3) persulphuric acid (Weissenstein process); (4) potassium persulphate (Pretzsch process); (5) ammonium persulphate (Riedel-Loewenstein process); (6) cathod reduction (Berl process); (7) Burning H_2 in O_2 or vice versa; (8) combination of H_2 and O_2 by silent electric discharge. (Dr. Harant, PB 25034; Nov. 1945; 20 p.; M. 50c; P. \$2.)

German Techniques for Handling Acetylene in Chemical Operations—The purpose of this report is to present the advances made in recent years by the Germans or, more particularly, I. G. Farbenindustrie in the technique of handling acetylene in chemical operations. This includes the research work done to establish the conditions under which acetylene undergoes explosive decomposition, how these data were used to design plants and set up operating conditions, and subsequent experience in these plants. Most of the processes described have been discussed in other reports so that they are considered primarily from the point of view of acetylene handling techniques. Some of the older and better known processes have not been included. In the early history of acetylene production, many accidents occurred until proper techniques of compressing and storing the material were developed. It can be compressed in slow-moving reciprocating compressors by stages with proper intercooling up to 15-20 atm. The storage cylinders are filled with a porous material, for example kieselguhr, and the acetylene is absorbed in acetone which is also added to the cylinder. Small lines are employed for the most part. Most of the present technique has been developed on a rule of thumb basis over a period of years, and the knowledge so accumulated has been of limited assistance to the chemist or chemical engineer desiring to use acetylene as a raw material under wholly different conditions. Work on acetylene chemistry was intensified just prior to, and during the war. Many of the processes developed required the use of acetylene under conditions not heretofore considered possible for safety reasons.

Added to this report are individual reports of the significant work investigated by the foremost German researchers on acetylene chemistry, photographs, graphs, tables and schematic flow charts (some of which have been translated and reproduced in better form) and the actual process descriptions of processes as carried out at Huls. (N. A. Copeland and M. A. Youker, PB 20078; Jan. 1946; 235 p.; M. \$2.50; P. \$16.)

Synthesis of Acetone—The information in this report was obtained during an interrogation of Dr. Sachsee of I. G. Farbenindustrie



"DON'T 'DEAR CHIEF' ME..."

...CUT DOWNTIME AND
REJECTS...OR ELSE!"

I HAD WRITTEN:

Mr. D. M. Whitney, President
John Doe Plywood Company
New York, New York

Dear Chief:

Our problem is resins. We don't seem to be able to get resins that will function successfully and uniformly within given ranges of operating variables. We have to "re-adjust" resin for every run. Then results are not dependable. Will continue experimenting with resins and work on getting speedier re-adjustments.

Sincerely,
J. T. Bailey
J. T. Bailey
Superintendent



HE HAD ANSWERED:

Mr. J. T. Bailey, Superintendent,
Plant 3
John Doe Plywood Company
Portland, Oregon

Dear Bailey:

Don't "Dear Chief" me. Cut downtime and rejects - or else! I hold you responsible for production and product quality. Have you never heard of specification resins?

Cordially yours,

D. M. Whitney
D. M. Whitney
President

...and that's where Interlake comes in!

JUST as Interlake has developed *specification resins* (together with necessary non-deteriorating catalysts) that perform *uniformly* and *dependably* for the plywood industry—so, in many other fields, Interlake Specification Resins have eliminated resin "adjusting", cut costs, and speeded production.

BRING YOUR RESIN PROBLEMS TO INTERLAKE, draw freely upon the wide experience of our research staff. We will gladly work with you on any resin problem, or discuss with you the pos-

sible advantage of using resins in any operation or process. Write Interlake Chemical Corporation, Plastics Division, 1931 Union Commerce Building, Cleveland 14, Ohio.

2500 SQUARE FEET IN ONE SHEET!

PHOTO ABOVE shows 50 foot long plywood sheet fabricated by Washington Veneer Company, Olympia, Wash. Used in building boats and houses.

INTERLAKE CHEMICAL

Corporation

• PRODUCTS FROM COAL •

*Specificity
IN RESINS*

Newark "END-SHAK" TESTING SIEVE SHAKER

Bring your laboratory and plant operating results into closer relationship by applying the same fundamental principle of screening to both.

With "END-SHAK" the sieves are given an ideally combined reciprocating and turning motion which causes the sample to spread uniformly over the sieve area eliminating jumping and bouncing of the particles. Operation is smooth and with all working parts submerged in oil, noise and wear are reduced to a minimum.

Write us for additional data on this efficient test shaker.

NOTE: We have a service now for re-covering Testing Sieve Frames at nominal cost. Don't throw away frames with worn cloth. Write us.



NEWARK
for **ACCURACY**

Newark Wire Cloth COMPANY

350 VERONA AVE.,

NEWARK 4, NEW JERSEY


plant at Ludwigshafen, May 28, 1945. The production of acetone at Ludwigshafen was 400 tons per month and the chemistry involved is a novel process. Raw materials are acetylene and water. These are passed in vapor phase over a catalyst of pure zinc oxide. Yields and efficiencies to acetone of 80 to 90 percent of the theoretical are claimed for the process. Byproducts of higher ketones and acetaldehyde are formed, which, if recovered, would raise the efficiency of the consumed acetylene. The method of operation does not attempt recovery of byproducts. (F. H. Roberts, PB 23747; Jun. 1945; 3 p.; M. 50c; P. \$1.)

Propargyl Alcohol; Dehydration and Oxidation to Hexadinediol—Aqueous propargyl alcohol recovered from the butinediol plant can be dehydrated by azeotropic distillation with 2,5-dimethyltetrahydrofuran. Experiments also in progress at Ludwigshafen indicated that benzene could be used in place of dimethyltetrahydrofuran. Air oxidation of propargyl alcohol in the presence of ammonium chloridocuprous chloride catalysts gives excellent yields of hexadinediol. Flowsheets for the dehydration process and the subsequent oxidation process are given. (J. D. Rose, PB 27124; Nov. 1945; 6 p.; M. \$1; P. \$1.)

Germany—Fats, Oils and Oilseeds, Holtz und Willemsen GmbH Oelfabriken—This concern operates a crude oil mill, a refinery, hardening plant and margarine factory in Uerdingen/Rhine. The processing in the press mill, in the refinery, in the fatty acid stills and in the margarine plant is described. The refinery contained a unique plant for the distillation of fatty acids from acidulated soap stock and for distillation of high free fatty acid oil prior to refining. The margarine is made according to the somewhat standardized formula of 60 percent hardened rapeseed oil, 40 percent liquid oil which is emulsified in the ratio of 80 percent fat to 20 percent water with addition of salt, carotene and potato meal. No diacetyl or glucose is added. (W. H. Goss and K. S. Markley, PB 25675; Sep. 1945; 6 p.; M. \$1; P. \$1.)

The Production of Synthetic Fuels by the Hydrogenation of Solid and Liquid Carbonaceous Materials—This report describes the principal methods of producing synthetic fuels by high pressure hydrogenation of coal and tar, as practiced in Germany. The various techniques of operation, designs of equipment, and characteristics of the products are described, and whenever possible, the relative merits and best uses of the different items are discussed. Important economic features of the industry are analyzed so that there is a technical basis for evaluation of the various phases in the light of existing local conditions. The data in this report were obtained either by interrogation of personnel, examination of documents collected from various plants, or by visual observation. Among the processes described are the TTH, "Tief-Temperatur-Hydrogenierung," or low temperature hydrogenation, and the Pott-Broche process. Appendix A contains tables among them being a table of German coals used for hydrogenation, the "brown" coal being used at Leuna and Wesseling and bituminous coal at Gelsenberg and Politz, and another table giving the summary of operation data for sump phase hydrogenation. Appendix C gives preparations for 5058 catalyst, and Welheim gas phase catalyst No. K 536. (John H. Howell and Roy M. Crawford, PB 27701; Aug. 1945; 121 p.; M. \$3; P. \$9.)

Production of Beryllium, "Degussa"—A detailed account of the method for producing metallic beryllium as practiced at the Deutsche Gold und Silber Scheide Anstalt plant at Frankfurt. The process is carried out essentially in two phases: first, the preparation of pure



Football isn't played in track trunks

Clad in track suit, what chance would a player have against a team equipped with the "armored" togs of football!

In many phases of production involving paper . . . essential industrial papers, that is . . . it also becomes vital to provide proper physical and chemical characteristics to withstand "unnecessary roughing". Modern MOSINEE papers for the plastics industry, for instance, are engineered specifically for plastics requirements. For the electrical industry and other mechanical applications, MOSINEE paper characteristics are pro-

vided for maximum arc resistance, high dielectric strength, low moisture absorption, high strength-weight ratio. For other products and processes, MOSINEE creates special stretching papers, high tensile, high fold and tear resistance, high absorption or moisture repellency papers . . . controlled maximum-minimum pH, and other scientifically created papers . . . dependable in uniformity and performance.

MOSINEE paper technicians are prepared to equip the paper you need with characteristics that improve product and production. Call MOSINEE.



MOSINEE

**PAPER
MILLS
COMPANY**


MOSINEE • WISCONSIN

Essential Paper Makers

*Please address
your letter
to Attention
Dept. C*

New! BUT BACKED BY YEARS of EXPERIENCE

Thomson Pumps



Rotary type, that because of its design and construction will operate at slow speed. Due to large internal pumping chambers it will handle liquids that contain solids or substance in suspension. Rotor is of an inverted bearing construction that places the bearing directly under the rotor load . . . packing glands are spring loaded type with metal sealing rings that assure perfect sealing under vacuum on pressures. Easily removed for cleaning or repairing. Thomson pumps will successfully handle chemicals, naphtha, oils, syrups, sugar, food products, soap, pharmaceuticals, water, etc.

Send for complete information.

THOMSON PUMP & EQUIPMENT CO Inc.
717 WEST 11 TH. STREET
LOS ANGELES 15, CALIFORNIA

CAPACITIES
FROM
1 TO 150
G.P.M.

DESIGNED
AND MANUFACTURED
BY EXPERIENCED ENGINEERS

THOMSON PUMPS

Research Pays Off

ANNEALING silica ware is only one step in Amersil's research program designed to produce silica and quartz ware that lasts longer on the job.

Amersil now offers an engineering service which includes development, research, design, controlled manufacture of major silica ware units, selection and purchase of auxiliaries—all under one contract—one responsibility.

If you have a problem involving extreme temperatures and highly corrosive operating conditions—get in touch with an AMERSIL engineer.

LASTS
a
minimum
of
10
TIMES
LONGER

Unsolicited advice from a consistent user* of AMERSIL ANNEALED SILICA TRAYS states they last a minimum of ten times longer than trays which have not been annealed.

*Name on request.

AMERSIL COMPANY Inc.

CHESTNUT AVENUE

ENGELHARD

HILLSIDE 5, N. J.

anhydrous beryllium chloride using the mineral beryl as the ore; and second, the electrolytic production of beryllium, which is about 99 percent pure. (W. B. C. Perrycoste, PB 25668; Nov. 1945; 12 p.; M. \$1; P. \$1.)

Anti-Oxidant 4010—This anti-oxidant was especially developed for the protection of tires, conveyor belts, and certain cable jackets against fatigue cracks. It does not provide protection against aging through sun-exposure but may be mixed with paraffin and ozokerite. The claim is made that this product is superior to all others including American products based on phenylbetanaphthylamine and diphenyl-p-phenylenediamine. Product 4010 replaces in whole or in part the use of phenyl-alphanaphthylamine and phenylbetanaphthylamine. The results of testing are given in tabular form. In German. (I. C. Farbenindustrie, PB 17640; Mar. 1939; 9 p.; M. 50c; P. \$1.)


The Development of New Dyes and Color Application Processes in Germany and Italy during World War II—This account surveys the German (I. C. Farbenindustrie) and Italian (Montecatini) dye laboratories to determine the new dyes and intermediates and new color applications developed during the war years, with particular attention to developments adaptable to the production of military products. Although research in Germany and Italy was at a low ebb during the war, the investigators report over one hundred new dyes. There is a general discussion of dyestuff developments in the two countries, and a total of 87 appendixes each giving individual specifications for new dyes and color applications. For parts 1 and 2, see PB 31002 and 31003 respectively. (M. A. Dahlen, PB 31004; Oct. 1945; 462 p.; M. \$10; P. \$31.)

Manufacture and Use of Some German Synthetic Adhesives and Raw Materials—This is a report on German synthetic adhesives. A number of firms were investigated and their manufacturing methods described. Products discussed are: (1) P600 cold setting glue, made by reacting phenol, 30 percent formalin, and caustic soda; (2) "Pressal," fundamentally 30 percent melamine formaldehyde resin and 70 percent starch; (3) "Polystyl U11," which is a 50 or 70 percent solution of "Desmodur TH" in ethylacetate; (4) "Desmodur T," which is a mixture of 216 and 214 diisocyanate toluene; (5) "Desmodur TH," which is produced by reacting "Desmodur T" with trimethylolpropane and butanediol; (6) various "Desmophens," made by reacting a polyhydric alcohol with adipic acid alone or with phthalic acid; (7) "Maltopren," made by mixing "Desmophen S8," "Desmophen 800," and carbon black; (8) Kaurit, made by reacting 30 percent formalin with urea; (9) "Iporka," made by reacting urea, hexantreal, and formalin; flow-sheets of some of the processes are also given. (N. A. De Bruyne, PB 27072; Jan. 1946; 67 p.; M. \$2; P. \$5.)

Cellulose Acetate Manufacture at Schering A. G., Berlin—The production of "Triacetate-Folie" is described. This is produced only by the Schering A. G. and is a special cellulose acetate film, used for cable wrapping, reported to be outstanding because of its unusual heat resistance. Cellulose (cotton linters or alpha cellulose from wood pulp) is treated in a glacial acetic acid bath for 5 hr. The acid is then drained. A special charging mixture is then used consisting of 40 parts acetic anhydride, 20 parts H₂SO₄, 40 parts benzene and 0.5 percent HClO₄, based on weight of cellulose. The cellulose is still in the wool form and the benzene is important in preventing solution as the acetylation process progresses. This is called the key to the whole process. Maximum theoretical possible acetylation of 62.5 percent is obtained, which the Schering

44 YEARS' PERFORMANCE SELLS SATISFIED USER TWO *MORE* B&W's

This new B&W 16,000 lb. per hour Integral Furnace Boiler was installed in 1945 —



— and another duplicate unit has replaced this original boiler, in service since 1901.

Distinctive Features of B&W Integral Furnace Boilers That Assure Faithful Performance:

1. Water-cooled furnace sidewalls and roof are of the same durable stud-tube construction used in large central-station boilers.
2. Deep furnace, fired from one end, provides ample space for complete combustion.
3. Bare metal blocks cover and protect the tubes of the water-cooled furnace floor, provide a surface readily cleared of ash.

4. Self-draining superheater design prevents accumulation of water in the tubes, and a stud-tube wall shields the second and third banks from direct furnace radiation.

5. Tubes of the third bank, which is in the zone of coolest gases, act as down-comers, insuring rapid, positive circulation at all loads.

Again it's the story of "satisfied customer comes back for more"...a story that has been an old one with B&W for many years.

Old, too, were the boilers the story's about — two B&W longitudinal-drum boilers purchased by The Lunkenheimer Company of Cincinnati back in 1901 — and still in daily operation at the time they were removed for plant expansion only last year.

In testimony to the performance of these

veterans, the two new units that replace them also bear the B&W name. They are modern B&W Integral-Furnace Boilers, a type that has won sweeping acceptance in almost every major industry for high availability and continuity of service...for rapid response to fluctuations in load demands...for the production of clean, dry steam...for over-all economy with all types of fuel.

G-322




Water-Tube Boilers, for Stationary Power Plants, for Marine Service . . . Water-Cooled Furnaces . . . Superheaters . . . Economizers . . . Air Heaters . . . Pulverized-Coal Equipment . . . Chain-Grate Stokers . . . Oil, Gas and Multifuel Burners . . . Seamless and Welded Tubes and Pipe . . . Refractories . . . Process Equipment.

BABCOCK & WILCOX

THE BABCOCK & WILCOX CO.
GENERAL OFFICES: 85 LIBERTY ST., NEW YORK & N.Y.
WORKS: ALLIANCE AND BARBERTON, O.; AUGUSTA, GA.

NICHOLS-WEDGE

MULTIPLE HEARTH FURNACES



Hundreds of industrial plants throughout the world use thousands of our multiple hearth furnaces for roasting, calcining, drying and revivifying ores, concentrates, sludges, pigments, limestone, bone char, etc. economically and efficiently.

Accurate temperature and close control of furnace atmosphere assured. Nichols engineers available for consultation.

Bulletins on request.

NICHOLS ENGINEERING & RESEARCH CORP.

60 WALL TOWER—NEW YORK 5, N. Y.
University Tower Bldg., Montreal, P. Q.

officials claim is responsible for the excellent electrical properties. Complete removal of the catalyst (HClO_4) is effected by keeping the acetate in the wool form, this resulting in markedly improved heat resistance. It is also claimed that the dye used for coloring (Ciba Blue 2R) has a definite stabilizing effect. A diagram of the acetylating equipment is included. Also included is a report, in German, of the process for the production of the cellulose triacetate, by Dr. Hinz, and a sales booklet also in German on its properties and uses. (J. Frederick Myers, PB 25663; Jan. 1946; 14 p.; M. \$1; P. \$1.)

Production of Aluminum Sulphate Giulini—The report deals with the Gebrüder Grulini plant in Mundenheim, Ludwigshafen. This plant was the principal producer of aluminum sulphate in Germany. The plant and operation is described briefly together with a summary of the products made. An analysis of the various products is included. The aluminum was produced in the following strengths 14-15 percent, 17-18 percent, 22-23 percent, and an ersatz sulphate of 9-10 percent. (Horn Freeman, PB 23809; Nov. 1945; 5 p.; M. 50c; P. \$1.)

Use of Monochlorobromomethane by the German Navy and Air Force as a Fire Extinguishing Agent—This report includes a discussion of the chemical properties of monochlorobromomethane and its use as a fire extinguishing agent. Monochlorobromomethane was developed and tested in 1939-40 by the I. G. Farbenindustrie A. G. As prepared commercially, it was commonly known as "C-B." This material was submitted to the German Army, Navy and Air Forces as an improved gas fire extinguishing agent. An extensive investigation had been carried out by the German Navy to develop a substitute for methyl bromide and mixtures of methyl bromide, used aboard naval vessels in fixed gas fire extinguishing systems. Extensive tests to determine the toxicity of "C-B" were conducted in 1940-41 by the Reich Public Health Office at the request of the German Navy. Based on actual fire tests and toxicity reports, the Oberkommando der Kriegsmarine in August 1941 approved "C-B" as the only gas fire extinguishing agent to be used on German naval vessels. In 1942, Junkers/Dessau undertook a research project to develop for the Luftwaffe a light, reliable extinguishing system to control fires in aircraft caused by incendiary shells or ruptured gasoline fuel lines. Tests established that "C-B" discharged by carbon dioxide gas pressure was the most efficient fire extinguishing agent available for this purpose. This mixture—65 percent "C-B" and 35 percent CO_2 —was called "Dachlaurin" or "D-L." The Luftwaffe in March 1945 approved a fire protection system for military aircraft using "C-B" as the fire extinguishing agent. New facilities to manufacture and bottle "C-B" were never fully completed before the end of the war. Graphs, diagrams and photographs. (Emmett A. Scanlan and E. Benner Hitchcock, PB 22808; Sep. 1945; 48 p.; M. 50c; P. \$4.)

The Synthesis of Hydrocarbons and Chemicals from CO and H_2 —This report describes the commercial application and development in Germany of the synthesis of hydrocarbons and chemicals from CO and H_2 during the war. The development took place along seven main lines. First was the Fischer-Tropsch (FT) process. By this method were produced special chemicals and chemical raw materials. In addition, there could be made poor quality gasoline, diesel oils, and intermediates for the production of special lube oils and detergents. The second development was the "Synol" process. By this process were produced mainly higher alcohols. These alcohols were almost exclusively straight main terminal alcohols

Here's help to speed your work with *Stainless Steel*


Successful fabrication with Stainless Steel needs exact methods. But these methods are difficult only when operations are inordinately severe or where an unusual alloy has had to be selected to withstand unusually severe conditions. In over 99% of the cases, Stainless Steel fabrication is *not* difficult . . . it is just *different*.

In this authoritative textbook, just off the press, these differences in fabricating techniques are thoroughly discussed.

Here in practical form are assembled the very latest findings on Stainless Steel welding, riveting, soldering and joint design—on machining, cutting, forming, annealing and pickling—on surface finishing and protection.

Here are listed for handy reference the various U-S-S Stainless Steels we produce—their physical properties and chemical compositions—the forms and sizes in which they are available—their resistance to various reagents.

This book is **FREE**—send for your copy. Use it as a guide to successful workmanship. And when unusual conditions confront you, ask for the assistance of our Stainless Steel specialists.



U-S-S STAINLESS STEEL

AMERICAN STEEL & WIRE COMPANY, Cleveland, Chicago and New York
CARNEGIE-ILLINOIS STEEL CORPORATION, Pittsburgh and Chicago
COLUMBIA STEEL COMPANY, San Francisco
NATIONAL TUBE COMPANY, Pittsburgh
TENNESSEE COAL, IRON & RAILROAD COMPANY, Birmingham
United States Steel Supply Company, Chicago, Warehouse Distributors
United States Steel Export Company, New York


We can supply U-S-S Chromium Nickel and Chromium Stainless Steel not only in many different analyses but in the widest, most complete range of forms, sizes and surface finishes anywhere obtainable. Our engineers are specialists in solving new and unusual problems in the use of Stainless.

UNITED STATES STEEL



NATIONAL Welded Products

From OPEN HEARTH,
STAINLESS, ALLOY and CLAD STEELS




Pressure Vessel 40" I.D., 95-3-4"
Long—7 8" Plate, 350#
Working Pressure—
A.P.I.-A.S.M.E. Code.

Fifty years of experience in building industry's specially designed and fabricated equipment—plus unexcelled engineering, modern production facilities, manufacturing skill, constant X-ray and manual inspections—is your assurance that National can fabricate your most intricately designed equipment with dependability, speed and economy.



3000 Gal. Jack-
eted Agitating
Drum (with
auxiliary drum)
1-3 8" shell—
A.S.M.E. Code
—U-68.



Receiver 5'0"
x 8'0"-3/8"
thick — Type
347 Stainless
Steel.

National
ANNEALING BOX COMPANY
API-ASME Codes • Stress Relieving • X-ray
Pledged to Quality Since 1895
WASHINGTON, PENNA.

NATIONAL PRODUCTS

- Pressure Vessels
- Galvanizing Kettles
- Annealing Covers
- Tin Pots
- Salt Annealing Pots
- Wire Annealing Pots
- Special Plate Work

with a carbon content up to C_{30} . In addition olefines and esters were also produced. The third development was the synthesis of high melting point waxes. This work was done at the Kaiser Wilhelm Institute and was only done on a laboratory scale. The products of this synthesis were wide mixtures of high boiling waxes with molecular weights as high as 10,000. The fourth development was the "isosynthesis" worked out on a laboratory scale at the Kaiser Wilhelm Institute. By this method may be produced mostly low boiling isoparaffins, isobutane being the largest individual component. The fifth development was the isobutanol synthesis. The sixth development was a new synthesis of methanol which may be carried out at 30 atm. This work was done on a laboratory scale and resulted in the assembly of a pilot plant. The seventh development was the OXO-synthesis. By this method higher boiling alcohols are prepared by reacting olefines with CO and H_2 over cobalt. These seven processes are of considerable importance since a wide range of products and many intermediary products may be produced which may be used as fuels, lubricants, plastics, in lacquers, and detergents. This report discusses each process in detail as to cost, products, catalysts and gives considerable information as to the production of each of the plants in Germany. (E. H. Reichl, PB 22841; n.d.; 30 p.; M. 50c; P. \$2.)

Pentaerythritol: Derivatives and Byproducts

—The folder contains business and technical correspondence on various compounds that can easily be obtained in the manufacture of pentaerythritol: (1) trimethylolnitromethane (nitroisobutylglycerol), which could be an important substitute for glycerol in the manufacture of explosives, especially those for civilian use; (2) tetraaminotetramethylmethane disulphate, which could also be used for explosives; (3) the so-called penta-byproducts; (4) pentaerythritol esters, which were tested for use as lubricants, especially those for weapons; and (5) pentaerythritol tetraacetate which is of interest as a carbon carrier. In German. (I. G. Farbenindustrie, PB 17589; Oct. 1940-Aug. 1944; 94 p.; M. \$1; P. \$7.)

The Production of Monomeric Vinyl Acetate in Germany—Monomeric vinyl acetate was produced in Germany by the vapor phase reaction of acetylene and acetic acid in the presence of zinc acetate catalyst at 170 to 200 deg. C. The catalyst was supported on activated carbon and had a maximum life of 800 tons of vinyl acetate per 2.2 tons of catalyst, or four months at the rated capacity of 200 tons per month. The reactor was a tube and shell vessel with 50-mm. tubes 3.5 m. long in which the yield per pass was 32 percent. Development work indicated that 35 mm. tubes would effect higher yields. Efficiencies were reportedly very high with only traces of acetaldehyde formed. (J. W. Biddle, PB 27700; Aug. 1945; 42 p.; M. \$1; P. \$3.)

Rohm und Haas, O. G., Darmstadt—The Rohm and Haas plant is one of the major producers of cast methyl methacrylate sold under the name of Plexiglas. Plexiglas was made by the customary oven process. However, the water bath process had been worked out and a plant designed and erected. This process is entirely different from British and American processes. The water bath polymerization is covered in some detail. In addition the manufacture of several other forms of methyl methacrylate are described which are used as injection molding powders, compression molding powders, and dental powders. An appendix includes a translation of the work by Dr. Trommsdorf on block polymerization which is considered of great value. (W. Hunter and H. C. Raine, PB 23816; Sep. 1945; 43 p.; M. 50c; P. \$3.)

Acetic Acid vs. Materials of Chemical Plant Construction—Part I

This is Part I of a symposium in which manufacturers evaluate their products for acetic acid service. Part II will be published next month.

CARBON, GRAPHITE, KARBATE

E. S. MALKIN
National Carbon Co., Inc.
Cleveland, Ohio

CARBON, graphite and certain grades of Karbate impervious carbon and graphite materials have been found satisfactory and chemically resistant by laboratory tests and commercial applications to all concentrations of acetic acid at temperatures up to the atmospheric boiling point. Some of the services were a combination of acetic acid with hydrobromic, hydrochloric, and sulphuric acids, chlorinated organics, and other compounds made from acetic acid which resulted in corrosive conditions decidedly more severe than from acetic acid alone. The grade of Karbate materials recommended for use depends on the temperature conditions and the impurities.

Porous carbon has been used successfully as a diffuser medium for mixtures of steam, formic, and acetic acids in agers in the textile industry. The pipe and fitting connections were all Karbate products. No corrosion or breakage from thermal shock has occurred in over one year of service.

Karbate graphite base products have been used in various industrial acetic acid processes as heat transfer and conveying equipment, such as plate and bayonet tank heaters, shell and tube evaporators and condensers, centrifugal pumps, globe valves, and pipe and fittings. The actual operating conditions for this equipment have not been made available by the users. However, it is known that acetic acid and combinations with other chemicals are present, and the equipment has been operated without any noticeable corrosion and with complete satisfaction for several years.

Laboratory tests of Karbate materials in glacial and other concentrations of acetic acid at the atmospheric boiling points showed no discoloration of the acid and no change in physical appearance of the material.

In the manufacture of equipment, the individual Karbate parts, such as tubes and tube sheets, are cemented together with impervious, synthetic resin cements simi-

lar in strength, durability and chemical inertness to the Karbate products. "National" No. 14 cement has been employed successfully in all Karbate equipment in acetic acid applications. Laboratory test joints made with No. 14 cement showed from none at all to small decreases in strength after several months exposure to various concentrations and temperatures of acetic acid. National No. 8 cement is slowly attacked by acetic acid and is not recommended for these applications.

ALUMINUM ALLOYS

ELLIS D. VERINK, JR.
Aluminum Co. of America
New Kensington, Pa.

FOR MANY years the mutual compatibility of aluminum and acetic acid has been recognized. Aluminum equipment has long





Fig. 1—Curves showing rate of attack of acetic acid on aluminum


been in use, not only for the production of acetic acid and acetic anhydride, but for the production of many products in whose manufacture acetic acid is employed.

For example, in the manufacture of

Aluminum tanks of welded construction for storage of acetic acid



Lowest Capital Installation Cost Per Ton= Sutton, Steele & Steele **AIR TABLE**



THE Air Table makes the same efficient separation regardless of ups and downs of business activity or fluctuating prices.

The Air Table does not require accessory equipment such as pumps, piping, etc., which are so hard to get today.

Now that financial adjustments have taken away surplus capital, the operator needs the least expensive installation. On materials suited to Air Tabling, capital installation costs of the entire plant, from crusher to finished product, are one-third less than any wet plant on the same material at the same tonnage.

Air Tables are very sensitive specific gravity separators, able to handle high tonnage of properly sized materials as coarse as $\frac{1}{2}$ " and as fine as 48 mesh, below which Sutton, Steele & Steele Controlaires are used.

• Our engineers will be glad to help solve your separating or concentrating problems and submit recommendations. Send sample for laboratory tests.

SUTTON, STEELE & STEELE, INC.
DALLAS, TEXAS
SALES OFFICES
SEPARATIONS ENGINEERING CORPORATION
110 EAST 42nd STREET, NEW YORK, N. Y.
OLIVER BUILDING, PITTSBURGH, PENNSYLVANIA
ENGINEERING BUILDING, CHICAGO, ILLINOIS
FLOUR EXCHANGE BUILDING
MINNEAPOLIS, MINNESOTA
41-43 DRUMM STREET
SAN FRANCISCO, CALIFORNIA

THE S&S PROCESS FOR BETTER PRODUCTS—FASTER

cellulose acetate, aluminum is used for storage tanks, acetylators, precipitators and centrifugal extractors. Of particular importance in this field is the fact that acetic acid can be handled without danger of dis-

Table I—Results of Tests With 2S Aluminum Immersed in Glacial Acetic Acid at Various Temperatures; Duration of Tests—48 Hours

Temperature	Average Mile Penetration Per Year	Remarks
77° F.	0.45	Specimens dulled and iridescently stained.
125° F.	1.6	Immersed areas stained and dulled, portion in vapors darkened.
160° F.	4.7	Immersed areas stained and dulled, portion in vapors darkened.
Boiling	5.3	Immersed areas had dull white appearance, portion in vapor non-uniformly stained.

Size of specimens was 3 in. x $\frac{1}{4}$ in. x 0.064 in., exposed area 2.775 sq. in.

coloration. Therefore, "water whiteness" of acetic acid and products made from acetic acid is assured by use of aluminum equipment.

The rate of attack of aluminum by acetic acid is indicated in Fig. 1. It will be noted that at room temperature the attack is of the order of 1 mil per year regardless of concentration. As the temperature is increased, the rate of attack is substantially increased; however, even at boiling temperatures, attack by glacial ac-

Table II—Elements in Aluminum Alloys

Alloy Designation Wrought Alloys	Cu.	Si.	Mn.	Mg.	Cr.
35
38	1.2
335	2.5	0.25
618	0.25	0.6	...	1.0	.25
Cast Alloys
43	...	5.0
B214	...	1.8	...	3.8	...
356	...	7.0	...	0.3	...
406	2.0

Table III—Typical Mechanical Properties of Aluminum Alloys

Alloy and Temper	Yield Strength, lb. per sq. in.	Ultimate Tensile Strength, lb. per sq. in.	Elong. Percent—2 in.			Shear Strength, lb. per sq. in.	Endurance Limit, lb. per sq. in.
			Sheet	Round Rod	Brinell		
2S-O	5,000	13,000	35	45	33	9,500	5,000
2S-1/2H	14,000	17,000	9	20	32	11,000	7,000
2S-H	21,000	24,000	5	15	44	13,000	8,500
3S-O	6,000	16,000	30	40	28	11,000	7,000
3S-1/2H	18,000	21,000	8	18	40	14,000	9,000
3S-H	25,000	29,000	4	10	56	16,000	10,000
335-O	14,000	29,000	25	50	45	18,000	17,000
335-1/2H	29,000	37,000	10	14	67	21,000	15,000
335-H	36,000	41,000	7	8	85	24,000	19,000
618-W	21,000	35,000	22	25	68	24,000	13,500
618-T	40,000	45,000	12	17	95	30,000	13,500
43	9,000	19,000	...	6.0	40	14,000	6,500
B214	13,000	30,000	...	2.0	50	17,000	...
356-T8	34,000	53,000	...	4.0	70	27,000	8,000
406	9,000	19,000	...	12.0	35	14,000	8,500

BETTER FILTER CLOTHS FOR Alkaline and Caustic Filtrations Are Your Filter Cloths Costing Too Much?

Do they "gum-up" and give a poor filtrate?
Are they short lived?
Do you wish to lower your filtration costs and improve your filtrate?

for

"LONG LIFE" filter cloths
TRY

THORATEX

Reg. U. S. Pat. Off.

For additional information and samples write:

METAKLOTH COMPANY


LODI, NEW JERSEY

WM. L. BARRELL CO., Inc., 40 Worth Street, New York, N. Y., Sales Agents


PITTSBURGH • DES MOINES

PRESSURE SPHERES

—Designed and built
to serve your specific
storage requirements



Pressure spheres for the storage of liquids and gases are designed and built by Pittsburgh-Des Moines to meet individual needs—in any type or capacity, and with accessory equipment suited to the particular requirements of the job. Our complete service is based upon many years of practical experience in this field, a continuous program of advanced research, superior fabricating facilities, and dependable construction craftsmanship. Your inquiry for an engineering consultation and estimates is invited, without obligation of any kind.



PITTSBURGH • DES MOINES STEEL CO.

PITTSBURGH, PA., 3417 NEVILLE ISLAND—DES MOINES, IOWA, 916 TUTTLE STREET
NEW YORK, ROOM 990, 270 BROADWAY • CHICAGO, 1207 FIRST NATIONAL BANK BUILDING
DALLAS, 1216 PRAETORIAN BUILDING • SAN FRANCISCO, 606 RIALTO BUILDING
SEATTLE, 507 FIRST AVENUE, SOUTH



NEW all-metal WESTON

MAXIMUM-MINIMUM

Thermometer



RED INDEX shows the highest or lowest temperature reached!

Simply swing the red index to the low side of the temperature pointer, and the index will move to the *lowest temperature reached*, and remain there until manually reset. For *highest temperature record*, simply swing the red index around to the high side of the pointer.

The index movement in no way impairs the guaranteed high accuracy of the WESTON Thermometer.

Thus the WESTON Maximum-Minimum Thermometer provides, at only slightly above ordinary thermometer prices, a means of obtaining high or low temperature records on equipment or processes where these extreme temperatures are critical. Ideal for transformers, sterilizers, ovens, chemical equipment, food processing, etc. For complete information, consult your nearest WESTON representative.

WESTON ELECTRICAL INSTRUMENT CORPORATION
590 Frelinghuysen Avenue, Newark 5, New Jersey




Fig. 1—Flowsheet showing use of aluminum equipment in manufacture of acetic acid from wood

tic acid is of a very low order. Table I shows the effect of increasing temperature on the rate of attack on 2S aluminum by glacial acetic acid.

The data given in Table I were obtained with commercially pure aluminum; however, the alloys listed in Table II should exhibit comparable resistance to acetic acid. These alloys are the most corrosion resisting aluminum alloys. Table III lists some typical mechanical properties.

Fig. 2 is a flow chart for the manufacture of acetic acid by the destructive distillation of wood, showing diagrammatically the pieces of equipment which have been successfully made of aluminum, as well as those which experimental data and installations indicate could be successfully made of aluminum.

The alloys which should be used for each of the elements of the system follow: Storage tanks—2S, 3S, 52S, 61S; stills—3S, 52S, 51S; condensers—3S, 52S, 61S; piping—2S, 3S, 61S; valves and fittings—43, B214 alloy; manholes, etc.—356, 406 alloy.

DURIMET AND CHLORIMET

W. D. STALEY
The Duriron Co., Inc.
New York, N. Y.

DURIMET T (22 Ni, 19 Cr, 3 Mo, 1 Cu, 1 Si, 0.07 max C.) and **Durimet 20** (29 Ni, 19 Cr, 3 Mo, 4 Cu, 1 Si, 0.07 max. C.) possess satisfactory resistance to both crude and pure acetic acid in all concentrations at temperatures normally encountered. This is in contrast to stainless steels of lower alloy content which often show border line passivity in acetic acid service, particularly at higher concentrations

CALL ON B&W

for the Right Tubing...



Section of petroleum cracking unit made of
B&W Croloy 25-20 Stainless Steel Tubing

for Any Process Requirement

FINDING the right tubing—seamless or welded—for any chemical processing requirement is greatly simplified when the problem is put up to Babcock & Wilcox. At B&W your problems are considered in the light of exceptionally broad experience in supplying tubing for applications requiring resistance to corrosion, oxidation, creep and other adverse conditions in high and low temperatures. This B&W experience embraces an exceptionally wide range of steels—from simple low carbons to high alloys, including stainless and other corrosion-resistant steels, carbon-molybdenum steels, and the many special B&W Croloys developed expressly for refinery and other chemical process services.

Matching tubes to jobs—finding the analyses best suited for your particular service conditions—is a specialty with B&W. So bring your problems to B&W to be sure of getting tubes that will give the most satisfactory and economical service.

TA 1387B



Other B&W Products

THE BABCOCK & WILCOX CO.
85 LIBERTY STREET • NEW YORK 6, N. Y.

Water-Tube Boilers, for Stationary Power Plants, for Marine Service • Water-Cooled Furnaces • Superheaters • Economizers • Air Heaters • Pulverized-Coal Equipment • Chain-Grate Stokers • Oil, Gas and Multi-fuel Burners • Refractories • Process Equipment.

**BABCOCK
& WILCOX**
**SEAMLESS
& WELDED TUBES**

THE BABCOCK & WILCOX TUBE COMPANY
GENERAL OFFICES: BEAVER FALLS, PA.
PLANTS: ALLIANCE, OHIO AND BEAVER FALLS, PA.

LOOK AT EYE SAFETY FROM THE WORKER'S ANGLE



WILLSON RUBBER MASK GOGGLE
X40 Series—especially designed for
chemical process industries.

ADD COMFORT TO PROTECTION

TO MAKE YOUR EYE SAFETY PROGRAM WORK

Your by-word may be "Safety First"—and it should be. But to most workers, comfort—or the lack of it—determines whether they wear the goggles or carry them around in their pockets.

Here is a rubber mask goggle that overcomes the usual objections. Its resilient rolled edge acts as a shock absorber and combines wearing comfort with protection against impact. The rolled edge fits all facial contours to assure snug fit, without pressure, excluding dust, flying particles and splashing liquids.

Maximum eye protection is afforded by Super-Tough* heat treated lenses whose large triangular shape permits wide vision. And the goggle may be worn over prescription glasses in comfort.

For help on your eye protection problems, consult your Willson Distributor or write direct.

W.F.M. REG. U.S. PAT. OFF.



Lenses are easily replaceable in the pliant rubber frame when they become pitted or scratched.



Ventilated goggle illustrated. Also available in non-ventilated type for maximum protection against dust and splashing chemicals and acids.



GOGGLES • RESPIRATORS • GAS MASKS • HELMETS
WILLSON
DOUBLE
PRODUCTS INCORPORATED
Established 1870

223 WASHINGTON STREET, READING, PA.

and temperatures. In addition to being satisfactory over the entire range of concentration, Durimet T and Durimet 20 show good resistance under nonacrated and reducing conditions.

Laboratory test data indicates negligible rates of corrosion as shown by the results in the accompanying table:

Corrosion Rate on Durimet T in Boiling Acetic Acid

Percent Acid	Mils Penetration Per Year
10	0.08
50	0.20
75	0.08
Glacial	0.10

Typical of laboratory tests on Durimet 20 is a test in an aerated solution of 70 percent acetic acid, 16 percent salicylic acid and 14 percent water at normal temperature. The greatest loss was equivalent to 0.6 mils penetration per year.

The limiting temperature for Durimet T and Durimet 20 in acetic acid is not known definitely but these alloys have been found unsuitable for handling strong acetic acid at temperatures over 300 deg. F. with pressures above 150 lb. per sq. in.

Numerous cases may be cited of results under actual service conditions and this information is generally more dependable than laboratory data for selecting the most suitable alloy for the job. Reference will be made to installations that include primarily Durimet pumps and valves inasmuch as these Durimet alloys are available only in the cast form, except for limited quantities of Durimet T bar. It is expected that Durimet 20 bar and sheet can be supplied at a later date.

Durimet equipment is giving satisfactory service under the following conditions:

1. Durimet T pumps: 20 percent acetic acid and 3-5 percent sulphuric acid at room temperature.
2. Durimet T pumps: Glacial acetic acid containing less than 0.5 percent each of sulphuric acid and sodium bichromate at 80 deg. F.
3. Durimet T plug valves: 10 percent acetic acid and mercury salts at atmospheric temperature.
4. Durimet 20 valves: Crude acetic acid with some formic acid at 200 deg. F. (Durimet 20 valves in good condition after eight months where valves in stainless compositions of lower alloy content had failed in about three weeks).
5. Durimet T valves, fittings, hose connections and gage glass fittings: Strong vinegar at normal temperatures.

Equipment available in Durimet T and Durimet 20 includes pumps, valves, steam jets, fittings, tank outlets and special items designed for production in stainless steel. Some of these items are more readily available in Durimet 20 than Durimet T because Durimet 20, being somewhat superior to Durimet T for certain applications, has been selected as a "standard" for production reasons.

Chlorimet 3, a nickel-base alloy (62 Ni, 18 Cr, 18 Mo, 3 Fe and 0.07 C) possesses good corrosion resistance to acetic acid and is the preferred high strength alloy for exceptionally severe conditions. Although this alloy possesses good resistance to most acids, particularly under oxidizing con-

PALMETTO *Pyramid*

the most talked
about "VEE" type
molded packing

... talked about because
**IT HAS
EVERYTHING!**



Packing users all over the country are talking about the new packing that seals completely with simple finger-tightening . . . that is entirely automatic in performance . . . that stands up longer under grueling service!

Here are some of the many features that make PALMETTO PYRAMID worth talking about—and installing! Its sealing action is effected by internal pressure...the greater the internal pressure—the tighter the seal. A unique "arrow-head reservoir", which stores and distributes the lubricant . . . plus the unusually heavy wall construction . . . reduces wear and adds to service life.

PALMETTO PYRAMID gives exceptional performance on reciprocating as well as rotating equipment . . . is recommended without reservation for a wide variety of services and conditions.

If you are operating hydraulic or pneumatic equipment—under tough conditions—it will pay you to investigate the PALMETTO line of Molded Packings. There's plenty of talk about their performance—because longer, more efficient, more economical service always gets talked about! Write now for full information on these PALMETTO Molded Packings: PALMETTO PYRAMID, PALMETTO "U-RING", PALMETTO KUP and PALMETTO FLANGE.



PALMETTO "U-RING"



PALMETTO KUP



PALMETTO FLANGE

"It pays to know your
PALMETTO Distributor!"

This coupon is for your
convenience. Mail it today!

GREENE, TWEED & CO.

Manufacturers of PALMETTO Packings

BRONX BLVD. AT 238th ST. NEW YORK 46, N. Y.

Plants at New York, N. Y. and North Wales, Pa.

GREENE, TWEED & CO.
New York 66, N. Y.

GT-1567

☐ Send literature on
PALMETTO Pyramid and
other Molded Packings.

☐ Send PALMETTO
representative to
discuss packings.

Name

Company

Street

City


State



TYPE "S-A-D"

OIL BURNER

insures stability of
ignition in burning
waste materials



It operates with waste material (pumped directly to the burner and blended with fuel oil within the venturi chamber.

Type "S-A-D" Steam Atomizing Dual Fuel Oil Burner insures stability of ignition; reduces obnoxious fumes and stack solids; uses steam or compressed air for atomization; functions entirely on fuel oil where supply of waste product is intermittent; operates continuously without clogging or cleaning.

Write for your copy of Bulletin 21, it describes Type "S-A-D" in detail.



Main Offices & Factory: 1235 EAST SEDGLEY AVENUE, PHILADELPHIA 34, PA.
Texas Office: 2nd National Bank Bldg., Houston

NETTCO FOR YOUR SPECIFIC AGITATING REQUIREMENTS

NETTCO Model WT Agitator Drive Unit

For nearly half a century, the New England Tank & Tower Company has developed standardized parts and units which can be economically combined to provide highly specialized stirring equipment of many sizes, types and ratios. The economy, sound engineering, and rugged construction of NETTCO equipment are contributing importantly to the efficient operation of many a well-known process plant. End your agitating problems — once and for all — with dependable NETTCO Equipment!

Write for Catalog.

NEW ENGLAND TANK & TOWER COMPANY

87 TILKSTON STREET, EVERETT 49, MASSACHUSETTS

ditions, plant and laboratory tests have shown no appreciable attack on Chlorimet 2 in anhydrous acetic acid—organic compound mixtures which are reducing in nature.

Chlorimet 2, a nickel base alloy (62 Ni, 32 Mo, 3 Fe and 0.10C) is not suggested for acetic acid applications because of the excellent corrosion resistance of Chlorimet 3 and the somewhat lower cost of Chlorimet 3.

GLASS LINED STEEL

O. I. CHORMANN

The Pfaunder Co.
Rochester, N. Y.

ALL CONCENTRATIONS of acetic acid, at room temperature, may be successfully stored in single shell, one-piece, glass lined steel equipment, up to and including a maximum capacity of 8,000 gal. and a maximum internal pressure range of 40 to 80 lb. per sq.in., depending upon steel thickness and type of heads specified.

The normal maximum capacity is 4,500 gal., yet this capacity may be increased to, but not exceeding 8,000 gal., after careful consideration of all the conditions involved. Chemical durability of Pfaunder standard glasses, as applied to a steel base, is excellent towards acetic acid. This is equally true for acetic anhydride.

Table I gives the corrosion rates for various concentrations of acetic acid, at room temperature, for Pfaunder standard glasses that would be specified for this service. Based upon a minimum thickness of the cover coat of glass of 27 mils and a maximum thickness of 36 mils, the estimated life of the glass is excellent.

Table I—Corrosion Rate of Pfaunder Standard Glasses in Acetic Acid at Room Temperature


Acid Concentration Percent by Wt.	Number of Glasses 42 PF			
	27	42	42 PF	24
2	0.0057	0.0038	0.0040	0.0057
5	0.0156	0.0037	0.0039	0.0019
10	0.0095	0.0020	0.0037	0.0019
20	0.0078	0.0019	0.0019	0.0019
40	0.0078	0.0037	0.0328	0.0058
60	0.0077	0.0092	0.0390	0.0074
80	0.0019	0.0018	0.0020	0.0019
Glacial Acetic anhydride	0.0036	0.0074	0.0038	0.0058
	0.0038	0.0019	0.0041

When jacketed glass lined steel equipment is considered for conducting reactions involving acetic acid at elevated temperatures and pressures, some modifications with respect to types of equipment and capacities are necessary.

For reaction units involving elevated temperatures and pressures, there are two standard series of glass lined steel units to select from in order to meet a given set of operating conditions.

The first type of standard glass lined steel reactors cover a capacity range of 5 to 2,000 gal., but owing to the fact that the top head is held in place by clamps, the maximum allowable internal working pressure and the jacket pressure is somewhat less than in the case of the jacketed one-piece, glass lined steel reactors. This standard type reactor, known as the P, S, M, L, LL, XL and XXL series, covers an internal pressure range of 15 to 38 lb. per

ONLY THE LIQUIDS MOVE



... when they're mixed the *SK* way

THE SK Liquid Mixing Eductor operates on the jet principle—contains not a single moving part.

One liquid, under pressure, issues from a jet orifice at high velocity. It entrains another liquid—and, through extreme turbulence and friction, the two liquids are thoroughly mixed in any desired proportion.

Used both internally and externally (see drawings) these space-saving units daily are being applied to the proportioning of wetting agents, fertilizers, and insecticides—to the diluting of concentrates—and to the blending of fluids in such operations as commercial water-softening.

Jet-mixing of liquids has been pioneered by Schutte & Koerting—resulting in the accumulation of application know-how. Write today for Bulletin 2M.



SCHUTTE & KOERTING CO.
Manufacturing Engineers

1190 THOMPSON STREET • PHILADELPHIA 22, PA.


JET APPARATUS • CONDENSERS AND VACUUM PUMPS • HEAT TRANSFER EQUIPMENT
VALVES • ROTAMETERS • FLOW INDICATORS • GEAR PUMPS • STRAINERS
OIL BURNING EQUIPMENT • SPRAY NOZZLES AND ATOMIZERS • RADIATION TUBES



The WORK of a GIANT

• Within these walls a giant stands ready to work for you. Giving him no thought at all, you touch the control button. At your command his mighty muscles go into action and the load moves.

The operating mechanism of Shepard Niles hoists is completely enclosed, assuring permanent alignment—more durable, trouble-free, efficient service. Whatever your lifting or handling requirements may be, there's a Shepard Niles hoist for the job—more than 5,000 types and sizes.



Powerful and rugged, Shepard Niles Cranes are available in any desired capacity and span—designed to handle greatly varying loads with precision, safety and economy. Shepard Niles Cranes have the same sound, progressive features as do the Shepard Niles Hoists. A request will promptly bring illustrated bulletins.

Shepard Niles

CRANE & HOIST CORPORATION

The experience and facilities of Shepard Niles engineers are at your service. Plan ahead now for the right material handling equipment. Your inquiry will receive prompt attention.

382 SCHUYLER AVE. • MONTAUR FALLS, N. Y.

sq.in., and a jacket pressure range of 50 to 100 lb. per sq.in.

Another type of standard glass lined steel reactors covers a capacity range of 350 to 2,000 gal. They are of one-piece construction thereby permitting higher internal and jacket pressures. The internal pressure range is from 50 to 125 lb. per sq.in., and the jacket pressure range from 85 to 90 lb. per sq.in.

Test data on the chemical durability of Pfaudler standard glasses towards boiling acetic acid, are shown in Table II. The increase in temperature resulted in a decrease in the corrosion resistance yet the life of the respective glasses is exceptionally good.

Table II—Corrosion Rate of Pfaudler Standard Glasses in Acetic Acid at Boiling Temperature

Acid Concentration Percent by Weight	Number of Glasses	
	42	42PF
5	0.2594	0.4595
40	0.0928	0.2401
Glacial	0.0413	0.0836

Taking the highest corrosion rate given in Table II, namely, 0.4595 mils per year for glass No. 42PF, and a minimum cover glass thickness of 27 mils, the life of the glass exceeds fifty years.

The standard types of glass lined steel equipment manufactured for the chemical industry have given satisfactory performance for the chlorination, esterification and sulfonation of acetic acid.

Attention is drawn to the fact that all jacket pressures must be reduced by the amount corresponding to a full vacuum within the inner glass lined steel shell whenever such an operating condition exists.


SILVER

L. C. BURMAN
Baker & Co., Inc.
Newark, N. J.

SILVER is recommended as a material of construction resistant to corrosive attack by acetic acid in all concentrations and at all temperatures. Excess oxygen in the solution has no effect upon the resistance of the silver to such attack. Palladium is equally resistant to attack by acetic acid but is considerably more expensive than silver though palladium-silver alloys are recommended for those situations where mechanical conditions require an alloy tougher than the comparatively soft and ductile silver. A feature of silver in organic operations is that many of the silver organic compounds are colorless and therefore not objectionable should small quantities contaminate the product.

Apart from the use of silver for its corrosion resistance are the superior heat transfer qualities and the ease of fabricating complicated shapes. Coil and tubular condensers and heat exchangers are successfully used against acetic acid corrosion. At pressures beyond which solid silver or silver alloys may not be used economically because of the weight of metal required for mechanical strength, silver clad materials are available and in use. Two types of cladding are in general use. One involves

The Man in the Field KNOWS when Pre-Fabricated Piping is Right



Men in the field who erect piping know when shop fabrication is well done . . . they know if the sub-assemblies fit correctly, line up easily and have all field welds or flanged joints in accessible positions. When this is the case, the erecting job is easier . . . saves both time and money.

Midwest has a Construction Department which has erected piping of all kinds for 46 years. The critical attitude of this department is the best stimulant to our four pipe-fabricating plants. The Construction Department also frequently contributes useful and practical suggestions for improving pipe fabrication.

This situation has a powerful effect in keeping the whole organization alert . . . and in encouraging continuous improvement. It is one of many reasons why you get the best when you buy Midwest Pre-Fabricated Piping . . . either as materials furnished or piping completely installed.

MIDWEST
CONTRACTING DEPARTMENT
Checks
MIDWEST PIPING QUALITY



MIDWEST

PIPING & SUPPLY CO., INC.

MAIN OFFICE: 1450 SOUTH SECOND ST., ST. LOUIS 4, MO.

Plants: St. Louis, Pasadic, Los Angeles and South Boston • Sales Offices: New York 7—30 Church St.
• Chicago 3—645 Marquette Bldg. • Los Angeles 33—320 Anderson St. • Houston 2—229 Shell
Bldg. • Tulsa 3—533 Mayo Bldg. • Atlanta 3—Red Rock Bldg. • South Boston 27—426 First St.

2266



Standard or Special Acid-Proof Pipe

Above are a few of many types of acid-proof pipe fittings regularly being made by Maurice Knight. Knight-Ware Acid-Proof Pipe with bell and spigot and flange type connections is made in standard and in special designs to meet unusual needs and installation conditions. Bore sizes range from one to 60".

Permanite Armored Knight-Ware Pipe is available where the pipe may be subjected to shock or physical damage.

Knight-Ware Acid-Proof Pipe is used in laboratories, commercial buildings and industrial plants. Since its entire body is acid-proof, not just the glaze alone, it is the ideal equipment for carrying corrosive liquids or gases.

MAURICE A. KNIGHT

111 Kelly Ave.

Akron 9, Ohio



the use of high pressure and heat for a metal to metal bond between silver and a base metal. The other involves fitting silver or silver alloy shapes to parts or equipment already fabricated or partially fabricated. In this latter case, the silver liner may be expanded into or drawn tightly over heavy walled tubing or pipe. Or a tube sheet and its holes may be lined to receive a bundle of tubes clad inside, outside or on both sides. In general, silver and the silver alloys are readily fabricated into any required shapes for the purpose of protecting base metal chemical equipment.

Techniques have been developed for the joining of silver lined tubing with or without flanges. The same is true for tubing clad on the outside, or inside and outside, except that these are joined without flanges. These techniques involve the use of silver rings inside or outside of the tubing, as required, and silver solders.


TANTALUM

FREDERICK L. HUNTER
Fansteel Metallurgical Corp.
North Chicago, Ill.

TANTALUM has been found inert to acetic acid or mixtures containing acetic acid at all concentrations or temperatures at which it has been tested or used. At low concentrations and mild temperatures, other materials are sufficiently resistant so that tantalum is recommended only for severe conditions, and for heat transfer surfaces.

Tests up to 175 deg. C. show no attack on tantalum. Above this temperature the effect, if any, is not known. So far as tests and actual service indicate, the degree of concentration, either general or localized, has no apparent effect upon tantalum.

It has been observed in industry that the presence of certain contaminating materials enhances the corrosive effect of acetic acid, but this does not seem to affect tantalum. A tantalum condenser has



Tantalum condensers have been used successfully for six years in hot distillation of crude acetic acid where contaminating materials cause severe corrosive conditions

been in service six years in the distillation of crude acetic acid from wood products under conditions where the acid quickly corroded other condenser materials which had been tried.

Tantalum heaters have been used successfully for heating crude acetic acid for distillation into pure acid. In this case, the use of tantalum in the condenser was not considered necessary.

Because of this peculiar effect of contaminating materials, users are urged to test materials of construction under actual operating conditions, and not rely upon laboratory tests with pure or commercial acid.

FROM THE LOG OF EXPERIENCE

DAN GUTLEBEN, Engineer

JOINTS in tanks and shells of manufacturing apparatus are now usually welded. No attention ever needs to be applied to them. However there are still in use millions of joints made before welding proficiency was achieved and so the maintenance slaves are occasionally annoyed with a cantankerous leak. If welding is applied, the entire joint and every rivet head has to be welded as the strain from the heat opens the joint or loosens the rivet ahead of the electrode, and it may even cause the previously welded joint to crack. Calking also lacks permanency on an old rusty joint especially if there is alternate heating and cooling.

SEAFARING MEN have a device to stop leaks in butt joints that land lubbers can apply with profit. The sketch shows the bottom cone of a 15-ft. water sedimentation tank with butt strapped joints that continued stubbornly to leak even after every rivet had been welded. The old shipyard stunt licked the difficulty. As shown in the sketch a hole was drilled through the outside buttstrap and tapped for the $\frac{1}{2}$ in. SAE threaded nozzle of a screw gun. The gun forced red lead paste behind the butt straps under high pressure and sealed the leaks. We have thus plugged leaks in sugar mixers 25 years ago. In fact the device is so old that it can now be safely re-described under the head of new discoveries.

SOME OF THE OLD JOINTS cannot be economically repaired because of the time-consuming dismantling of the circulator drive above as well as the condenser connections. The sugar boiler just cannot spare the pan although he keeps right on kicking about the deficiency of the vacuum. To maintain his happiness, two joints, 30 years old, were made with a copper butt strap riveted on the inside as shown and then packed behind by the aid of the red lead gun referred to above. It required a 36-hr. week-end punishment and 70 lb. of red lead putty but it avoided inconvenience

to the customers. This joint may not be permanent as geologists reckon time but none of us will live long enough to disprove it.





ROW BOATS that old Elisha Mills used to build for his fishing trips were made of clear "cork pine" that was still available in the Michigan lake country in 1900. To secure a tight joint between the longitudinal boards, Elisha compressed the fibers of the edge of the boards by means of a hickory swage about 2 in. wide. Thus he obtained a shiplap cross section with a quarter inch of the board thickness compressed a sixteenth to an eighth of an inch. Then he planed off the edge that was not compressed and assembled the boards into the hull. When the boat hit the water the compressed edges swelled rapidly and made tight joints.

THE OLD BOLTED JOINTS in the shell of copper vacuum pans, designed partly for stiffness, are usually made with red lead paste as the surfaces are not smooth enough for gaskets of rubber or asbestos. In recent years other joint sealing pastes have come into use. But anyhow after 10 years of exposure to boiling out alternately with caustic soda and hydrochloric acid for scale removal, the joints begin to leak. In this case the joint is separated and a $\frac{1}{4}$ -in. soft copper calking strip, covered with thin red lead paste, is inserted. The old $\frac{7}{8}$ in. bolt holes are reamed out for $1\frac{1}{4}$ in. bolts and then the bolts are pulled up with

a long-handled wrench till a caliper shows that they are beginning to stretch. The copper strip is then calked on the inside, and forever after protects the red lead from exposure. The same device is used on the juice side of calandria tube sheets; the steam side can be made permanently tight with red lead, but the important thing is to use oversize bolts even though the designer says it's crazy! It is also important to pull up all of the bolts evenly. The last round that stretches the bolt may gain less than an eighth of a turn.

EVERY BEET SUGAR ESTATE has a staff of agriculturists who circulate among the farmer clientele and establish a mentor-disciple relationship. These peregrinating pedagogues furnish the highly specialized technology that beet culture demands plus the latest in farm mechanics and, for good measure, they exude cultural influence. The beet has the unique characteristic that it projects a network of roots into the soil as far as seven feet in depth. After the harvest these supply a ton of humus per acre and leave a honeycomb of channels for aeration, bacterial action and water supply, which improve the soil for rotation with other crops. Beet culture demands superior intelligence, deep plowing and thorough soil preparation but in return it increases the productive capacity of the lands and raises the taxes. Then along comes an exploding city like Los Angeles and demands onions and carrots whose waterlogged quality renders long-

Tank butt joints can be sealed as shown (lower left) in the sketch. Row boat construction gives an idea for use in wooden tanks and containers (upper right). Old bolted joints (below) may be calked with copper strips. Sugar boilers have repaired joints (lower right) by using a butt strap and red lead gun



Help for your CHEMICAL STORAGE and PROCESSING PROBLEMS •



STAINLESS STEEL STOCK POTS

• Solve many of your storage and processing problems with these rust-proof, acid-resisting, easy-to-clean Stock Pots.

Made throughout of 16 gauge, 18-8 Stainless Steel, welded construction, with all inside welds ground smooth and polished.

SPECIAL EQUIPMENT

These pots can be purchased with or without covers and if desired can be fitted with casters to make them portable.

Write for complete specifications and prices.

We also manufacture a complete line of Storage Tanks and Equipment.

METAL GLASS PRODUCTS CO. DEPT. C
BELDING, MICH.

Disposal Problem?



Here's the
American Grinder
that will help you
solve it . . .

Illustration at left shows typical compact brewery installation. An increasing number of plants and laboratories are finding the use of the American Laboratory Grinder the most efficient method of grinding for disposal purposes.

Many plants throughout the country depend upon this efficient method of production grinding—and crushing for disposal and other purposes. Crushes a wide variety of fibrous and friable materials to uniform size. Sturdily-built—compact—gives maximum performance with minimum maintenance for continuous operation. Capacities from 100 to 2,000 lbs. per hour.



Write for detailed information and complete specifications.

American PULVERIZER COMPANY
Originators and Manufacturers of
Rins Crushers and Pulverizers
1219 Macklind Ave.,
ST. LOUIS 10, Mo.

distance transport costly while the concentrated dried extract from the beet is a good traveller. Moreover the garden-plot subdivisions near the cities are not big enough for sugar planting with modern mechanization. Beets require processing in transit to the consumer while the garden produce, being a ready-to-use product, attracts a higher price. Anyhow, the sugar factory, having improved its competitor's position, is driven from the field and moves with its accessory activities of stock feeding to open country.

THE END PRODUCTS from cane and beets after the extraction of sugar were originally dross, refused even at the public dump. Land-baron Hihn magnanimously and for the annual rental of \$1 executed a 10-yr. lease for the site of a 50-ton beet sugar factory near the great California resort of Santa Cruz. The factory was built in 1874 at an outlay of \$70,000 and produced some sugar and an amount of molasses disproportionately large. After four years the crude little factory defaulted its rental payment and reverted to farmer Hihn. He cast out the machinery to make room for hay but the stubborn, tar-like molasses resisted his efforts at disposal. He lacked knowledge for its preparation for stock feed. His law abiding instinct plus the fact that he did not know how, prevented him from converting the nuisance into "white mule," an activity promoted in recent years by Uncle Sam for the Virgin Islanders. This product provides bread-and-butter for the islanders and headaches for the "nephews."

BEET LEAVES, now highly prized for stock feed, were recommended by a farmer of Lamar, Colo. as long ago as 1903 for use in the manufacture of Pittsburgh Stogies. As reported in the *Planter*, he has made cigars from beet leaves soaked in an infusion of tobacco. "These cigars," he avers, "have a better flavor than many now on the market and are superior in sweetness and delicacy of flavor to any Connecticut cabbage fillers ever made."

BEEF STEAK is a byproduct of beet sugar production. The company farm at the Tracy, Calif., sugar estate, now classed as manufacturing equipment, originally alternated white patches of alkali with salt grass. Not even weeds would grow on this soil. For years the farm was flooded with the sewage from the factory which flushed the alkali through the drainage system and left the plant food in the soil. Now this farm is featured as souvenir postal cards glorifying the beauties of California. The field now produces beets about every third year and rotates with hay and grain. The hay and grain, tempered with cottonseed oilcake, and mixed with exhausted beet pulp and final molasses are fed to steers. The end product from the feed pens and the drainage are returned to the fields. The waste water from the Steffen process is elaborated into the meat extender, mono sodium glutamate, by the aid of which the housewife can convert corn meal mush with a judicious admixture of nuts, celery, onions and tomatoes into a delectable meat loaf. Cowboy Collinson (imported from Texas) is charged with the responsibility

You Will Want to Know More About These


SW
*Sanitary
Type*

STRUTHERS WELLS

EVAPORATORS



Stainless Steel, double effect sanitary evaporator.



Construction view
of one effect.

STRUTHERS WELLS design and build dependable evaporators and other required equipment for the concentration of fruit and vegetable juices, milk, meat extracts and other food products. Stainless Steel, Nickel, Inconel and other alloys best suited to the material being processed are used. All internal parts are highly polished and easily accessible for cleaning. Arrangements for precision control of temperatures and heating time prevent product damage.

Pasteurizing equipment is also available for processing at elevated temperatures and with closely controlled heating time.

Write for Bulletin A-35
Technical & Informative
Describing All Types of
**STRUTHERS WELLS
EVAPORATORS**

STRUTHERS WELLS CORPORATION

PROCESS EQUIPMENT DIVISION

WARREN, PENNA.

PLANTS AT WARREN, PENNA. AND THOUSVILLE, PENNA.

6 WAYS VIRGINIA SO₂

Can Save Money for You!

1
**REDUCING
AGENT**

2
**REACTION
VEHICLE**

3
**ACIDIFICATION
REAGENT**

4
**SELECTIVE
SOLVENT**

5
**BLEACHING
AGENT**

6
**FOOD
PRESERVATIVE**



VIRGINIA "ESOTOO"
shipped in 150 lb. cylinders,
ten drums, single-unit
and multi-unit tank cars

VIRGINIA

SMELTING COMPANY

WEST NORFOLK, VIRGINIA

SALES OFFICES—76 BEAVER ST. NEW YORK 5 — 131 STATE ST. BOSTON 4



Processors of sugar, clay, minerals, leathers, textiles, foods and other products report better process control, higher yield, and improved finished product quality with VIRGINIA "ESOTOO". This uniformly pure reagent is also gaining acceptance as a dechlorinator for water purification. What is your product? Ask us how "ESOTOO" can improve your process.

of providing satisfactory working conditions so that the steers can eat, rest, extract contentment out of life and produce beef. Among the comforts, he supplies a scratcher to relieve the itch of stretching hide. This device consists of a discarded beet elevator chain draped over two posts seven feet high with the ends securely anchored in the ground after the manner



of a suspension bridge. By going under or over the catenary or by straddling the inclined anchorage chain, fore or aft, the steer reaches every part of his anatomy and enjoys relief.

AN IMPORTANT BYPRODUCT of the stress and strain of the daily task is humor used on the spot as an antidote for gloom and frayed nerves. It is a mystic thing once dispensed by specialists as a sedative at the courts of harassed kings. The boys extracted it even out of old Doc Portius' Prussian discipline. Doc, also affectionately known as "Raffinose," was the chief of staff at Chino. As star performer he demanded obsequious respect from the subordinates. He graduated from the University of Jena about 1876, taught for two years at the Braunschweig Sugar Institute and then worked in a German sugar house till Oxnard discovered him in '91 and commissioned him to select an operating crew and proceed to Chino, Calif., to make sugar.


He used to bid goodnight with a flourish to publicize his departure, and when everybody had settled down to the enjoyment of freedom from kibitzing, he would suddenly reappear right in the midst of a crap game. Occasionally at low twelve he might slip over in his carpet slippers from his bachelor quarters above the office. Thoughtlessly he switched on the light and thus unwittingly flashed the signal which the official lookout broadcast to warn the craftsmen.

WALTER TURNER, the colored coachman with impaired hearing and a sluggish mentality, used to meet Doc at the Pomona station at 7 p.m. with the old two-seated surrey, the rear seat of which had become loose. The roads were rough and dusty. The old gray mare always started with a jerk and, if Doc ever made any objections, they were lost on Walter's perception. The surrey's rattle soothed Walter's ears and besides he had grown callous to bawling out. One evening when he drew up at the Chino clubhouse he waited for Doc to get out. Sensing no stir in the rear, he looked around and was surprised to observe that both Doc and the seat were gone. He drove back and found Doc undamaged but exhibiting a ruffled temper.

DOC'S OCCASIONAL TRIPS to Los Angeles served the purpose of surcease from toil. He usually met Engineer Baur there and Southern Pacific's chief engineer William Hood for the enjoyment of music or the "Gemütlichkeit" of a Rathskeller. On one occasion he met an important Chino villager making holiday accompanied by

**Trade Mark of
Genuine Jeffrey
Replacement Parts**

The familiar Jeffrey trade mark on replacement parts identifies them with a background of many years of sound engineering and skilled metallurgy. When improvements can be made on the original part, Jeffrey will make them. For exact fit, long life and smooth operation, insist on Jeffrey parts. Look for the important JM trade mark on the part itself.



(Reg. U. S. Pat. Off.)

THE JEFFREY

MANUFACTURING COMPANY


309-39 NORTH FOURTH ST., COLUMBUS 16, OHIO

Baltimore 1	Buffalo 2	Cleveland 13	Hartford	Minneapolis 11	Pittsburgh 13
Birmingham 3	Chicago 9	St. Louis 3	Newark 3	New York 7	Salt Lake City 1
Boston 16	Channahon 7	Detroit 13	Hattington 13	Philadelphia 3	San Antonio 3

**ESTABLISHED
1877**

JM

**LOWER COST
COOLING
FOR
INDUSTRIAL POWER
EQUIPMENT**



NIAGARA AERO HEAT EXCHANGERS provide a closed system of re-circulated clean jacket water at controlled temperatures and without the consumption of cooling water except for the small amount which is evaporated. Heat is absorbed at the rate of 1000 BTU per pound of water evaporated.

Ample cooling capacity is available in compact, economical equipment. There are additional savings in the cost of piping and pumping.

The operating dependability of NIAGARA AERO HEAT EXCHANGERS is assured by their record of long years of service under the most difficult industrial conditions. Ask for Bulletin 96-CE

NIAGARA BLOWER COMPANY

Over 30 Years of Service in Industrial Air Engineering
405 LEXINGTON AVE., NEW YORK 17, N. Y.
Field Engineering Offices in Principal Cities

INDUSTRIAL COOLING  HEATING • DRYING
NIAGARA
HUMIDIFYING • AIR ENGINEERING EQUIPMENT

two attractive young women. Doc suggested dinner. He had in mind the German custom while respondents contemplated the American plan. Doc enjoyed the dinner and urged generous selection from the menu or as he expressed it, "Griefen sie hinein ins menschlichen Leben." At the conclusion of the festivities, Doc picked up his check and paid for it, leaving the others to do likewise, all in accordance with the sensible custom of Dutch treat.

UNUSUAL EXPERIENCES in never-ending variety come to the craftsmen. Something happened in one of Tom Lacey's wells at the Santa Ana factory and before anyone knew it, the condensers, leg pipes and sewer were plugged with sand and the water overflowed into the pans and evaporators and flooded out the works. No mechanical damage was suffered but the works lost five hours of production.

THE MOLASSES STORAGE TANK back of the machine shop had a 4-ft. square patch welded on by a wartime welder just in line with the passage through the shop. One Saturday evening when the tank was full this patch grew tired and let go, sending a gusher of 80-Brix molasses through the shop and boiler house. In a few seconds the draft ducts under the boilers were sealed. The fireman had the presence of mind to shut off the fuel gas. The feed pumps chattered to a stop but the hot furnaces maintained combustion for a time with molasses. The engineman saw the avalanche of molasses headed towards his station and tripped the throttle on the engine. The big flywheel was just idling to a stop when the molasses reached the pit.

THE HUNTINGTON BEACH factory was erected by skipper Tony Tovatt. After the close of a Saturday night show he drove home by way of the factory. He roamed about the building in the moonlight to appraise the day's accomplishment and lingered about the well-drilling operation. Here he observed an odor of gas and when he struck a match a tongue of flames leaped up above his head. He grew excited and hastened to the bedside of Boss Sinsheimer to deliver the tremendous news. He urged immediate liquidation of the sugar house and the expenditure of the proceeds plus the balance of the construction account for expansion of their 64-acre property. The boss told him to go to bed and sleep it off! However ten years later the Holly Sugar Corp. abandoned sugar operations there and developed its underground assets into the highly profitable Holly Oil Co.

A JUSTIFIABLE HOBBY possesses the quality of interest or usefulness beyond the individual hobbyist. Oliver Swan while manager of the Grand Island, Neb., beet sugar factory, pursued the hobby of pheasant production. He grew large flocks and then released them to propagate on the prairies. This developed into a public benefaction. It brought profit to the farmers who sold hunting licenses to tired businessmen. It also brought to Swan a letter of thanks from the governor of the state.

NAMES IN THE NEWS



J. J. Keville, Jr.

John J. Keville, Jr., has been appointed director of product application of the plastics division of Celanese Corp. of America, where he will head the corps of engineers who evaluate markets for Celanese plastics and study techniques and processes for the fabrication of new products.

Perry A. Martinson has resumed duties with Johns-Manville in Chicago after discharge from military service. Mr. Martinson has returned to his position as chemical engineer in the filler and filtration department.

Ivan Bloch, chief of the Bonneville-Power Administration's division of industrial and resources development, has been loaned to the Department of the Interior as special consultant to Secretary J. A. Krug. In this capacity, Mr. Bloch will prepare a series of reports dealing with the economic growth of the nation, particularly in the West and in Alaska.

Robert Wilson, Harvard University physicist formerly with the Los Alamos, N. M., laboratory of the Manhattan District Project, has been elected chairman of the Federation of American Scientists.

Frederick Whittier has joined the Bickford Research Laboratories at Avon, Conn. Mr. Whittier was formerly engaged in research and other technical work for the Barrett Division of the Allied Chemical & Dye Corp.

R. J. Schrader, formerly head of the chemical engineering department of Tennessee Eastman Corp. at Oak Ridge, has been transferred to the plant at Kingsport, Tenn., where he has been assigned duties in the research division.

R. R. Williams, retired director of chemical research of the Bell Telephone Laboratories, has been announced the recipient of the 1947 Perkin Medal. Presentation will take place in January.



J. R. Ruhoff

John R. Ruhoff, lately colonel, Corps of Engineers, U. S. Army, has rejoined the staff of Mallinckrodt Chemical Works, St. Louis, as technical director.

W. Burling Tucker, for many years district engineer for the California State Division of Mines, Los Angeles, has been appointed chief of the division with headquarters in San Francisco to fill the vacancy left by the retirement of **Walter W. Bradley**.

Everett B. Evleth has been appointed president of Ray Control Co., Pasadena, a subsidiary of Lane-Wells Co. Mr. Evleth was formerly vice president and general manager of Brown Instrument Co. of Philadelphia.

William H. Milton, former assistant general manager of the chemical department, General Electric Co., is to continue as administrator in the company's operation of the Hanford Engineer Works in eastern Washington. **David H. Lauder**, former general manager of the service engineering division of the company's apparatus department, is works manager.

Edward A. Schraishuhn has been released from service in the Navy and has joined the chemical engineering staff at the University of Pennsylvania. Mr. Schraishuhn is a Pennsylvania graduate.

Harold M. Vessey has joined the chemical engineering group of the technical department at the South Charleston division of Westvaco Chlorine Products Corp. Mr. Vessey before joining Westvaco's staff, was employed by the Pennsylvania Industrial Chemical Corp., while at the same time doing graduate work in chemical engineering at the University of Pennsylvania. Two other additions include **Albert G. Draeger**, who was employed by Victor Chemical Co. before coming to Westvaco, and **Henry C. Watlington** who was with the research group of the Dan River and Riverside Cotton Mills.



E. D. Wingfield

E. D. Wingfield has been appointed general manager of Freeport Sulphur Co. Mr. Wingfield has been assistant general manager for about the past two years. He will continue to have offices in New Orleans, headquarters for the company's mines in Texas and Louisiana.

Frederick D. Rossini, chief of the thermochemistry and hydrocarbons section of the National Bureau of Standards, has been elected president of the standing committee of thermochemistry of the International Union of Chemistry.

Nathan E. Van Stone, director of manufacturing operations of the Sherwin-Williams Co., has been appointed vice president and executive director of the special chemical products division.


M. H. Clarke has been appointed to the post of vice president and director of manufacturing of the Dayton Rubber Manufacturing Co. He will direct engineering, production, laboratory, traffic, safety and plant protection activities in all the company's operations.

D. B. Keyes has been elected a member of the board of directors of the American Potash and Chemical Co. Dr. Keyes still retains his membership on the boards of Heyden Chemical Corp. and American Plastics Corp.

Frederick B. Sackett has been appointed manager of the Defender plant of the Du Pont photo products department in Rochester. Mr. Sackett succeeds **L. Dudley Field**, who became the department's adviser on paper products.

Horace D. Acaster has been appointed to fill the newly created office of manager of industrial relations of the Calco Chemical Division, American Cyanamid Co.

C. William Lenth is director of research of the Jaques Manufacturing Co. of Chi-



Stainless & Alloy Steel Castings for Modern Requirements!

Experience symbolizes progress. Atlas foundrymen having pioneered many of the revolutionary casting methods in use today, have the experience so necessary to meet modern requirements. Complete facilities for casting all analyses alloys for all purposes—under the direction of skilled metallurgists—assure you of the finest in stainless and alloy steel castings.

Our illustrated 8 page bulletin 45 is available, now. Write for it.



**ATLAS STAINLESS STEEL CASTING
DIVISION**

ATLAS FOUNDRY COMPANY

540 LYONS AVENUE IRVINGTON 11, N. J.

276

cago. Dr. Lenth succeeds J. R. Chittick, who has held the post for 30 years, and who will continue actively to serve the company as technical consultant.

R. P. Hutchins, after 15 years in the development department of Procter and Gamble Co., has joined the staff of the French Oil Mill Machinery Co. as technical director of the solvent extraction division.

Frederick C. Nachod is now with Sterling-Winthrop Research Institute, Rensselaer, N. Y. Dr. Nachod was formerly with Atlantic Refining Co. in Philadelphia and with the Permutit Co. in New York.

Arno C. Fieldner, chief of the Fuels and Explosives Branch of the Bureau of Mines, received the Percy Nicols Award, given by AIME and ASME Gas Division, Oct. 24.

William T. Read has been appointed as a scientific research advisor to the Research and Development Division of the War Department's General Staff. Dr. Read represents chemistry and chemical engineering in the Scientific Liaison Group.

Ralph H. Ball, assistant director of the plastics division of the Celanese Corp. of America, is now chairman of the Paint, Varnish and Plastics Division of the American Chemical Society, succeeding Adolph C. Elm of New Jersey Zinc Co.

Harry A. Reed has been elected vice president of Day & Zimmerman, Inc., and will coordinate new business activities. Thomas W. Hopper succeeds Mr. Reed as engineering manager.

Howard K. Nason has been promoted to associate director of the central research department of Monsanto Chemical Co. in Dayton, Ohio.

Edward M. Hubbard, Milton Kosmin and Ralph R. Werner have been appointed group leaders at the central research department of Monsanto Chemical Co. in Dayton, Ohio.


Whitney Weinrich has joined the teaching staff in chemical engineering at the University of Pennsylvania. During the war Mr. Weinrich was a member of the refining division of the Petroleum Administration for War in Washington, and has been associated most recently with the research and chemical engineering departments of the Phillips Petroleum Co. in Bartlesville, Okla.

James N. Pryor has taken a leave of absence from the research and development department of the Davison Chemical Corp. to accept a position on the chemical engineering staff at the University of Pennsylvania. Mr. Pryor is a graduate in chemical engineering of John Hopkins University.

Charles W. Weitzel has resumed his duties as an engineer with Johns-Manville in New York after discharge from the Army. Mr. Weitzel came with the company in 1937, after graduation from Cornell University and previous employment

General Controls
SAUNDER'S TYPE
HYDRAMOTOR VALVES

G-2-17



Hydramotor operated Saunders valves for chemical solutions, acids and pulpy liquids.

Simplified two-wire control returns to the closed position on current failure assuring trouble-free operation.

Hydramotor operator is sealed in oil for life, eliminating oiling and annual checkups, which represents a saving in maintenance costs.

Write for new 1946 Catalog 52C.

GENERAL CONTROLS
801 ALLEN AVENUE GLENDALE 1, CALIF.

FACTORY BRANCHES: PHILADELPHIA • ATLANTA
BOSTON • CHICAGO • KANSAS CITY • NEW YORK
DALLAS • DENVER • DETROIT • CLEVELAND • HOUSTON
SAN FRANCISCO • SEATTLE • PITTSBURGH
DISTRIBUTORS IN PRINCIPAL CITIES

2-3


Reservoir for Industry

In drum or tank car lots... whether for construction or maintenance, processing or production... the reservoir of Flintkote Industrial Products offers many time-and-money-saving advantages.

Tire cord solutioning is one of the many applications of Flintkote Syntex[®] aqueous dispersions of rubber.



An outstanding use of Flintkote Hydralt[®] coatings is the protection of steel against corrosion.



Flintkote fluid rubber compounds are used for rugs and carpet backing and also as saturants, coatings, and bonding cements.



All types of insulation require the kind of protection from the elements that Flintkote insulation coatings provide.



Fibre board for containers is made water-resistant with Flintsize[®] added during manufacture.



Flintkote sound-deadening materials and industrial adhesives are important components of automobiles and many other consumer durable goods.



*TM Reg. U. S. Pat. Off.
Trade-mark

A reservoir of supply for your needs. That's another way of describing Flintkote's complete research, development and manufacturing facilities. Let us help you. Write us today.

Flintkote-Products for Industry

THE FLINTKOTE COMPANY-INDUSTRIAL PRODUCTS DIVISION
Atlanta • Boston • Chicago Heights • Detroit • Houston



30 ROCKEFELLER PLAZA, NEW YORK 20, N. Y.
Los Angeles • New Orleans • Washington • Toronto • Montreal


IN 1929

—was installed the first of the Paul O. Abbé mills now in place in the plants of

VITA-VAR CORPORATION

—of Newark, New Jersey, nationally known for the high quality of its paints and enamels.

These mills have been running night and day since they were installed. The first mill has been in continuous operation since it was set up in the Vita-Var plant seventeen years ago. The original burrstone lining is still in place.



A Typical Paul O. Abbé Mill
Widely Used by Paint Manufacturers.

Paul O. Abbé mills and mixers have won a place as standard equipment in many other industries by half a century of efficient production. Let us know your grinding or mixing problem.

PAUL O. ABBÉ

375 Center Avenue
LITTLE FALLS, N. J.

with Consolidated Gas Co. He is presently employed as chemical engineer for filter aids and fillers manufactured by the Celite Division for the processing industries.

G. L. Alcorn, former manager of the Weyerhaeuser Timber Co. pulp mill at Everett, Wash., is to manage a kraft mill Weyerhaeuser has under construction at Longview, Wash. Mr. Alcorn will be succeeded by Russel J. LeRoux, who has been associated with the Rhineland Paper Co., Rhineland, Wis.

Norman C. Hill is now chief chemist of the government synthetic rubber laboratory in Akron.

Nathan E. Van Stone, director of manufacturing operations of the Sherwin-Williams Co., has been appointed vice president and executive director of the special chemical products division of the company and its affiliates. Arthur B. Holton has been appointed technical director of paint, varnish and lacquer products.

Maurice H. Bigelow has rejoined the staff of the Plaskon Division, Libbey-Owens-Ford Glass Co., as director of technical service after Army service as a lieutenant colonel in the CWS.

Lawrence L. Jones has been named superintendent of General Electric Co.'s new factory for the manufacture of Glyptal alkyd resins at Anaheim, Calif.

Robert Gottschalk has joined Standard Oil Co. (Ind.) as assistant manager of the development and patent department.

J. W. Dykes, formerly manager of the pharmaceutical manufacturing division at the Bound Brook plant of Calco Chemical Division, American Cyanamid Co., has been named production manager of the new Willow Island, W. Va., works of the company. Harold T. Lacey is now senior chemist of the new Willow Island works, and a member of the technical committee of the company's Marietta works, Marietta, Ohio.

James F. Bourland is now chief chemist in the pharmaceutical department of the new Willow Island works of Calco Chemical Division, American Cyanamid Co.

Byron Elmer Lauer, former professor of chemical engineering at North Carolina State College, and recently in charge of procurement of war materials for the construction division, Office of Inspector General, has been appointed professor in the department of chemical engineering at the University of Colorado, Boulder.

Robert B. Coons, senior partner in Coons, Milton & Co., San Francisco, has joined the executive staff of American Potash & Chemical Corp., Los Angeles. Mr. Coons will give up his general partnership with Coons, Milton & Co., but will remain identified with its activities.

Gordon A. Boelter, formerly production superintendent of Goodyear Synthetic Rubber Corp., Los Angeles, has been ap-

You'll find
everything you
want to know about
MOTOR CONTROLS
IN THE
FEDERALOG



Bring your electrical equipment data file up to date . . . with a copy of the FEDERALOG! Just off the press, the FEDERALOG is one of today's most-needed catalogs on Motor Controls, Safety Switches, Circuit Breakers, Service Equipment, Panelboards and Multi-Breakers. Mail the coupon today!

MOTOR CONTROLS
for the
CHEMICAL INDUSTRIES



MAGNETIC A.C. STARTER. Bulletin 504—equipped with weatherproof, water-tight cast iron enclosure; built in 4 sizes for motors up to 50 hp 440-600 v.

FEDERAL ELECTRIC PRODUCTS CO., INC.
50 Paris St., Newark 5, N. J. (Dept. C-3)

Please send a copy of the FEDERALOG to

Name and Title _____

Company _____

Address _____

**Your production
problems solved**

by using



**BUFLOVAK Research
and Testing Service**

Modern semi-plant units embody most advanced design.

In the development of new and better processes, BUFLOVAK can help you save time and money by processing your product in full semi-plant scale.

To assist you in the solution of processing problems and the development of new methods, BUFLOVAK operate modern Research and Testing Laboratories. Here practical research is conducted on pilot-plant units; designed for drying, evaporating and processing foods or chemicals.


Vacuum Double Drum Dryer and Experimental Evaporator in the BUFLOVAK Research Laboratory.



Vacuum Rotary Dryer.

Tests, such as these, give you definite results that safeguard your investment in New BUFLOVAK Equipment, because they show unmistakably—right at the start, what will be obtained from a given process.

Some of the Evaporator equipment in the BUFLOVAK Research Laboratory.



BUFLOVAK Research and

Testing Laboratories

There's a valuable "Know-How" learned through completing more than 5000 processing tests. May we share that experience with you?

BUFLOVAK EQUIPMENT DIVISION
OF BLAW-KNOX CO.
1551 Fillmore Avenue • Buffalo 11, New York

**HAVE YOU HEARD
HOW THIS MILL
CAN HELP YOU?**



**FINER GRINDING,
MORE UNIFORM
DISPERSIONS RESULT
IN BETTER PRODUCTS**

The Eppenbach High Speed Wet Grinding and Colloid Mill is a dual purpose machine:

- ① It reduces particles to sub-micro-dimensions by grinding, and
- ② Effects perfect dispersion of such particles into fluid or plastic materials.

An examination of the turbine design shows why it is possible for a single machine to perform these two distinct operations. Liquid is broken up into minute globules by high velocity impact at top of turbine. Suspended material is mechanically sheared by the rotor and stator teeth, and hydraulically sheared by the final smooth surfaces of rotor and stator.

Eppenbach Mills are available in laboratory and production sizes. Capacities range from 1/2 to 3600 gallons per hour or higher.

Write for complete details. Ask for a copy of Catalog No. 401.

EPPENBACH, INC.

LONG ISLAND CITY 1, N. Y.

Eppenbach

pointed plant superintendent to succeed Jack K. Lockridge, who has become manager of the new plastic production division of Goodyear Aircraft Corp., Akron, Ohio. Benjamin A. Rosinski will replace Mr. Boelter as production superintendent.

Charles Tichy is the new general manager for the Reynolds Metals Co. aluminum extrusion plant, Phoenix, Ariz. William F. Hunt is the new chief engineer.

Donald J. Will has been elected president of Stuart Oxygen Co., San Francisco. Patrick Coyne assumes the presidency of the company's subsidiaries, Standard Acetylene Co., Ltd., Oakland; Valley Oxygen Co., Hanford, Calif.; and Pacific Carbide & Alloys Co., Portland.

Roland V. Rodman, vice president and general manager of Bay Petroleum Corp., has been named president, succeeding Charles U. Bay, who has been chosen chairman of the board of directors.

Thomas E. Brown has been appointed assistant superintendent of the Bacchus, Utah, plant of Hercules Powder Co.

C. Burke Miles has been appointed director of the Newark, Calif., division of the technical department of Westvaco Chlorine Products Corp.

Carleton Ellis, Jr., has returned to his position of manager of the new products division of the Plaskon Division of Libbey-Owens-Ford Glass Co., after active duty as a Navy lieutenant.

Charles C. Randolph, Jr., and Baxter Blitz are now administrative assistant to the manager and resident engineer, respectively, at the Willow Island works, Calco Chemical Division, American Cyanamid Co.

C. C. Crawford has been appointed assistant manager of the chemical products department of Phillips Petroleum Co. Dr. Crawford is in charge of the special products, product development, and Perco divisions.

Don R. Carmody is now supervisor of process research at the Texas State Research Foundation. Other recent additions to the staff include: Edward R. Boedeker, John R. Clopton, Alex G. Oblad and Lord G. Sharp.

Howard W. Morgan, who resigned recently as vice president of Munising Paper Co., Munising, Mich., will assume active duty as manager of the pulp division of Weyerhaeuser Timber Co., Longview, Wash. Mr. Morgan succeeds R. B. Wolf, who has been manager since the company built its first mill in 1931.

Benjamin D. Van Evera, professor of chemistry and executive officer of the chemistry department has been appointed co-ordinator of scientific activities, a newly created office at George Washington University.

Bert S. Taylor has been named factory manager in the newly created plastics production division in The B. F. Goodrich Co. Robert H. Wattleworth has been

Now released!

The first authoritative report on the incendiary bomb in modern warfare—

—Revealing
the story of its
development by
the Chemical
Warfare Service



This book brings you the complete story of how the incendiary bomb was developed and supplied by the Chemical Warfare Service during the war—the history of its use in warfare, its gradual development, and the materials which produce it. The book traces the development of incendiary weapons from the fire arrow to the pyrotechnic mixture bomb used against Tokyo. Much of the matter included has been released only recently from security regulations.

Just published!

INCENDIARY WARFARE

By GEORGE J. B. FISHER

Colonel, Chemical Warfare Service, United States Army

125 pages, 5 1/2 x 8, 10 figures, 4 tables, \$3.00

Here is a book that treats combustion and fire-raising as agencies of destruction—it supplies accurate data on the powers of devastation of the incendiary weapon, and analyzes the implications for the future, both in its further development and use, and in protection against it. It supplies an analysis of the materials that constitute incendiary agents, together with the techniques and tactics concerned with their use. The book is written in non-technical language.

Supplies up-to-date facts on:

- How fires start and spread
- What materials serve for military incendiary purposes
- Necessary measures for protection of municipalities against incendiary bombing
- Comparative uses of high explosive and incendiary bombs
- Future of incendiary warfare in the atomic age
- Results of incendiary bombing of Japan and Germany

8 chapters cover these subjects:

The Explosive and the Incendiary	Warfare Fire Defense
Incendiary Agents	Preparedness Against Incendiary Attack
Incendiary Munitions	Evolution of Incendiary Warfare
Tactics of Incendiary Bombing	Propagation of Fire

See it 10 days FREE • Mail Coupon

McGraw-Hill Book Co.,
330 W 42 St., N. Y. C. 18

Send me Fisher's INCENDIARY WARFARE for 10 days' examination on approval. In 10 days I will send \$3.00, plus few cents postage, or return book postpaid. (Postage paid on cash orders.)

Name


Address

City and State

Company

Position CE 11-46

(For Canadian price, write Embassy Book Co., 12 Richmond St. E., Toronto, E.)



YOU WOULDN'T THINK a pretzel had any relation to a chemical process furnace. But it does, and here's why:

A baking company recently lined a pretzel oven with B&W K-20 Insulating Firebrick. Immediate results—50% reduction in baking time (6 minutes to 3 minutes) and over 57% reduction in heating-up time from a cold start (7 hours to 3 hours).

Of course your business is different, but whether it's bending pretzels or bending molecules, in polymerization, pyrolysis, heating, distillation or any other chemical process—it's B&W I.F.B. that helps to do the trick better and more economically.

Because they are the lightest in their class, B&W I.F.B. have the lowest heat conductivity and lowest heat storage capacity. Furnaces lined with B&W I.F.B. come to operating temperature quickly, require less fuel to operate. This means cycle time is often substantially cut; overall operating costs go down—production goes up.

Throughout the country, B&W Refractory Engineers are guiding progressive industries to reduced costs through increased furnace operating efficiency. Why not take advantage of their practical training and years of experience? A call or a post card will bring your local B&W Representative . . . without obligation, of course.

R-269



Water-Tube Boilers, for Stationary Power Plants, for Marine Service . . . Water-Cooled Furnaces . . . Superheaters . . . Economizers . . . Air Heaters . . . Pulverized-Coal Equipment . . . Chain-Grate Stokers . . . Oil, Gas and Multifuel Burners . . . Seamless and Welded Tubes and Pipe . . . Refractories . . . Process Equipment.



WHAT IS LEKTROMESH?

Lektromesh is metal screen made by electro-deposition... a one-piece solid metal product with no woven structure to ravel. It is stiff, tough, and strong; in filters, strainers and other uses for industrial wire mesh it supplements woven mesh and is most applicable in the finer sizes beyond the limits of perforated metal. Lektromesh combines high accuracy of hole dimensions with a smooth surface, and is readily fabricated by drawing, stamping, welding, soldering or other processes. In size 40 to 400 mesh .. in standard rolls or fabricated into parts to your specification.

We will be pleased to send you samples of LEKTROMESH for your further consideration.

**THE C. O. JELLIFF
MFG. CORP.**
Southport, Connecticut



named general superintendent of the processing division to succeed Mr. Taylor.

William L. Wasley, formerly assistant professor of chemistry at Washington University, St. Louis, Mo., joined the research staff of Ansco's general research department in the capacity of group leader.

Frank J. Kaszuba and **Hermann Hoerlin**, respectively, have been named managers of the chemistry and physics laboratories—two new posts in the general research department of Ansco, Binghamton, N. Y.

Chad Raseman has joined Boyle-Midway Inc., household products division of American Home Products Corp., as chemical engineer for its five plants.

John D. Rue is now works manager of the Tacoma, Wash., plant of Hooker Electrochemical Co. Mr. Rue, formerly located at Niagara Falls as executive assistant to the chief engineer, has been with Hooker since 1931.

OBITUARIES

William E. Smith, 73, former president of the Standard Oil Co. of Kentucky, died in Louisville October 2.

De Lancey Kountze, 68, chairman of the board of Devco & Reynolds, paint manufacturers, died in New York October 2.

Ignace Moscicki, 78, former president of Poland and a well-known electrochemist before he went into politics, died in Switzerland October 2.

Walter Douglas, 75, former president of the Phelps Dodge Corp., died in Chauncey, N. Y., October 3.

Joseph H. Percy and **R. Max Goepf, Jr.**, were killed in the crash of the American Overseas Airlines plane near Stephenville, Newfoundland. Dr. Percy was enroute to Germany to investigate synthetic detergents. He was director of chemical products, division of research and development, Colgate-Palmolive-Peet Co. Dr. Goepf was returning to Germany to complete a study of emulsifiers and detergents. He was director of organic research for the Atlas Powder Co. The accident occurred October 3.

Rudolf Zane, chemical engineer with the U. S. Bureau of Mines, Seattle, Wash., on his way to Germany to translate captured scientific documents, and Mrs. Zane were also among the victims of the plane crash of October 3.

Frederick M. Prall, 52, director of the Rayon Technical Patent Section of E. I. du Pont de Nemours & Co., died in Wilmington October 11.

Andrew L. Winton, 82, prominent chemist and food plant histologist, died in Wilton, Conn., October 17.

Frederic Juenger, 63, traffic manager of the Texas Gulf Sulphur Co., died in New York October 21.



This Is MARION, INDIANA Another 100% Layne City

—Marion, a busy, progressive and forward looking city of east central Indiana gets its entire water supply from Layne Well Water Systems. And taking a tip from the city are a brewery, a food processing plant, a radio and television station, two meat packers, a military home, a wire and rubber manufacturer, a glass company, a laundry and a wire and cable company—all of whom have their own individual Layne Water System plants.

—Seldom does an industrial product enjoy such dominating preference as is accorded to Layne Well Water Systems by Marion City and Factory executives. Such preference was earned through recognized reputation of superior quality and basically sound operation economy.

—Layne Well Water Systems are known to be the best that specialized engineering research can produce—and the best that American dollars can buy. For late catalogs and illustrated literature address Layne & Bowler, Inc., General Offices, Memphis 8, Tenn.

HIGHEST EFFICIENCY

Layne Vertical Turbine pumps are available in sizes to produce from 40 to 16,000 gallons of water per minute. High efficiency saves hundreds of dollars on power cost per year.

AFFILIATED COMPANIES: Layne-Arkansas Co., Stuttgart, Ark. • Layne-Atlantic Co., Norfolk, Va. • Layne-Central Co., Memphis, Tenn. • Layne-Central Co., Mishawaka, Ind. • Layne-Louisiana Co., Lake Charles, La. • Louisiana Well Co., Monroe, La. • Layne-New York Co., New York City • Layne-Northwest Co., Milwaukee, Wis. • Layne-Ohio Co., Columbus, Ohio • Layne-Pacific, Inc., Seattle, Wash. • Layne-Texas Co., Houston, Texas • Layne-Western Co., Kansas City, Mo. • Layne-Western Co. of Minnesota, Minneapolis, Minn. • International Water Supply Ltd., London, Ontario, Canada • Layne-Hispano Americana, S. A., Mexico, D. F.



**WELL WATER SYSTEMS
VERTICAL TURBINE PUMPS**

ORGANIC CHEMICALS


ACETONE
ALLYL ALCOHOL
ALLYL CHLORIDE
SECONDARY BUTYL ALCOHOL
TERTIARY BUTYL ALCOHOL
DIACETONE ALCOHOL
ISOPROPYL ALCOHOL (REFINED 99%)
ISOPROPYL ALCOHOL (REFINED 91%)
ISOPROPYL ETHER
MESITYL OXIDE
METHYL ETHYL KETONE
METHYL ISOBUTYL CARBINOL
(METHYL AMYL ALCOHOL)
METHYL ISOBUTYL KETONE

SHELL CHEMICAL CORPORATION



100 BUSH STREET, SAN FRANCISCO 6
500 FIFTH AVENUE, NEW YORK 18
Los Angeles • Houston • Chicago
St. Louis • Cleveland

**Zenith
CONTINUOUS
PULP PRESS
DEWATERS UP TO 26
TONS OF WET PULP OR
SLURRY PER HOUR**



**Motor or
Pulley
Drive
Optional**

The Zenith Pulp Press, with capacity up to 26 tons per hour, thoroughly dewater wet pulps and slurries such as:

**Best Pulp • Citrus Wastes
• Tomato Pomace • Cherries
• Corn Fibre • Paper Pulp
• Reclaimed Rubber, etc.**

Heavy screw-type spindle applies smooth, continuous pressure, forces pulp or slurry against selective resistance. Rifle drilled resistors permit use of steam when necessary. Minutely perforated screens assure efficient drainage, hold pulp losses to minimum. Ball thrust bearings and oversize shaft bearings reduce power load.

New uses for the remarkably efficient, profitable Zenith Pulp Press are being constantly developed. An experimental press is available for trial in your plant.

Write for full
Information.



**JACKSON & CHURCH CO.
SAGINAW, MICHIGAN**

INDUSTRIAL NOTES

Johns-Manville Corp., New York, has elected Lewis H. Brown chairman of the board of directors and chief executive officer. R. W. Lea has been elected president. The general managers of the six operating divisions appointed by the new president are: J. A. O'Brien, industrial products division; Harold R. Berlin, building products division; A. S. Elsenbast, celite division; and E. C. Brockett, Canadian products division. E. S. Crosby continues as general manager of the international division. A. R. Fisher, vice-president for production, will act as general manager of the asbestos fiber division.

United States Rubber Co., New York, has promoted James E. Stevenson to the position of manager of V-belt sales. George R. Vila has been moved up to the post of sales manager for latex, Lotol, rubber dispersions and plastics products.

Pennsylvania Salt Mfg. Co., Philadelphia, has placed Louis M. Kuilema in charge of the Wisconsin territory as district sales manager. His offices are located in Chicago.

C. B. Peters Co., New York, has been reactivated by Col. Carl B. Peters who was recently separated from the United States Army. Offices are located in the Graybar Building, 420 Lexington Ave., New York 17, N. Y. The company will again concentrate on materials of interest to the

fertilizer, chemical, explosive and soap industries.

E. I. du Pont de Nemours & Co., Wilmington, will establish a Grasselli Chemicals department district office in Minneapolis. On January 1, the company will handle the sale of acids, chemicals, insecticides, and agricultural products from the new office which will be located in the Foshay Tower.

Steel Improvement & Forge Co., Cleveland, has established a turbine forgings division with Carl I. Schweizer in charge. The company also announced the appointment of Arthur Zimmerman as sales manager.

SKF Industries, Inc., New York, has named Harrison Wood as New York district manager to succeed John D. Williamson who has resigned after heading the district for the last 23 years.

Dow Chemical Co., Los Angeles, announces that Howard P. Atkin, after four years service with the Army Air Corps, has recently become a member of the company's cathodic protection sales staff.

Fluor Corp., Ltd., Los Angeles, has promoted W. Earl Dunn to the post of general manager. James P. Wiseman, former district engineer in the Houston office, has been moved up to the post of general



U.S. INSTRUMENTS Tell The Truth



**PRESSURE, TEMPERATURE, FLOW, ELECTRICAL
AND LEVEL MEASURING INSTRUMENTS**

UNITED STATES GAUGE


**DIVISION OF AMERICAN MACHINE AND METALS, INC.
SELLERSVILLE, PENNSYLVANIA (1)**

6 out of 10

manufacturers of
original equipment
specify U.S.G.

Uniform Filter Fabrics Mean Efficiency in Filtering


High efficiency in filtering operations goes hand in hand with a high degree of uniformity in the fabric used. That is why the selection of Mt. Vernon Extra for your filter fabrics is so important. Beginning with top grades of cotton that are spun and woven with the skill of half a century's experience and carefully checked by rigid laboratory controls in each step of production, our constant aim is to make Mt. Vernon Extra filter fabrics better, stronger and more uniform to increase the efficiency and improve the economy of your filtering operations.



Mt. Vernon-Woodberry Mills

TURNER HALSEY

COMPANY

Selling  Agents

40 WORTH ST. • NEW YORK

Branch Offices: CHICAGO • NEW ORLEANS • ATLANTA • BALTIMORE • BOSTON • LOS ANGELES • AKRON

CHEMICAL ENGINEERING • NOVEMBER 1946 •

RELIABILITY

*most desired quality
in every product . . .*

...IT'S YOURS

in every product built by Hardinge

Sound engineering, sturdy construction, advanced design, the skilled hands of master craftsmen — all these combine to give Hardinge equipment its unusually long life and low maintenance costs . . . its reliability through the years.

CONICAL MILLS Ball and Pebble mills for grinding wet or dry, in open or closed circuit, for granular or fine products.

RUGGLES-COLES DRYERS Built in 9 distinct types for direct, indirect, or indirect-direct heat drying of all products.

CONICAL SCRUBBERS Clean by mass contact and natural displacement at lower power and water requirements than others.

AUTO-RAISE THICKENERS Distinctive features are the spiral scrapers and the "Auto-Raise" drive mechanism.

COUNTER-CURRENT CLASSIFIERS Used for making size separations of ores, sands, and other materials (one moving part).

AIR CLASSIFIERS Compact, efficient, self-contained units . . . fineness up to 99% passing 325 mesh can be secured.

CONSTANT-WEIGHT FEEDERS Measure by weight, not volume, thus eliminating variations of 10% to 40% common in other types.

A. B. W. SAND FILTERS The new effluent filters with the remarkable automatic backwash feature.

Write for descriptive Catalogs

HARDINGE

COMPANY INCORPORATED
TOLK, PENNSYLVANIA — 246 Arch St. • Main Office and Works
NEW YORK 17—122 E. 42nd St. • 305 W. Wacker Drive—CHICAGO 6
SAN FRANCISCO 5—501 Howard St. • 200 Bay St.—TORONTO 1



A.B.W. SAND FILTER




CONSTANT WEIGHT FEEDER



HARDINGE MILL



ROTARY DRYER




CONICAL SCRUBBER



AUTO-RAISE THICKENER



COUNTER-CURRENT CLASSIFIER



AIR CLASSIFIER

sales manager. Both men are now located in the Los Angeles office.

Elliott Co., Jeannette, Pa., has appointed Quentin Graham manager of the Ridgway (Pa.) division. Mr. Graham was formerly manager of the company's electrical engineering department. H. S. Pahren, former manager of the division has moved to New York as Elliott district manager.

Joshua Hendy Iron Works, Sunnyvale Calif., announces that Joseph H. Wadsworth, formerly with California Shipbuilding Corp., has been appointed director of public relations.

Sier-Bath Gear and Pump Co., North Bergen, N. J., is the new name of the former Sier-Bath Gear Co., Inc. The company is located at 9252 Hudson Blvd.

Parke, Davis & Co., New York, has awarded engineering and construction contracts for a new building in Detroit to house the production and development of streptomycin and other antibiotics to the H. K. Ferson Co. The four story structure will provide office, laboratory, process and development facilities. Construction is now under way.

Maas & Waldstein Co., Newark, N. J. has purchased the Smith-Davis Paint Co., 10751 Venice Blvd., Los Angeles. The company will continue to manufacture industrial finishes, trade sales and maintenance sales paints. C. R. Parry will supervise the new plant.

Pittsburgh Plate Glass Co., Pittsburgh, has acquired the Mork Brush Mfg. Co., San Francisco. The unit will continue operations as the Mork Brush division of the company.

Atlas Mineral Products Co., Mertztown, Pa., has a new affiliate organization called Atlas Mineral Products Co. of Texas, Inc. It is located at Houston and includes a plant manufacturing sulphur cements and other products. The Texas unit handles sales in western Tennessee, Mississippi and Louisiana. It also handles all sales west of the Mississippi with the exception of Minnesota, North Dakota, and eastern Missouri.

Durez Plastics & Chemicals, Inc., North Tonawanda, N. Y., has changed the name of its oil soluble resin division to protective coating resins division and the name of its technical sales division to industrial sales division. These changes were made to clearly define the functions of the departments.

Komline-Sanderson Engineering Corp., Ridgewood, N. J., has been formed for the purpose of developing and marketing machinery and equipment for the treatment of sewage and industrial wastes. Partners in the concern are Thomas R. Komline and Walter H. Sanderson.

Shell Chemical Corp., New York, has appointed Merle L. Griffin to the post of assistant to the western division sales manager. He was formerly assistant to the

ARMSTRONG Unit Trapping* still pays

ARMSTRONG MACHINE WORKS pioneered UNIT TRAPPING* back in the days when it was customary to pipe a half dozen, or more, drain lines into one big pot type trap . . . when traps were considered "a necessary evil" . . . when the main idea was to use as few traps as possible. Armstrong made it practical and profitable to use UNIT TRAPPING* by developing:

1. A trap that does not require attention. (All Armstrong traps are non-airbinding and self-scrubbing.)
2. Small traps with big capacity. (Unexcelled—thanks to Armstrong's patented valve.)
3. Moderately priced traps—economical to use on individual units; a size for every purpose.
4. Scientific data on how to use traps.

TODAY, ENGINEERS EVERYWHERE KNOW THAT AN INDIVIDUAL TRAP SHOULD BE USED ON EACH DRAIN LINE. YET THERE ARE STILL NUMEROUS PLACES WHERE OLD-FASHIONED TRAPPING IS COSTING PLANTS MONEY EVERY DAY!

It will pay such plant to give "trap modernization" top priority in postwar planning. Most of these jobs require only small expenditures and little labor, yet they pay big dividends. Ask for a copy of the Armstrong Handbook on Condensate Drainage—it gives you all information needed to plan your jobs.

ARMSTRONG MACHINE WORKS
858 Maple St., Three Rivers, Mich.

**B
I
G
D
I
V
I
D
E
N
D
S
!**



\$25 DAILY GAS SAVING
Heineman Chemical Co., Crosby, Pa.



20% REDUCTION IN HEATING UP TIME
Paper Board Company in Canada



170 TONS LESS COAL BURNED PER YEAR
Northwestern Store Co., Milwaukee, Wisc.



\$250 FUEL SAVING PER SEASON
B. C. Packers, Ltd., Stevenson, B. C.



50% CUT IN COAL BILL
High School, Springfield, Ohio



ARMSTRONG

Inverted Bucket


STEAM TRAPS

Over a Million in Use... For Power... Process... Heating



WIRE CLOTH COST AND SEPARATING SPEED

PERFECTLY BALANCED



To increase separating speed and lengthen your screen life, select a higher quality alloy.

Such alloys are woven by "Buffalo Wire." They permit you to go to a mesh of lighter gauge, and thereby achieve the perfect balance of productivity and screen life. The relatively higher cost of a durable alloy is more than offset by greater separating speed and less frequent wire cloth replacements.




NEW FOLDER 596

Tells how "Buffalo" Stainless Steel Wire Cloth cuts costs and improves performance in thousands of installations. Valuable data on corrosion-resistance. Write for your copy.

MANUFACTURER OF ALL KINDS OF
WIRE CLOTH SINCE 1869

Buffalo WIRE WORKS CO., INC.
ESTABLISHED 1869 BY SCHMIDT & SONS



482 TERRACE

BUFFALO 2, N. Y.

general manager in New York. V. C. Irvine has been named manager of head office sales development in San Francisco.

Brill Equipment Co., New York, has made Stephen M. Schuster advertising manager. Mr. Schuster was recently released from active duty in the Navy.

Bowser, Inc., Fort Wayne, Ind., has placed J. C. Lungerhausen in the post of chief development engineer in the industrial pump division.

Esselen Research Corp., Boston, is the new firm name of Gustavus J. Esselen, Inc. There will be no change in the management, personnel or policies of the business.

Rhodes Industrial Corp., East Hampton, N. Y., has been formed by Philip H. Rhodes. The new firm has offices and laboratories in that city. Officers of the company are: P. H. Rhodes, president; A. L. Alk, treasurer and chief chemist; and E. Libby, director of pilot plant operations.

Hydraulic Press Mfg. Co., Mount Gilead, Ohio, has appointed Col. Robert F. Ohmer vice president in charge of administration.

Oronite Chemical Co., San Francisco, has announced appointment of H. E. Bramston-Cook as sales manager, national and international, for the firm's new synthetic detergent, phthalic anhydride, and other chemical products. Oronite has just moved to new headquarters at 200 Bush Street, San Francisco.


American Marietta Co., Chicago, has purchased Adhesive Products Co. of Seattle and Pacific Chemical Co. of Los Angeles. The company also bought two Seattle paint plants a year ago.

W. E. Major Industries, Los Angeles, has recently been organized with W. E. Major as president to act as exclusive agents for chemical products of the iron and steel division of Kaiser Co., Inc., Growers Chemical Supply Co., and Wilson Carbon Co., and as non-exclusive agent for the coal-tar and chemical products of Geneva Steel Co. and of Union Oil Co. of California. Mr. Major for many years West Coast manager for General Chemical Co., was recently manager of the chemical division of Union Oil in Los Angeles.

A. Brothman and Associates, Long Island City, N. Y., has moved from 114 East 32nd St., New York, to 2928 41st Ave., Long Island City 1, N. Y.

Young Radiator Co., Racine, Wis., has promoted Peter J. Fink to the post of service manager. Lloyd B. Smith has been made special representative in the Pacific Northwest territory.

American Cyanamid Co., New York, has made the following changes in the Calco Chemical division: John B. Fried has been made a metropolitan New York district sales representative in the pigment department; Wendell G. Beauchamp is now



● FILTER CAKE IN ONE CONTINUOUS SHEET... WASHED CLEAN—THOROUGHLY DEWATERED

This easy-to-process filter cake is being discharged from an FE Chemical Washing Filter. Built up to just the right thickness on the filter drum, it has been thoroughly washed, and dewatered. As you see it here, it has just been lifted off the surface of the revolving filter drum by the FE string discharge (no scraper), and is being carried (still supported by the strings) to the discharge roll.

The uniform filter cake pictured above is just one of the many results you can achieve with FE continuous filtration. FE filters are basically good, sturdy, trouble-free vacuum filters to which can be added exclusive FE features that improve washing, produce lower cake moistures, and improve results—all at lower costs.

The FE string discharge does away with scrapers and "blow-back." No wire winding is needed to hold the filter cloth in place, and no severe mechanical strain or abrasive wear shortens the life of the cloth. It permits handling filter cakes as thin as 1/16 in., and successfully filters semi-colloidal slurries and "slimes." Cloth changes are less frequent, and can be made in a fraction of the time required for scraper-type filters.

The FE compression mechanism can be added to squeeze 2 to 6% more moisture out of the

filter cake. It also reduces vacuum power requirements by closing up cracks that may occur in the cake.

Better cake washing is possible with the FE washing mechanism. Less residual impurities and better recovery of solubles result from the non-atomizing, uniform, water wash that is spread evenly over the entire cake with the help of a highly absorbent wash blanket. Both the washing and dewatering cycle are long—you get a clean cake with minimum moisture.

FE filters are available in sizes from 9 to over 700 sq. ft. filtering area, for handling a wide variety of materials including chemicals, food products, paper pulp, mining slimes and concentrates, sewage sludges, clay, sugar muds, starches, cements and many others. We will be glad to help with your filtration problems.



858 Summer Avenue


Newark 4, N. J.

Canada: The Northern Foundry & Machine Co., Ltd., Sault Ste. Marie, Ont.

Continental Transmission Drives

We are equipped to engineer and specify the correct drive for each individual installation—whether a positive drive such as Chain or Gears or a flexible drive such as V-Belt or Flat Belt

V-Belt Drives



A complete line of V-Belt Sheaves for "A" through "E" section belts in standard bushed, taper bushed or made-to-order types. Continental V-Belts "A" through "E" section carried in stock for prompt shipment. All Sheaves made from close grain, high tensile strength Meehanite iron, assuring longer life expectancy and highest drive efficiency

Roller Chain Drives



Complete range of stock size Sprockets and single strand Roller Chains, from 3/8" to 2 1/2" pitch, carried in stock for quick delivery. Steel or cast iron construction, with standard hubs, are available on order.

Send your inquiries to our
nearest District Office.

67-A

INDUSTRIAL DIVISION
CONTINENTAL GIN COMPANY

BIRMINGHAM, ALABAMA



ATLANTA

DALLAS

MEMPHIS



Pacific coast regional sales manager of the pigment department; M. H. Mettee III has been transferred to plastics sales for the dyestuff department; and George A. Jonic has been named a sales representative in the metropolitan district.

Diamond Alkali Co., Pittsburgh, has appointed Donald S. Carmichael of Cleveland, assistant secretary of the company. He has been located in the main office since November 1.

Edwal Laboratories, Inc., Chicago, has added Herbert C. Stecker to its staff. He will serve as assistant to Dr. Hendrey who is in charge of chemical sales.

Beaumont Birch Co., Philadelphia, has purchased the complete line of Hagan steam jet ash conveyors from the George J. Hagan Co. of Pittsburgh.

Centro Research Laboratories, Inc., Briarcliff Manor, N. Y., announces that Dr. Vaman R. Kokatnur, president of Autoxygen Inc., has joined its staff as research associate but will retain his New York office for chemical consultation.

Foxboro Co., Foxboro, Mass., has under construction a new plant for its affiliate, The Foxboro Co., Ltd., in the Ville LaSalle section of Montreal, Canada. It will be ready for operation in the spring.

Rheem Research Products, Inc., Baltimore has appointed the Mitchell-Bradford Chemical Co., Stratford, Conn., as exclusive distributor for Iridite in the New England area.


James Stewart & Co., New York, has elected James M. Jensen to the newly created position of assistant to the president. Mr. Jensen, who has been with the company for 31 years, had been serving as project manager in charge of the company's construction of pulp and paper plants at Macon, Ga.

Pittsburgh Lector dryer Corp., Pittsburgh, has appointed D. B. Gooch, Birmingham, Ala., as sales representatives for all of the Carolinas and parts of Alabama and Georgia.

Timken Roller Bearing Co., Canton, Ohio, has transferred Russell P. Proffitt from Chicago to the Washington office where he will serve as district manager.

Logan Engineering Co., Chicago, is now represented in the Southwest, Mexico, and Central America by the Patterson Sales Co. of El Paso, Texas.

E. I. du Pont de Nemours & Co., Wilmington, has opened an office for the organic chemicals department at Atlanta. The Charlotte, N. C., office which formerly handled sales south of Virginia will concentrate on North and South Carolina. D. C. Newman will continue as sales manager in charge of the entire southern district. A. B. Owens, formerly sales development manager of the dyestuffs division at Wilmington, will be manager of the Atlanta office.



Modern Machines Deserve MORFLEX Couplings

Chicago Pneumatic Tool Company's portable hydraulic system, adaptable to cold riveting, piercing, pressing and pulling operations, uses Morflex Couplings on the power unit shaft between motor and pump. Morflex Couplings absorb shock, vibration, prolong machine life in the severest service. MORSE CHAIN COMPANY, Detroit 8, Michigan; Ithaca, N. Y.



MORSE *ROLLER and SILENT CHAINS and COUPLINGS*

**IF YOU HAVE A SOLUTION
FEEDING PROBLEM**



Install

OMEGA ROTODIP FEEDERS

Don't let your feeding problems get you down — the Omega Rotodip feeds chemical solutions with the accuracy of a meter . . . handles all kinds of low viscosity liquids and suspensions. Rotodip is available in special materials of construction to feed every solution from food products to acids. The rotating dippers are of unique design to insure delivery with an accuracy of $\pm 1\%$; the Omega variable speed drive permits exact adjustment of the feeding rate over a 100 to 1 range.



Omega Rotodip Feeder, cutaway view. Capacity 1 to 800 g.p.h. Widely used with automatic and proportional control devices in many process plants.

Write for Bulletin

OMEGA PRODUCTS

Gravimetric Feeders • Dust Removal Equipment
Volumetric Dry & Solution Feeders
Lime Slaking Equipment
Laboratory Stirrers • Bucket Elevators

OMEGA MACHINE CO.

(Division of Builders Iron Foundry)

29 Coddling Street, Providence 1, R. I.

CONVENTION PAPER ABSTRACTS

CONTENTS

Atomic Energy Act.....	292
Research Obstacles.....	294
Fertilizer Industry Forecast.....	294
Corrosion of Oilwell Pipelines.....	296
Lignin-Reinforced Rubber.....	298
Balance German Economy.....	300
Human Factors Affect Costs.....	302
Rectification	302
Studies of Turbine Deposits.....	304
Vulcanization of GR-S.....	306

THE ATOMIC ENERGY ACT

THE FAMOUS "Atomic Energy" Act of 1946, which was passed by Congress and signed by the President, is an example of the unfortunate tendency toward compulsory licensing of patents and the extension of government control. The Act, while professing to be interested in continued research and development activities in the field of nuclear processes, the production of atomic energy, and the utilization of fissionable and radioactive materials, discourages the making and development of inventions in that field by establishing a tight government control over sources of material, such as uranium and thorium; fissionable material including the artificially produced plutonium and uranium enriched in the isotope 235; byproduct material;

facilities for the production of fissionable materials; and the utilization of atomic energy. At the same time, it provides that inventions and discoveries in the production and utilization of fissionable material shall not be the subject matter of patents.

It does not seem consistent that, while patents have in the past been the great stimulating force promoting the making of inventions, this force should be removed in connection with the very important field of atomic energy. True, the Act provides for so-called "just compensation" for the inventor, but as almost everyone knows, what might be considered such by a Commission, might be hardly adequate to satisfy the inventor. In any event, an inventor would not have the incentive that he would have had under a free right to invent and patent his inventions, in accordance with the patent law as it stands aside from the Atomic Energy Act.

Besides this, the Act provides for compulsory licensing of patents already granted in the atomic energy field, making it the duty of the Commission to declare any such patents affected with a public interest.

So the Act is deplored as tending to weaken the rights of inventors by taking from them the right to patent within a specified field. It might be urged that the field is well-defined, but this is not so. Although at the present time, the sources of fissionable material are practically limited to uranium and thorium, who can tell



CORROSION RESISTANT

KETTLES

... For Your Plant

Experienced LEE engineers and master craftsmen, with complete modern shop facilities—a flexible production organization—enables LEE to build the type of industrial corrosion-resistant KETTLES you need, in any desired size.

All Lee Kettles are made to ASME Code and Certificates furnished with each job.

WRITE FOR DESCRIPTIVE BULLETIN

LEE

**METAL PRODUCTS
COMPANY, INC.**

415 PINE STREET, PHILIPSBURG, PA.

WE KNOW



**All
Or Any Step
In Design,
Engineering,
Fabrication,
Or Erection
of
Process Plants
for the
Oil, Gas
and Chemical
Industries**

**P O Box 2634
Houston 1, Texas**

Texas . . .

Richest state in oil, gas, sulphur, salt
. . . heavily productive of many other
natural resources.

Texas . . . With fine harbors; good rail,
highway and air transportation; rich
markets; favorable labor conditions;
climate that permits all year around
work out of doors.

No wonder Texas is the Capital of the
Petro-Chemical Industry. No wonder
Chemical makers are coming to Texas
for expansion and plant location.

In coming to Texas, you'll benefit from
the complete services of Brown & Root,
Inc.,—old enough to offer 32 years of
broad engineering and construction
experience in Texas; big enough to
carry on \$100,000,000 in work at a time;
broad enough to handle all or any part
of plant location research, design,
process, engineering, fabrication and
erection . . . AND


WISE enough to give every advantage
of its skill and experience to your job.

BROWN & ROOT, Inc.

AGITAIR FLOTATION

Offers

Quick and Positive Control



Controlled Aeration

Agitair Flotation machines allow instant control of induced air to each cell by readily accessible air valves. Too, by a touch of an air header valve, instant air control of the entire circuit assures smooth and uninterrupted operation. The effect of unavoidable variances in ore and reagents is thus quickly controlled. There need be no froth run-aways with Agitair.

Froth Depth

Froth overflow weirs on each cell allow adjustments of froth depth to the optimum position. Froth paddles are not required.

You, too, can profit from Agitair time-tested performance. Write today for Bulletin 421, which explains and illustrates Agitair in full detail.

"Leaders in Experience and Service"

THE GALIGHER CO.

Home Office
48 South 2nd East St.
Salt Lake City 1, Utah

Eastern Office
921 Bergen Avenue
Jersey City 6, N. J.

but that other sources may not be found, or that other materials not at present considered fissionable may not eventually be found to be in that category. Suppose that copper is eventually found to be fissionable, that would take the great copper industry from private enterprise and put them under government control.

Towson Price, Westinghouse Electric Corp., before Radio Business Forum, New York, Oct. 1, 1946.

OBSTACLES IN THE WAY OF RESEARCH

WHAT of the future of research? With its past record one may wonder why further incentives for research are needed. The fact is, however, that in spite of this history of achievement there are some serious clouds on the horizon, which threaten the ability of research to continue its vital contribution to the life of our nation. One such cloud is the fact that the simpler and easier problems have been solved. We are left with the more difficult ones. The law of diminishing returns is beginning to apply to many fields of research.

A second obstacle to research is the serious shortage of technical men which faces us, particularly during the next five years. As industrial operations become more complex, technically trained men are needed as operators or supervisors, and such jobs generally have priority over research. It will be impossible for our educational institutions to meet the demand for technical men during the next several years. This shortage stems back largely to the shortsighted policy pursued by the military authorities in drafting thousands of technical men for non-technical jobs, and particularly in uprooting almost completely the young students who were part way through our technical schools.

Third difficulty in expanding our research program is the accumulated deficiency in basic research. During the war we made tremendous advances in applying known principles of science, but we discovered very little that was basically new or fundamental. This is one field where we have been drawing upon our reserves at an alarming rate.

Fourth threat to the future of research arises out of the attempt of a relatively small group to wreck our patent system. They have misrepresented the basic facts about patents and have filled the papers with discussions of a few unusual and nontypical patent-control schemes, with which our antitrust laws are quite adequate to deal.

R. E. Wilson, Standard Oil Company of Indiana, before Princeton University Bicentennial Conference, Oct. 4, 1946.

FERTILIZER INDUSTRY FORECAST

WHEN the supply and demand for fertilizers strike a balance again, there will be a shaking out of the distribution pattern not possible during the restrictions of the war years. The assimilation of war-built nitrogen fixation plants into our peacetime economy has begun. The construction and operation of phosphate mining

FOR DEPENDABLE SUPPLY AND SERVICE PLACE 1947 CONTRACTS EARLY!



Now is the time to contract for your 1947 requirements of Spencer Industrial Anhydrous Ammonia (NH_3) and assure your future production schedules for the manufacture of *Fertilizers, Explosives, Petroleum Products, Chemicals, Sulphuric Acids, Rayon, Wood Pulp Treating, Refrigerants...*

CONTRACT orders mean a sure supply of 99.5% pure Spencer Anhydrous Ammonia.

CONTRACT orders mean prompt delivery throughout 1947.

CONTRACT orders mean price protection—full protection against market fluctuations.

CONTRACT orders mean good business—enable you to reduce inventories and plan with certainty for orderly economical production.

Spencer Chemical
COMPANY

General and Sales Offices: Dwight Building, Kansas City 6, Mo.
Works: Pittsburg, Kansas



ON CONTRACT...ON SCHEDULE...ON TIME

when you buy **STAINLESS STEEL** **PROCESSING EQUIPMENT**

*Get All the advantages
the alloy offers*

LONGER SERVICE




MAXIMUM CORROSION RESISTANCE



LOWER MAINTENANCE COST



FASTER CLEANING



It takes a specialist to transform stainless steel sheet into processing equipment that gives you the best out of the alloy. We work with stainless steel alloys exclusively. That means we're equipped to protect your investment in stainless steel processing equipment—know all the fabricating safeguards that give you the maximum benefits of the original alloy in your finished vessel. Consult with us on your requirements.

S. BLICKMAN, INC. • 611 GREGORY AVE. • WEEHAWKEN, N. J.

S. BLICKMAN, INC.
Guards Alloys in Fabrication

SEND FOR THIS VALUABLE BOOK

A request on your letter-head will bring our guide, "What to Look For When You Specify Stainless Steel for Your Processing Equipment."



CORROSION RESISTANT PROCESSING EQUIPMENT



TANKS • KETTLES • STILLs • HEAT EXCHANGERS • AGITATORS • MIXERS • TOWERS • PIPING

and processing facilities is well started. It will continue with emphasis on ability to serve the recently enlarged demand in the north central and west coast areas.

During the five year prewar period, 1935-1939, agriculture in the United States used an average fertilizer volume of 7½ million tons annually. By 1945 this had increased 81 percent to 13.2 million tons. The fact that the major plant nutrients contained in that tonnage increased during that same span of years more than 86 percent is an indication of a sound trend which we can be certain will continue.

Through the fertilizer industry, agriculture in the United States purchases more than 13 million tons of chemicals. For the year ending June 30, 1947, prospects are that a 14 million ton total will be so delivered as one of the important contributions toward an abundant food supply.

Barring interruptions of supply, this will be 91 percent more ton volume and 103 percent more of the three major plant nutrients than was used on an average during the five years 1935 through 1939.

From an industry using large proportions of natural organic byproducts, fertilizer manufacture has changed in less than a generation to a business of predominantly inorganic chemical nature. Even as long ago as 1925 only one-fourth of fertilizer nitrogen used here in the United States was from natural organics. By 1940 this proportion had decreased to one eighth. For the year ending next June 30 there will be a further decline to less than one-twentieth. Conversely ammonia and its solutions which in 1925 had as yet assumed no measurable percent of the fertilizer nitrogen supply picture, had claimed one eighth of the market by 1940. They bid fair to make up one-fourth of the total this year. Solid ammonium nitrate, of which little or none was used as fertilizer in this country in 1925, has now assumed one-fifth of the market.

Phosphates in the fertilizer industry have also undergone some changes and made progress, critics of the industry notwithstanding. Phosphate rock recovery processes and volume have been stepped up. Fused phosphates have recently entered the picture and will apparently amount to about one hundred thousand tons of material for the current year.

Maurice H. Lockwood, National Fertilizer Association, before the Chemical Market Research Association, New York, Sept. 17, 1946.

CHECKING CORROSION OF OIL WELL PIPELINES

CORROSION has become an increasingly serious problem in the oil fields because of the high pressures at which the wells operate and the danger of resultant accidents. The corrosive attack, due to carbon dioxide, water, and organic acids, is erratic, and wells standing side by side do not show the same effects or the same intensity of effects.

Gas condensate wells themselves were used as a laboratory to study the action of the gas stream on the interior of the pipes through which the gas is produced. From the data gathered, the wells were grouped

If you use PETROLEUM SULFONATES



or if you haven't



yet investigated them

PENN-DRAKE

has an important message for you!

Penn-Drake PETROSULS—a series of fully refined petroleum sulfonates largely developed and perfected for war-time applications—are now available for civilian use. Principal applications are for use where surface-active agents are required or desirable. Two types are offered:

PETROSUL 745 SERIES—a low molecular weight, oil-soluble, "mahogany soap." It is readily soluble in cold water, forming a clear solution.

PETROSUL C SERIES—high molecular weight petroleum sulfonates in either aqueous or petroleum oil concentration.

Write for data and samples. Our technical staff will gladly cooperate with you in adapting Penn-Drake PETROSULS to your needs.




PENNSYLVANIA REFINING CO.

GENERAL OFFICES • BUTLER, PA.

Makers: White Oils; U.S.P. and Technical; Petrolatum; all grades and colors; INSECTISOL (deodorized insecticide base); Deodorized and other Naphthas; Petroleum Sulphonates; Waxes; Industrial and Motor Lubricants and Greases; Fuel Oils, and other petroleum products.

TERRISS SEAMLESS, STAINLESS STEELWARE



TANKS: 18-8 Stainless Steel. Highly polished No. 4 finish inside and out. Pitched bottom, self-draining. Stainless Steel covers. Stands pipe leg type. Built-in agitators for fast or slow speed, if desired. 25, 35, 50, 60, 100, 160, 200, 300, 400 and 500 gallon sizes . . . also built to special specifications.



BATCH CANS

Monel metal or stainless steel. Endless iron ring, handles attached, reinforces top. Bottom reinforced by iron cross welded to iron chime. 10 to 75 gallons.

DIPPERS

72 oz. with handle. Also some one, two and four-quart FLAT dippers.



PAILS

Seamless stainless steel. Capacities, 12 and 15½ qts.



We carry a full line of Filter Paper. Also, Hose for all purposes. Send us a sample of your needs.

Immediate Delivery

**CONSOLIDATED
SIPHON SUPPLY CO., INC.**
DEPT. C., 22-24 WOOSTER ST., NEW YORK CITY

into three general types, critical, non-corrosive, and intermediate.

In the critical corrosive type not only has the rate of attack been steady and severe, but small deep holes appear in the metal. Another type was the protective attack in which, after an initial attack, there was little if any further attack until that surface was removed. No pitting and very little penetration or corrosion of the steel takes place with this type of well.

The third type noted was intermediate between the corrosive and so-called non-corrosive well. In this type well the corrosion takes place at a slow steady rate. Local attack and pitting do not seem to take place. This type of corrosion is not as serious since the even, general effect permits accurate calculation of the life of the pipe. Thus by observation of the weight change of a pipe and microscopic examination of the surface a means of predicting the corrosive behavior of the well could be established.

Corrosive agents and operating conditions were similar in the corrosive and non-corrosive type wells, indicating that the non-corrosive well contained a substance which reacted with the surface of the pipe to provide a protective film, arresting the corrosion.

The naphthenic acids were believed to meet the requirements and could conceivably be present under these conditions. A laboratory test showed that the addition of a very small amount of this acid formed a protective film which inhibited the attack of organic acid. Injection of naphthenic acid into a corrosive type well also

seemed to be effective. Not only was there little metal lost, but more important, the surface became similar to that demonstrated by the non-corrosive well and no pits formed.

Tests with sodium chromate or dichromate showed a slight initial attack followed by little or no change over a period of eight weeks.

Norman Hackerman and D. A. Shock, University of Texas, before the Division of Industrial and Engineering Chemistry, American Chemical Society, Chicago, Sept. 12, 1946.

RUBBER REINFORCED WITH LIGNIN


In a new process, lignin is mixed with either synthetic or natural rubber in latex form so that it is coprecipitated or coagulated with the rubber, forming a material ready for compounding and molding by the usual means. The process may be adapted, with minor variations, to most of the plants now making synthetic rubber.

Rubber articles strengthened and toughened with lignin reveal unusual properties. One of these is light weight. Lignin is only 72 percent as heavy as carbon black. Used in rubber tires, lignin could save approximately 7 percent of the weight of the tire. In other rubber goods where more pigments, heavier than carbon black, are used, the saving in weight is considerably more. Thus, shoe soles or heels are 35 percent lighter when lignin is used.

Lignin also offers another advantage, long sought by the rubber industry—light, bright-colored articles that are as tough and

PUMPS THAT PAY

All centrifugals are alike in principle; the vital differences are in their performance. The BEST pump is the one that delivers at least cost per unit of material handled, per year of service. . . . On this basis we invite comparison of LAWRENCE CENTRIFUGAL PUMPS with all others. Their records are convincing evidence that THEY DO PAY PROFITS. . . . There probably is not a "pumpable" material in the handling of which we have not had notable success—to the purchaser's profit. . . . Why not discuss your pumping problems with us? A request will place you under no obligation.



LAWRENCE MACHINE & PUMP CORP.

369 Market Street

LAWRENCE, MASS.

LAWRENCE CENTRIFUGALS
FOR EVERY PUMPING DUTY

**GENERAL CHEMICAL
RESEARCH
ANNOUNCES**

genetron*

100

**first of its
important series of
ALIPHATIC ORGANIC
FLUORINE COMPOUNDS**

Long the leader in development of inorganic fluorides and fluoborates, General Chemical Fluorine Research now enters the field of organic chemistry as it presents the Genetrons . . . an important series of aliphatic organic fluorine compounds.

First of the group is Genetron 100, a product significant not only as a new industrial chemical, but also as the parent compound for this family of commercially valuable organic fluorine derivatives.

Its physical properties point to various applications . . . as a refrigerant; intermediate in the preparation of aerosol dispersants, dielectrics, high pressure lubricants, selective solvents, and mixed olefinic halide monomers. Some of these uses are already being confirmed by manufacturers who recognize the unusual industrial potentialities of this low-boiling organic liquid.

Genetron 100 may merit your thorough investigation, too. For experimental samples write General Chemical Company, Fluorine Division, 40 Rector Street, New York 6, N. Y.

genetron* 100

PHYSICAL PROPERTIES

Formula	CH ₂ CHF ₂
Molecular Weight	66.05
Color	Colorless
Melting Point	-117.6° C
Boiling Point	-24.7° C
Density	1.004 at -25° C
Latent heat of vaporization	137 B.t.u./lb.

vapor pressure (p.s.i. abs)

-30° C	12.0
-10° C	25.9
10° C	53.8
30° C	108.0

BASIC CHEMICALS



FOR AMERICAN INDUSTRY

GENERAL CHEMICAL COMPANY


40 RECTOR STREET, NEW YORK 6, N. Y.

Sales and Technical Service Offices: Albany • Atlanta • Baltimore
Birmingham • Boston • Bridgeport • Buffalo • Charlotte
Chicago • Cleveland • Denver • Detroit • Houston • Kansas City
Los Angeles • Minneapolis • New York • Philadelphia • Pittsburgh
Providence • San Francisco • Seattle • St. Louis • Wenatchee
Yakima (Wash.)

In Wisconsin: General Chemical Wisconsin Corporation,
Milwaukee, Wis.

In Canada: The Nichols Chemical Company, Limited
Montreal • Toronto • Vancouver

*Trade Mark, General Chemical Company



This new-type, fluid-activated pump depends on Ampco Bronzes for high strength and resistance to corrosion, erosion, and abrasion

Here is a handy pump to have around. It supplies a pressure of over 15,000 psi for hydrostatic testing of christmas-tree fittings used in the oil fields. This same pump can also be used for injecting a chemical into a line in any proportion desired. Other applications include the homogenizing of milk, maintenance of high car-washing pressures, spray painting with red lead, etc.

Here's what the engineer who helped design this pump says about its construction:

"The main castings and most parts of the pump are of an aluminum bronze which has high strength, great resistance to sea-water corrosion, and particularly great resistance to erosion and abrasion. (He is talking about Ampco Bronzes.) Because of the excellent wearing qualities, no liner is required in the main cylinder. (He's still talking about Ampco Bronzes.) This alloy is the same used for safety tools, and the non-sparking quality presents a desirable safety feature in use around explosive paint sprays, natural gas, and other explosive fluid mixtures. (He keeps on talking about Ampco Bronzes.) The exterior of the pump has a pleasing golden color and does not require painting or other upkeep."

Ampco Metal is a complete aluminum bronze series, varying from soft to hard, with physical quality closely controlled to fit specific service conditions. Call in an Ampco field engineer or write for bulletins and find out how Ampco Metal can help you.



AMP CO METAL, INC.
Department CM-11 • Milwaukee 4, Wisconsin
Field Offices in Principal Cities

strong as those of black rubber. Light colors are possible because lignin has itself a comparatively weak tinting power. Its natural dark brown color fades out on blending with minor proportions of white pigments and colors. The small amounts used do not impair the strength or toughness of the rubber except where near-white shades are desired.

Lignin-reinforced rubbers also provide advantages to the rubber converter. Lignin-coprecipitated rubber requires only one-fifth the breakdown time and the time for mixing pigment is eliminated entirely.

Lignin can serve a dual role in coprecipitation processes for other reinforcing pigments. The use of lignin as dispersant has the considerable merit that it actually aids coprecipitation and that after coprecipitation the lignin remains to act as a reinforcing pigment.

This process of reinforcing with lignin can be applied to any rubber which occurs in latex form. In using lignin an alkaline solution is first made and this is then mixed with latex in the desired proportions. The lignin and rubber are then precipitated together. This coprecipitate, or crumb, is then filtered and dried. The principal change in equipment over that now in use is in the type of filters. When suitable filters are installed, their use also offers other manufacturing advantages.

The tensile strength of lignin-reinforced rubber compares favorably with that of rubbers containing the best reinforcing pigments known. At loadings higher than normal lignin provides higher tensile strengths than any other material tested.

J. J. Kellen and Arthur Pollak, West Virginia Pulp and Paper Co., before the Rubber Division, American Chemical Society, Chicago, Sept. 13, 1946.

GERMAN ECONOMY SHOULD BE BALANCED NOW

It is better to have Germany attain a balanced economy, even if a much larger proportion of German war-potential industries must be retained than is now planned. Proper control of such industries by competent representatives of the four occupying powers, perhaps over an indeterminate period, would then be a "must." Without a balanced economy in Germany, the future economy of Europe is at stake. Existing conditions are strangling German enterprise and bringing the population daily closer to starvation. A feeling of hopelessness pervades German life today.

In addition to the crippling curtailment of heavy industry, most vital part of the country's prewar industrial life, the Allies' delay in carrying out the Potsdam agreement to treat Germany as an economic unit is wreaking havoc in all four occupation zones. At present, in none of the four areas can the occupation be designated as successful. The drastic conditions of economic life stemming from the firmly maintained trade barriers are too apparent for contention.

There appears to be no firm basis for the future reestablishment of a normal, non-aggressive state, willing and eager to earn its way back to acceptance into world accord. Hundreds of millions of American taxpayers' dollars are now flowing abroad

STERLING SLO-SPEED GEARED MOTORS

GEARED
POWER
FOR
INDUSTRY

THROUGHOUT America, in great and small production plants alike, wherever power turns the wheels of industry—Sterling Slo-Speed (Geared) Motors are leading the way to increased production records.

Sterling Slo-Speed (Modern Gear System) Motors give machinery manufacturers and production executives a complete power drive in one soundly engineered—compact—flexible—ultra efficient unit.


Write today for complete information

STERLING ELECTRIC MOTORS, INC.
NEW YORK • CHICAGO • LOS ANGELES
Representatives in Principal Cities

WRITE YOUR OWN TICKET

H.P.—From $\frac{1}{2}$ to 15

GEAR RATIOS—From 3:1 to 50:1



STERLING ELECTRIC MOTORS

for Greater Perform-ability



WHY PUSH WHEN YOU CAN CONVEY

Pushing material around is not only slow, hard work — it's costly material handling — there's an easy way to do it.



Investigate the use of conveyors. Conveyors handle a wide variety of parts, packages, units, cans, bottles, barrels, bundles, drums and boxes. Available in light, medium or heavy-duty types — portable or stationary — as systems, sections or units — power or gravity fed, they give you remarkable savings in time, money and manpower conservation. They relieve confusion and congestion.

Standard Conveyor Company has the experience and facilities to engineer, recommend and furnish the right type of conveyor for your particular needs.

Write today for catalog No. CM116 "Conveyors by Standard" — a ready reference on conveyor types and systems.

STANDARD CONVEYOR CO.

General Offices: North St. Paul 9, Minn.
Sales & Service in Principal Cities



ROLLER-BELT-SLAT-PUSHBAR CONVEYORS • PORTABLE CONVEYORS
AND PILERS • SPIRAL CHUTES • PNEUMATIC TUBE SYSTEMS



PRODUCTION LINES

Slat type conveyor used to speed assembly and crating of refrigerators.



STORAGE AREAS

Portable "Handibilt" conveyors used as a continuous conveyor line in storage area.



LOADING PLATFORM

Oil drums leave the warehouse for loading into boxcars on gravity roller system.

annually to keep Germany running. Large expenditures will be necessary so long as a balanced economy is not reached. The American people are unlikely to agree complacently to contribute to Germany's economy for more than two or three years.

Under these circumstances, what usually results is an investigation by a Congressional committee. The findings may be that the regulations are too severe, and the subsequent recommendations that the controls should be relaxed.

The danger is that future leniency may go beyond the measure of advisability.

Roger Adams, University of Illinois, before American Chemical Society, Chicago, Sept. 11, 1946.

HUMAN FACTORS AFFECT EFFICIENCY AND COSTS

CHEMICAL processes of the future must be designed with more appreciation of the human factor. Regardless of how a design corresponds to the various codes, it will not run at top efficiency if it does not take into account the safety and health of the people who have to operate it. With the industrial trend toward higher operating pressures, the production and transporting of more highly flammable and more highly toxic substances, the need for greater emphasis on chemical process safety becomes imperative.

Greater emphasis should be placed on safety in engineering in the professional schools, however, it should be an integral part of all courses rather than a separate study in itself. In methods used to protect personnel, property and product against loss by accident, fire, explosion or toxic properties, greatest attention must be given to the human element since it is responsible for over 80 percent of all accidents.

Much more progress in industrial safety will be made when the emphasis is shifted from the humanitarian point of view, commendable as it is, to the production point of view of efficiency and cost.

William F. O'Connor, New York University, before the Industrial and Engineering Division, American Chemical Society, Chicago, Sept. 9, 1946.

RECTIFICATION FOR THE ELECTROLYTIC INDUSTRIES

DURING the war the a.c.-d.c. conversion equipment in the electrolytic industry was expanded to 4.5 million kw. The major part of such conversion equipment is in aluminum, magnesium, chlorine, copper and zinc. At the peak of operation during the war, these five processes consumed approximately 31 billion kwh. annually. This is more energy than is consumed by any other single industry.

Nearly all of the conversion equipment installed in the aluminum industry since 1931 has been of the mercury arc rectifier type. The only complete and new installation of rotating apparatus covers gas-engine-driven d.c. generators installed during the war because of a shortage of power. They were installed in a location where natural gas was plentiful.

Of the approximately 525,000 kw. of conversion apparatus installed for magne-

An Important Announcement About Fire Extinguishing Equipment



The Mathieson Alkali Works (Inc.) is now producing a complete line of carbon dioxide (CO₂) fire-fighting equipment. Types include both high and low pressure installations of automatic and manual design. Surveys and recommendations are made for plants requiring built-in systems.

Orders are now being taken. Address your inquiries to The Mathieson Alkali Works (Inc.), 60 East 42nd Street, New York 17, N. Y.

Carbonic Gas...Dry Ice...Caus-
tic Soda...Soda Ash...Liquid Chlor-
ine...Chlorine Dioxide...Ammonia,
Anhydrous & Aqua...MTH Products
Fused Alkali Products...Synthetic
Salt Cake...Bicarbonate of Soda
Sodium Chloride Products
Sodium Methylate

Mathieson
CARBON DIOXIDE



First Aid Equipment
—75-lb. capacity
wheeled portables.



Cylinder batteries —
designed for small
capacity, built-in sys-
tems. ICC cylinders.



1000-lb. capacity
A.S.M.E. containers.
Designed for built-in
systems using masses
of high pressure CO₂.



***PRESSURE-IZED**
liquid CO₂ units. Ca-
pacities 2000 lbs. to
200,000 lbs. Designed
for your large capac-
ity fire systems.



Recharge service.

*Temperature—Pressure
Controlled CO₂



Available in barrels
and tank cars

INDOPOL

Polybutenes
Bulletin 12

INDONEX

Rubber Plasticizers
Bulletins 13 and 13A

INDOIL

Hydrocarbons
Bulletin 10

INDOIL

Petroleum Sulfonates



Address inquiries to

STANDARD OIL COMPANY (INDIANA)

CHEMICAL PRODUCTS DEPARTMENT

910 South Michigan Avenue

Chicago 80, Illinois

sium production, 75,000 kw. are in rotating apparatus and the remainder in mercury arc rectifiers.

There are so many different kinds of chlorine cell lines that it is difficult to compile very complete data on them. About every type of conversion equipment is represented and many operating voltage levels. Approximately 175,000 kw. of conversion equipment is in mercury arc rectifiers and 115,000 kw. in rotating apparatus.

Zinc and copper cell lines usually require about 10,000 amp. Zinc cell lines have usually been installed at 500 to 600 v., while copper cell lines have been installed at 200 to 300 v. Some foreign installations have been made using voltages up to 800 or 850 v.

For normal operation, the cell line is operated at substantially constant d.c. voltage. Where rectifiers are applied to zinc lines, the voltage adjustment has been obtained by regulating transformers or grid control. There have been no rectifiers applied, in this country, to copper processes, probably because of the low d.c. voltage requirements and because of the state of the art at the early dates at which most of the copper lines were installed.

The mercury arc rectifier has become well established in the electrochemical field. While there were several individual rectifier installations in the electrochemical industry prior to 1935, rectifiers can be

Industry	Rotating D. C. Kilowatts	Rectifier D. C. Kilowatts	Total
Aluminum	516,985	2,941,750	3,458,735
Magnesium...	72,800	448,140	520,940
Chlorine.....	114,370	173,790	288,160
Zinc.....	169,100	58,736	227,836
Copper.....	55,230	0	55,230
Total...	928,485	3,622,416	4,550,901

considered to have become generally acceptable at about that time. Large rotating apparatus installations made before 1935 are not evidence that rectifiers were unsuitable.

If the cell-line voltage is 250 v., the rectifier equipment is competitive in first cost with rotating apparatus, when building cost, ventilation, and foundations are considered. Rectifier equipment is in the neighborhood of 50 to 55 dollars per d.c. kilowatt installed. Below 250 v., rotating apparatus is generally installed because the operating advantages of rectifiers cannot overcome the advantage of rotating apparatus in first cost and efficiency.


T. R. Rhea and B. R. Connell, General Electric Co., before the Electrochemical Society, Toronto, Oct. 17, 1946.

DIFFRACTION STUDIES OF TURBINE DEPOSITS

A study of a number of steam turbine deposits using x-ray diffraction techniques as a means of identifying the crystalline phases present was made. The study has been limited to those compounds which may be the result of carry-over of material from the boiler.

With the exception of amorphous silica, compounds found in turbine deposits are normally well crystallized, indicating that the conditions surrounding their occurrence are favorable for grain growth.

Evidence was found of the tendency of sodium metasilicate, sodium disilicate,



Any Method of Branch Pipe Connection is Made Easier with WELDOLET FITTINGS!

• Whether your branch lines are to be butt-welded, socket-welded or threaded, Weldolet Fittings will make the job easier. Above are shown the three types of outlets available in Weldolet Fittings—each designed and manufactured to provide a safe, strong, easy-to-use method of making branch pipe outlets.

In addition to providing safe, strong,

easy-to-install branch pipe outlets, the exclusive funnel-shaped inlet of these Fittings increases flow efficiency. This design eliminates excessive turbulence and friction which is encountered at right-angle pipe intersections.

To get the complete story on these modern fittings, write today for a copy of the Weldolet Fittings Catalog—it will be sent you without obligation.

Forged Fittings Division

BONNEY FORGE & TOOL WORKS • 344 Green Street, Allentown, Pa.



WELDOLETS


TRADE MARK REG. U. S. PAT. OFF. PAT. IN U. S. & FOREIGN COUNTRIES

WELDING OUTLET - THREADED OUTLET - SOCKET OUTLET

For Welded Branch Pipe Outlets



PEERLESS



VERTICAL DEEP WELL TURBINE PUMPS

• Engineered for Efficient, Low Cost Industrial Water Supply Services

Peerless Vertical Deep Well Turbine Pumps develop capacities from 15 to 30,000 g.p.m. from any practicable depth. Exclusive engineering features enable Peerless Turbine Pumps to more efficiently maintain continuous, heavy duty water pumping demands in modern industry. Peerless Deep Well Turbine Pumps are available in both oil or water lubricated types (water lubricated illustrated) and are adaptable to all forms of drives.

Peerless FIRE PUMPS

(FORMERLY DAYTON-DOWD)

Built by Fire Pump Specialists Underwriters' Approved

Illustrated right with complete fittings but without relief valve



Peerless Type AF Fire Pump

CAPACITIES: From 500 to 2000 g.p.m. DEVELOPS PRESSURES TO 125 lbs.

High efficiency fire pumps embodying advanced design. Adaptable to motor or engine drive or combinations.

PEERLESS

PUMP DIVISION

FOOD MACHINERY CORPORATION

Factories: 301 W. Ave. 26, Los Angeles 31, Calif.
Quincy, Illinois - Canton 6, Ohio

quartz, and amorphous silica to occur as a series in the order named with decreasing temperatures. Other components of turbine deposits, such as sodium chloride, fail to show a temperature relationship.

Some compounds such as sodium chloride, burkeite, and the sodium sulphates appear to be related to low-pressure operation. Acmite has so far been found associated with high-pressure operation. Other compounds such as sodium disilicate, quartz, and amorphous silica appear to have no relation with the operating pressure.

L. A. Burkardt and C. E. Imhoff, Allis-Chalmers Mfg. Co., before Division of Water, Sewage and Sanitation Chemistry, American Chemical Society, Chicago, Sept. 10, 1946.

VULCANIZATION OF GR-S WITH HALOGEN COMPOUNDS

AN ENTIRELY new class of nonsulphur vulcanizing agents for butadiene-styrene copolymer rubbers has been discovered. This consists of halogenated compounds which may be divided into three types: (1) halogenated aliphatic hydrocarbons con-

taining at least one $-CX_n$ group, where X represents chlorine, bromine, or iodine, (2) halogenated aryl methyl compounds containing at least one halogen in the methyl group, and (3) aliphatic compounds containing a $-CX_n$ group and another reactive group, such as ethyl trichloroacetate. Each of these types behaves somewhat differently with respect to activation by metal oxides and other substances, but all will give vulcanizates having high moduli and good tensiles. The vulcanizing agents of the second type are of particular interest since by their use vulcanizates of unusual aging properties can be produced. These vulcanizates show no increase in moduli or decrease in elongations on 1-2 day 100 deg. C. oven aging, and sometimes even show reversion on aging, which is a very unusual phenomenon for GR-S.

These halogenated vulcanizing agents may lead to new concepts of the vulcanization process.

B. M. Sturgis, A. A. Blum and J. H. Trepagnier, E. I. du Pont de Nemours & Co., before Division of Rubber Chemistry, American Chemical Society, Chicago, Sept. 11, 1946.


FOREIGN LITERATURE ABSTRACTS

SULPHATES IN DRINKING WATER

SULPHATES in water are usually determined either gravimetrically as barium sulphate, or by Marty's method of successive approximations. There is also a volumetric method for the determination of soluble sulphates using a reagent with a barium

chromate base which was applied to sodium sulphate by Goise. This complicated method has now been simplified and the blank test eliminated. The determination is carried out as follows: 200 cc. of water is measured into a 500 cc. Erlenmeyer flask. Approximately 2 g. of pulverized barium chromate is added and 2 cc. of pure hydro-

MATERIALS MOVED FASTER!




with a Brooks **LOAD LUGGER**

Try this handy system of moving materials between processing points or to packaging stations. A Brooks Load Luger mounted on your truck chassis serves any number of detachable bucket bodies . . . operates from power take-off . . . needs only 15 seconds for hoisting or dumping. Crystals, pigments, acids, residue—almost any type of material, whether liquid, solid or gaseous, are easily loaded into low-level buckets. Less labor required and less truck maintenance because one Load Luger with set of buckets is equivalent to several trucks. Write for catalog today.


503 Davenport Rd., Knoxville 8, Tenn.

Distributors in all Principal Cities

Brooks EQUIPMENT AND MFG. CO.



Whether it's just a simple closed cylinder or a massive complex processing tank—it's a job that can be done best by Nooter. From the blueprint—through the fabrication—and to the assembled, tested tank and even in erection—Nooter engineering takes over with experience and with the most modern efficient tank building facilities available. Tank fabrication of alloy, clad or lined construction is at its best with Nooter DuraPure Welding. For safety, permanent strength and resistance to corrosion the DuraPure Weld, exclusive with Nooter, is the symbol of fine tank building.



28,000 KVA transformer tank and radiators fabricated and DuraPure Welded by Nooter in two knock-down sections.



5'6" x 120" steel fractioning tower, complete with bubble trays and caps, fabricated and DuraPure Welded by Nooter.

SAVE THOSE WORN MECHANICAL PARTS FROM EXPENSIVE REPLACEMENT with NOOTER METALLIZING

Shafts, bearings, cams and mechanical parts, no matter how badly worn, scored or corroded, are built up with original metal or superior metal and then machined to original or revised dimensions by the Nooter Metallizing Division.



Flywheel and air compressor crankshaft built up to fit new flywheel bore.



Worn 4"x96" shaft being Nooter Metallized to original dimensions with 4 metal spray units in simultaneous operation using .8% carbon steel analysis deposition.



Battery of 8' x 20" stainless steel jacketed, stainless steel milk storage tanks of DuraPure Weld construction.

Whatever your tank problems or plans, consult Nooter. Write, wire or telephone. Nooter engineers and estimators are at your service.



A practical approach



to your Pulverizing problem

WHEN you need finer grinding; when more uniform particle size or more thorough dispersion of your pulverized material will improve your finished product—if you feel your milling costs are too high—we invite you to take what many concede is the most practical first step toward the solution of a pulverizing problem.

Let us send you our Confidential Test Grinding Data Sheet. It is especially designed for your convenience in supplying all the pertinent information required for a competent analysis of your problem. Upon receipt of it and a working sample of your material, we can make available to you, without obligation, the facilities of our Laboratory and Test Grinding Department.

There, an actual grinding test on your sample, will, with the aid of this confidential test information, provide for a complete recommendation as to the indicated answer to your problem, and the type of equipment needed. This offers you a sound basis upon which to plan your production operations. Send for your Data Sheet today.

SEND FOR

—your copy of the new 48-page illustrated MIKRO-PULVERIZER and MIKRO-ATOMIZER catalog just issued. Contains the latest information on the improved production of fine and ultra-fine powders through mechanical pulverization.

PULVERIZING MACHINERY COMPANY

55 CHATHAM ROAD • SUMMIT, N. J.

NOW . . . 2 TYPES TO MEET MOST PULVERIZING NEEDS

MIKRO-PULVERIZER

MIKRO-ATOMIZER

Reg. U. S. Pat. Off.

chloric acid. The mixture is boiled for 2 min., and then ammonia is added until there is a definite odor. The mass is permitted to cool, placed in a calibrated 250 cc. glass tube and the distilled water used for washing out the Erlenmeyer flask several times, is added. The mixture is then filtered several times until a clear liquid is obtained, 125 cc. of this liquid is removed, and 1 g. of pure potassium iodide and 10 cc. of $\frac{1}{2}$ sulphuric acid is added. It is titrated with N/20 sodium hyposulphite in the presence of starch paste. N cc. are consumed; $N \times 0.00163 =$ sulphates per liter of water expressed as sulphuric acid.

Digest from "Determination of Sulphates in Drinking Water" *Bull. Trav. Soc. Pharm. Bordeaux* 83, No. 1, 9-11, 1945. (Published in France); *Chimie et Industrie* 55, No. 4, 272, 1946.

MEXICAN PETROLEUM AND GAS

MEXICO has fabulous quantities of gas which are being wasted and which could be an important base for chemical industries on a large scale. It has liquid hydrocarbons in the entire series of possible types, from the highly asphaltic petroleum to that having a paraffin base. This country's production has reached second place in the world, and only a small proportion of the potential sources has been exploited so far. For many years Mexico's petroleum has been under the control of international trusts, a situation which is very discouraging to the future development of this industry. If Mexico is to develop an important chemical industry based on liquid and gaseous hydrocarbons, it is essential that the government make it possible for private enterprise to develop in the country and discourage foreign control.

Digest from "National Chemical Industry" by Jose D. Lavin, *Química IV*, No. 2, 31-36, 1946. (Published in Mexico.)


ARGENTINE CLAYS

KNOWLEDGE of the chemical composition of kaolins is important in their utilization, but it is also necessary to know the proportion of the accompanying materials to the aluminum hydrosilicate, content and type of sand, physical properties, etc. Samples were taken from the Maria Eugenia mine in Buenos Aires and the Mutouin mine in Catamarca. They were subjected to an elemental chemical analysis; a rational chemical analysis to separate the soluble silicic acid from the insoluble by means of sodium carbonate (the soluble part corresponds to aluminum hydrosilicate and the insoluble to quartz and feldspar); a physico-chemical analysis to determine the water-soluble salts which may harm the consistency of the finished material; a physical analysis to determine the quantities of coarse and fine sand, and its size, as well as the quantity of pulverulent clay capable of forming mud.

Digest from "Physico-Chemical Study of Argentine Clays", *Industria Minera VI*, No. 56, 69-70, 1946. (Published in Argentina.)

BIOTIN

BIOTIN, a compound which is widely distributed in nature, even if in very small quantities, is not only important as a stimulant for the growth of yeast and various



These easy-to-clean stainless steel dyeing machines illustrate but one of many applications for lustrous Republic ENDURO in processing industries. Others include: mixers, condensers, evaporators, filters, valves, drums and tubing.

Enduro Pays in many ways

Improved Employee Relations
Easy to Clean
Non-Contaminating
Strong—Long Lasting
Resistant to Rust and Corrosion
Resistant to Heat
Easy to Fabricate
Universal Acceptance
Low Ultimate Cost

Lustrous, bright, sanitary appearance—plus factor of Republic ENDURO Stainless Steel—pays prompt dividends in improved employee relations.

ENDURO is clean—and remarkably easy to clean. It makes work easier. Employees take pride in keeping it spotless. They find new incentive in the bright, cheerful atmosphere created by gleaming ENDURO equipment. And its smooth, shiny surface never wears out because ENDURO is solid stainless steel all the way through.

There are many other reasons, too, why it will pay you to specify ENDURO Stainless Steel. See your equipment manufacturer or write directly to:

REPUBLIC STEEL CORPORATION
Alloy Steel Division • Massillon, Ohio
GENERAL OFFICES: CLEVELAND 1, OHIO
 Export Department: Chrysler Building, New York 17, New York



Republic


ENDURO STAINLESS STEEL

Reg. U. S. Pat. Off.

Other Republic Products include Carbon and Alloy Steels—Pipe, Sheets, Strip, Plates, Bars, Wire, Pig Iron, Bolts and Nuts, Tubing

Ingenious New Technical Methods

To Help You with Your
Reconversion Problems



12,000 Holes per Hour! With New Gearless Multiple Spindle Drillhead!

The **Zagar Gearless Drillhead** can accommodate up to 400 drills in one head—drill up to 400 holes at one time! This revolutionary unit runs noiselessly and vibration-free on needle, tapered roller and precision ball bearings, and is lubricated by a patented automatic oiling system to insure trouble-free operation.

With this unit all holes are drilled at one pass, and valuable time is saved by the elimination of indexing and extra handling. It may be used on standard drill presses, or furnished as a complete hydraulic machine by the factory.

Another time saver, as well as a help on a tedious job, is chewing gum. The simple act of chewing seems to make the work go faster, easier—helping to relieve worker's fatigue—so that a better piece of work can be turned out with greater safety. Wrigley's Spearmint Gum may be used even when both hands are busy—right where the work is being produced.

You can get complete information from
Zagar Tool, Inc.
23881 Lakeland Blvd., Cleveland 17, Ohio



Zagar 220 Spindle Gearless
Drillhead



microorganisms, but is also a phytohormone which affects the growth of higher plants. Nor is there any doubt that it is also essential to the health of higher animals and man. It occurs in the tissues of various organs, especially the liver and kidneys, and is a constant component of urine, blood serum, milk and many food products. Biotin is identical to the coenzyme "R," a factor of growth and respiration of *Rizobia trifolii* and with vitamin H. Biotin is extracted from such materials as yeast, egg yolk, liver, etc. by taking advantage of its capacity for adsorption on carbon, followed by extraction with an ammonia solution of acetone and other solvents. It was found that biotin and its methyl ether are equally active. In many cases desthiobiotin is just as active, but the diaminopelargonic acid made from it has only 10 percent of the activity of biotin. Alpha-biotin, beta-alanine, and hexylglyoxidone show a biotin activity to a lesser degree.

Digest from "Biotin," by N. G. Yartseva, *Uspekha Khimii* XV, No. 2, 203-204, 1946. (Published in Russia.)

SULPHO-OXIDIZED SOAPS FROM PETROLEUM BYPRODUCTS


RESIDUES from the manufacture of lubricating oils by cracking serve as raw material in the Van Andel process. These residues, which have not been utilized so far, are distilled and the 160-310 fraction contains a large proportion of olefins. Suitable treatment with H_2SO_4 results in sulpho-oxidized soaps of a quality comparable to that of products now available on the market. Sulpho-oxidized soaps have the same colloidal properties as ordinary soaps, properties which influence their detergent power. If the latter soaps have a general formula of RCO_2Na (carboxylates), then the sulpho-oxidized soaps have the formula $R\cdot SO_3Na$ (sulphonates) or $R\cdot O\cdot SO_3Na$ (alkyl sulphates) or a mixed formula. Presence of the CO_2Na group gives the soaps properties similar to those of carbonates: precipitation by all the metallic salts except the alkalis; ready decomposition by the acids. The sulphonates and the alkyl sulphates, on the contrary, are soluble no matter what cation is bound to the functional group. As a result, they are not precipitated either by the salts of calcium or magnesium or by hard water nor are they decomposed either by acids or by sea water. Their solubility in water is much greater than that of ordinary soaps. The viscosity of their solutions is very low. All in all, their detergent and wetting power is definitely better. The sulpho-oxidized detergents produced by the Van Andel process are superior to all the other products—their aqueous solutions are still fluid at 35 percent, whereas the other sulphonates or alkyl sulphates cannot be used at more than 5 percent, and the soaps at more than 1 percent; their lime and magnesium salts are very soluble and sea water does not attack them. These are the best products for cleaning, laundering, bleaching and scouring in the textile and dyeing industry.

Digest from "Manufacture of Sulpho-Oxidized Soaps from Petroleum Byproducts. Van Andel Process," *Genie Civil*, 122, No. 4, 27-29, 1945. (Published in France); *Chimie et Industrie* 55, No. 5, 368, 1946.

AA-100

CHEMICAL ENGINEER'S BOOKSHELF

LESTER B. POPE, Assistant Editor



Continuous pressure filters in a sugar plant

SOLIDS FROM LIQUIDS

THEORY AND PRACTICE OF FILTRATION.

By George D. Dickey and Charles L. Bryden. Reinhold Publishing Corp., New York. 346 pages. \$6.

ONE of the most widely used separation methods, filtration, is used in nearly every chemical processing plant. This book is primarily devoted to the separation of solids from liquids by the use of porous media. Generally, it can be divided into two parts, the first dealing with history, theory and principles as a foundation for the proper understanding and interpretation of filtration. The remaining part, and by far the bulk of the book, is devoted to the various types of filters, auxiliary equipment, and information concerning these.

Historically, the whole subject is treated from ancient times to the present. Early concepts, patents, and the various important developments are covered. Theory and principles are discussed in some detail and the contributions of various persons in this field are outlined. This is followed by a study of filtration objectives in which the major purposes are discussed and process variables such as rate of flow, temperature, concentration, etc., are shown in relation to the problem. Use of such materials as coagulants, precoat, filter aids, and adsorbents, is described. An excellent discussion of filter media, their characteristics and applications, helps provide a good basic knowledge of this most important element of filtration equipment.

Seven full chapters are used to describe the various major types such as gravity filters, pressure filters, vacuum filters, hydraulic pressure and squeeze presses, expellers, centrifugals, and auxiliary equipment. Depending on the particular type of equipment described the author has gone into sufficient detail so that the reader can

evaluate a particular filter with respect to his own problems. In many cases the discussion of each filter is broken down into sections on construction, operation, materials handled, advantages, disadvantages, materials of construction, and sizes. Certain subjects, such as water filtration and sewage clarification, are considered by themselves. A number of typical applications are shown, and the subjects of testing and selecting filters as well as installation and operation are treated.

A large number of illustrations including photographs, cutaway views, diagrammatic sketches and flowsheets are used to illustrate principles, equipment, applications, and installations. On the whole, the book presents a comprehensive review of the subject of filtration and is a book that can be used to practical advantage by engineers.

AVENUE OF APPROACH

VAPOR ADSORPTION. By Edward Ledoux. Chemical Publishing Co., Brooklyn. 360 pages. \$8.50.

Reviewed by E. R. McLaughlin

VAPOR adsorption, a laboratory phenomenon which has grown to be a vital adjunct in industry, is still somewhat of a mystery. Present methods are limited to operating experience. There is a definite need for a guide to aid those making their initial survey of adsorption theories and methods. The author's preface outlines a text which might fill this need. However, the subsequent treatment given to each subdivision of the subject is rather superficial, as it must necessarily be to be included in a small volume. The various principles are given and numerous theories are summarized with examples to substantiate some of them. Nearly a third of the book is devoted to static adsorption. An understanding of static adsorption provides

essential fundamentals, but the industrial application of vapor adsorption is seldom static.

The second part of the book is a hasty recapitulation of psychrometry, heat transfer, and vapor transfer as a build up to the problem of dynamic adsorption.

Only twelve pages each are devoted to dynamic adsorption, and to dynamic desorption. For comparison, dehumidification by refrigeration is discussed for several pages, and absorption, which is an entirely different phenomenon, rates twelve pages. Industrial applications include air conditioning, conditioning underground spaces, hygroscopic materials, compressed gases, and vapor recovery.

A book of this nature cannot possibly contain all of the known information on adsorption. The operating engineer will find no trade secrets. However, the treatment offers an avenue of approach to the subject for the student exploring the field for the first time.

COLLOID PRIMER

COLLOIDS, THEIR PROPERTIES AND APPLICATIONS. By A. G. Ward. Interscience Publishers, New York. 133 pages. \$1.75.


Reviewed by F. C. Nachod

THIS little booklet is indeed a fine primer of colloid science. It is subdivided into three main parts: the nature of the colloidal state, the colloidal systems, and colloids in industry and in living matter. In this last part, various industries in which colloid chemistry plays an important role, such as rubber, cellulose, proteins, clays, paints, lacquers, varnishes, detergents are dealt with briefly and in a descriptive manner. A bibliography refers the reader elementary and advanced texts.

It is to be hoped that other members

RECENT BOOKS RECEIVED

- Atomic Theory for Students of Metallurgy. By W. Hume-Rothery. Institute of Metals, London. 7s. 6d.
- Chemical Analysis of Metals. American Society for Testing Materials. \$4.50.
- The Chemistry of Heterocyclic Compounds. By A. A. Morton. McGraw-Hill. \$6.
- Fuels, Combustion and Furnaces. By J. Griawold. McGraw-Hill. \$5.50.
- Incendiary Warfare. By G. J. B. Fisher. McGraw-Hill. \$3.
- Introduction to the Chemistry of the Silicates. E. G. Rochow. Wiley. \$2.75.
- Oil Field Development. 3rd ed. By L. C. Uren. McGraw-Hill. \$7.
- Personal Adjustment. By H. Dunlap. McGraw-Hill. \$4.
- Statistical Quality Control. By E. L. Grant. McGraw-Hill. \$5.
- What Industry Ows to Chemical Science. Chemical. \$5.
- When the Oil Wells Run Dry. By W. M. Fuchs. Industrial Research Service. \$3.75.



TANKS

We build and erect a complete line of elevated tanks for the storage of liquids of all kinds—ranging in size from 5,000 to 2,000,000 gallons, with hemispherical, ellipsoidal and conical bottoms.

In addition to elevated tanks, we specialize in oil and water storage tanks, pressure vessels, acid tanks, pulp digesters, refinery towers, creosoting cylinders—and all forms of fabricated steel plate construction, both riveted and welded.

Estimating figures or firm quotations supplied without obligation to you. Write for a copy of our catalog—"Tank Talk."


R.D. COLE MFG. CO. ESTABLISHED 1854
Newnan Ga.



ROBINSON

PROCESSING  EQUIPMENT

ATTRITION MILLS



Attrition Mills for grinding all types of material. Adjustable for coarse or fine grinds. Hard iron grinding plates. Capacities to your requirements. Robinson Processing Equipment is designed by engineers whose reputation is founded upon doing things right. Literature available. Inquiries invited.

ROBINSON MANUFACTURING CO.

Plant: Muncy, Pa.

SALES REPRESENTATIVE

MERCER-ROBINSON COMPANY, INC.
30 CHURCH ST., NEW YORK, N. Y.

of Blackie's "Technique" series, where Mr. Ward's colloid chemistry text made its first appearance in England, will be made available in this country.

SUPPLEMENTARY READING

GERMAN FOR THE SCIENTIST. By Peter F. Wiener. Chemical Publishing Co., Brooklyn. 238 pages. \$3.50.

Reviewed by M. G. Callahan

This new scientific reader includes approximately 40 pages of grammar, 52 pages of chemistry passages and 31 pages of physics passages. The rest of the book is devoted to a translation of these passages and a vocabulary. This book should provide good supplementary reading for Fotos and Shreve's "Advanced Readings in Chemical and Technical German."

RUSSIAN ENIGMA

TWO WORLDS. By William B. Ziff. Harper & Brothers, New York and London. 335 pages. \$3.


Reviewed by H. C. Parmelee

THE meeting of the Assembly of the United Nations Organization in New York is a perfect background for reading this book, with Russia alternately frightening the delegates with Mr. Molotov's disquieting speeches, and then reassuring them with Mr. Stalin's disarming answers to United Press questions. The rest of the world can hardly be blamed if, at one minute it looks around apprehensively for the cyclone cellar, and then wonders if it can believe its ears at sounds of peace and harmony. But all this emphasizes the enigma of Russia in international relations, particularly with the U.S.A. which, Mr. Ziff believes, must take drastic measures to survive the tide of Communism now flowing over the world. Don't read this book if you dislike facing unpleasant realities and prefer to spend your evenings quietly in the comfort and security of your home. On the other hand, it may be just as well to get the basic idea that, although Russia may from time to time change its tactics, it never changes its strategy for the conquest of the world for the proletariat. This goal is just as explicit in the writings and speeches of Stalin and other Russians, as was Hitler's in *Mein Kampf*. Anyhow, you can't say Mr. Ziff didn't warn you.


The author has a style and vocabulary that sets a swift pace, giving the impression that time is short, and that maybe it is already too late to set up the two worlds he envisages—one dominated by the U.S.S.R. and the other by the U.S.A. But he documents his contentions with historical facts and figures that seem inescapable, laying bare the "jungle of international diplomacy," the ultimate resort to power politics that undermine efforts at collaboration, and the violation of agreements like those reached at Yalta, Teheran, Moscow, and Potsdam.

Discarding the United Nations Organization as an ineffective instrumentality for world peace—not much better than the old League of Nations—the author sees nothing but war in pursuing the present policies of the U.S.S.R. and the U.S.A. Their philosophies, ideologies, historical

FOR TODAY'S **TOUGHER JOBS,** HERE'S A NEW **TOUGHER MOTOR**



WHERE IT'S WET Wet weather doesn't bother the new totally-enclosed Tri-Clad motor. Neither do frequent "washdowns" in food plants.



WHERE IT'S CORROSIVE Acids, alkalis, and fumes are kept out of these new Tri-Clads. Cast-iron enclosures are corrosion-resistant, extra strong.



WHERE IT'S DIRTY Dirt and dust can't get into these Tri-Clads to shorten their life. Smooth surfaces are convenient to clean.



WHERE IRON DUST FLIES Harmful iron dust and metal filings can't get past the inner wall. Bearings are protected from dust.




WHERE QUARTERS ARE CLOSE When space is limited for a totally enclosed motor, you'll like these trim, compact new Tri-Clads.



WHERE EXPLOSION HAZARDS EXIST The new Tri-Clad motors are available in explosion-proof constructions where needed.

THE G-E **TRI-CLAD** TOTALLY ENCLOSED MOTOR (1 TO 1000 HP)

In 1940 you welcomed the Tri-Clad open motor with its *extra protection features*. More Tri-Clads have since gone into service than any other integral-horsepower motor. Now G.E. is ready with a new line of tough, totally enclosed Tri-Clad motors for use in adverse atmospheres. *We believe they are industry's most dependable motors.* Their longer life and lower maintenance will make them a sound investment on almost every job. Apparatus Dept., General Electric Co., Schenectady 5, N. Y.



10-POINT PROTECTION

1. A cast-iron, double-wall frame completely encloses and protects the windings and punchings.
2. Corrosion-resistant cast-iron end shields are machined to provide a tight seal, and protect the motor from dust, dirt, and moisture. Primer and finish coat of Glyptal[®] varnish affords high rust-resistance.
3. A pressure-relief greasing system, which can be packed with long-life lubricant, protects the bearings.
4. The cast-iron conduit box is diagonally split for easy wiring. Boxes are independently explosion-proof on Class I motors.
5. Nonshrinking compound around motor leads protects motor interiors from

- dust and moisture at the point where leads pass through the frame.
6. Rotating labyrinth seal further protects motor interior from damage by foreign matter.
7. Large air passages provide adequate protection from overheating. They're easy to keep clean and open, too.
8. Modern, "ageless" insulation treatment includes windings of "Formex magnet wire."
9. The powerful external fan is removable to simplify maintenance; nonsparking type in explosion-proof motors.
10. Individual dynamic balance of rotors and external fans protects against vibration hazards, even under severe operating conditions.

FOR THE COMPLETE STORY

Apparatus Department, Section 750-278C
General Electric Company
Schenectady 5, N. Y.

- ☐ Please send me GEA-4400, which describes the new Tri-Clad totally enclosed motors.
- ☐ Please send me GEA-4131, "Motors and Control for Hazardous Locations."

NAME

COMPANY

ADDRESS

8039

^{*}Trade-mark Reg. U. S. Pat. Off.

GENERAL ELECTRIC

Handling Bales with BAKER TRUCK proves more profitable than "manhandling"



*Excerpt of Letter from The
American Thread Company*

* At our Willimantic plant car loads of raw cotton are received in bales weighing from 450-750 pounds. Prior to the Baker Fork Truck installation, this cotton was all man handled by the use of hand trucks, and cotton was stored "one bale" high on end, in two sheds at opposite ends of the plant. With the Baker Fork Truck we are able to stack bales six high which has increased the storage capacity of our "active" cotton shed by 1500 bales. Normally these 1500 bales would have gone into our concrete warehouse, then rehandled and moved to the "active" cotton shed before going into process. Thus we have saved double handling on 1500 bales.

**THE AMERICAN THREAD COMPANY
WILLIMANTIC, CONN.**



No matter what type of material you handle in your plant, you can cut intraplant transportation, storage or carloading costs with Baker Trucks. Call your nearest Baker representative or write us direct.

BAKER INDUSTRIAL TRUCK DIVISION of the Baker-Raulang Company
2145 WEST 25TH STREET • CLEVELAND, OHIO
In Canada: Railway and Power Engineering Corp., Ltd.



Members Electric Industrial Truck Association

Baker INDUSTRIAL TRUCKS

background and culture are mutually exclusive and offer no promise of a permanent alliance. But he regards these two nations—each a Federation of States—as natural nuclei for the formation of two World Federations that can be self-sustaining and sufficiently strong to resist aggression. These are his "Two Worlds," composed of central powers and their adhering states, one in the West and one in the East. Patterning the former on the latter, "The union we should seek to achieve should reach from Pole to Pole, and from Dover, England, to Perth, Australia. It should embrace all territories on which a human being can subsist in either the Atlantic or Caribbean oceans; and in the Pacific up to the very doors of Japan." In the author's opinion the clock of destiny is now striking and giving the U.S.A. its great opportunity to create a free world fit for free men to live in.

FIFTH REVISION

PHYSICAL CHEMISTRY FOR COLLEGES.
Sixth edition, By E. B. Millard.
McGraw-Hill Book Co., New York. 682 pages. \$4.50.

TWENTY-FIVE years is a long time for a textbook to remain current in a field which is advancing as rapidly as that of physical chemistry. But such is the case with Millard's which had its first copyright in 1921. And the new revision has modernized the text to give new crops of students the benefit of latest theories and discoveries. Much of the text has been rewritten and new problems have been added. Selection and order of topics has been retained but some shifting of emphasis is apparent.

RECENT BOOKS and PAMPHLETS

Chemical Engineering as a Profession. By W. T. Read. Vocational Booklet No. 3, National Roster of Scientific and Specialized Personnel. Available from Superintendent of Documents, U. S. Government Printing Office, Washington 25, D. C. 21 pages. 10 cents. The field, growth and outlook of the profession; the work of the engineer; where employed; qualifications; conditions of employment; how careers are started.

Chemistry as a Profession. By W. T. Read. Vocational Booklet No. 2, National Roster of Scientific and Specialized Personnel. Available from Superintendent of Documents, U. S. Government Printing Office, Washington 25, D. C. 20 pages. 10 cents. Data given for chemistry under the same headings as for Chemical Engineering as a Profession.

Potential Hazards in Molten Salt Baths for Heat Treatment of Metals. Published by National Board of Fire Underwriters, 85 John St., New York 7, N. Y. 40 pages. Contributory factors responsible for many incidents encountered. Suggested workable requirements and regulations safeguarding nitrate baths.

The Metallurgy of Quality Steels. By Charles M. Parker. Published by Reinhold Publishing Corp., 330 West 42nd St., New York 18, N. Y. 248 pages. \$6. Manufacturing methods, inspection, testing, effects of alloys, hardening.

Rubber Statistical Bulletin. Published by London Rubber Secretariat. Distributed by India Rubber World, 386 Fourth Ave., New York. Annual subscription, \$5. Vol. 1, No. 1 of a new monthly publication issued by an organization set up by the Governments of the United Kingdom, France and the Netherlands to collect and collate statistical and other general information on rubber.


Assembly, Testing and Operation of Laboratory Distilling Columns of High Efficiency.

WELDCO

CORROSION RESISTING TUBING

**LIGHT
WALL**

**LARGE
SIZES**



USE ALLOYS TO DECREASE
MAINTENANCE COSTS

ADVANTAGES . . . You buy just as much effective corrosion resistance in a light wall tubing of corrosion-resisting material as you do in a heavy wall. Why pay for the extra metal when you don't need it for low pressures?

STAINLESS STEELS . . . AISI Types: 302B, 304, 308, 309, 310, 316, 317, 321, 330, 347, and Special Chromium Nickel Steels.

ALLOY METALS . . . Cupro Nickel (70-30) Monel, Nickel, Alloy Steels, Inconel, other weldable material.

SIZES . . . Outside diameters: 3½, 4, 4½, 5, 5-9/16,

6, 6½, 7½, 8, 8½, 9½, 10, 10¾, 12, 12¾, and larger O. D. on request.

GAUGE . . . 16, 14, 12 U. S. S., 1/8", 5/32", 3/16" and 1/4".

LENGTH . . . Standard length is 10 feet on wall thicknesses under 3/16"; 12 feet is standard for 3/16" and heavier.

TYPE WELD . . . Submerged arc welding assures full penetration and is finished in conformity with the best practices to provide maximum corrosion resistance. All excess weld metal is removed from the interior of the tube.

Ask for the bulletin on Weldco Tubing, Fittings, and Fabricated Piping. Contains specifications, working pressures for different metals and other useful data. Mailed promptly.

THE YOUNGSTOWN WELDING & ENGINEERING CO.

WELDCO


Specialists in Corrosion Resistance

**LABOR
IS
SCARCE**

...so why not let

DRACCO

**PNEUMATIC CONVEYORS
MOVE YOUR MATERIALS**



Consult
DRACCO
Engineers

DRACCO Pneumatic Conveyors move chemicals, grains and granular materials with a minimum of manual labor. In most installations ONE man and a DRACCO Pneumatic Conveyor replaces SEVERAL men. Wherever installed, DRACCO Pneumatic Conveyors handle materials more efficiently and cheaper . . . with fewer man hours. Why not let DRACCO Engineers check your present material handling methods with a view of recommending a BETTER method requiring LESS labor. They have over 30 years of experience in material handling.

For Further Information Write

DRACCO CORPORATION

4071 E. 116th St., Cleveland 5, Ohio New York Office: 130 W. 42nd St.

**DUST CONTROL EQUIPMENT
PNEUMATIC CONVEYORS • METAL FABRICATION**

By C. B. Willingham and F. D. Rossini. Research Paper RPI724 National Bureau of Standards. Available from Superintendent of Documents, U. S. Government Printing Office, Washington 25, D. C. 29 pages. 10 cents. Assembly, testing and operation of columns used in the Bureau in the work of API research project 6 (analysis and purification of hydrocarbons) and in the preparation of standard samples.

Bacterial Chemistry and Physiology. By J. R. Porter. Published by John Wiley & Sons, 440 Fourth Ave., New York 16, N. Y. 1,071 pages. \$12. Graduate and undergraduate textbook as well as for reference use.

Application of Shaped Explosive Charges to Mining Operations: Tests on Steel and Rock. By R. S. Lewis and G. B. Clark. Bulletin No. 1, published by Department of Mining Engineering, University of Utah, Salt Lake City. 48 pages. \$1.25. Shaped charges have a definite and useful application in mining operations both in secondary rock breakage and drilling holes for blasting solid faces of rock. Includes a brief history of the Munroe effect which made bazookas possible.

Finishing Metal Products. Second edition. By H. R. Simonds and A. Bregman. Published by McGraw-Hill Book Co., 330 West 42nd St., New York 18, N. Y. 352 pages. \$4. Techniques involved, commercial aspects, sales value, economics, equipment, part design, and metal finishing costs.

Communist Infiltration in the United States. Published by Chamber of Commerce of the United States, Washington 6, D. C. 40 pages. 10 cents. Nature of communism and how to combat it.

Extractives From Northeastern Woods. Bulletin No. 9, published by Northeastern Wood Utilization Council, 839 Chapel St., New Haven, Conn. 62 pages. \$1. Commercial production in the Northeast, economic extraction of essential oils, and a literature review.

Safety, Sanitary, and Survival. By W. J. Wiswesser, director of chemical research, Willson Products, Inc., Reading, Pa. 2 pages. Mimeographed sheet which stresses the fact that everyone loses in radioactive and biological warfare. Gives three steps toward "Universal Safety."

Standard Metal Directory. 1946 edition. Published by Atlas Publishing Co., 425 W. 25th St., New York 1, N. Y. 842 pages. \$10. Plants, foundries, mills, manufacturers, distributors, fabricators, etc.—a reference book for the steel and metal industries.

Trane Air Conditioning Manual. Published by the Trane Co., La Crosse, Wis. 376 pages. \$5. New edition.

1946 Classified Directory. Published by Association of Consulting Chemists and Chemical Engineers, 50 East 41st St., New York 17, N. Y. 98 pages. Tenth edition of the listing of qualifications of 88 member concerns of the Association.

A Quick Look at Portland. Published by Industries Dept., Portland Chamber of Commerce, 824 S. W. Fifth Ave., Portland 4, Ore. 8 pages. A short study of natural resources, power, transportation facilities, labor and industry, taxes, and culture in the Portland area.

New Factories for California Communities. Pamphlet 11, published by State Reconstruction and Reemployment Commission, Sacramento, Calif. 21 pp. es. Prepared by J. N. Mills & Co. Shows how certain small California communities have provided facilities for factories and thereby induced firms to establish plants in this State.

Economic Base for Power Markets in Ferry, Stevens, and Pend Oreille Counties, Wash. By Peter Palmer. Published by Bonneville Power Administration, Portland 8, Ore. 47 pages. A survey appraising prospects for electric power consumption in these counties. Reviews the physical base, people and their incomes, public facilities and finance. Maps, photographs, and appendix tables are included.


Tungsten Deposits of Osgood Range, Humboldt Co., Nevada. By S. W. Hobbs and S. E. Clabaugh. Bulletin 40, published by Nevada Bureau of Mines and Mackay School of Mines, University of Nevada, Reno, Nev. 50 cents. Includes 11 maps of properties of the Getchell district with descriptions of properties and estimates of ore reserves.

Industrial Raw Materials for Portland-Vancouver Area. Prepared by Industries Dept., Portland Chamber of Commerce, 824 S. W. Fifth Avenue, Portland 4, Ore. 8 pages. Availability, quality, and economics of limestone, industrial carbon, ferruginous bauxites, gypsum, salines, silica and other chemical and industrial raw materials of the area.

Because Aluminum is nonmagnetic, it helps catch tramp iron



Permanent magnets in Eriez Non-Electric Magnetic Separators provide the powerful pull which removes and holds on to tramp iron.



All the power of these Alnico permanent magnets is available for useful work—removing tramp iron from materials passed near them. Their mounts are nonmagnetic Alcoa Aluminum, so there's no short circuiting of the magnetic forces.

Some users go a step farther, and make complete chutes and troughs of Alcoa Aluminum, thus avoiding dissipation of magnetic forces there. Materials passed through them get added protection; aluminum is highly

resistant to corrosion, so there's less chance of contamination.

Whether your problem is one of engineering or manufacturing, our engineers stand ready to assist in incorporating Alcoa Aluminum. Call the nearby Alcoa office, or write ALUMINUM COMPANY OF AMERICA, 2151 Gulf Building, Pittsburgh 19, Pennsylvania.

ALCOA FIRST IN ALUMINUM

IN EVERY COMMERCIAL FORM



A NEW "SOLID" SPRAY NOZZLE



Fig. H-530

Here is a new nozzle with two round tangential inlets (instead of several small slots) which permit relatively large solid particles to pass right through and out the orifice. Produces fine breakup, even distribution, and solid cone spray suitable for numerous applications.

Available in Brass, or made to order in any machinable material. 1/4" I.P.S. capacities from 12 to 75 gph @ 10 lbs. water pressure.

Send Monarch an outline of your spray problem—if the liquid can be sprayed with direct pressure at all—Monarch can furnish the nozzle.

NOZZLES FOR:

- ACID CHAMBERS
- AIR WASHING
- CHEMICAL PROCESSING
- COOLING POND
- DESUPERHEATING
- GAS SCRUBBING
- HUMIDIFYING
- OIL BURNERS
- SPRAY DRYING

Do you have our Catalogs
6A and 6C?

MONARCH MFG. WORKS, INC.

2730 E. WESTMORELAND ST.
PHILADELPHIA 24, PA.

GOVERNMENT PUBLICATIONS

The following recently issued publications are available at prices indicated from the Superintendent of Documents, Government Printing Office, Washington 25, D. C. In ordering any publications noted in this list always give complete title and the issuing office. Remittances should be made by postal money order, coupons or check. Do not send postage stamps. All publications are in paper cover unless otherwise specified. When no price is indicated, the pamphlet is free and should be ordered from the bureau responsible for its issue.

Fifth Annual Report of Special Committee Investigating the National Defense Program (formerly Truman Committee, later Mead Committee, now Kilgore Committee). Senate Report No. 110, Part 7. Price 25 cents.

Industrial Classification Manual. Bureau of the Budget. Volume 1, Manufacturing Industries. Part 1, Titles and Descriptions of Industries. Price 75 cents. Part 2, Alphabetic Index. Price \$1.

Committee on Food Research—Research Program 1945-1946. Quartermaster Corps Manual QMC 17-8. Available free on request to Quartermaster Food and Container Institute, 1849 West Pershing Road, Chicago 9, Illinois.

Statistics and Maps for National Market Analysis (Basic Information Sources). Department of Commerce, Inquiry Reference Section. Unnumbered, mimeographed, September 1946.

Synthetic Organic Chemicals, United States Production and Sales, 1944. Tariff Commission, Report No. 155, Second Series. Price 25 cents.

United States Import Duties, June 1946. 1. Titles I and II of the Tariff Act of 1930 (Dutiable and Free Lists). 2. Changes in Import Duties since 1930 (Prepared by the U. S. Tariff Commission). Department of State Publication 2540, Commercial Policy Series 87. Price 70 cents. Also flat-opening, plastic-ring-binder type, price \$1.25.

Suggested Charter for an International Trade Organization of the United Nations. Department of State Publication 2598. Commercial Policy Series 93.

Workers in Subjects Pertaining to Agriculture in Land-Grant Colleges and Experiment Stations, 1945-46. Department of Agriculture Miscellaneous Publication No. 603. Price 25 cents.

Rapid Photometric Methods for Determining Rubber and Resins in Guayule Tissue and Rubber in Crude-Rubber Products. By Hamilton P. Traub. Department of Agriculture Technical Bulletin 920. Price 10 cents.

Research on Peanuts and Peanut Products at the Southern Regional Research Laboratory. By K. S. Markley. Bureau of Agricultural and Industrial Chemistry, AIC-109. Mimeographed.

Glutamic Acid Review and Bibliography. By H. S. Olcott and G. H. Brother. Bureau of Agricultural and Industrial Chemistry, AIC-119. Mimeographed.

Report of Studies on Uniformity of Quality of Beet Sugars. By C. A. Fort and others. Bureau of Agricultural and Industrial Chemistry, AIC-123. Mimeographed.

A Power Sprayer for Applying Concentrated Insecticides. By Joseph N. Tenhet. Bureau of Entomology and Plant Quarantine, ET-231. Mimeographed.

A System of Filing and Routing Samples of Chemicals for Insecticide Testing. By M. W. Oberg, et al. Bureau of Entomology and Plant Quarantine, ET-233. Mimeographed.

The Use of DDT for Roach Control. By L. S. Henderson. Bureau of Entomology and Plant Quarantine, E-701. Mimeographed.

Field Studies on the Effect of DDT on Aquatic Insects. By C. H. Hoffman, et al.

BARECO Microcrystalline WAX

NOT a By-Product NOT a Side Line BUT

The EXCLUSIVE and ONLY Product of Our LARGE REFINERY at Barnsdall, Okla.

Yes, the ever-growing demand for our Be Square and Victory Microcrystalline Waxes has necessitated our converting our entire Barnsdall Refinery to the manufacture of these outstanding products.

Although microcrystalline waxes have been one of our major products for many years, and have become standard over the world, their applications have become so extensive and important to the many users, that we now find it advisable to discontinue the manufacture of all other petroleum products at Barnsdall, and to devote our entire facilities and activities to microcrystalline wax production.

Bareco Waxes, in other words, are now, more than ever, made "on purpose"—thus eliminating the usual variables in quality and supply so often found in by-products waxes. Bareco Waxes are uniform—their production is constant, because WAX IS OUR BUSINESS!

Buy Bareco Waxes with Confidence!
They are made "On Purpose"!

BARECO OIL COMPANY

BOX 2009
TULSA, OKLAHOMA



WIDENER BLDG.
PHILADELPHIA 7, PA.

Samples of Be Square and Victory Waxes are available in a wide range of hardnesses, colors and melting points.



FOR SAFE,
UNOBSTRUCTED VISION
WITH
LIGHTWEIGHT
COMFORT

A-O Panoram *Plastic* SAFETY GOGGLES

The result of long research and experimentation, the new No. 600 A-O Panoram Plastic Safety Goggles provide safety, clear wide-angle vision, lightweight comfort and attractive appearance. They have *easily replaceable* plastic lenses; frames that conform closely to forehead and facial contours; eyecups that provide maximum protection, yet give sufficient ventilation to reduce fogging; bridge which fits any size nose comfortably—without pressure or facial resistance. Goggles may be worn directly over eyes or over personal glasses. Frames and lenses are available in either clear or green acetate. Especially recommended for jobs such as chipping, grinding, babbitting, riveting, hand tool and machine operations, rail and rivet cutting and spike driving.

Send to your nearest A-O Safety Representative for bulletin which describes the many unusual features of this new A-O development.


American  Optical
COMPANY
Safety Division

SOUTHBRIDGE, MASSACHUSETTS
BRANCHES IN PRINCIPAL CITIES

DURALOY

Queer Looking, Aren't They?

They're the left and right burners for an ingot treating furnace, each weighing about 600 pounds, alloyed with about 25% chromium and 12% nickel. The manifold openings were cast separately and then welded onto the centrifugally cast pipes.



These burners are typical of the countless different shapes and sizes of high alloy castings made for Duraloy and Duraspun customers. To every job we bring the experience that comes from working in this field continuously and exclusively since 1922. To every job we bring the facilities of one of the most modern high-alloy foundries in the country.

If you would like suggestions as to the proper alloying for your chrome-iron and chrome-nickel casting requirements, our metallurgists will be glad to help.

THE DURALOY COMPANY

Office and Plant: Scottsdale, Pa. • Eastern Office: 12 East 41st Street, New York 17, N. Y.
 Los Angeles & San Francisco • Chicago & Detroit
 KILSBY & HARMON • F. B. CORNELL & ASSOCIATES
 METAL GOODS CORP., St. Louis • Houston • Dallas • Tulsa • New Orleans • Kansas City

Bureau of Entomology and Plant Quarantine, E-702. Mimeographed.

Water Levels and Artesian Pressure in Observation Wells in the United States in 1943: Part I. Northeastern States. By E. O. Meinzer and others. Geological Survey Water-Supply Paper 986. Price 50 cents.

Nickel Investigations in Southeastern Alaska. By George C. Kennedy and Matt S. Walton, Jr. Geological Survey Bulletin 947-C. Price 15 cents.

Copper Deposits of the Nizina District, Alaska. By Don J. Miller. Geological Survey Bulletin 947-F. Price 15 cents.

The German Steel Castings Industry. By Charles W. Briggs and Maz T. Ganzauge. Bureau of Mines, Information Circular I. C. 7362. Mimeographed.

Perlite, Source of Synthetic Pumice. By Oliver C. Ralston. Bureau of Mines, Information Circular I. C. 7364. Mimeographed.

Safety Record of Mine No. 7, Island Creek Coal Co., Holden, Logan County, W. Va. By A. U. Miller and C. E. Linkous. Bureau of Mines, Information Circular I. C. 7365. Mimeographed.

Review of Fischer-Tropsch and Related Processes for Synthetic Liquid Fuel Production. By Norma R. Golumbic. Bureau of Mines, Information Circular I. C. 7366. Mimeographed.

Coal-Research Activities of the Bureau of Mines. By A. C. Fielder. Bureau of Mines, Information Circular I. C. 7367. Mimeographed.

Mica and Beryl Examination and Exploration in Cleburne, Randolph, Clay, Coosa, Chilton, Tallapoosa, and Lee Counties, Ala. Bureau of Mines, Report of Investigations R. I. 3905. Mimeographed.

Concentration of Bauxite for Milling in the 50-Ton Bureau of Mines Pilot Plant, Bauxite, Ark. By S. M. Runke and R. G. O'Meara. Bureau of Mines, Report of Investigation R. I. 3909. Mimeographed.

Exploration of the New Dale Rundell Zinc Mine, Mifflin District, Iowa County, Wis. By Francis C. Lincoln. Bureau of Mines, Report of Investigations R. I. 3912. Mimeographed.

Exploration of Spirit Mountain Nickel Prospect, Canyon Creek, Lower Copper River Region, Alaska. By Harold C. Pierce. Bureau of Mines, Report of Investigations R. I. 3913. Mimeographed.

Exploration of the Copper Butte Mine, Mineral Creek Mining District, Pinal County, Ariz. By Harlow D. Phelps. Bureau of Mines, Report of Investigations R. I. 3914. Mimeographed.

Storage of Subbituminous Slack Coal in Open Pits. By John B. Goodman, et al. Bureau of Mines, Report of Investigations R. I. 3915. Mimeographed.

Exploration of the Shanton Iron-Ore Property, Albany County, Wyo. By Eugene Frey. Bureau of Mines, Report of Investigations R. I. 3918. Mimeographed.

Magnetic Reconnaissance in North-Central Minnesota in 1945. By E. Y. Dougherty and F. F. Fitzhugh, Jr. Bureau of Mines, Report of Investigations R. I. 3919. Mimeographed.

Control of Gelation in Extraction of Alumina from Lime-Soda-Clay Sinters. By Guy Ervin, Jr., et al. Bureau of Mines, Report of Investigations R. I. 3923. Mimeographed.

Sponge-Iron Experiments at Longview, Tex. By Whitman E. Brown. Bureau of Mines, Report of Investigations R. I. 3925. Mimeographed.

Exploration of Glass Buttes Mercury Deposit, Lake County, Oregon. By Glenn C. Reed. Bureau of Mines, Report of Investigations R. I. 3926. Mimeographed.

Exploration of the Mount Hope Mine, Esmeralda County, Nevada. By E. J. Matson. Bureau of Mines, Report of Investigations R. I. 3928. Mimeographed.

Preliminary Exploration of Bi-Metallic Molybdenum Deposit, Okanogan County, Washington. By R. H. Storch. Bureau of Mines, Report of Investigations R. I. 3932. Mimeographed.

Clark Fork Lead-Zinc District, Bonanza County, Idaho. By S. H. Lorain. Bureau of Mines, Report of Investigations R. I. 3992. Mimeographed.

Remember
this trademark



when you have a

WATER CONDITIONING PROBLEM

it means...

Processes

FOR WATER CONDITIONING

Removal of

Hardness, Turbidity, Color,
Odor, Taste, Iron, Silica, Oil,
Total Dissolved Salts, Oxy-
gen, Other Gases

FOR OTHER LIQUIDS

Removal of

Undesired Impurities from
Syrups, Juices and Chemi-
cal Solutions

Recovery of

Valuable Substances from
Solution or Suspension

Products

Chemical Products and Me-
chanical Equipment for
Water Conditioning for
Household, Industrial and
Municipal Use; also for Con-
ditioning of Other Liquids:

Cation and Anion Exchangers

Zeolite Water Softeners

Ion Exchange Equipment

Demineralizing Equipment

Filtration Equipment

Diatomite Filters

Chemical Feeds

Sludge Blanket Units

Cold Lime-Soda Softeners

Hot Process Softeners

Continuous Blowoff Systems

Deaerating Heaters

Vacuum Deaerators

Authoritative Advice . . .

because offered by recognized lead-
ing water-conditioning experts and
pioneers, with more than a quarter
century of experience in this field.

Impartial Recommendations...

because LIQUON Processes and
Equipment are not limited in scope
. . . they include every process and
every type of apparatus for soften-
ing, demineralizing and clarifying
water and other liquids.

Complete Service . . .

because the LIQUON organization is
prepared to analyze your specific
problem and to furnish the ion-ex-

change materials, process and entire
treating system to meet your par-
ticular requirements.

Most Effective Results . . .

because LIQUON methods, mate-
rials, and apparatus are the most
modern in the art, and each installa-
tion carries an overall guarantee of
performance.


It will pay you well to consult the
LIQUID CONDITIONING engineers.
Your request for advice and recom-
mendations will not involve the
slightest obligation on your part and
may develop unexpected possibili-
ties for improvements and greater
economy in your water-conditioning
operations.

LC-101

LIQUID CONDITIONING CORPORATION

423 West 126th Street, New York 27, N. Y.

The Engelhard Flualizer



Complete Testing Unit


For checking CO₂ and flue gas temperature, the ENGELHARD FLUALIZER combines a thermocouple with a Wheatstone bridge, in a rugged, portable unit. Complete with aspirator bulb, a dryer, hose and all accessories. Weight only 8 lbs.

Write for descriptive
Bulletin 700

Charles Engelhard Inc.

233 N.J.R.R. Ave., Newark 5, N. J.

DRY FEEDING BY WEIGHT?



SYNTRON

"Weigh-Flow"

**WEIGHING
FEEDERS**

Provide a positive, accurate and automatic "Weigh-Flow" of material.

Eliminate all guess work—and feed exactly the right amount—by weight.

Write for catalog data.

SYNTRON CO.
610 Lexington Homer City, Pa.

MANUFACTURERS' LATEST PUBLICATIONS

Chemical Engineering's Readers' Service, in cooperation with manufacturers, makes it possible for you to secure catalogs, bulletins, and other publications herein listed without cost or obligation (unless a price is specifically mentioned). Please check the items you wish to receive and fill out the coupon. Please send requests to Readers' Service, Chemical Engineering 330 W. 42nd St., New York 18, N. Y.

1

Autoclaves. Autoclave Engineers, Inc., Chicago, Ill.—Bulletin No. 5. 8-page illustrated booklet describing high pressure stainless steel valves and fittings, autoclaves for visual observation, high pressure reactors, and other high pressure equipment.

2

Ball Mills. Abbe Engineering Co., New York, N. Y.—Catalog No. 63. 24-page booklet describing and illustrating jar mills and jar rolling machines for pulverizing, grinding, dispersing mixing, compounding, blending and extracting. The various types of equipment are illustrated and described. Sizes and capacities are given for each type of equipment. A list of products and materials that have been successfully ground or processed in the company's equipment is given. A section is devoted to the selection of grinding media.

3

Batch Cooking System. Selas Corp. of America, Philadelphia, Pa.—Bulletin No. 333-F. 12-page illustrated bulletin describing the Selas system for batch cooking. It includes sectional and schematic drawings, tables, operating principles, applications, characteristics and advantages of this company's developments in the field of batch cooking. Includes data and information on the various individual components.

4

Blowers. Roots Connersville Blower Corp., Connersville, Ind.—Bulletin 120-V-13 is an 8-page folder illustrating the centrifugal blowers and exhausters available for a wide range of applications.

5

Cable Clamps. National Production Co., Detroit, Mich.—Folder illustrating and describing space-line wire rope clamps.

6

Catalyst. American Cyanamid Co., New York, N. Y.—8-page booklet describing the new Microspheroidal synthetic fluid cracking catalyst made by this company. Includes information on chemical characteristics, particle size control, activity, and applications.

7

Catalytic Cracking. M. W. Kellogg Co., New

York, N. Y.—16-page illustrated brochure featuring the fluid catalytic cracking process. Contains a straightforward description of process operation illustrated by a multi-colored flow chart. Some design problems are discussed in detail. Several tables show a comparison of yield from various crudes.

8

Chemicals. Armour & Co., Chicago, Ill.—4-page booklet entitled "The Arneels as Plasticizers", discusses the use of aliphatic nitriles as plasticizers for certain synthetic rubbers, resins, etc. Contains a table of properties of the different types of Arneels.

9

Chemicals. Carbide & Carbon Chemical Corp., New York, N. Y.—A new edition of this company's book on emulsions contains 72 pages of complete information on chemical products in recently developed emulsion formulas. Contains over 113 suggested formulas and methods for emulsifying industrial oils, fats, waxes and greases.

10

Chemicals. Emery Industries, Inc., Cincinnati 2, Ohio—Section 2 of Emery Facts containing 7 pages which describe the chemistry and uses of fatty acids.

11

Chemicals. Mallinckrodt Chemical Works, St. Louis, Mo.—26-page booklet describing the metallic soap which gives the properties and uses of metallic stearate. Properties and industrial applications are discussed in some detail. Sections are devoted to gelling action, lubricating, waterproofing and water repelling, flattening action, covering powder and miscellaneous applications.

12

Chemicals. Philadelphia Quartz Co., Philadelphia, Pa.—4-page pocket size leaflet describes the use of potassium silicate as a paint vehicle, a binder in flux coating for welding rods, detergents and catalysts.

13

Chemical Stoneware. General Ceramics & Steatite Corp., Keasbey, N. J.—Bulletin CHE-R1 is a catalog of chemical stoneware equipment such as towers, pumps, agitators and kettles, storage vessels, pipes and fittings. Vari-

MAILING COUPON—GOOD UNTIL JAN. 31, 1947, ONLY

Readers' Service

Chemical Engineering

330 West 42nd Street, New York 18, N. Y.

Please have manufacturers send me, without obligation, literature checked below

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
17	18	19	20	21	22	23	24	25	26	26	28	29	30	31	32
33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
49	50	51	52	53	54	55	56	57	58	59	60	61			

Name

Title

Company

Street Address

City Zone State

Please fill out this coupon completely in order to avoid delay in handling
Coupon numbers correspond to descriptive paragraph numbers in the text.

N HIGH PRESSURE INSTALLATIONS

"Buffalo"

**CENTRIFUGAL
COMPRESSORS**

Can Save You Money!



Above.—Motor Drive side of Buffalo Type "CC" Centrifugal Compressor—built in a wide range of capacities for pressure up to 4 lbs.

Below.—Drive side of Buffalo Type "CC" Centrifugal Compressor for direct connection to motor. Carbon stuffing box provides air tight design. Used in aircraft industry for high altitude testing.



Whether you handle high air pressures for experimental work, for glass, steel and chemical processes, for oil or gas furnace firing, for scale and water blowoff . . . or any other use requiring *up to 4 pounds per square inch in a single stage* . . . "Buffalo" Heavy-Duty Pressure Blowers keep your operating costs down!

Their tough, all-welded housings give a smooth surface for air passage . . . and the sturdy, vibrationless narrow-blade rotors are a precision product of the Buffalo Vacuum Test Pit.

If you need high pressure air, it will pay you to investigate "Buffalo" Blowers. Send today for Bulletin 3553, which describes them completely.

BUFFALO FORGE COMPANY

501 BROADWAY

BUFFALO, NEW YORK

Canadian Blower & Forge Co., Ltd., Kitchener, Ont.

"Buffalo"

First For
Fans

**HEAVY-DUTY
PRESSURE BLOWERS**

Stokes MICROVAC PUMPS

"Higher" Vacuum is the new key to many processing operations formerly impossible.

Applications in the fields of chemistry, food processing, medicine, metallurgy, electronics, etc., call for the latest in high vacuum systems.

Stokes MICROVAC High Vacuum Pumps are the heart of such vacuum systems. A pioneer product in this field, Stokes Pumps maintain pressures in the low micron range. They combine high volumetric efficiency with low power requirements.

Rugged, compact, simple, these pumps are built for long life at minimum maintenance cost.

Available in five sizes — from 10 to 235 cu. ft. per minute. For additional features, write for catalog.



F. J. STOKES MACHINE CO., 5920 Tabor Road, Phila. 20, Pa.

Stokes High Vacuum
PUMPS • GAUGES • EQUIPMENT

ous types of equipment are illustrated and sizes and dimensions are given.

14

Color Conditioning. E. I. duPont de Nemours & Co., Finishing Division, Wilmington, Del.—32-page illustrated booklet featuring industry color conditioning. Illustrates and describes research and experiments with color to increase production, improve seeing conditions, and creating a better working environment. Safety color code for industry is outlined.

15

Combustion. The Bryant Heater Co., Cleveland, Ohio—First ten of a series of data sheets prepared for combustion and process engineers includes mathematical tables, properties of gases, metals and other materials, and gas orifice capacity tables. Available in notebook punched sheets.

16

Concentrator. The Humphreys Investment Co., Denver, Colo.—Bulletin 5, 8-page bulletin describes the Humphreys spiral concentrator used for concentration of minerals. Principles of operation are discussed and many details are included such as operating costs, pilot plant testing, closed circuit ore testing. Contains several photographs and sketches to illustrate industrial applications and operating principles.

17

Concrete Shrinkage. The Master Builders Company, Cleveland, Ohio—34 page booklet entitled "The Action of Embeco in Concrete and Mortar." This booklet explains the principle of specially prepared metallic aggregate in controlling shrinkage. Contains charts, graphs and useful technical data. Discusses the general theory of shrinkage, factors affecting shrinkage, flocculation or dispersion of the cement, and other similar information.

18

Corrosion Inhibitor. J. K. Harbinson & Co., Buffalo, N. Y.—6-page pocket-size leaflet describing Masters metallic compound for use as a lubricant, rust and corrosion inhibitor, and seal. It is used to prevent destructive bonding of pipe threads and to efficiently seal and lubricate flanges and threaded joints. A number of applications are listed for this compound which is claimed to provide a tight seal at all joints working under pressures up to 600 lb. per sq. in. and temperatures up to 625 deg. F.

19

Disolvers. The Cowles Co., Cayuga, N. Y.—4-page illustrated folder describing the disolver made by this company. Standard, stationary and portable types are available, each adjusted to the viscosity, gravity and special characteristics of the materials to be handled. Principle of operation is described and illustrated.

20

Dust Collectors. The Aerotec Co. and Thermix Engineering Co., Greenwich, Conn.—Bulletin 310 illustrates and describes the integral dust collector made by this company. Details of this collector are described and illustrated.

21

Electric Motors. The Louis Allis Co., Milwaukee, Wis.—Bulletin No. 720, 12-page booklet illustrating and describing the Type OG standard squirrel cage induction motor made by this company. Features of this motor are shown by cutaway views and photographs and are described in detail.

22

Electric Motors. Electric Machinery Mfg. Co., Minneapolis, Minn.—20-page booklet entitled "The ABC of Synchronous Motor Control." Contains a large number of diagrams and photographs to illustrate the various principles of operation.

23

Electric Equipment. Allis-Chalmers Mfg. Co., Milwaukee, Wis.—12-page engineering bulletin describing remote indicating and control systems. A number of applications in various process industries are discussed briefly.

24

Electric Equipment. Century Electric Co., St. Louis, Mo.—Form 646, 8-page booklet featuring alternating and direct current generators and motor generator sets, made by this company.

25


Equipment. Allis-Chalmers Mfg. Co., Milwaukee, Wis.—16 page booklet designed for student training entitled "The ABC of Turbo Blowers, Rotary Compressors and Vacuum Pumps." The booklet is well illustrated showing simple construction of the turbo blower. Various curves are included for depicting pressure volume, influence of water vapor on

WHITE LEAD PROPERLY, THOROUGHLY DRIED

AT RATE OF 1500 POUNDS PER HOUR IN

PROCTOR

CONTINUOUS CONVEYOR SYSTEM



Drying white lead to a uniform moisture content, on a large scale production basis, is made possible by the Proctor Continuous Conveyor System combined with a Fin Drum Feed. In the particular installation illustrated, the white lead is first mechanically dewatered by means of a continuous rotary filter, from which it is discharged into the hopper of the Proctor Fin Drum Feed. In this hopper the paste-like substance is pressed into the grooved surface of the internally-heated revolving fin drum, by pasting rolls. On this drum, the material is dried sufficiently to be discharged to the conveyor of the dryer, in the form of small sticks of uniform thickness. It is then possible to circulate heated air through the bed of material on the conveyor, thus promoting rapid, uniform drying. By forming the material into small, uniform shapes, more rapid diffusion is possible, which accounts for the rapid drying and uniformity. This particular application for one type of Proctor Pre-forming feed, combined with a continuous conveyor dryer, illustrates just one installation. These systems are literally tailor-made to meet individual plant or product requirements. If the drying of wet-solids is a part of your operation, it will pay you to have Proctor engineers consider your drying problem. Their recommendations will be made only on the basis of facts gathered in tests involving your product—and will assure you the right drying system. Write today.

1. White lead is delivered from continuous filter to hopper of fin drum feed of dryer with moisture content of approximately 69.3% (B.D.W.B.*).

2. Partially dried on fin drum, white lead is preformed into small sticks of uniform size and thickness and discharged to moving conveyor of the dryer.

3. Loaded on moving conveyor, the white lead is carried through the dryer. Temperatures are 250° F. at beginning of cycle and graded down to 190° F. at end of cycle.

4. White lead, uniformly dried, is discharged from dryer with moisture content of .075% (B.D.W.B.) at the rate of 1500 lbs. (C.D.W.†) per hour.

*Bone Dry Weight Basis.

†Commercial Dry Weight.

PROCTOR & SCHWARTZ INC. PHILADELPHIA 20, PA.

AIRVEYOR CONVEYS MANY MATERIALS IN MANY WAYS

Lower your production and handling costs by installing The Airveyor for unloading and conveying fine, crushed and granular materials.

Airveyor Systems are handling over 80 different materials in many different ways... unloading from box and hopper-bottom cars, barges and ships; conveying to storage and reclaiming from storage, for delivery to process throughout the plant. Many transfer units are in use—the Airveyor installed on an auto truck or trailer, with a tank body—employed by plants not located on a railroad, for unloading and delivering materials to the plant at some distant point.

The Airveyor can be operated by one man, greatly reducing labor and storage charges; also speeding up operation.



Fuller

FULLER COMPANY
CATASAUQUA, PENNSYLVANIA

Chicago 3 - 190 So. LaSalle St.
San Francisco 4 - 491 Chancery Bldg.
Washington 5, D. C. - 618 Colorado Bldg. A-68

volume and correction curves for volume to maintain constant air weight with changes in temperature and barometric pressure.

26

Equipment. Henry Vogt Machine Co., Louisville, Ky.—14-page booklet illustrating a number of applications of the Class VL bent tube boiler made by this company. Details of construction and installation are shown in diagrammatic sketches.

27

Expansion Joints. Cook Electric Co., Chicago, Ill.—12 page illustrated bulletin describing Magnilastic standard packless expansion joints, anchor joints and low pressure large diameter expansion joints. Lists complete engineering data, dimensional tables and specifications and contains information on offsets, turbo and jacket joints as well as high temperature exhaust bellows and other similar equipment.

28

Filter Aids. The Dicalite Co., Los Angeles, Calif.—Bulletin No. B-11. 16-page booklet describing industrial filtration with Dicalite filter aids. Principle of filtration using filter aids is discussed in detail. Photomicrographs illustrate the types of diatoms found in Dicalite filter aids. A typical filter system using this material is shown in schematic form. A number of applications are listed. Bulletin S-51 describes the use of filter aids in the manufacture of paper products.

29

Filters. Davis Filtration Equipment Co., Inc., New York, N. Y.—8-page booklet illustrating and describing the Clearflow "200" filters made by this company. Includes information on operation, construction features, capacities. Various applications are illustrated by schematic diagrams.

30

Fire Protection. American-LaFrance-Foamite Corp., Elmira, N. Y.—10-page booklet illustrating and describing the all-weather, water repellent, mildew resisting fire hose made by this company. The manufacture of this hose is illustrated and described.

31

Fire Protection. Cardox Corp., Chicago, Ill.—8-page booklet illustrating and describing the fire extinguishing systems and equipment available from this company.

32

Fire Protection. The Mearl Corp., New York, N. Y.—4-page leaflet describing Mearl-foam-5, how it performs, and its applications. This material is a liquid mechanical foam compound which when mixed with water and air in proper proportions produces fire extinguishing foam.

33

Fire Protection. Randolph Laboratories, Inc., Chicago, Ill.—20-page booklet entitled "How to Fight Fires and Protect Property" includes information on types of fire hazards and graphically explains the various techniques in fighting fires with carbon dioxide and other fire extinguishers. Includes information on the improved methods of operation for carbon dioxide, soda-acid, foam, pump tank and carbon tetrachloride extinguishers.

34

Furnaces. Eclipse Fuel Engineering Co., Rockford, Ill.—Bulletin D-9. 8-page booklet illustrating and describing the Eclipse Rotair airdraw furnace for use in heat treating at temperatures below 1250 deg. F. Operation details, construction details, and outstanding features of this equipment are described. Operating data is given in tabular form as well as sizes and specifications. A cutaway view illustrates the principles of operation.

35

Glass Apparatus. Scientific Glass Apparatus Co. Inc., Bloomfield, N. J.—8-page booklet illustrating and describing glass heating jackets constructed of fiberglass and fiberglass wool for use in laboratory work.

36

Glass Products. Oklahoma Planning & Resources Board, Oklahoma City, Okla.—26-page brochure outlining the advantages of locating glass manufacturing plants in the State of Oklahoma. Contains a graphic presentation which shows location of present glass plants, location of raw materials, fuel resources, power supply, transportation, population, labor, and markets.

37

Heat Exchangers. The Patterson-Kelley Co., Inc., East Stroudsburg, Pa.—12-page booklet illustrates and describes Freon water coolers for air conditioning and refrigeration equipment. Dry expansion water coolers using Freon are discussed and standard construction speci-

Philadelphia MOTOREDUCER



A "Self-contained" Drive FOR EVERY PURPOSE

The MotoReducer is truly an "exclusive" Phillie Gear product, and its design and construction is based upon nearly 55 years' gear making and speed reducer experience.

These Units are available in both Horizontal and Vertical Types, and form the "ideal combination" of a high-grade motor and a Planetary Speed Reducer—a balanced, neat-looking unit that operates with minimum vibration and requires little or no attention. Another feature is, that every part is easily accessible; i.e., either the motor or reduction gears may be removed without disturbing the others—and these units are easily bolted in place, even in the most out of the way places.


Send for our 52 page Catalog, using your business letterhead, please.



Philadelphia


GEAR WORKS INCORPORATED

ERIE AVE. AND G ST., PHILADELPHIA 34, PA.
NEW YORK • PITTSBURGH • CHICAGO • IN CANADA WILLIAM AND J. G. GREY LIMITED, TORONTO



Industrial Gears and Speed Reducers
Limitorque Valve Controls

The relative cost of this HEAT EXCHANGER



with tube sides of various alloys
is interesting

This exchanger is of FIXED TUBE SHEET design, 12 1/4" OD shell, 10' tube length, having 126 tubes 3/4" OD x 18 ga. x 10' long, rolled into the tube sheets, with shell expansion bellows. The shell side is carbon steel, but all parts in contact with

the tube side are of the alloy or tube side metal. The shell is baffled on 6" centers with steel segment cut baffles. This is a typical job in the chemical industry, suitable for use as an organic vapor or solvent condenser, heat exchanger, or cooler, etc.

The relative costs are all total cost for the exchanger, f.o.b. our shop compared to steel at 1.

TUBE SIDE METAL

RELATIVE COST (Steel = 1)

Steel	\$1.00
Aluminum 3-5	1.29
Copper	1.33
Silicon Bronzes (Copper tubes)	1.35
70-30 Cupro-Nickel	1.51
Stainless Steel 304	2.00
Monel	2.09
Stainless 347	2.17
Nickel	2.26
Stainless 316	2.34
Inconel	2.34

Relative costs of metals are based on Downingtown costs today and formulated on the cost of 12" vessels. In large exchangers the ratio of alloy cost to steel cost will probably be considerably more than the value shown for 12" exchangers in the table.

Downingtown specializes in the fabrication of alloy exchangers.



Send for this interesting catalog—it's "packed-full" of valuable information.



cations are given. Includes diagrammatic layouts and sketches of the piping and control arrangement of this cooler in various applications. Detailed instructions for selecting the right size of water cooler are given and a 2-page cooler selection data chart in color is shown. Pertinent engineering data is given in tabular form.

38

Heat Treating. The Drever Co., Philadelphia, Pa.—2-page leaflet illustrating and describing the heat treatment of electrical steels by use of special atmospheres. Contains illustrations of ammonia dissociators.

39

Heaters. D. J. Murray Mfg. Co., Wausau, Wis.—12-page illustrated booklet gives details and capacity tables on the different models of grid unit heaters with high test cast iron heating sections. Features of design and construction are described.

40

Hydraulic Cylinders. Miller Motor Co., Chicago, Ill.—Volume 1, No. 1, a new house organ entitled "Hyd-Air" has been issued by this company. Contains technical items of interest to the hydraulic and air engineer, designer, manufacturer, and user.

41

Instruments. W. C. Dillon & Co., Inc., Chicago, Ill.—Booklet entitled "The Dillon Dynamometer Manual" gives information on the traction type dynamometer used in the simplification of testing and weighing procedures in many industries.

42

Instruments. General Electric Co., Schenectady, N. Y.—Bulletin GEA-4572. 8-page bulletin describes and illustrates the Type CF-2 inkless temperature recorder. Various industrial applications for this new unit such as recording temperatures in generators, transformers, ovens, air ducts, etc., are listed, along with complete specifications. Accessories are illustrated and described.

43

Instruments. Gotham Instrument Co., Inc., New York, N. Y.—Catalog No. G12. 8-page illustrated catalog covering this company's line of pressure gages. Complete listing of illustrations of various types of indicating gages includes data on structural features, together with tables of dimensions. The first issue of a new house organ entitled "The Gotham Bulletin" has also been issued.

44

Instruments. Mason-Neilan Regulator Co., Boston, Mass.—Catalog No. 301. 44-page catalog describing the control valves made by this company. Sections cover valve flow characteristics, selection, types of control valves, construction, specifications. Mechanical designs, operation of these control valves, are described and illustrated. Dimensions, weights, materials of construction and other specifications are included.

45

Instruments. McAlear Mfg. Co., Chicago, Ill.—Bulletin No. 105 is a 28-page booklet featuring the various types of diaphragm motor valves manufactured by this company. Cutaway views are used to illustrate the various parts of the valve. Design features, construction, trim and other details are discussed. The various types of construction available are shown and a section is devoted to inner valve design and selection. Dimensional charts for the various types of valves are included. Prices are listed in a supplement section of the bulletin.

46

Instruments. Northern Equipment Co., Erie, Pa.—Bulletin 463. A 16-page booklet describing boiler feed control installations in various types of plants.

47

Instruments. Pittsburgh Equitable Meter Division, Rockwell Mfg. Co., Pittsburgh, Pa.—Bulletin 1136. 12-page booklet illustrating and describing gas appliance regulators with pressure cast aluminum alloy cases. Features of this regulator are illustrated schematically and some applications are described.

48

Instruments. Thwing-Albert Instrument Co., Philadelphia, Pa.—6-page booklet illustrating and describing the Currier size tester for use in evaluating the sizing in paper.

49

Instruments. Transcoil Corp., New York, N. Y.—2-page leaflet illustrating and describing the Transcoil 60 cycle, 2 phase, low inertia Servo-Motor for remote control applications.

50

Insulated Tile Conduit. Ric-Wil Co., Cleveland, Ohio



Clean Wax



AND NO CLOGGED LINES


WITH SARCO SCRAPER STRAINER

In many plants there is a flow of liquid—hot or cold—right in the production line. For years industry endured daily and hourly stoppages to clean out the lines—and rejects due to foreign materials were taken as a matter of course.

Now, with the Sarco Scraper Strainer, a few turns by hand—or motor—clear the strainer and the work goes on. In your plant, it may be syrup, varnish, fruit juices, oil or plain river water—the results are the same.

No messy basket to be lifted out and cleaned. No exposure of the liquid to airborne contamination and no lost time.

Sarco Scraper Strainers are available in sizes from $\frac{3}{4}$ to 8" and 200 lbs. Hand or motor operated. Also a complete line of standard strainers for steam and liquid lines. Ask for Catalogs Nos. 1200 and 1225.



SAVED A DAY EVERY DAY

This pair of Sarco 8" Scraper Strainers made unnecessary the all-day job of cleaning unit heaters and main lines.

135

SARCO

**SAVES
STEAM**

SARCO COMPANY, INC.

Represented in Principal Cities

475 FIFTH AVE., NEW YORK 17, N. Y.

SARCO CANADA, LTD., TORONTO 1, ONTARIO




For Commercial Purposes they are Identical in Purity

Here is a new process by Cochrane that is of vital importance to the manufacturer of pharmaceuticals, chemicals, beverages, food and other process-manufactured products. When the cost of pure water, commercially equivalent to distilled water, can be reduced to as low as one-twentieth of its present cost, the result is bound to show up favorably in terms of profits—and it is high time something should be done along these lines.

The process is the relatively new one of removing minerals or salts from water by ion exchange and acid adsorption. The water is first passed through a carbonaceous or resinous ion exchange (zeolite) which has the ability to exchange metallic ions for equivalent quantities of hydrogen. The effluent is then passed through a resinous material which adsorbs the mineral

acids. The carbonic acid which has been unchanged by the process, if objectionable, can be removed by passing through a Decarbonator.



The new self-contained Model CDM Unit

A new self-contained unit with reaction tanks, chemical tanks, special piping and all necessary fittings. Only ordinary piping and electrical connections needed to install. Write for a copy of Publication 4181 and details of the new Model CDM Unit.

COCHRANE CORPORATION

3113 N. 17th St.,
Phila. 32, Pa.



COCHRANE CORPORATION
3113 N. 17th St., Philadelphia 32, Pa.

Please send us a copy of your Publication No. 4181 on Demineralization.

Name _____ Title _____
Firm _____
Address _____
City _____ State _____

land, Ohio.—10-page pamphlet describing the installation of underground steam conduits used by municipal power systems to serve steam to industrial plants. It is well illustrated with photographs and blueprints and contains figures and other technical data.

51

Insulation. Industrial Mineral Wool Institute, New York, N. Y.—20-page booklet discussing the use of mineral wool for various insulation applications. Contains information on selection of insulating materials for high temperatures, and illustrates the various forms in which mineral wool can be used. Contains several typical case histories illustrating how mineral wool insulation is used in various industrial applications. Actual savings of money resulting from this insulation installation are shown.

52

Materials Handling. Lisbon Hoist & Crane Co., Lisbon, Ohio.—8-page folder illustrating and describing this company's line of electric cable hoists. Outstanding features are given and cutaway views show the various parts.

53

Materials Handling. Automatic Transportation Co., Chicago, Ill.—8-page folder featuring the Transtacker. Explains and illustrates this high lift tiering unit. Sketches and photographs show the operation and construction of the various models. Contains dimensional specifications, weights and load capacities.

54

Pumps. Chicago Pump Co., Chicago, Ill.—Bulletin 190B. A 20-page catalog illustrating the Scraper-Peller sludge pumps made by this company. The various types are illustrated by photographs. The principle of operation is described and specification data given. A number of applications are illustrated with diagrammatic sketches and performance curves shown. Also a 4-page folder illustrating and describing the company's gas mixing system for use in the chemical process industries.

55

Pumps. Economy Pumps, Inc., Hamilton, Ohio.—Catalog No. C746 contains 8 pages illustrating and describing the Type DMD, two stage pump made by this company. Details of construction are given, selection tables are shown, and cutaway views and photographs show some of the parts in detail.

56

Pumps. Peerless Pump Division, Food Machinery Corp., Los Angeles, Calif.—6-page leaflet describes the design, construction and application of three types of Peerless vertical centrifugal pumps for general purpose pumping in a variety of industrial services such as sump and drainage pumping, general water supply, mine station service, cooling tower service, etc. Sectional drawings show the various parts.

57

Pumps. Portable Pump Co., St. Louis, Mo.—Data sheets illustrating and describing the small capacity, self priming, centrifugal portable pump made by this company. It is used in such service as unloading carboys, unloading drums, underground storage tanks, and in various continuous processes. A list of corrosive solutions which may be handled by this stainless steel pump is given. Details of the pump are given in a dimensional sketch.

58

Pumps. Warren Steam Pump Co., Warren, Mass.—Bulletin 241. 6-page booklet illustrating and describing the 4- and 6-stage Type TM. pump made by this company. Details of construction are shown in cutaway views, and the metal specifications for the various parts are tabulated. It is designed for boiler feed and other high-pressure services.

59

Process Equipment. Industrial Process Engineers, West New York, N. J.—8-page booklet describing the services available from this company as well as processing equipment manufactured. Kettles, stills, autoclaves, mixers and auxiliary equipment are illustrated.

60

Proportioning Equipment. Proportioners, Inc., Providence, R. I.—Bulletin 1,200. 28-page booklet illustrates and describes the automatic proportioning equipment for continuous treating, sampling, blending, and diluting in process operations. Diagrammatic sketches are used to illustrate these applications. Selection tables are given for the various equipments and specifications are included.

61

Recovery System. The Babcock & Wilcox Co., New York, N. Y.—16-page booklet entitled "Recovery of Chemicals and Heat in the Alkaline Pulp Industry" describes and illustrates the B&W Tomlinson recovery unit.

CHEMICAL ECONOMICS

H. M. BATTERS, Market Editor

PRODUCTION AND CONSUMPTION OF CHEMICALS PROMISE TO MAKE GOOD SHOWING IN FINAL QUARTER

WHILE SHORTAGES of materials and problems in transportation remain as unfavorable factors, preliminary figures for industrial production so far this quarter, point to a heavy tonnage movement of chemicals. Steel mills made their best showing of the year in October and fertilizer mixers have been operating at a very high rate. Deliveries of explosives have been rising in volume and the increase in flat glass output is moving the industry totals to new highs. Production of chemicals has been affected appreciably by the transfer of government ammonia plants to the control of private companies. The shortage of raw materials is stressed in many industries yet at their convention held this month, the president of the National Paint, Varnish and Lacquer Association told the members that despite shortages of raw materials, paint production is higher than ever before. Plastics manufacturers complain about shortages yet figures show that plastics production is increasing steadily. Hence shortages exist because consuming demand has risen faster than the facilities to meet the demand. On the other hand shortages have resulted in some curtailment of outputs as lack of hides brought the closing of some tanneries in October. Production of soap in the third quarter dropped very sharply with sales of 494 million pounds the lowest since 1937 and nearly 25 percent below those for the corresponding 1945 quarter.

The preliminary index of Chemical Engineering places industrial consumption of chemicals in September at 205.58 compared with a revised figure of 212.54 in August. While the September figure shows a decline it resulted more from a drop in the number of working days than from any change in daily operating rates. The index numbers for August and September last year were 187.07 and 184.00 respectively.

Federal Reserve Board index for production of industrial chemicals in August has been revised to 398—the preliminary figure was 390—and September is placed at 403. Detailed production data for September show higher outputs for such basic chemicals as ammonia, calcium carbide, chlorine, electrolytic caustic soda, and sulphuric acid but a falling off commensurate with the reduced number of working days was noticed in the case of the majority of the other chemicals. The Board also reported a rise in all production with the September index as 182 and the revised August figure 179. In each case these numbers are the highest for the year to date.


Operations at vegetable oil crushing plants moved up in September with a consumption of 637,234 tons of oil-bearing

materials compared with 585,035 tons for the preceding month. The rise was due largely to greater activities at cottonseed oil crushing establishments as new crop seed became available in larger volume. A material drop was reported in production of soybean oil. Refining plants operated pretty much in harmony with the crude oil pattern but more coconut oil was refined than in August even though crude production was lower. Trading in vegetable oils has been more active in recent weeks because price decontrols brought out larger offerings and the rising price trend failed to check buying interest.

The international food control body which recommends allocations of oils and fats that move in import and export trade emphasizes that supplies are short with requirements in excess of 4,600,000 long tons and available supplies less than 2,500,000 long tons. Final recommended allocation for the United States is 354,000 long tons, this including oils, fats and the oil equivalent of oil-bearing materials.

Chemical Engineering Index Industrial Consumption of Chemicals

	1935 = 100	
	Aug. Revised	Sept.
Fertilizers	44.94	46.30
Pulp and paper	22.80	20.65
Petroleum refining	19.71	18.98
Glass	23.95	22.70
Paint and varnish	22.27	20.46
Iron and steel	12.77	12.20
Rayon	20.10	18.93
Textiles	11.48	11.00
Coal products	9.73	9.35
Leather	4.70	4.30
Explosives	6.92	7.86
Rubber	6.90	6.65
Plastics	6.77	6.50
	212.54	205.58



Hope for improvement in the supply position of soda ash rests entirely on the installation of new productive capacity together with the renovation of some equipment now in use. Production of ash this year has been slowed because of strikes at producing plants aided by shortages of coal and difficulties in transporting raw materials. The average monthly output—ammonia-soda and natural—for January-August this year was 366,155 tons. This was considerably above the monthly average for any prewar year but was nearly 7 percent below the peak monthly average of 393,203 tons reached in 1944. In the present year production of natural ash has been the highest on record so the falling off has been in the ammonia-soda product.

The highest monthly output of ammonia-soda ash was 399,758 tons in March 1944. This may be taken as an indication of the capacity at that time as operations were reported to be at full capacity rates. In the latter half of 1944 production was on a downward trend but in January 1946 full scale operation was again reported with an output of 387,012 tons which may indicate that plant efficiency fell off more than 12,000 tons a month from the 1944 peak. Again in August, full operation was reported with an output of 364,178 tons which may register a further drop in plant efficiency since the preceding January. While the fall in efficiency may result from the use of over-worked equipment, other factors, such as a higher percentage of unskilled labor, also may contribute.

It has been estimated that the current rate of production falls short by 15 percent of filling essential requirements. This gives proof that present demands for ash are the highest in the history of the industry and that full requirements can not be met without the installation of new capacity. As a first step in that direction, CPA

Trentweld STAINLESS STEEL TUBING

Made to
Your Need
for application when
you are considering



corrosion

high pressure

high temperature


THE physical characteristics of Trentweld tubes—made in sizes from $\frac{1}{8}$ " to 24" diameters—are such that it has specific application in a wide range of processing industries. This thin-walled tube or thick-walled tube, made by a singular automatic method of rolling and welding, is very uniform in composition and structure. It is further conditioned for chemical use by precisely controlled annealing and pickling operations. The result is an austenitic stainless steel tube that offers much more than ordinary capacity for service. The carbon content can be as low as 0.02 — 0.03%.

Trent engineers are glad to co-operate with you in determining the best alloy among stainless steels or Inconel to fit your specific need. Without obligation, address Department 10 on applications you have in mind, or write for the Trentweld Data Bulletin.

Sales Office: 664 N. Michigan Ave.
Chicago 11, Ill.

TRENT TUBE MFG. CO.

Mill at
East Troy, Wisconsin



has approved construction of a new unit at Detroit by Solvay Process Co. at a cost of \$460,000 and a similar expenditure by Wyandotte Chemical Corp. for a new unit at Wyandotte, Mich. In the meantime the industry has restored the voluntary distribution plan used during the war. It also has been agreed that the 110,000 tons per year allotted for aluminum will be raised by 45,000 tons. Control over exports likewise has been established.

Average Monthly Production Of Soda Ash

	Total Tons	Ammonia- Soda Tons	Natural Tons
1946 (8 mo.)....	366,155	348,738	17,417
1945.....	379,757	364,585	15,172
1944.....	393,203	378,208	14,995
1943.....	380,929	367,302	13,627
1942.....	327,063	315,715	11,348
1941.....	308,964	300,669	8,595
1940.....	263,083	251,250	11,833
1939.....	246,727	235,652	11,075
1937.....	253,118	243,222	9,896
1935.....	209,071	201,141	7,930

The most important change which the war has brought in productive capacity for chemicals is found in the expansion of synthetic nitrogen facilities. Of the 9 government-owned synthetic ammonia plants built during the war, five have been sold or leased to private companies and the additions have more than doubled the synthetic nitrogen capacity of the country.

Private Synthetic Nitrogen Rated Capacity

Owner or Operator	1,000 tons	Nov. 1945*	Sept. 1946
Allied Chemical & Dye Corp.....	200.0	208.0	308.0
E. I. du Pont de Nemours & Co.....	138.7	168.8	168.8
Shell Union Oil Co.....	24.3	24.0	24.0
Hercules Powder Co.....	10.0	10.0	10.0
Dow Chemical Co.....	8.4	11.3	11.3
Mathieson Alkali Works.....	4.9	4.0	48.0
Pennsylvania Salt Mfg. Co.....	4.0	5.0	5.0
Spencer Chemical Co.....			89.0
Lion Oil Co.....			89.0
Commercial Solvents Corp.....			44.0
Totals.....	390.3	431.1	797.1

* Source: U. S. Department of Agriculture.

It's the ***SIDE***
OF A V-BELT
that DOES the **WORK!**
and GETS the **WEAR!**

That's Why the
CONCAVE SIDE
is **IMPORTANT!**
(A GATES PATENT)

V-Belt In Sheave

Clearly, it's the sides of a V-Belt that do all the gripping on the pulley and get all the wear against the sheave-groove wall. That's why longer life for the sides means longer life for the belt!



Look at any V-Belt in its sheave groove and you see at once that the sidewall is the part that gets the wear!

The *sidewall* is what grips the pulley. The sidewall picks up the power from the driver pulley, transmits that power to the tension member, then grips the driven pulley and transmits the power to it!

That explains why you have always noticed that the sidewall of the *ordinary* V-Belt is the part that wears out first. Clearly, anything that lengthens the life of the sidewall will lengthen the life of the belt.

The simple diagrams on the right show exactly why the ordinary, *straight-sided* V-Belt gets excessive wear along the *middle of the sides*. They show also why the Patented Concave Side *greatly reduces* sidewall wear in Gates Vulco Ropes. That is the simple reason why your Gates Vulco Ropes are giving you so much longer service than any straight-sided V-Belts can possibly give.

*** MORE Important NOW
Than Ever Before!**

Now that Gates Specialized Research has resulted in V-Belts having much stronger tension members—tension members of Rayon Cords and Flexible Steel Cables, among others—the sidewall of the belt is often called upon to transmit to the pulley much heavier loads. Naturally, with heavier loading on the sidewall the life-prolonging Concave Side is more important today than ever before!

THE GATES RUBBER CO., Denver, U. S. A.
World's Largest Makers of V-Belts

GATES VULCO ROPE DRIVES

Engineering Offices
and Jobber Stocks

IN ALL INDUSTRIAL CENTERS of the U. S. and
71 Foreign Countries

CHEMICAL ENGINEERING • NOVEMBER 1946 •

Straight Sided
V-Belt

FIG. 1

How Straight Sided
V-Belt Bulges
When Bending Around
Its Pulley



You can actually feel the bulging of a straight-sided V-Belt by holding the sides between your finger and thumb and then bending the belt. Naturally, this bulging produces excessive wear along the middle of the sidewall as indicated by arrows.

Gates V-Belt with
Patented Concave
Sidewall

FIG. 2

Showing How Concave
Side of Gates V-Belt
Straightens to Make Perfect
Fit in Sheave Groove
When Belt Is Bending
Over Pulley




No Bulging against the sides of the sheave groove means that sidewall wear is evenly distributed over the full width of the sidewall—and that means much longer life for the belt!



THE MARK OF SPECIALIZED RESEARCH

4611

PRODUCTION AND CONSUMPTION TRENDS



DECONTROL of prices currently is one of the most important factors affecting both values and production trends of chemical products. The effect on production results from an increase in available stocks of scarce materials because of the higher prices they command. Among the materials from which price controls have been removed recently are vegetable tanning materials, vegetable oils and fats, barium chemicals, calcium chloride, furnace carbon blacks, and a long list of petroleum chemicals. The petroleum chemicals thus affected are interpreted to be those of which more than 50 percent of total production is by petroleum refiners, compounders, and blenders. They include synthetic ethyl alcohol, isopropyl alcohol, cresylic acid, phthalic anhydride from xylene, toluol, secondary butyl alcohol, methyl ethyl ketone and several others.


The removal of controls on oils and fats was immediately followed by a sharp rise in prices for most of the products of that industry but the decontrol of chemicals found no general upsurge in sales schedules and where price adjustments were made they were of moderate proportions.

The outlook for larger supplies of pulpwood from Canada has been improved by the removal of price ceilings effective October 31. Paper mills have operated at a very high rate for several months but there always was the possibility that pulpwood supplies would not hold up. In anticipation of this decontrol, sales have been made for some time on an adjustable basis but the situation has been greatly clarified by the OPA action.


The fertilizer industry continues to exert a more than normal influence on the chemical industry in general. Fertilizer tag sales for September were 49 percent above those for September 1945 and the 9-month sales for the 16 reporting states amounted to 7,234,000 tons or 14 percent over the corresponding 1945 period. Demand for fertilizer chemicals not only has influenced the reopening of ammonia plants but has expanded requirements for potash, phosphorus and nitrogen. Production of superphosphates in September was 721,475 tons which is the second highest monthly output on record with the same holding true for consumption of phosphate rock and sulphuric acid. In addition to home requirements, large amounts of fertilizer materials, notably ammonium nitrate and sulphate of ammonia, are exported.

Controls over distribution of certain chemicals still are in effect and are regarded with disfavor because they entail longer freight hauls and greater transportation costs. Recently the industry advisory committee discussed this question with government agencies with particular reference to caustic soda. Producers still make allotments to wartime buyers even though the delivery point is far from the point of production and these customers might be better served by a more favorably situated producer. This condition, however, probably will not change until caustic supplies are brought up to full requirements.

Westco
Turbine Pumps



Fairbanks-Morse
Centrifugal
Pumps



How much does it cost to make a Pump?

It costs a lot of money to make any pump—especially if you want to be a leader, not a follower, and to build a pump so efficient, so dependable that it will be second to none.



You pay the expense of maintaining well-staffed laboratories for product investigation and research—for continuous search for high efficiencies, better applications—and for the thorough testing of your finished product.



You pay the expense of providing production facilities and techniques; you pay for new materials, new methods which, with the cost-reducing benefits of mass production, assure your customers of greatest satisfaction.



Finally, you've the problem of making it easy for your customers to reach you for sales, service and consultation; you must network the country with distribution centers manned by experts.

Yes, all this costs a lot of money. No wonder, then, that there are so few pump manufacturers with this valued background. Among them, Fairbanks-Morse is an unquestioned leader in all phases of liquid-moving service . . . For all pumping problems, first see your Fairbanks-Morse dealer or call at the nearest Fairbanks-Morse branch office.

Fairbanks-Morse
Propeller Pumps



Fairbanks-Morse and
Fomosa Deepwell
Turbine Pumps

FAIRBANKS-MORSE



A name worth remembering

BRINE CONDENSERS • DRILL PUMPS • HAMMERS • HORIZONTAL • MOTORS • PUMPS
SEALS • SINKERS • STEAMER MOTOR CARS AND EQUIPMENT • TANK EQUIPMENT

4360

"IN STOCK"

ITEMS

of

EVERLASTING FASTENINGS

... non-rusting bolts, nuts, screws, washers, rivets, nails made of brass, bronze, copper, Monel or stainless steel. Write for circular.

THE H. M. HARPER COMPANY, 2633 Fletcher Street, Chicago 18, Ill.

Branch offices or representatives in principal cities.

HARPER

Chicago



FILTER CLOTH

FILTER PRESS SACKS

all kinds

Woven Glass and "Duraklad"

(ACID RESISTANT)

Filter Fabrics

Made into all sizes and constructions for filter cloths, tubes, discs, gravity bags, centrifuge liners, rotary filters, flotation blankets, etc.

Glass Cloth for High Temperatures

Is acid and alkali resistant, has a smooth, hard surface, free from lint, made into a wide variety of weaves and widths. Can be fabricated to meet your requirements.

VACUUM BAGS & DUST ARRESTING TUBES

for all purposes

Send Sketch or Specifications of Material Required

WM. W. STANLEY CO., Inc.

401 Broadway, New York 13, N. Y.

United States Production of Certain Chemicals					
August 1946, August 1945 and Eight-Month Totals for 1946 and 1945					
Chemical and Basis	Units	August 1946	August 1945	Total, 8 Months 1946	1945
Ammonia, synthetic, anhydrous ¹	Tons	75,794	46,787	404,713	376,923
Ammonium nitrate (100% NH_4NO_3)	Tons	77,638	400,116
Ammonium sulphate, synthetic, technical	M lb.	10,683	129,949
Calcium arsenate (100% $\text{Ca}_3(\text{AsO}_4)_2$)	M lb.	8,081	28,649
Calcium carbide, commercial	Tons	53,399	55,090	351,982	491,360
Calcium phosphate:					
Monobasic (100% $\text{CaH}_2(\text{PO}_4)_2$)	M lb.	6,738	4,525	46,992	40,016
Dibasic (100% $\text{CaH}_2(\text{PO}_4)_2$)	M lb.	4,432	5,110	50,103	29,610
Carbon dioxide:					
Liquid and gas	M lb.	24,279	19,704	146,942	144,905
Solid (dry ice)	M lb.	72,292	68,858	442,405	468,414
Chlorine	Tons	102,505	97,095	753,138	826,842
Chrome green (C.P.)	M lb.	1,436	500	12,947	3,805
Chrome yellow and orange (C.P.)	M lb.	3,410	3,275	38,810	26,323
Hydrochloric acid (100% HCl)	Tons	29,519	33,839	218,579	288,292
Hydrogen	M cu. ft.	1,676,000	1,914,000	11,418,000
Lead arsenate, acid and basic	M lb.	253	4,723	46,193	56,043
Molybdate chrome orange (C.P.)	M lb.	443	146	3,439	987
Nitric acid (100% HNO_3)	Tons	59,144	37,088	332,258	316,410
Oxygen	M cu. ft.	1,008,061	977,548	14,875,015	10,341,158
Phosphoric acid (50% H_3PO_4)	Tons	74,260	57,952	550,900	453,778
Soda ash (commercial sodium carbonate):					
Ammonia soda process					
(98-100% Na_2CO_3)					
Total wet and dry ²	Tons	364,178	363,802	2,780,906	2,925,271
Finished light ³	Tons	167,983	188,086	1,400,445	1,562,506
Finished dense	Tons	139,678	120,680	996,353	933,799
Natural ⁴	Tons	19,250	15,865	139,339	122,882
Sodium bicarbonate, refined	Tons	17,054	14,593	134,566	111,415
Sodium bichromate and chromate	Tons	7,254	6,537	57,982	52,996
Sodium hydroxide (100% NaOH):					
Electrolytic process:					
Liquid ⁵	Tons	99,807	92,057	729,610	783,729
Solid	Tons	18,145	17,786	127,907	149,977
Lime soda process:					
Liquid ⁶	Tons	63,745	60,261	491,234	492,644
Solid	Tons	20,504	19,947	155,439	161,812
Sodium phosphate:					
Monobasic (100% NaH_2PO_4)	Tons	1,218	1,336	7,740	9,957
Dibasic (100% Na_2HPO_4)	Tons	5,103	5,574	38,162	39,775
Tribasic (100% Na_3PO_4)	Tons	7,958	7,637	64,266	55,748
Meta (100% NaPO_3)	Tons	2,373	2,227	18,333	17,694
Tetra (100% $\text{Na}_4\text{P}_2\text{O}_7$)	Tons	4,778	3,905	49,045	26,401
Sodium silicate, anhydrous	Tons	36,915	34,806	269,301	300,427
Sodium sulphate:					
Anhydrous, refined	Tons	10,285	5,717	135,448	51,894
Glauber's salt	Tons	13,209	12,490	118,245	139,064
Salt cake, crude	Tons	43,779	48,974	295,865
Sulphuric acid (100% H_2SO_4): ⁷					
Contact process, net ⁸	Tons	467,750	469,483	3,591,050	3,870,904
Chamber process	Tons	244,874	280,756	1,990,447	2,145,695
Zinc yellow	Tons	2,216	1,159	12,251

Data for this tabulation have been taken from "Facts for Industry" series issued by Bureau of the Census and WPB Chemical Bureau. Production figures represent primary production and do not include purchased or transferred materials. Quantities produced by government-owned arsenals, ordnance works, and certain plants operated for the government by private industry are not included. Chemicals manufactured by TVA, however, are included. All tons are 2,000 lb. Where no figures are given, data are either confidential or not yet available. ¹Includes a small amount of aqua ammonia. ²Total wet and dry production, including quantities diverted for manufacture of caustic soda and sodium bicarbonate, and quantities processed to finished light and finished dense. ³Not including quantities converted to finished dense. ⁴Data collected in cooperation with the Bureau of Mines. ⁵Figures represent total production of liquid material, including quantities evaporated to solid caustic and reported as such. ⁶Includes oleum grades, excludes spent acid. ⁷Data for sulphuric acid manufactured as a byproduct of smelting operations are included.

United States Production of Certain Synthetic Organic Chemicals				
July 1946, July 1945 and Seven-Month Totals for 1946 and 1945				
Chemicals	July 1946	July 1945	Total, 7 Months 1946	1945
Acetic acid:				
Synthetic ¹	23,907,485	20,459,033	157,243,691	162,345,956
Recovered ^{2,3}	99,522,121	671,431,383
Natural	2,423,405	2,806,968	15,226,625	20,825,769
Acetic anhydride ⁴	44,520,734	43,866,916	300,703,919	316,667,234
Acetone	24,666,012	185,447,727

(Continued on page 548)

MATERIALS of CONSTRUCTION

for Chemical Engineering Equipment

★ Reprints of *Chemical Engineering's* Twelfth Report on Materials of Construction will be available soon. This 92-page booklet gives data on 58 materials used in the process industries. It also includes an article on corrosion problems of the Oak Ridge atomic plant and 8 pages of data and information on gaskets and packings


\$1

Editorial Department

CHEMICAL ENGINEERING • 330 West 42nd St., New York 18, N. Y.



Make This **PUMPING CHECK**



SEE HOW *"Buffalo"* PUMPS CAN SAVE YOU MONEY!

Whether your pumps handle clear water up to 600 degrees or ordinary general service water—it's a **PAYING PROPOSITION** to check them up regularly against your pumping budget! For example—

✓ **HOW ARE THEY DELIVERING?** Are they still pumping every gpm stated in their rated capacity? Properly designed "Buffalo" pumps retain their original efficiency.

✓ **HOW DO THEY STAND UP?** Do breakdowns occur too frequently? In "Buffalo" Pumps you'll find all oversize parts . . . extra deep stuffing boxes . . . alloy bearings and impellers . . . the sturdy construction that keeps them on the job longer!

✓ **HOW LONG ARE YOUR MAINTENANCE TIME-OUTS?**

✓ Do they cause shutdowns that cost too much? "Buffalo" pumps are designed with **ACCESSIBILITY** in mind . . . parts quickly reached and replaced with minimum time out.

✓ **POWER COSTS?** If a pump lacks efficiency, it's using too much power! A "Buffalo" pump, on its rated job, gives you peak delivery which means real power economy year after year!

✓ **WRITE FOR YOUR FACTS!** Bulletin 980-A has all data on construction, ratings and performance of "Buffalo" RR Multistage Pumps . . . yours to examine in view of cutting pumping costs!

BUFFALO PUMPS INC.

501 BROADWAY

Canada Pumps Ltd., Kitchener, Ont.

BUFFALO, N. Y.

"Buffalo"

CLASS RR PUMPS

The
best protection is
PERFECTION



GOTHAM

Manufacturers of
INDUSTRIAL INDICATING,
REMOTE READING
and RECORDING
THERMOMETERS

•
CONTROLLERS
for Time, Pressure
and Temperature

•
PRESSURE GAUGES
and RECORDERS

Illustrated catalog CM
on request

GOTHAM
INSTRUMENT CO., Inc.
NEW YORK • CHICAGO • SAN FRANCISCO
Representatives
in all Principal Cities

U. S. Production of Synthetic Organic Chemicals (Cont. from page 340)

Chemicals	July 1946	July 1945	Total, 7 Months 1946	1945
Acetylsalicylic acid.....	572,337	813,540	6,133,980	6,196,165
Aniline.....	8,213,302		49,630,831	
Barbituric acid derivatives: ¹ 5-Ethyl-5-Phenylbarbituric acid and salts (Phenobarbital).....	38,331	24,442	233,715	170,027
Benzene:				
Motor grade:				
Tar distillers ⁴	502,580		5,878,385	
Coke-oven operators ⁴	3,134,602		16,915,257	
All other grades:				
Tar distillers ⁴	1,381,563		13,485,968	
Coke-oven operators ⁴	9,660,166		143,099,456	
Butyl alcohol, primary, normal.....	8,303,378		137,321,771	
Carbon bisulphide.....	23,360,877		169,962,214	
Carbon tetrachloride.....	10,674,553		79,184,839	
Chlorobenzene, mono.....	20,887,731		154,786,586	
Creosote oil:				
Tar distillers.....	8,623,813	9,840,860	63,410,035	77,196,867
Coke-oven operators.....	2,616,423	3,051,086	13,330,262	21,768,001
Creosole ⁵ :				
Meta-para.....	536,301	544,690	2,602,862	4,506,548
Ortho-meta-para.....	1,063,308	813,723		
Creosylic acid, refined ⁷	2,190,642	2,375,299	12,470,554	17,440,024
Dibutyl phthalate.....	1,118,944			
Dichlorodiphenyltrichloroethane (DDT).....	3,573,122		25,426,428	
Ethyl acetate (85 percent by wt.).....	9,577,090	9,455,760	51,792,265	64,497,550
Ethyl ether, technical ¹ and U.S.P. ⁸	3,448,050	7,223,495	20,704,437	54,992,768
Formaldehyde (37 percent by wt.).....	38,094,994		162,404,221	
Methanol:				
Natural.....	1,326,054	* 1,537,800	9,193,597	* 11,407,406
Synthetic.....	44,841,123	41,951,520	271,267,700	295,453,440
Naphthalene:				
Tar distillers (Less than 79° C.) ⁴	17,505,571	17,014,259	102,709,008	117,603,097
Tar distillers (79° C. and over) ⁴	7,372,432	6,685,383	55,726,247	41,517,645
Coke-oven operators (Less than 79° C.) ⁴	7,316,084	7,715,663	33,518,022	53,034,961
Penicillin ⁹	2,292,287		14,783,755	
Phenol, synthetic and natural.....	13,492,879		114,317,441	
Phthalic anhydride.....	8,921,278	10,934,029	60,037,291	77,989,479
Styrene (Government owned plants only).....	32,835,374		216,803,308	
Toluene:				
Coke-oven operators ⁴	1,397,822		9,249,671	
All other ^{4,10}	1,050,287		7,625,111	


All data in pounds except benzene (gal.), creosote oil (gal.), toluene (gal.), and penicillin (million Oxford units). Statistics collected and compiled by U. S. Tariff Commission except where noted. ¹ Absence of data on production indicates either that returns were unavailable or confidential. ² Excludes the statistics on recovered acid. ³ Acid produced by direct process from wood and from calcium acetate. ⁴ All acetic anhydride including that from acetate acid by vapor-phase process. ⁵ Product of distillers who use purchased coal tar only. ⁶ Statistics are given in terms of bulk chemicals only. ⁷ Statistics collected by Bureau of Mines. ⁸ Total production including data reported both by coke-oven operators and by distillers of purchased coal tar. ⁹ Reported to U. S. Bureau of the Census. ¹⁰ Reported in gal. by Bureau of the Census but converted to lb. for comparison with the production of synthetic methanol. ¹¹ Includes toluene produced from petroleum by any process.

HETHERINGTON & BERNER

JACKETED PIPE and FITTINGS



Typical arrangement of jumper connections, using standard pipe and fittings.



Cutaway section of jacketed pipe, showing the packing gland construction.

FOR MAINTAINING UNIFORM TEMPERATURES (Hot or Cold)

Wherever the maintenance of a uniform temperature in the process pipes is required, Hetherington & Berner Jacketed Pipe and Fittings make for efficient processing. This is equally true whether the processing requires a hot or cold temperature, and whether the heating medium is hot water, steam, or hot oil. Materials which at atmospheric temperature are in a solid or semi-solid state can also be efficiently handled with a H & B jacketed pipe system.

Write for Bulletin S-44
which gives complete information.

HETHERINGTON & BERNER INC.

705 Kentucky Avenue

Indianapolis 7, Indiana






**What
jobs have
you for**

CARMET

to do?

In addition to a most complete line of Carmet cutting tools and blanks, we are equipped to make pre-formed parts of sintered carbides to practically *any* specification for type, size, shape or tolerance—furnished plain or finish-ground. • Solve that "problem-part" of yours—call for an Allegheny Ludlum Tool Engineer.

Address Dept. CM-47



**Here's an Example!
Plunger, Bearing and
Cutting Die, made of
CARMET Carbide**





Allegheny Ludlum Steel Corporation

CARBIDE ALLOYS DIVISION, Ferndale (Detroit) Michigan

3 good packings to know

Here are 3 Johns-Manville Packings that have earned a big reputation in the process industries —for their long-wearing, money-saving qualities:


J-M Service Sheet has long been the first choice sheet packing among engineers in the process industries. They know it for its ability to deliver dependable long-term performance under a wide range of service conditions...to pack successfully against many different types of corrosive chemicals, as well as against superheated steam, air, gas, water and oil.



J-M Mogul Rod and Valve Stem Packing is an exceptionally adaptable general utility packing that remains permanently soft and resilient throughout its service life. Recommended for service against air, water, ammonia, oil, and many chemicals where a soft, pliable packing without rubber is needed. Mogul is graphited inside and outside to relieve internal stresses in the packing.



J-M Interlocked Braided Rod Packing is braided solid and square by an exclusive process which eliminates jackets and plait. Therefore, it can't ravel or come apart in service. It presents a better contacting area and provides a tight seal with minimum gland pressure and take-up. This resilient, long-wearing packing is suitable for either reciprocating or rotating service.



There's a Johns-Manville Packing for every service condition. You'll find the right one, together with recommendations for its selection, in the J-M Packing Catalog. Write for your free copy: Johns-Manville, Box 290, New York 16, New York—or see your J-M Distributor.



Johns-Manville PACKINGS & GASKETS

CHEMICAL ENGINEERING Weighted Index of Prices for CHEMICALS

Base = 100 for 1937

This month.....	112.66
Last month.....	111.82
November, 1945.....	108.78
November, 1944.....	108.81

CURRENT PRICES

The accompanying prices refer to round lots. Where it is trade custom to sell f.o.b. works, quotations are so designated. Prices are corrected to November 11.

INDUSTRIAL CHEMICALS

Acetone, tank, lb.	90.07	—
Acid, acetic, 29% bbl, 100 lb.	3.38	— 83.63
Boric, bbl, ton	109.00	— 113.00
Citric, drums, lb.	.224	— .23
Formic, cba, lb.	.104	— .11
Hydrofluoric, 30% drums, lb.	.08	— .085
Lactic, 44% tech., light, bbl, lb.	.073	— .075
Muriatic, 18% tanks, 100 lb.	1.05	—
Nitric, 36% carboys, lb.	.05	— .024
Oleum, tanks, wks, ton	18.50	— 20.00
Oxalic, crystals, bbl, lb.	.114	— .124
Phosphoric tech., tanks, lb.	.04	—
Sulphuric, 60% tanks, ton	13.00	—
Tartaric, powd., bbl, lb.	.544	— .56
Alcohol, amyl from pentane, tanks, lb.	.131	—
Alcohol, butyl, tanks, lb.	.144	— .23
Alcohol, ethyl, denatured, No. 1 special, tanks, gal.	.542	—
Alum, ammoniac, lump, lb.	.044	—
Aluminum sulphate, conr. bags, 100 lb.	1.15	— 1.45
Ammonia, anhydrous, cyl, lb.	.144	—
Ammonia, anhydrous, tanks, ton	59.00	— 61.50
Ammonium carbonate, powd., casks, lb.	.094	— .10
Sulphate, wks, ton	30.00	—
Amyl acetate, tech. from pentane, tanks, lb.	.181	—
Aqua ammonia, 26% drums, lb.	.024	— .03
Arsonic, white, powd., bbl, lb.	.05	— .084
Barium carbonate, bbl, ton	65.00	— 75.00
Chloride, bbl, ton	75.00	— 78.00
Nitrate, casks, lb.	.094	— .11
Blanc fixe, dry, bags, ton	60.00	— 70.00
Bleaching powder, f.o.b., wks, drums, 100 lb.	2.50	— 3.00
Borax, gran., bags, 100 lb.	45.00	—
Calcium acetate, bags, 100 lb.	3.00	—
Arsenate, dr., lb.	.074	— .08
Carbide, drums, ton	50.00	—
Chloride, flake, bags, del., ton	18.50	— 25.00
Carbon bisulphide, drums, lb.	.05	— .05
Tetrachloride, drums, gal.	.73	— .80
Chlorine, liquid, tanks, wks, 100 lb.	1.834	— 2.10
Copperas, bags, f.o.b., wks, ton	17.00	— 18.00
Copper carbonate, bbl, lb.	.194	— .20
Sulphate, bbl, 100 lb.	5.65	— 6.15
Cream of tartar, bbl, lb.	.45	— .50
Diethylene glycol, dr. lb.	.144	— .154
Epsom salt, dom., tech., bbl, 100 lb.	1.80	— 2.00
Ethyl acetate, tanks, lb.	.084	— .114
Formaldehyde, 30%, tanks, lb, wks	.032	—
Furfural, tanks, lb.	.094	—
Glauber's salt, bags, 100 lb.	1.05	— 1.10
Glycerine c.p. drums, extra, lb.	.184	— .19
Lead:		
White, basic carbonate, dry, casks, lb.	.10	—
Red, dry, sck., lb.	.104	—
Lead acetate, white crys., bbl, lb.	.124	— .13
Arsenate, powd., bags, lb.	.134	— .144
Lithopone, bags, lb.	.044	— .049
Magnesium, carb., tech., bags, lb.	.074	— .08
Methanol, 95%, tanks, gal.	.60	—
Synthetic, tanks, gal.	.24	—
Phosphorus, yellow, casks, lb.	.23	— .25
Potassium bichromate, bags, lb.	.10	— .104
Chlorate, powd., lb.	.094	— .12
Hydroxide (caustic potash) dr. lb.	.07	— .074
Muriate, 60% bags, unit.	.534	—
Nitrate, ref., bbl, lb.	.08	— .09
Permanganate, drums, lb.	.194	— .20
Prussiate, yellow, casks, lb.	.16	— .17
Sal ammoniac, white, casks, 100 lb	4.50	— 5.00
Salaoda, bbl, 100 lb.	1.00	— 1.05
Salt cake, bulk, ton	15.00	—
Soda ash, light, 58% bags, contract, 100 lb.	1.104	—
Dense, bags, 100 lb.	1.204	—
Soda, caustic, 76% solid, drums, 100 lb.	2.414	— 3.15
Acetate, del., bbl, lb.	.064	— .06
Bicarbonate, bbl, 100 lb.	1.70	— 2.00
Bichromate, bags, lb.	.074	— .08
Bisulphate, bulk, ton	16.00	— 17.00
Bisulphite, bbl, lb.	.03	— .04

CHEMICAL ENGINEERING

Weighted Index of Prices for OILS & FATS

Base = 100 for 1937

This month.....	286.77
Last month.....	161.52
November, 1945.....	145.63
November, 1944.....	145.56

Chlorate, kegs, lb.....	\$0.061	\$0.061
Cyanide, cases, dom, lb.....	.14	.15
Fluoride, bbl, lb.....	.07	.08
Hyposulphite, bags, 100 lb.....	2.25	2.50
Metasilicate, bbl, 100 lb.....	3.40	4.00
Nitrate, bulk, ton.....	27.00	27.00
Nitrite, tanks, lb.....	.081	.07
Phosphate, tribasic, bags, 100 lb.....	2.70	2.70
Prussiate, vel, bags, lb.....	.101	.11
Silicate, 40°, dr, wks, 100 lb.....	.80	.85
Sulphate, crys, bbl, lb.....	.024	.024
Sulphur, crude at mine, long ton.....	16.00	16.00
Dioxide, cyl, lb.....	.07	.08
Dioxide, tanks, lb.....	.04	.04
Tin crystals, bbl, lb.....	.39	.39
Zinc chloride, grains, bbl, lb.....	.054	.06
Oxide, lead free, bags, lb.....	.08	.084
Oxide, 5% leaded, bags, lb.....	.08	.084
Sulphate, bbl, cwt.....	3.85	4.00

OILS AND FATS

Castor oil, No. 3 dr, lb.....	\$0.29	\$0.30
Chinawood, oil, tanks, lb.....	.39	.39
Coconut oil, ceylon, N. Y., lb.....	.24	.24
Corn oil crude, tanks (f.o.b. mill), lb.....	.26	.26
Cottonseed oil crude (f.o.b. mill), tanks, lb.....	.26	.26
Linseed oil raw, car lots, dr, lb.....	.353	.353
Palm, casks, lb.....	nom.	nom.
Peanut oil, crude, tanks (mill), lb.....	.26	.26
Rapeseed oil, refined, bbl, lb.....	nom.	nom.
Soybean, tanks, lb.....	.23	.23
Menhaden, light, pressed, dr, lb.....	nom.	nom.
Crude, tanks (f.o.b. factory), lb.....	.214	.214
Grease, yellow, loose, lb.....	.214	.214
Oleo stearine, lb.....	nom.	nom.
Oleo oil, No. 1, lb.....	.38	.38
Red oil, distilled, bbl, lb.....	.29	.29
Tallow, extra, loose, lb.....	.191	.191

COAL TAR PRODUCTS

Alpha-naphthol, crude, bbl, lb.....	\$0.52	\$0.55
Alpha-naphthylamine, bbl, lb.....	.32	.34
Aniline oil, drums, lb.....	.114	.124
Aniline salts, bbl, lb.....	.22	.24
Benzaldehyde, tech, dr, lb.....	.25	.50
Benzidine base, bbl, lb.....	.70	.75
Benzoic acid, USP, kegs, lb.....	.54	.56
Benzol, 90%, tanks, works, gal.....	.15	.15
Benzyl chloride, tech, dr, lb.....	.22	.24
Beta-naphthol, tech, drums, lb.....	.21	.22
Cresol, USP, dr, lb.....	.114	.114
Cresylic acid, dr, wks, gal.....	.81	.83
Diphenyl, bbl, lb.....	.15	.15
Diethylaniline, dr, lb.....	.40	.45
Dinitrotoluol, bbl, lb.....	.18	.19
Dinitrophenyl, bbl, lb.....	.22	.23
Dip oil, 15%, dr, gal.....	.23	.25
Diphenylamine, dr, f.o.b. wks, lb.....	.25	.25
H acid, bbl, lb.....	.45	.50
Hydroquinone, bbl, lb.....	.90	.90
Naphthalene, flake, bbl, lb.....	.094	.10
Nitrobenzene, dr, lb.....	.08	.09
Para-cresol, bbl, lb.....	.41	.43
Para-nitroaniline, bbl, lb.....	.42	.43
Phenol, USP, tanks, lb.....	.10	.11
Picric acid, bbl, lb.....	.35	.40
Pyridine, dr, gal.....	1.55	1.60
Rosercinol, tech, kegs, lb.....	.65	.70
Salicylic acid, tech, bbl, lb.....	.26	.33
Solvent naphtha, w.w., tanks, gal.....	.26	.26
Toluidin, bbl, lb.....	.96	.96
Toluol, drums, works, gal.....	.27	.27
Xylo, com, tanks, gal.....	.22	.22

MISCELLANEOUS

Casein, tech, bbl, lb.....	nom.	nom.
Dry colors:		
Carbon gas, black (wks), lb.....	\$.0365	.097
Prussian blue, bbl, lb.....	.36	.37
Ultramarine blue, bbl, lb.....	.11	.26
Chrome green, bbl, lb.....	.24	.33
Carmin, red, tins, lb.....	5.50	6.00
Para toner, lb.....	.75	.80
Vermilion, English, bbl, lb.....	2.50	2.60
Chrome yellow, C.P., bbl, lb.....	.17	.18
Gum copal, Congo, bags, lb.....	.09	.55
Manila, bags, lb.....	.09	.15
Damar, Batavia, cases, lb.....	.10	.22
Kauri, cases, lb.....	.18	.60
Magnesite, calc, ton.....	64.00	64.00
Pumice stone, lump, bbl, lb.....	.05	.07
Rosin, H., 100 lb.....	8.77	8.77
Shalac, orange, fine, bags, lb.....	.72	.72
Blotch, bonedry, bags, lb.....	.71	.71
T. N. bags, lb.....	.67	.67
Turpentine, gal.....	1.16	1.16

A good man to know



He's your Johns-Manville Packing Distributor—and he is one of 400 conveniently located industrial distributors who stock Johns-Manville Packings in many forms and styles.

Call on him when you need packing. You'll find his service prompt . . . and his knowledge of packing problems a big help in selecting the right packing for your job.

The sign of a good man to know



The Johns-Manville Packing Distributor in your community displays this sign. You'll find his place of business a convenient supply depot—not only for Packing, but for many other industrial supplies as well. Whenever you need an essential part, or tool, or material, you can count on your Johns-Manville Packing Distributor for prompt, efficient service at all times.

Your Johns-Manville
PACKING DISTRIBUTOR



NEW CONSTRUCTION

PROPOSED WORK

Calif., Glendale—Lambert Pharmacal Co., 1608 East 15th St., Los Angeles, plans to construct a research and administration building on Verdugo Rd. near Indian Springs. Estimated cost \$1,000,000.

Fla., Panama City—International Paper Co., Southern Kraft Div., Panama City, plans to construct a soda recovery unit. Estimated cost \$80,000.

La., Gretna—Southern Cotton Oil Co., Gretna, plans to construct a 4 story refinery. Estimated cost \$55,000.

Mich., Sheboygan—Paper Corporation of America, Sheboygan, plans to construct an addition to its paper mill. Estimated cost \$300,000.

O., Shawnee—Claycraft Brick Co., Shawnee, plans to enlarge its plant. Estimated cost \$400,000.

Tex., Borger—Phillips Petroleum Co., Borger, plans to reconstruct portion of its plant recently destroyed by fire. Estimated cost \$100,000.

Tex., Houston—Atlas Mineral Products Co. of Texas, Old Liberty Rd., plans to construct a new plant for producing sulphur cement, etc. Estimated cost \$150,000.

Tex., Houston—Southern Acid & Sulphur Co., LaPorte Rd., plans to construct an addition to its existing ammonium phosphate fertilizer plant. Estimated cost \$125,000.

Va., Waynesboro—E. I. du Pont de Nemours & Co., Inc., Wilmington, Del., plant to construct an addition to its rayon plant here. Estimated cost \$5,000,000.

B. C., Vancouver—British Columbia Pulp & Paper Co., Ltd., Vancouver, plans to construct a steam plant at its wood fibre plant here. Estimated cost \$100,000.

Ont., Hamilton—Canadian Industries, Ltd., 1135 Beaver Hall Hill, Montreal, Que., plans to construct an addition to its plant here. Estimated cost \$1,000,000.

Ont., Hamilton—World Plastics Corp., Hamilton, plans to construct a factory. Estimated cost \$55,000.

Ont., Toronto—Comet Cigarette Paper Co. of Canada, Ltd., 15 Toronto St., plans to construct a factory. Estimated cost \$60,000.

Ont., Toronto—Slick Glass Co., Gas City, Ind., plans to construct a factory here. Estimated cost \$90,000.

Que., Montreal—Gamlen Chemical Co. of Canada, Ltd., 57 West St. James St., plans to construct a plant. Estimated cost \$60,000.

CONTRACTS AWARDED

Conn., Norwalk—Norwalk Tire & Rubber Co., Winnepaug St., has awarded the contract for the construction of a 2 story, 80x90 ft. plant on Belden Hill Rd., to W. J. Lyons, 9 Mechanic St. Estimated cost \$55,000.

Del., Wilmington—E. I. du Pont de Nemours & Co., Inc., du Pont Bldg., will construct a chemical manufacturing plant at Edgemoor, with own forces. Estimated cost \$114,700.

Fla., Jacksonville—Wilson & Toomer Fertilizer Co., Talleyrand Ave., has awarded the con-

tract for a sulphuric acid manufacturing plant to George D. Auchter Co., foot of East 56th St. Estimated cost \$300,000.

Ill., Chicago—Globe Roofing Products, 2211 Schrage St., Whiting, Ind., has awarded the contract for a 1 story, 75x400 ft. felt mill to Paul Schwendener, 7553 South Chicago St., Chicago. Estimated cost \$150,000.

Ill., North Chicago—Abbott Laboratories, 1400 Sheridan St., has awarded the contract for a 1 and 2 story, 90x180 ft. brick fermentation building and connecting tunnel, to Carroll Construction Co., 333 North Michigan Ave., Chicago, at \$382,000.

Mo., St. Louis—Mallinckrodt Chemical Works, 3600 North Second St., has awarded the contract for altering its warehouse to Dickie Construction Co., Loudermann Bldg. Estimated cost \$60,000.

Mo., St. Louis—Standard Oil Co., 910 South Michigan Ave., Chicago, Ill., has awarded the contract for a 1 story engineering and research building, 100 octane cracking plant, etc., at Sugar Creek to Stone & Webster Corp., 33 South Clark St., Chicago. Estimated cost including equipment \$20,000,000.

N. C., Old Fort—United Rayon Mills, Old Fort, have awarded the contract for a rayon knitting plant to Potter & Shackleford, Greenville, S. C. Estimated cost \$88,000.

Pa., Philadelphia—Kessler Chemical Co., Inc., State and Cottman Sts., has awarded the contract for a 1 story, 40x121 ft. storage building to Edgar M. Wamboldt, 201 North Broad St. Estimated cost \$55,000.

S. C., Charleston—American Agricultural Chemical Co., 50 Church St., New York, N. Y., will construct an addition to its sulphuric acid plant here. Work will be done with own forces. Estimated cost \$60,000.

Tenn., Chattanooga—Lockout Oil & Refining Co., Kirkland Ave., will alter its plant and warehouse using day labor. Estimated cost \$75,000.

Tenn., Morristown—American Enka Corp., Asheville, N. C., has awarded the contract for the design and construction of a synthetic yarn plant to H. K. Ferguson Co., 1650 Hanna Bldg., Cleveland, O. Estimated cost \$20,000,000.

Tex., Houston—Diamond Alkali Co., Oliver Bldg., Pittsburgh, Pa., has awarded the contract for design and construction of chemical plant units to Brown & Root, Inc., Route 3. Estimated cost \$240,000.

Tex., Houston—Shell Oil Co., Inc., Shell Bldg., has awarded the contract for enlarging its plant to C. F. Braun & Co., Nils Esperson Bldg. Estimated cost \$2,500,000.

	Current Projects		Cumulative 1946	
	Proposed Work	Contracts	Proposed Work	Contracts
New England.....	\$.....	\$55,000	\$1,165,000	\$7,314,000
Middle Atlantic.....	55,000	26,096,000	34,490,000
South.....	5,185,000	26,138,000	66,177,000	119,713,000
Middle West.....	700,000	532,000	16,339,000	74,752,000
West of Mississippi.....	375,000	28,800,000	99,830,000	152,109,000
Far West.....	1,000,000	208,000	13,055,000	31,485,000
Canada.....	1,365,000	2,440,000	1,770,000	18,233,000
Total.....	\$8,575,000	\$58,288,000	\$224,432,000	\$438,096,000

Tex., Pasadena—Champion Paper & Fibre Co., Pasadena, has awarded the contract for altering, improving and construction addition to paper manufacturing plant to Ebasco Service, Inc., Pasadena. Estimated cost \$2,900,000.

Tex., Texas City—Monsanto Chemical Co., Texas City, has awarded the contract for constructing a polystyrene plant and converting present plant for the manufacture of styrene to W. S. Bellows Construction Co., 716 North Everton St., Houston. Estimated cost \$2,600,000 and \$500,000 respectively.

Wash., Seattle—The Texas Co., 135 East 42nd St., New York, N. Y., will construct an oil storage and distribution plant on Harbor Island. Work will be done by day labor. Estimated cost \$268,020.

W. Va., Parkersburg—American Cyanamid Co., Calco Chemical Div., 30 Rockefeller Plaza, New York, N. Y., has awarded the contract for a 1 and 2 story manufacturing plant and warehouse at Willow Island, near here, to Turner Construction Co., 420 Lexington Ave., New York, at \$3,500,000; chemical plant equipment to Rust Engineering Co., Clark Bldg., Pittsburgh, Pa., at \$2,000,000.

Ont., Toronto—Abitibi Power & Paper Co., Ltd., 408 University Ave., Toronto, has awarded the contract for an addition to its plant to Piggott Construction Co., Ltd., Harbour Commission Bldg. Estimated cost \$75,000.

Ont., Toronto—McColl-Fontenac Oil Co., Yardley Bldg., has awarded the contract for a grease and lubrication plant to Foundation Co. of Ontario, Ltd., 1220 Bay St. Estimated cost \$430,000.

Que., Sorel—Canadian Celanese Ltd., 1401 McGill College Ave., Montreal, has awarded the contract for a plant building to Marine Industries, Ltd., 174 du Roi St., Sorel. Estimated cost \$1,000,000.

Que., Valleyfield—Merck & Co., Ltd., 560 de Courcelle St., Montreal, has awarded the contract for an addition to its processing plant at Grand Isle to Raphael Belanger, 47 Jacques Cartier St., Valleyfield. Estimated cost \$85,000.

Que., Ville La Salle—Dominion Tar & Chemical Co., 2220 Sun Life Bldg., Montreal, has awarded the contract for a warehouse and specialty building to J. L. Heuson, Ltd., 660 St. Catherine St., W., Montreal. Estimated cost \$250,000.

Que., Ville La Salle—Montreal Coke & Manufacturing Co., Ltd., 435 St. Patrick St., has awarded the contract for an addition to its plant to By-Product Coke Co. of Canada, Ltd., P. O. Box 6110, Montreal. Estimated cost \$600,000.